

ROMAN ROADS & MILESTONES OF ASIA MINOR

FACI LIULIANORI ET
VICTORS AC
TRIUMFATORI
ERPET CAUC
IMCSS
MΩIII

DAVID H. FRENCH

VOL. 3 MILESTONES
FASC. 3.2 GALATIA

British Institute at Ankara

Electronic Monograph 2
2012

CONTENTS

1. ACKNOWLEDGEMENTS	3
2. BIBLIOGRAPHY	5
2.1 Abbreviations	5
2.2 Bibliography	5
3. NOTES AND COMMENTS	10
3.1 Administrative Areas and Codes, and Map	10
3.2 Dates	10
3.3 <i>Caput Viae</i>	11
3.4 Absence of Milestones	11
3.5 Provincial Boundary	11
4. MILESTONES	12
4.1 List of Numbered Milestones	13
4.2 Conspectus of Designated Roads and Numbered Milestones (with Maps 5.1.1-2)	14
4.3 Epigraphic Conventions	21
4.4 Texts	22
A. In Asiam	23
C. In Pontum et Bithyniam	40
D. Per Cappadociam in Pontum et Bithyniam	50
F. In Cappadociam	57
G. Galatia	136
H. De Lycia et Pamphylia in Galatiam	141
J. In Ciliciam, Isauriam et Lycaoniam	168
P. Per Pontum et Bithyniam, Galatiam, Cappadociam et Ciliciam, Isauriam et Lycaoniam ad Syriam usque	174
4.5 Concordances	223
4.6 Indices	233
5. ILLUSTRATIONS: MAPS	252
5.1.1-2 Conspectus Maps	15
5.2.1-4 Distribution Maps	253
6. ILLUSTRATIONS: FIGURES	261
6.1 Facsimiles of Published Texts	261
6.2 Drawings from Squeezes	273
7. ILLUSTRATIONS: PLATES	304
7.1 Milestones	304
7.2 Squeezes	331

1. ACKNOWLEDGEMENTS

As ever, I am indebted to a host of people both inside and outside Turkey. Some have been named in RRMAM Fasc. 1: to the many others, in villages and towns throughout the Ankara region, I here record my grateful thanks.

To my long-suffering *temsilciler* I owe a debt which can never be repaid in full:

- 1974 Ahmet Tırpan
- 1975 Orhan Gürman
- 1976 Mahmut Arslan
- 1977 Sedat Heper, İbrahim Atalay
- 1978 İbrahim Atalay
- 1981 Bayan Pınar Türkan
- 1982 İsmet Ediz
- 1983 İsmet Ediz
- 1984 İsmet Ediz
- 1993 Yaşar Yılmaz

A great deal of my work was carried out in the central provinces of Turkey. I therefore wish to thank the Directors and Staff of the following Museums:

- Ankara
- Çorum
- Karaman
- Konya
- Yalvaç

To the Directorate-General of Antiquities and Museums in Ankara I would like to offer my gratitude for the granting, year-on-year, of the necessary permission and for their strong support for my researches.

To Professor Dr Semavi Eyice I am grateful for his drawing to my attention the milestones preserved at the Ala-ed-Din Cami in Konya, and for his gift of a photograph (here Pl. 7.1.13 [p. 308]).

Dr Douglas Baird generously allowed me to use the text of a milestone (here no. 81) discovered on the Konya Plain Survey directed by him.

I would here like to mention the sponsorship which the British Academy and the British Institute of Archaeology at Ankara gave to my researches in the early years of the work. The Faculty of Classics at the University of Cambridge made a handsome grant towards the expenses of re-formatting of the Catalogue of Milestones.

Dr Joyce Reynolds reviewed, with great thoroughness and diligence, a preliminary draft of this volume. Professor Dr Werner Eck and Professor Stephen Mitchell have on several occasions offered sound advice and criticism and have corrected numerous errors of fact. To them my grateful thanks. The late Dr Michael Ballance generously made available his notes on Calder's notebook for 1910. By kind permission of the librarian, Colin A. McLaren, University Archivist, University of Aberdeen, I was able to inspect the Calder notebooks now held in the Department of

Special Collections and Archives.

To Mark Duncan, Christine Phillips, Benni Claasz Coockson and Brian Williams who drew the maps and the milestones, to Christal Türkmen and Figen Kirişçioğlu who prepared the first version in ChiWriter and to Christine Perrier who re-formatted the Catalogue of Milestones in Word I wish to offer my heartfelt thanks.

Finally, to all at the British Institute at Ankara who assisted in the preparation of this digital version – Abby Robinson, Research Scholar, Michele Massa, Research Scholar, and the Director, Lutgarde Vanderput – I am deeply indebted for their help and assistance.

2. BIBLIOGRAPHY

2.1 Abbreviations

The following abbreviations, for journals and serials and for books and series, are not generally found in the current lists.

- AdI Annali dell’Istituto di Corrispondenza Archeologica
- AST Araştırmalar Sonuçları Toplantısı
- BdI Bullettino dell’Istituto di Corrispondenza Archeologica
- Bull Robert (J. and L.) Bulletin Épigraphique
- KST Kazı Sonuçları Toplantısı

RECAM Regional Epigraphic Catalogues of Asia Minor (BIAA Monographs)

RRMAM Roman Roads and Milestones of Asia Minor (BIAA Monographs)

StPont Studia Pontica 1-3,1. Brussels

2.2 Bibliography

Note: The abbreviations primarily employed here are listed in *L’Année Philologique*, “Index of Articles”; they are supplemented, where necessary, by AJA 90 (1986), 384-394 “Abbreviations for Periodicals and (2) for Individual Works” and AJA 104 (2000), 10-24, and by *Zeitschriftenverzeichnis nach Abkürzungen, JdI Archäologische Bibliographie*

Anderson, J.G.C.

- 1897-98 Exploration in Asia Minor during 1898: First Report. *BSA* 4, 49-78
- 1899 Exploration in Galatia cis Halym. Part 2. *JHS* 19, 52-134 and 280-318
- 1910 A Celtic cult and two sites in Roman Galatia. *JHS* 30, 163-167

Anlağan, Ç.

- 1968 Akkuzulu Tümülüüsü Kazısı. *Anadolu* 12, 1-7 and Pl. 1-7

Ballance, M.H.

- 1958 Roman Roads in Lycaonia. *AnatSt* 8, 223-234
- 1960 *An Archaeological Re-assessment of the Classical Period in Central Asia Minor*.

PhD Diss. Edinburgh

Bittel, K.

- 1932 Beobachtungen in der Umgegend Ankaras. *AA*, 260-261
- 1942a *Kleinasiatische Studien*. Berlin (*IstMitt* 5)
- 1942b Archäologische Funde aus der Türkei. *AA*, 77-99
- 1955 Funde in östlichen Galatien. *IstMitt* 6, 22-41
- 1957 Zwei römische Meilensteine aus Galatien. *Anatolia* 2, 89-94
- 1985 *Beobachtungen an und bei einer römischen Strasse im östlichen Galatien*. Heidenheim

Bosch, K. E.

- 1967 *Quellen zur Geschichte der Stadt Ankara im Altertum*. Ankara (Turk. Hist. Soc., Publ. Ser. 7 no. 46)

Buckler, W.H., Calder, W.M. and Cox, C.W.M.

- 1924 Asia Minor 1924, 1. Monuments from Iconium, Lycaonia and Isauria. *JRS* 14, 24-84

Cagnat, R.

- 1903a Report in ‘Travaux’. *BAntFr*, 132-134
- 1903b Africana. In *Festschrift zu Otto Hirschfelds sechzigsten Geburtstag*, 167-170. Berlin
(Beitr. z. alt. Gesch. u. gr.-röm. Alt.-kunde)

Calder, W.M.

- 1911 *Preliminary Report to the Wilson Trustees for the year 1911*. Aberdeen University Callander, T.
- 1906 Explorations in Lycaonia and Isauria, 1904. In Ramsay, W.M. (ed.), *Studies in the History and Art of the Eastern Provinces of the Roman Empire*, 157-180. Aberdeen (Univ. St. 20)
- Christol, M. and Drew-Bear, T.
- 1986 Documents latins de Phrygie. *Tyche* 1, 41-87
- 1987 *Un Castellum Romain près d'Apamée de Phrygie*. Wien (DenkschrWien 189)
- Christol, M., Drew Bear, T. and Özsait, M.
- 1993 Trois milliaires d'Asie Mineure. *Anatolia Antiqua* 2, 159-169
- Christol, M. and Loriot, X.
- 1993 Aurelius Basileus, gouverneur de Cappadoce, problèmes de géographie administrative dans la première moitié du III^e siècle après J.-C. *Cahiers du Centre G. Glotz*, 209-221
- 2001 P. Alfius Avitus et P. Plotius Romanus, gouverneurs de Galatie. *AC* 70, 97-121
- Conti, S.
- 2004 *Die Inschriften des Kaiser Julians*. Stuttgart (Altertumswiss. Kolloquium 10)
- Cousin, G.
- 1904 *Kyros le Jeune en Asia Mineure*. Nancy (Lyons; repr. Paris 1905)
- Cronin, H.S.
- 1902 First Report of a journey in Pisidia, Lycaonia and Pamphylyia. Parts 1 and 2. *JHS* 22, 94-125 and 335-376
- Devreker, J. and Strubbe, J. H. M.
- 1996 Greek and Latin Inscriptions from Pessinus. *EpigrAnat* 26, 53-70
- Devreker, J. and Waelkens, M.
- 1984 *Les fouilles de la Rijksuniversiteit te Gent à Pessinonte 1967-73*, 1-2. Brugge (Diss. Arch. Gond. 22)
- Donati, S.
- 1765-75 *Ad novum thesaurum veterum inscriptionum L. A. Muratorii supplementum, collectore S. Donato* 1(1765) and 2 (1775). Luca
- Ehrenberg, V. and Jones, A.H.M.
- 1949 *Documents Illustrating the Reigns of Augustus and Tiberius*. Oxford
- Eyice, S.
- 1970-71 Konya'nın Alaaddin tepesinde Selçuklu öncesi ait bir eser, Eflatun Mescidi. *Sanat Tarihi Yıllığı* 4, 269-303
- Flottwell, von
- 1895 *Aus dem Stromgebiet des Qyzyl Yrmaq (Halys)*. Gotha (Pet. Mitt. Erg.-bd 24, Erg.-hft 114)
- French, D.H.
- 1973 (ed.) Ankara. *A Guide to the City and District*. Ankara (Ankara Soc. Promotion Tourism, Antiqu. & Museums)
- 1974 A study of Roman Roads. *AnatSt* 24, 143-149
- 1976a Researches on Roman Roads and Milestones in 1974. *TürkAD* 22,1, 51-54 (in Turkish)
- 1978a Roman Roads in Central Anatolia. In Akurgal, E. (ed.), *Proceedings of the 10th International Congress of Classical Archaeology* 1, 293-294. Ankara
- 1979b CIL XVII Miliaria, Fasc. 5 Asia Minor, Report for 1978. *Anat St.* 29, 6-7
- 1980 The Roman Road System of Asia Minor. In Temporini, H. and Haase, W. eds, *ANRW* 2.7, 2, 698-729. Berlin
- 1981 Milestones of Pontus, Galatia Phrygia and Lycia. *ZPE* 43, 149-174
- 1986 A Severan Milestone in the Antalya Museum. *EpigrAnat* 8, 84-90 and Pl. 7
- 1987 Küçük Asya, Roma Yolları ve Miltaşları 1986. *AST* 5.1 (Ankara), 191-204
- 1988 1987 Roma Yolları ve Miltaşları Çalışması. *AST* 6 (Ankara), 273-281
- 1989 Aurelius Basileus, Governor of Cappadocia. In Herzog, H.E. and Frei-Stolba, R. eds,

- Labor omnibus unus. Gerold Walser zum 70. Geburtstag*, 38-44. Wiesbaden (Historia Einzelschr. 60)
- 1990a 1989 Roma Yolları, Miltaşları ve Yazıtları Araştırması. *AST* 8 (Ankara), 229-240
 - 1990b Galatya bölgesi Roma Yolları ve Miltaşları. *AnadoluYıl* 5, 6-31
 - 1991b New Milestones from Pontus and Galatia. In Rèmy, B. (ed.), *Pontica 1. Recherches sur l'histoire du Pont dans l'Antiquité*, 77-96. Istanbul (Varia Anatolica 5)
 - 1997 Inscriptions in the Museum of Akşehir and Yalvaç. *EpigrAnat* 29, 59-66
 - 2003 *Roman, Late Roman and Byzantine Inscriptions of Ankara. A Selection*. Ankara
- Garstang, J.
- 1908 Notes on a Journey through Asia Minor. *LivAnnArchAnthr* 1, 1-12
- Habicht, Chr.
- 1971 Ein neuer Meilenstein des A. Larcius Macedo für Kaiser Hadrian aus Galatien. *ZPE* 8, 96
- Halfmann, H.
- 1986 *Itinera principum. Geschichte und Typologie der Kaiserreisen im Römischen Reich*. Wiesbaden (Heidelb. Alth. Beitr. u. Epigr. St. 2)
- Hamilton, W. J.
- 1842 *Researches in Asia Minor, Pontus and Armenia* 1, 2. London
- Henzen, W.
- 1862 Colonne migliaie retrovate nell'Asie Minore. *BdI*, 66-69
- Jerphanion, G. de
- 1928 Mélanges d'archéologie anatolienne. Monuments préhelléniques, gréco-romains, byzantins et musulmans de Pont, de Cappadoce et de Galatie. *MelBeyrouth* 13, 1-332
- Kienast, D.
- 1996 *Römische Kaisertabelle. Gründzüge einer römischen Kaiserchronologie*. Darmstadt (2nd ed.; reprinted 2004)
- Laminger-Pascher, G.
- 1992 *Die kaiserzeitlichen Inschriften Lykaoniens. Fasz. 1: Der Süden*. Wien (DenkschrWien 232)
- Le Bas, Ph.
- 1853-58 *Voyage archéologique en Grèce et en Asie Mineure* 3. *Inscriptions grecques et latines recueillies en Grèce et en Asie Mineure. Part 5. Asia Minor. 1. Inscriptions grecques et latines, 2. Explication des inscriptions*. Paris
- Le Bas, Ph. and Waddington, W. H.
- 1870 *Voyage archéologique en Grèce et en Asie Mineure* 3. *Inscriptions grecques et latines recueillies en Asie Mineure. Part 5. Asia Minor. 1. Inscriptions grecques et latines. 2. Explication des inscriptions*. Paris (repr. Hildesheim 1972)
- Part 5 (the inscriptions of Asia Minor) was printed, as were the other components of Le Bas' work, in instalments or fascicules (*livraisons*) but, at the time of his death, it was incomplete. Le Bas had published the whole of the first half (the inscriptions in majuscule) of part 5 (sections 1-12 and 13 Additions) and section 1 ("livraison 47" [printed in Paris in 1858] pages 1-26) of the second half (the texts in minuscule, and the explanatory notes). The first half of the Asia Minor inscriptions – the texts in majuscule – began with "livraison 41" (printed in Paris in 1853), and ended with "livraison 46" (printed in Paris in [?]1858). Waddington completed the second half from Le Bas' papers. Both halves were then printed in Paris in 1870 as a unified whole.
- Leschhorn, W.
- 1992 Die Anfänge der Provinz Galatia. *Chiron* 22, 315-336
 - 1993 *Antike Ären. Zeitrechnung, Politik und Geschichte in Schwarzmeerraum und in Kleinasien nördlich von Taurus*. Stuttgart (Historia Einzelschr. 81)
- Lewick, B.
- 1985 *The Government of the Roman Empire. A Source Book*. Beckenham
- Lriot, X.
- 1978 Un milliaire de Gordien II découvert près de Césarée de Palestine et l'extension aux

- provinces de l'insurrection de 238 après J.-C. *REA* 80, 72-84
- Macpherson, I.W.
- 1954 Roman Roads and Milestones of Galatia. *AnatSt* 22, 111-120
 - 1958 *New Evidence for the Historical Geography of Galatia*. PhD Diss., Cambridge
- Magie, D.
- 1950 *Roman Rule in Asia Minor* 1, 2. Princeton
- McCrumb, M. and Woodhead, A.G.
- 1961 *Select documents of the principates of the Flavian Emperors AD 69-96*. Cambridge
- Mamboury, E.
- 1933 *Ankara. Guide Touristique*. Ankara
- Marek, Chr.
- 1993 *Stadt, Ära und Territorium in Pontus-Bithynia und Nord-Galatia*. Tübingen (Ist. Forsch. 39)
- Miltner, Fr. and H.
- 1937 Epigraphische Nachlese in Ankara. *ÖJhBeibl* 30, 9-66
- Mitchell, S.
- 1973 A Hadrianic Milestone from Galatia. *ZPE* 10, 73-74
 - 1993 *Anatolia. Land, Men, and Gods in Asia Minor* 1, 2. Oxford
- Mommsen, Th.
- 1884a Additamenta tertia ad Corporis vol. III. *EphEp* 5, 1-104
 - 1884b Accutarium additamentorum ad Corporis vol. III. *EphEp* 5, 569-624
- Orelli, J. K. von and Henzen, W.
- 1856 *Inscriptionum Latinarum selectorum amplissima collectio*, 3. Turin
- Pace, B.
- 1916-20 La zona costiere da Adalia a Side. *ASAtene* 3, 29-71
- Perrot, G.
- 1867 *De Galatia provincia romana*. Paris.
- Perrot, G., Guillaume, R and Delbet, J.
- 1872 *Exploration archéologique de la Galatie et de la Bithynie, d'une partie de la Mysie, de la Phrygie, de la Cappadoce et du Pont exécutée en 1861 et publiée sous les auspices du Ministère de l'instruction publique* 1, 2. Paris
- Ramsay, A.M.
- 1909 *Preliminary Report to the Wilson Trustees for the year 1909*. Aberdeen
- Ramsay, W. M.
- 1905 Lycaonian and Phrygian Notes. *CR* 19, 413-429
 - 1906a *Pauline and other Studies*. London
 - 1907 *The City of St Paul*. London
 - 1909a *The Revolution in Constantinople and Turkey*. London
 - 1909b On Perta of Lycaonia. *CR* 23, 7-9 and 82
 - 1916 Colonia Caesarea (Pisidian Antioch) in the Augustan Age. *JRS* 6, 83-134
 - 1926 Studies in the Roman Province Galatia 7-9. *JRS* 16, 105-119
 - 1941 *The social basis of Roman power in Asia Minor*. Aberdeen
- Robert, L.
- 1965 *Hellenica* 13. Paris
- Rohde, G.
- 1943/44 Tebliğler No. 7 Ankara ve çevresinde yeni Yunanca ve Lâtinçe kitabe buluntuları. *AÜDTCFDergi* 2 (no. 5), 807-809 (with parallel German text: Neu gefundene griechische und lateinische Inschriften aus Ankara und Umgebung)
- Sandys, J. E.
- 1919 *Latin Epigraphy*. Cambridge (2nd ed. 1926)

Sarre, F.

- 1896a Reise in Phrygien, Lykien und Pisidia. *AEMÖ* 19, 26-57
- 1896b *Reise in Kleinasien. Sommer 1895*. Berlin

Sterrett, J.R.S.

- 1883-84 *An epigraphical journey in Asia Minor*. Boston (Pap. Amer. School Class. St. 2)
- 1884-85 *The Wolfe Expedition to Asia Minor*. Boston (Pap. Amer. School Class. St. 3)
- 1885 *Preliminary report of an archaeological journey made in Asia Minor during the summer of 1884*. Boston

Strobel, K.

- 2007 Die Meilensteine aus Tavium und aus seinem Stadtterritorium. In Mayer I Olivé, M., Baratta, G. and Almagro, A. G., (eds) *XIII Congressus Internationalis Epigraphiae Graecae et Latinae. Provinciae Imperii Romani Inscriptionibus Descriptae*. Barcelona, 3-8 Septembris 2002, 1405-1419

Strobel, K. and Gerber, Chr.

- 2003 Tavium (Büyük Nefes, Provinz Yozgat). *IstMitt* 53, 162-177
- 2007 Tavium (Büyük Nefes, Provinz Yozgat) – Bericht über die Kampagnen 2003-2005. *IstMitt* 57, 547-21

Süel, A.

- 1989 1988 yılı Çorum ili yüzey araştırmaları. *AST* 7, 341-345

Texier, Ch.

- 1839-49 *Description de l'Asie-Mineure* 1-3. Paris

Thomasson, B.

- *Laterculi Praesidum* 1. Göteborg 2009 (2nd ed.)

Tournefort, J. Pitton de

- 1717a *Relation d'un voyage du Levant fait par ordre du Roi, contenant l'histoire ancienne et moderne de plusieurs Isles de l'Archipel, de Constantinople, des Côtes de la Mer Noire, de l'Arménie, de la Georgie, des Frontières de Perse et de l'Asie Mineure* 1, 2. Paris

- 1717b *Relation d'un voyage du Levant* etc. 1-3. Lyon

- 1718 *Relation d'un voyage du Levant* etc. 1-2. Amsterdam

- 1741 *Relation d'un voyage du Levant* etc. 1-3. London (English translation)

Waldmann, H.

- 1981 Neue Inschriften aus Pisidien. *ZPE* 41, 95-102

Winter, E.

- 1996 *Staatliche Baupolitik und Bauforschung in den römischen Provinzen des kaiserzeitlichen Kleinasien*. Bonn (Asia Minor Studien 20)

ADDENDUM

Mitchell, S. and French, D. H.

- 2012 *The Greek and Latin Inscriptions of Ankara (Ancyra). Vol. I. From Augustus to the end of the third century AD*. München (Vestigia 62)

3. NOTES AND COMMENTS

3.1 Administrative Areas and Codes, and Map

3.1.1 Administrative Areas and Codes

The province (*il* or *vilayet*) and the sub-province or district (*ilçe* or *kaza*) are both named at the head of the rubric for each milestone. These names are followed by their official codes. The third digit (in the group) records the sub-district (*bucak*) – which is not named in the rubric – in which the milestone is now located or from which the stone has been removed (e.g. to a museum).

3.1.2 Map

A map reference follows below the administrative code. The reference is based on the 1:200,000 maps issued by the General Directorate of Mapping, Ankara; it indicates a named map/sheet in that series and the grid square on the sheet. These named sheets form a single set and are based on a series of Ottoman maps (now extremely rare) which were printed c. 1890 in Ottoman script. Under the Republic all names on the Ottoman maps were transliterated into a Latin font. The latest revision- and printing-date of the post-Ottoman maps seems to be c. 1941.

The grid squares are designated, in sequence, from N to S by a letter of the Turkish alphabet – a-z, Ia-z, then IIa-i – and from W to E by a number, 1 seqq. Occasionally, for the purpose of greater precision, an additional reference is used, as follows: 55.99 (for example), the first two digits represent millimetres along a W-E coordinate, the second pair indicates millimetres along a S-N coordinate.

The 1:200,000 maps have great value for the topographer. They show routes and tracks – surviving from earlier times – as they existed in the 19th century; they indicate, moreover, 19th century village-names and toponyms (reflected in the early travellers) and in some cases ancient sites. Frequently it is now difficult to trace old village-names without recourse to the (rare) volumes (offering old and modern concordances of place-names) issued by the relevant Turkish authorities, notably *Köylerimiz* (İstanbul 1933, issued by the Dahiliye Vekâleti), *Türkiye'de Meskûn Yerleri Kılavuzu* 2 vols (Ankara 1946, issued by the T. C. İçişleri Bakanlığı) and, *inter alia*, the *Genel Nüfus Sayımı, İdarî Bölümü 26.10.1975* (Ankara 1977, issued by the Başbakanlık Devlet İstatistik Enstitüsü).

3.2 Dates

The dates, cited here, for the Imperial tribunician power, consulship and (if any) imperial acclamation, are taken from the tables published by Kienast (1996).

It has not always been possible, however, fully to correlate the figures for tribunician power and consulship, as, for instance, on Trajanic milestones where the inscribed text reads TR·POT·COS·II for, presumably, TR·POT·⟨II⟩·COS·II. In this instance the consulship figure is consistently inscribed COS·II; a lapicide's error in the notation of the consulship may, therefore, be discounted. The text prepared for the lapicide to copy, nevertheless, may well have been in error and the figure II was given (wrongly) to COS instead of TR POT. This anomaly occurs consistently on the milestones attributed to the roads of northern Galatia..

On the other hand, a modern reading may be incorrect, as for, example, on the milestone at Yöreli

(no. 126[B]); see the comment on the text.

For those milestones on which the Emperor's *tribunicia potestas* is inscribed but without enumeration, i.e. simply TR·P, the non-presence of a number is here taken to indicate the initial year of his *tribunicia potestas*, e.g. AD 222, 13.iii-09.xii Severus Alexander *Augustus*.

3.3 *Caput Viae*

A separate entry, indicating the starting-point both of the road and of the measurement given in the distance figure has been inserted, for each milestone, immediately below the given text and above the entry for the date. Because of inherent difficulties (such as loss of, or damage to, the text), the *caput viae* is listed in hierarchical sequence, according to the degree of probability or possibility, as follows:

- Ancyra – the *caput viae* is inscribed in the text, in the form A (or Ab) + city-name
- (Ancyra) – the distance-figure is inscribed but the *caput viae* omitted,
- [Ancyra] – neither *caput viae* nor the distance figure have survived, but the city-name is here restored on the basis of probability.

Perhaps the most contentious interpretation is to be found at İskilip (no. 34), where the distance figure has not been corroborated by the discovery of other milestones in this area. A comparable instance or parallel may be drawn from the text of Çağırkan 1 (no. 68[A]): a high distance figure without indication of the *caput viae*. In both cases the milestones were located (it is here assumed) at or near the territorial boundary of the city and or province.

3.4 Absence of Milestones

The roads on which a milestone is thought to have been located are listed in section 4.2 Synopsis of Designated Roads and Numbered Milestones. It is there immediately apparent when no milestone has survived on a given road.

A notable example of the absence (or near-absence) of milestones is the road from Ancyra to Flaviopolis and Claudiopolis in Pontus-Bithynia, although it is thought that the Emperor Caracalla travelled by this route to Ancyra in AD 215 (Halfmann 1986, 224, 244). On the other hand, four large and massive milestones dedicated to Caracalla survive on the Pilgrim's Road west of the city of Iuliopolis; they are dated to AD 215/216.

Of some historical significance, perhaps, is the date – Flavian – of the earliest milestones on the road from Ancyra (established as the provincial capital in 25 BC under Augustus) to the Augustan colony of Germa and thence to the sanctuary at Pessinus. The Flavian date for the paving of the road – *viam stravit* – is some one hundred years later than the creation of the province itself. There is, in this example, a clear contrast with the action of Augustus in S Galatia: the construction – *viam fecit* – of the *Via Sebaste*, in 6 BC, between Perge and the Augustan colonies at Antiochia, Iconium and Lystra.

3.5 Provincial Boundary (Maps 5.1.1-2)

The boundary of the province Galatia, at the beginning of Septimius Severus' rule, is illustrated here on Maps 4.2.1-2 Synopsis of Designated Roads; a description of the relevant terrain and physical features is given in the parallel volume, RRMAM 4. Fasc. 2 The Roman Roads of Galatia.

4. MILESTONES

4.1 List of Numbered Milestones

- | | | |
|-------------------------|---------------------------------|-----------------------------|
| 01. Çayyolu | 48. Körpeli | 94. Dedeçam 1-2 |
| 02. Alacaatlı | 49. Haydarbeyli 1-3 | 95. Kıyakdede 1-5 |
| 03. Dodurga 1 | 50. Dambasan 1-2 | 96. Kireli |
| 04. Dodurga 2 | 51. Karakeçili 1-3 | 97. Selki 1-3 |
| 05. Balıkuyumcu | 52. Yazır 1-2 | 98. Yunuslar |
| 06. Malı | 53. Yekbaş 1-2 | 99. Değirmen |
| 07. Bacı | 54. Kaymaz 1-2 | 100. Bayat 1-2 |
| 08. Mülk | 55. Gökçam | 101. Hatunsaray 1-4 |
| 09. Ertuğrul | 56. Ekmekçi | 102. Kavak 1-4 |
| 10. Ballıhisar | 57. Çomar | 103. Apa |
| 11. Bahçesaray | 58. Eskiypar 1-2 | 104. Beypazarı |
| 12. Meydan | 59. Alaca 1-2 | 105. Bayram |
| 13. Sarayönü | 60. Akören | 106. İlyağut 1-2 |
| 14. Ladik | 61. Çopraşık | 107. Çoğlu 1-2 |
| 15. Bakırpinar | 62. Bolatçık | 108. Tatlar |
| 16. Çapalı 1-3 | 63. Küçük Nefes 1-2 | 109. Susuz 1-2 |
| 17. Balıkhisar 1-3 | 64. Musabeyli | 110. Erkeksu Çiftlik |
| 18. Sünlü | 65. Tol 1-2 | 111. Eryaman 1-2 |
| 19. Taşpınar | 66. Köseli | 112. Ankara, Etimesgut |
| 20. Cüçük | 67. Abazlı 1 | 113. Yuva |
| 21. Ömercik | 68. Karakeçili, Burun
Mevkii | 114. Macun |
| 22. Akkuzulu 1 | 69. Çağırkan 1-2 | 115. Ankara, Batıkent |
| 23. Akkuzulu 2-3 | 70. Konya 1-6 | 116. Ankara, Akköprü |
| 24. Koyunbaba | 71. Konya, Dikilitaş | 117. Ankara 1-13 |
| 25. Şemseddin | 72. Tilki Han | 118. Ankara, Çankaya 1-2 |
| 26. Kınık
(27. Mart) | 73. Kulak Murat Hanı 1-5 | 119. Ankara, Ahlatlibel 1-2 |
| 28. Yukarı Yanlar | 74. Eğribyat 1-5 | 120. Emirgöl |
| 29. Akyurt 1-2 | 75. Muşki Yayla | 121. Örencik 1-3 |
| 30. Kalabağ | 76. Kızılçakuyu 1-3 | 122. Oğulbey 1-5 |
| 31. Elecik | 77. Akbaş Yayla | 123. Beynam Çiftlik |
| 32. Çiftlik 1-2 | 78. Divanlar | 124. Ahiboz 1-2 |
| 33. Kalecik 1-2 | 79. Obruk 1-8 | 125. Günalan 1-2 |
| 34. İskilip | 80. Abditolu 1-2 & (?) | 126. Karaali 1-2 |
| 35. Ankara, Siteler | 81. Karkın | 127. Abazlı 2-3 |
| 36. Kayaş | 82. Ennek 1-2 | 128. Bağıçı 1-4 |
| 37. Ortaköy | 83. Ağsaklı | 129. Yöreli 1-2 |
| 38. Hasanoğlan 1-4 | 84. Altınekin 1-4 | 130. Bezirhane |
| 39. Elmadağ 1-3 | 85. Yazıbelen | 131. Afşar 1-7 |
| 40. Sungurlu | 86. Uluborlu | 132. Sarıhüyük |
| 41. Cevheri | 87. Yassıören 1-2 | |
| 42. Demirşeyh | 88. Esendere 1-5 | |
| 43. Hacılarhanı | 89. "Sarıyar" | |
| 44. Zincir | 90. Gençalı 1-8 | |
| 45. Büyük Nefes 1-3 | 91. Aşağı Kaşıkara 1-2 | |
| 46. Bicikler | 92. Kumdanlı | |
| 47. Eski Karaağıl | 93. Sücüllü 1-2 | |

4.2 Conspectus of Designated Roads and Numbered Milestones (with Maps 5.1.1-2)

A. IN ASIAM

1. Ancyra - Pessinus (- Amorium)	(5.A.3)	01-10
01. Çayyolu		
02. Alacaatlı		
03. Dodurga 1		
04. Dodurga 2		
05. Balıkuyumcu		
06. Mali		
07. Bacı		
08. Mülk		
09. Ertuğrul		
10. Ballıhisar		
2. Ancyra - Pessinus (- Dorylaeum)	(5.A.2)	
3. Colonia Germa (- Midiaeum - Dorylaeum)	(5.A.1)	
4. Laodicia Combusta (- Amorium)	(5.A.4)	
5. Colonia Iconium - Laodicia Combusta (- Philomelium)	(5.A.6)	11-15
11. Bahçesaray		
12. Meydan		
13. Sarayönü		
14. Ladık		
15. Bakırınpınar		
6. Colonia Antiochia (- Philomelium)	(5.A.7)	
7. Colonia Antiochia (- Iulia?)	(5.A.8)	
8. Pessinus (- Philomelium)	(5.A.5)	
9. <i>Via Sebaste</i> (Apollonia) (- Apamea)	(5.A.9)	16
16. Çapalı 1-3		


B. DE ASIA PER GALATIAM IN CAPPADOCIAM

1. (Amorium -) Comitanassus (- Salaberina) [<i>Tabula Peut.</i>]	(5.B.1)(3.B.1)
--	----------------

C. IN PONTUM ET BITHYNIAM


1. Ancyra (- Cratia Flaviopolis - Claudiopolis)	(4.B.1)
2. Ancyra - Gangra (- Hadrianopolis)	(4.B.3)
17. Balıkhisar 1-3	
18. Sünlü	
19. Taşpinar	
20. Cüciük	
21. Ömercik	
22. Akkuzulu 1	

5.1 Synopsis Maps



5.1.1 Galatia West

5.1 Synopsis Maps



5.1.2 Galatia East

23. Akkuzulu	2-3
24. Koyunbaba	
25. Şemseddin	
26. Kınık	
(27. Mart)	
28. Yukarı Yanlar	
3. Gangra (- Amastris)	(4.B.4)
4. Gangra (- Pompeiopolis / Ionopolis)	(4.B.5)

D. PER CAPPADOCIAM IN PONTUM ET BITHYNIAM

1. Ancyra per territorium Amasiae (- Amisus)	(3.D.1)(4.D.1)	29-34
29. Akyurt 1-2		
30. Kalabağ		
31. Elecik		
32. Çiftlik 1-2		
33. Kalecik 1-2		
34. İskilip		

E. DE PONTO ET BITHYNIA PER GALATIAM IN CAPPADOCIAM

1. (Claudiopolis -) Antoniopolis (- Amasia)	(4.E.1)(3.E.1)
---	----------------

F. IN CAPPADOCIAM

1. Gangra (- Amasia)	(3.A.5)	
2. Ancyra (- Amasia - Neocaesaria - Nicopolis - Satala)	(3.A.9)	35-43
35. Ankara, Siteler		
36. Kayaş		
37. Ortaköy		
38. Hasanoğlan 1-4		
39. Elmadağ 1-3		
40. Sungurlu		
41. Cevheri		
42. Demirşeyh		
43. Hacılarhanı		
3. Ancyra - Tavium (- Zela - Neocaesaria)	(3.A.11) 44, 45(A)-(B), 46-62	
44. Zincir		
45. Büyük Nefes 1-2		
46. Bicikler		
47. Eski Karaağıl		
48. Körpeli		
49. Haydarbeyli 1-3		
50. Dambasan 1-2		
51. Karakeçili 1-3		

83. Ağsaklı

12. Ancyra (- Nysa - Tyana) (3.A.1))

G. GALATIA

H. DE LYCIA ET PAMPHYLIA IN GALATIAM

1. Via Sebaste (6.A.1) . . 86-100, 101(C)

- 86. Uluborlu
- 87. Yassören 1-2
- 88. Esendere 1-5
- 89. "Sarıyar"
- 90. Gençaltı 1-8
- 91. Aşağı Kaşıkara 1-2
- 92. Kumdanlı
- 93. Sücüllü 1-2
- 94. Dedeçam 1-2
- 95. Kıyakdede 1-5
- 96. Kireli
- 97. Selki 1-3
- 98. Yunuslar
- 99. Değirmen
- 100. Bayat 1-2
- 101(C). Hatunsaray 3

I. IN LYCIAM ET PAMPHYLJAM

1. *Via Sebaste* (Apollonia) (- Colonia Parlaïs - Prostanna) . . (6.B.1, 2)
2. *Via Sebaste* (Apollonia) (- Colonia Parlaïs - Prostanna) . . (6.B.1, 2)
3. Colonia Antiochia (- Prostanna) (6.B.3)

J. IN CILICIAM, ISAURIAM ET LYCAONIAM

1. *Via Sebaste* (Neapolis) (- Mistea - Isaura Nova) . . . (7.A.4)
 2. *Colonia Lystra* (- Isaura Nova) (7.A.3)
 3. *Colonia Lystra* (- [?] Dalisandus) (7.A.2) 101(A)-(B),(D) 102-103

 101(A)(B)(D). Hatunsaray 1-2, 4
 102. Kavak 1-4

103. Apa

4. Colonia Lystra (- Laranda) (7.A.1)
 5. Colonia Iconium (- Laranda) (7.A.5)

K. PER CILICIAM, ISAURIAM ET LYCAONIAM IN LYCIAM ET PAMPHYLIAM

1. Colonia Iconium (- Mistea - Amblada) (- Side) (7.B.1)(6.G.1)

**P. PER PONTUM ET BITHYNIAM, GALATIAM, CAPPADOCIAM
ET CILICIAM, ISAURIAM ET LYCAONIAM AD SYRIAM USQUE**

1. [The Pilgrim's Road] (Chalcedon - Nicaea - Iuliopolis -) Ancyra (- Colonia Archelaïs - Tyana - *Via Tauri* - Tarsus - Antiochia) (4.P.1)(3.P.1)(7.P.1)(8.P.1) 104-132

- 104. Beypazarı
- 105. Bayram
- 106. İlyagut 1-3
- 107. Çoğlu 1-2
- 108. Tatlar
- 109. Susuz 1-2
- 110. Erkeksu Çiftlik
- 111. Eryaman 1-2
- 112. Ankara, Etimesgut
- 113. Yuva
- 114. Macun
- 115. Ankara, Batıkent
- 116. Ankara, Akköprü
- 117. Ankara 1-13
- 118. Ankara, Çankaya 1-2
- 119. Ankara, Ahlatlibel 1-2
- 120. Emirgöl
- 121. Örencik 1-3
- 122. Oğulbey 1-5
- 123. Beynam Çiftlik
- 124. Ahiboz 1-2
- 125. Günalan 1-2
- 126. Karaali 1-2
- 127. Abazlı 2-3
- 128. Bağıçı 1-4
- 129. Yöreli 1-2
- 130. Bezirhane
- 131. Afşar 1-7
- 132. Sarıhüyük

4.3 Epigraphic Conventions

MAJUSCULE	Letters read on the stone (or preserved in an earlier copy) but not understood by the editor
[α β γ] [a b c]	Letters, lost through breakage or no longer visible, restored by the editor
{α β γ} {a b c}	Letters cut in antiquity but thought by the editor to be superfluous
⟨α β γ⟩ ⟨a b c⟩	Letters thought by the editor to have been accidentally omitted in antiquity and, therefore, supplied by the editor
(α β γ) (a b c)	Letters supplied by the editor in order to complete or to amplify an ancient abbreviation
[[α β γ]] [[a b c]]	Letters erased in antiquity but still wholly visible
[[α β γ]] [[a b c]]	Letters erased in antiquity and only partly preserved
[[[α β γ]] [[a b c]]]	Letters erased in antiquity, no longer visible, restored by the editor
α β γ a b c	Letters, damaged and/or only partly preserved, the interpretation of which is open to doubt; consult the drawing (where available)
(sic)	Words or letters correctly cut but thought to be grammatically or orthographically remarkable or unusual; where possible, given by the editor as preserved on the stone
* α β γ * a b c *	(A modern error) Letters or words emended from an earlier copy of an inscription which is not now available to the editor; a note is given in the apparatus or in the commentary
/α β γ/ /a b c/	(An ancient error) Letters or words incorrectly cut, or malformed, or for which, in error, different letters or words have been inscribed on the stone; suggested corrections are supplied by the editor; consult the drawing (where available) and the commentary
underline α β γ underline a b c	Letters seen by an earlier copyist but no longer visible or preserved
(vac) or (v)	vacat, i.e. an empty space
[. . 4 . .] [.]	The figure, or the number of dots, within the square brackets indicates the precise number of letters required to fill a known space or to complete the inscription
[- - - -] - - - -	The dashes within the square brackets indicate an indefinite number of letters to be restored in the text in order to fill a known space or to complete the inscription; if the square bracket is not present, the number of missing letters (and hence of missing lines) is not known
ligatures	The presence of ligatured letters is indicated in the commentary
αβΙγ ablc αβ γ ab c	The vertical line indicates the original line-divisions, whether falling in a single word or between two words, in an inscription which is printed as continuous text or as verse
αβΙΙγ abllc αβ γ ab c	The double vertical line indicates the end of every fifth line (the fifth, tenth, fifteenth and so on), whether falling in a single word or between two words, in an inscription printed as continuous text or as verse

4.4 Texts

A. IN ASIAM

A.1 ANCYRA - PESSINUS (- Amorium)

01. Çayyolu, form. Kutuğun

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Yenimahalle 06-03-0
<i>Map</i>	Ankara 57-v
<i>Provenance</i>	In the village, beside the mosque. Now in the Roman Baths, Ankara [Inv. no. 186.3.1974, previously 3.1.1974]
<i>Copy</i>	DHF 06.ix.1974, 12.xi.1974, 28.x.2005. DHF squeeze in BIAA. Text from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 72, Çayyolu
<i>Publication</i>	RRMAM 2, 1. 124 (notice only)
<i>Description</i>	A simple cylinder. Broken above and below. Hard, grey limestone. There are round holes in the top and bottom surfaces. The shaft was roughly dressed; the inscription of text (1) was cut on a smoothed panel. Surface and letters: very worn
<i>Dimensions</i>	Ht (ex.) 1.01; diam. (top) 0.43, (bottom) 0.54. Letters: (text 2) 0.05
<i>Text</i>	(1) (in a smoothed panel) illegible; perhaps deliberately erased (2) (partly above, partly on the l., of the panel)

Imp Caes [- - -]
traces of 8 lines

<i>Caput Viae</i>	[Ancyra]
<i>Comment</i>	“No visible inscription” (RRMAM)

02. Alacaath

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Yenimahalle 06-03-0
<i>Map</i>	Ankara 57-v
<i>Provenance</i>	In the village cemetery. Now in the Roman Baths, Ankara [Inv. no. 186.2.1974, previously 2.1.1974]
<i>Copy</i>	Anderson Summer 1898; DHF 06.ix.1974, 12.xi.1974. DHF squeeze (drawing, Fig. 6.2.1 [p. 275]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 53, Alacaatlı
<i>Publication</i>	Anderson 1899, 93 no. 74 CIL 3. 14184 ⁵⁹ (text of Anderson) Bosch 1967, 148 no. 124 (text of Anderson) French 1976a, 52 (notice only) RRMAM 2, 1. 091 (notice only)
<i>Description</i>	A simple cylinder. Broken above and below. Hard, grey limestone. Letters: worn. Note the broken-bar A (line 7).
<i>Dimensions</i>	Ht (ex.) 0.79; diam. 0.58. Letters: (line 3) E of NE 0.044, (line 9) PR PR 0.068

Text (1) (underneath text [2])
obliterated

(2) (on the top of text [2])
 [Imp Caesari]
 dīvī Tr̄[aiani P]ar(t)hi-
 ci f dīvī [Nerv]ae ne-
 4 poti Trajanō Hadri-
 ano Aug·pontif maxi
 tri pot VI cos·III (sic)
 per A Larcium Ma-
 8 cedonem leg Aug (sic)
 (vac) pr pr
 (vac) mi VIII

line 2: P]ar(t)hi- cp. 22. Akkuzulu 1 line 2, or perhaps a ligature, **TH**

line 3: ligature **NE**

line 5: ligature **NT**

line 8: ligature **NE**

line 10: ligature **MI**

Caput Viae (Ancyra)
Date AD 121/122, 10.xii-09.xii Hadrianus *Augustus*

03. Dodurga 1

Province, Sub-Province + Admin. Code Ankara, Yenimahalle 06-03-0
Map Ankara 57-v
Location “Quinque horis ab Ancyra euntibus Sevrihissar, ubi transitur summus mons, ad puteum” (CIL). Present whereabouts not established (DHF visit 06.ix.1974).
Copy von Domaszewski [1882]. The stone has not been examined by DHF. Text here of CIL (von Domaszewski)
Publication Mommsen 1884a, 38 no. 80 (text from von Domaszewski)
 CIL 3. 6902 (text of von Domaszewski)
 RRMAM 2, 1. 129 (notice only)
Description & Dimensions Not given

Text B F D n Imp Caes L Do[m]
 2 Aureliano p f
 invicto Aug

Caput Viae [Ancyra]
Date AD 270, ix-275, ix/x Aurelianus *Augustus*

04. Dodurga 2

Province, Sub-Province + Admin. Code Ankara, Yenimahalle 06-03-0
Map Ankara 57-v
Location “In via publica ab Angora horis quattuor German versus” (CIL). Present

whereabouts not established (DHF 06.ix.1974)
Copy Mordtmann [A.D.] 1858 (see CIL 3. 771). The stone has not been examined by DHF. Text here of CIL (Mordtmann)
Publication CIL 3. 317 (text from Mordtmann)
Bosch 1967, 366 no. 304 (text of CIL [Mordtmann])
RRMAM 2, 1. 130 (notice only)

Description & Dimensions Not given

<i>Text</i>	IMPCAES
2	CN
	AT
4	HIMPE
	AXIMI
6	PIVALX
	IM
8	AP

possible restoration

	Imp Caes [C Aur Val]
2	[Dio]cle[^{**} tiano]
	[p f in]vi[^{**} cto Aug]
4	et Imp ^{**} C aes M Aur Val]
	[M]aximi[ano p f inv Aug]
6	[et] Fl·Val [*] C [*] onstantio]
	[et Gal Va] ^l M[aximiano]
8	[nobb C]ae [*] ss]

Caput Viae [Ancyra]
Date (?) AD 293, 21.v(?)-305, 01.v Diocletianus and Maximianus *Augusti* with Constantius I and Galerius *Caesares*

05. Bahkuyumcu

Province, Sub-Province + Admin. Code Ankara, Yenimahalle 06-03-2
Map Ankara 56-y
Provenance Formerly in the village cemetery. Now in the Roman Baths, Ankara [Inv. no. 186.1.1974, previously 1.1.1974]
Copy Anderson Summer 1898; DHF 06.ix.1974, 12.xi.1974. DHF squeeze (drawing, Fig. 6.2.2 [p. 275]) and photos in BIAA. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
Squeeze: 06. Ankara 65, Balıkuyumcu
Stone: (2) Col. Slide: DHF 090.04-06
Publication Anderson 1897-98, 72 (notice only)
Anderson 1899, 93 no. 73
CIL 3. 14184⁶⁰ (text of Anderson)
Bosch 1967, 148 no. 125 (text of Anderson)
French 1976a, 52 (notice only)
RRMAM 2, 1. 116 (notice only)

<i>Description</i>	A simple cylinder. Complete. Grey limestone. Top flat. Letters: slightly worn																		
<i>Dimensions</i>	Ht 1.80; diam. (top) 0.63. Letters: (line 1) E of CAE 0.07, (line 3) E of NER 0.039, (line 7) E of NEM 0.045																		
<i>Text</i>	<table> <tr> <td></td> <td style="text-align: right;">Imp Caesari di-</td> </tr> <tr> <td>2</td> <td style="text-align: right;">vi Traiani Parthici f di-</td> </tr> <tr> <td></td> <td style="text-align: right;">vi Nervae nepoti Tra-</td> </tr> <tr> <td>4</td> <td style="text-align: right;">iano Hadriano Aug</td> </tr> <tr> <td></td> <td style="text-align: right;">pont max tr pot VI</td> </tr> <tr> <td>6</td> <td style="text-align: right;">cos·III per A Larci-</td> </tr> <tr> <td></td> <td style="text-align: right;">um Macedonem</td> </tr> <tr> <td>8</td> <td style="text-align: right;">leg Aug·pr·pr·</td> </tr> <tr> <td></td> <td style="text-align: right;">m XXIV</td> </tr> </table>		Imp Caesari di-	2	vi Traiani Parthici f di-		vi Nervae nepoti Tra-	4	iano Hadriano Aug		pont max tr pot VI	6	cos·III per A Larci-		um Macedonem	8	leg Aug·pr·pr·		m XXIV
	Imp Caesari di-																		
2	vi Traiani Parthici f di-																		
	vi Nervae nepoti Tra-																		
4	iano Hadriano Aug																		
	pont max tr pot VI																		
6	cos·III per A Larci-																		
	um Macedonem																		
8	leg Aug·pr·pr·																		
	m XXIV																		

lines 5-6: horizontal bar over the numerals

Caput Viae (Ancyra)
Date AD 121/122, 10.xii-09.xii Hadrianus Augustus

06. Mai

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Polatlı 06-18-1
<i>Map</i>	Ankara 55-y
<i>Location</i>	In an old cemetery; on the NE side of the village
<i>Copy</i>	DHF 08.xi.1973. DHF squeeze (drawing, Fig. 6.2.3 [p. 276]) and photos (Pl. 7.1.01 [p. 306]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
Squeeze:	06. Ankara 89, Mali
Stone:	(1) B/W Neg.: DHF R/73/05.12 (2) Col. Slide: DHF 108.24
<i>Publication</i>	French 1976a, 52 (notice only) RRMAM 2, 1. 159 (notice only)
<i>Description</i>	A simple cylinder. Broken below. White limestone. Top flat. Letters: extremely worn
<i>Dimensions</i>	Ht (ex.) 1.06; diam. 0.48. Letters: (line 1) P of IMP 0.04
<i>Text</i>	(1) (underneath text [2]) obliterated
	(2) (on the top of text [1])
	Imp Caesari
	d̄ivi Traian̄i
	Parthici f di-
4	vi N̄ervae ne-
	pot̄i Traian̄o
	Hadriano Auḡ
	p̄ont̄ m̄ax t̄ pot̄
8	[. . .] cos III [. . .]

	[... c.11 ...]
10	[... c.11 ...]
	[-----]
12	[-----]

line 9: three unintelligible letters at the end of the line

possible restoration of ll. 8-12

8 [VI] **cos III** [pe]r
 [A Larcium Mac]-
 10 [edonem leg Aug]
 [pr pr]
 12 [m . .]

Caput Viae [Ancyra]
Date Hadrianus Augustus, (?)AD 121/122

07. Bacı

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Polatlı 06-18-1
<i>Map</i>	Ankara 47-y
<i>Location</i>	At a fountain, c. 5 km SE of Bacı
<i>Copy</i>	DHF 02.iv.1973. DHF squeeze (drawing, Fig. 6.2.4 [p. 276], and photo., Pl. 7.2.1 [p. 334]) and photos (Pl. 7.1.2 [p. 306]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 06. Ankara 59, Bacı (= B/W Neg.: Squ. M/15.07-08)
	Stone: (1) B/W Neg.: DHF 35/73/01.01-09 (2) Col. Slide: DHF 102.10-16
<i>Publication</i>	French 1978b, 294 and Fig. French 1980, 727 Map 3 (no. 16) (notice only) RRMAM 2, 1. 108 (notice only)
<i>Description</i>	A simple cylinder. Broken above. Grey limestone. Inscribed area smoothed, recessed and surrounded by a deep-cut border. Surface very worn. Letters worn
<i>Dimensions</i>	Ht (vis.) 1.36; diam. 0.46. Letters (line 6) P in VIAS·PRO 0.032
<i>Text</i>	[Imp·Caesar·divi·Vespas]- [iani·f·Domitianus] [Aug·pont·ma]xim[us]·tri[b] 4 p[o]tes[·ce]ns·cos·VII·per· A·Ca[ese]nnium·Gallum· legatum·pro·pr·vias·pro· vinciarum·Galatiae· 8 Cappado[c]iae·[P]onti·Pisi· diae [Paphl]agoniae·Luca· oniae·Armeniae·Mino- (vac) ris·stravit· 12 [-]

line 4: horizontal bar over the numeral

Caput Viae [Ancyra]
Date AD 81, 30.ix-31.xii Domitianus *Augustus*
Commentary According to Kienast (1996, 116), Domitianus' TR P began on 30 September 81, and his COS VIII on 01 January 82. He became COS VII DES VIII "seit Mitte Marz 81" (Kienast) before the death of Titus but the change in his titulature is not indicated in the text here.
According to Kienast (l.c.), Domitianus was not given *censoria potestas* until April(?) 85.

08. Mülk

<i>Province, Sub-Province + Admin. Code</i>	Eskişehir, Sivrihisar 26-06-0
<i>Map</i>	Sivrihisar 49-Ib
<i>Location</i>	Present whereabouts not established (DHF visit 27.x.1975). The village lies c. 18 km NE of Sivrihisar, on S side of the Pütek Çay
<i>Copy</i>	Hamilton 16 September, 1836. The stone has not been examined by DHF. Text here of CIL (Hamilton) (facsimile of the printed text, Fig. 6.1.1 [p. 263])
<i>Publication</i>	Hamilton 1842, 1, 436 no. 139 and 2, 428 no. 139 Orelli and Henzen 1828-56, 3, 389 no. 6913 (text of Hamilton) Henzen 1862, 66 (text of Hamilton) Le Bas and Waddington 1870, 2, 425 no. 1784 (text of Hamilton) CIL 3. 318 (text of Hamilton) ILS 1. 263 (text of Hamilton) Bosch 1967, 62 no. 66 (text of Hamilton) French 1976a, 53 (notice only) French 1980, 716 no. 9 (text of Hamilton) RRMAM 2, 1. 375 (notice only) " . . . from a rough marble column" (Hamilton)
<i>Description</i>	" . . . from a rough marble column" (Hamilton)
<i>Dimensions</i>	Not given

<i>Text</i>	[I]mp T Ca[es]ar̄ divi Ves- pasiani f Aug pont max trib potest X imp XV cos 4 VI[II] censor p p [et] Caes [[divi f Domitianus]] cos VII [p]rinc iuventutis (vac) [per] (vac)
	8 [A] Caes[ennium Gallum] leg pro pr vias provinci- aru[m] G[ala]tiae Cappad[o]- ciae Ponti Pisidiae Pa- 12 phlagoniae Lycaoniae Armeniae Minoris (vac) straverunt (vac) LXXI

line 4: **VICENSORPP XX** (Hamilton); **VI[II]** (CIL)
line 7: om. Hamilton

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 80, 01.vii-81, before mid-March Titus <i>Augustus</i> with Domitianus (name erased) <i>Caesar</i>
<i>Commentary</i>	According to Kienast (1996, 112 and 116), Titus' TR P X ran from 01 July 80 to 30 June 81; his COS VIII began on 01 January, 80 and his COS DES IX "seit Mitte Marz" 81; Domitianus became COS VII DES VIII also "seit Mitte Marz" 01.i.81

09. Ertuğrul

<i>Province, Sub-Province + Admin. Code</i>	Eskişehir, Sivrihisar 26-06-0
<i>Map</i>	Emirdağ 48-Id
<i>Provenance</i>	In the village; formerly in front of the <i>kahve</i> (coffee-house); then at the <i>Orta Okul</i> (Middle School). Now in the Excavation dépôt at Ballıhisar [Inv. no. 83.1]
<i>Copy</i>	DHF 21.viii.1983; Schuddeboom 2004; Strubbe 2004. DHF squeeze (photo., Pl. 7.2.2 [p. 334]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Photograph</i>	Squeeze: 26. Eskişehir 04, Ertuğrul (= B/W Neg.: Squ. M/15.05-06)
<i>Publication</i>	RRMAM 2, 1. 369 (lines 8-9 only) Devreker in Devreker and Waelkens 1984, 1, A, 23 (notice only) Strubbe in Devreker and Waelkens 1984, I, 216 n.2 (notice only) IK 66 (ed. Strubbe). 183 and Pl. 5, Figs 1-2 AE 2005. 1476 (text in IK)
<i>Description</i>	A simple cylinder. Complete. Hard, white, granular marble. Top flat; in the centre, a round hole. Letters: slightly worn
<i>Dimensions</i>	Ht (vis.) 0.86; diam. (top) 0.37. Letters: (line 1) P of IMP 0.075, (line 4) O of ENO 0.028

<i>Text</i>	Imp·Caes·P·
2	Lic·Valeriano
	p·f·Aug et P·
4	Lic·Gallieno
	p·f·Aug·et P·
6	Lic·Valer-
	nobil·Caes·
8	civitat·Pess·
	mil·III

line 8: possibly civitat(e) Pess(inuntis), i.e. (the milestone was set up) by the agency of the city of Pessinus, or perhaps civitat(is) Pess(inuntis), i.e. of the city of Pessinus (this is) the sixth *mil(iarium)*

<i>Caput Viae</i>	Pessinus
<i>Date</i>	AD 255-257/258 Valerianus and Gallienus <i>Augusti</i> with Valerianus Iunior <i>Caesar</i>

10. Ballıhisar

<i>Province, Sub-Province + Admin. Code</i>	Eskişehir, Sivrihisar 26-06-0
---	-------------------------------

<i>Map</i>	Emirdağ 48-Iç
<i>Provenance</i>	“Precise find spot unknown; now in the Archaeological Museum at Ballıhisar” (Devreker and Waelkens) [Inv. no. 68.10]
<i>Copy</i>	Photo. Devreker 12 September, 1987. The stone has not been examined by DHF. Text here from a photograph supplied by Devreker Strubbe in Devreker and Waelkens 1984, I, A, 224 no. 36
<i>Publication</i>	RRMAM 2, 1. 368 (notice only) Devreker and Strubbe 1996, 61 no. 10 and Pl. 14 AE 1996. 1493 (text of Strubbe) IK 66 (ed. Strubbe). 41 and Pl. 1 Fig. 1
<i>Description</i>	“White marble column, broken below. The upper side has a rectangular hole for fixing another stone” (Devreker and Waelkens)
<i>Dimensions</i>	“Ht 0.33; diam. 0.20; letters ht 0.025-0.03” (Devreker and Waelkens)

<i>Text</i>	B [F]	
2	Imp Ceas Gal Val	(sic)
	[[Maximino p]] fel	
4	invicto Aug et In-	(sic)
	pr Cea Fla Val	(sic)
6	Co<n>stantino	
	p fel iny[icto]	
8	[Aug - -]	

line 3: [[Maximiano p]] **fel** is also possible

<i>Caput Viae</i>	[Pessinus]
<i>Date</i>	AD 311, beg. May-313, Aug/Sept. [[Maximinus]], Constantinus I [and Licinius I] <i>Augusti</i> or AD 307-308 Galerius and Constantinus I <i>Augusti</i>

A.5 COLONIA ICONIUM - LAODICIA COMBUSTA (- Philomelium)

11. Bahçesaray, form. Nevenne

<i>Province, Sub-Province + Admin. Code</i>	Konya, Sarayönü 42-15-0
<i>Map</i>	Ilgin 56-In
<i>Location</i>	“Han on Ladik-Konya road below Nevine” (MAMA); in an old han c. 200 m W of Dağdere village junction on Konya-Afyon highway. Seen there on a first visit (DHF 05.viii.1977); before a second visit (DHF 18.ix.1993) the stone had been removed.
<i>Copy</i>	(?) Calder et al. 1928 (see MAMA 7, xvi). Examined by DHF 05.viii.1977. No squeeze. No photo. Text here of MAMA (facsimile of the published drawing, Fig. 6.1.2 [p. 263]) and of DHF notes
<i>Publication</i>	MAMA 7. 9 and Fig. (p. 125) (text of Calder et al.?) Ballance 1958, 230 no. 29 (notice) RRMAM 2, 1. 604 (notice only) Conti 2004, 89 no. 43 (text and comment)
<i>Description</i>	“On a round pillar” (MAMA). A simple cylinder. Broken above and below. Hard, grey limestone. Letters: slightly worn
<i>Dimensions</i>	“Ht 1.70; diam. 0.36. Letters: 0.03 to 0.07” (MAMA)
<i>Text</i>	(1) traces of letters at the end of l. 1 and below l. 4 (see the facsimile, Fig. 6.1.2 [p. 263]) (2) Fl^sCl Iuliano 2 victor<i><i></i>sac triumfatori 4 [p]erpet^sAug μι Θ' line 4: [p]erpet(uo) Aug (usto) line 5: ligature ΜΙ , μι (λια); “In line 5 the earlier inscription gave VIII; Θ was carved over V, of which traces remain” (MAMA)
<i>Caput Viae</i>	(Laodicia Combusta)
<i>Date</i>	(1) (?) (2) AD 361, 03.xi-363, 26/27.vi Iulianus Augustus

12. Meydan

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-1
<i>Map</i>	Ilgin 57-Im
<i>Location</i>	“Old cemetery 1 km. ESE of Meidan Stn” (WMR). The cemetery has been cut through by a village şose (18.ix.1993); the cemetery is 1.6 km ESE (110° magnetic) from the station. Present whereabouts not established (DHF visit 18.xi.1993).
<i>Copy</i>	W.M. Ramsay (? date). The stone has not been examined by DHF. Text here from a W.M. Calder notebook, now in Aberdeen University Library, Special Collections and Archives, box no. 3286/4; in this notebook are listed texts “Copied from WMR’s notebook”, (?) date.

<i>Description</i>	“Large cippus” (WMR)
<i>Dimensions</i>	Not given
<i>Text</i>	[Imp Caesar Divi] 2 [Tr]aiani [Parthici f] [Divi] Nervae [nep Tra]- 4 [ianus Hadrianus] [Aug p]ont[ifex max] 6 tribu[niciae pot]- [est]atis XIII [cos] 8 [(vac) III p p (vac)] [- -]
<i>Caput Viae</i>	[Laodicia Combusta]
<i>Date</i>	AD 128/129, 10.xii-09.xii Hadrianus <i>Augustus</i>
<i>Comment</i>	The text has been here restored, in part, on the basis of 078(A). Obruk 1

13. Sarayönü

<i>Province, Sub-Province + Admin. Code</i>	Konya, Sarayönü 42-15-0
<i>Map</i>	Ilgın 56-In
<i>Location</i>	Not given. Present whereabouts not established (DHF visit 02-03.viii.1977)
<i>Copy</i>	Text among Ramsay papers (BIAA archive); copy marked, in Ramsay’s hand, Serai (R. 1906; R.C. 1910)”. The stone has not been examined by DHF. Text here from BIAA archive (facsimile of Ramsay’s copy, Fig. 6.1.3 [p. 263])
<i>Publication</i>	RRMAM 2, 1. 662 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	Imp C[aesari] 2 Gaio V[alerio] Dioc[letiano] 4 pio f[elici in]- vict[o Augusto] (vac) m [p]
<i>Caput Viae</i>	(Laodicia Combusta)
<i>Date</i>	AD 284, 20.xi-286, 01.iv Diocletianus <i>Augustus</i>

14. Ladik

<i>Province, Sub-Province + Admin. Code</i>	Konya, Sarayönü 42-15-0
<i>Map</i>	Ilgın 55-In
<i>Location</i>	“In stable; in very dark store room: r(ea)d by candle” (WMR). Present whereabouts not established (DHF visit 18.xi.1993)
<i>Copy</i>	W.M. Ramsay (? date). The stone has not been examined by DHF. Text here from a W.M. Calder notebook, now in Aberdeen University Library, Special Collections and Archives, box no. 3286/4; in this notebook are listed texts “Copied from WMR’s notebook”, (?) date.
<i>Description</i>	Not given but “letters in upper part very good considering period” (WMR). Letters (from WMR copy): (text 1) note the twin forms, straight- and broken-

bar A, square E and the lunate form of E in CONSTANTE (line 6), curvilinear S and the *gamma*-shape form (only in line 7) of S in CAESS, and also the rectilinear T; (text 2) the broken bar *alpha*, the lunate *epsilon*, the late form of L, i.e. with an oblique lower bar, H (= N), the curvilinear T, i.e. with a lunate, vertical hasta, U (= V)

Dimensions

Not given

Text

(1) (above text [2])

		ΔΔ nn	(sic)
2	Imp Caes Fl Valerio		
	Constantino p f invicto Aug		
4	et Fl Constantino		
	et Fl Cons[t]antio Aug		
6	et Fl Constante		
	(vac) nnll Caess		
8	(vac) μ γ'		

line 1: ΔΔ for DD

line 5: Aug added at a later date?

line 7: nnll Caess = nobilissimis Caesaribus

line 8 μ(iλια)

(2) (below text [1])

	dd NN Fl Valentiniano	
2	et LRATIA et Fl Valente	
	(vac) ANO Auggg	

line 2: et ⟨Fl⟩ /G/ratia added at a later date

line 3: ANO belongs to LRATIA in line above; G added to AVGG

Caput Viae

(Laodicia Combusta)

Date

(1) AD 333, 25.xii-335, 18.ix Constantinus I *invictus Augustus* with Constantinus II, Constantius II and Constans *Caesares*; addition in line 5 post-337?
 (2) AD 364, 28.iii-367, 24.viii Valentinianus I and Valens *Augusti*, then Gratianus *Augustus* added, AD 367, 24.viii-375, 17.xi

15. Bakırpinar, form. Büyüzkengi*Province, Sub-Province + Admin. Code*

Konya, Sarayönü 42-15-0

Map

Ilgin 56-Im

Location

Not given. Present whereabouts not established (DHF visit 18.xi.1993)

Copy

W. M. Ramsay (? date). The stone has not been examined by DHF. Text here from a W. M. Calder notebook, now in Aberdeen University Library, Special Collections and Archives, box no. 3286/4; in this notebook are listed texts “Copied from WMR’s notebook”, (?) date; recorded under “Zengi”.

Description

“Round column” (WMR).

Dimensions

Letters: straight-bar *alpha*, lunate *epsilon* and *sigma*, curvilinear *omega*

Not given

Text

(1) a Latin text

(2) (upside down to text [1])

Φλ' Ο[ναλε]ρίφ
2 Κεον[ήρω] (vac)
και Ἄ[αλε]ρίφ
4 Ούα[λερί]φ
Μα[ξιμεί]νφ
6 ἐπι[φανε]τάτυς
Κέε[αρε]ν

(sic)

Caput Viae

[Laodicia Combusta]

Date

(1) (?)
(2) AD 305, 01.v-306, 25.vii Severus and Maximinus *Caesares*

A.9 [Via Sebaste] (APOLLONIA) (- Apamea)**16(A). Çapalı 1**

<i>Province, Sub-Province + Admin. Code</i>	Afyon, Dinar 03-04-0
<i>Map</i>	Dinar 38-Io
<i>Provenance</i>	At Büyük Sancar mevkii (Kocasancar on 1:200,000 Map) where there is a well; on N of the <i>şose</i> (village-road) to Uluborlu; c. 6.5 km NE of Çapalı. Now in the Dinar open-air dépôt
<i>Copy</i>	Ramsay (W.M.) 1905; DHF 22.vii.1978; Drew Bear (? date). DHF squeeze (drawings, Figs 6.2.5-7 [pp. 277-278] and photos, Pl. 7.2.3-4 [p. 335]) and photos (Pl. 7.1.3 [p. 306]) in BIAA. Texts here from DHF squeeze and from Christol and Drew Bear drawings (facsimiles, Fig. 6.1.4-5 [p. 264])
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 03. Afyon 97, Çapalı 1 (= B/W Neg.: Squ. M/16.1-10)
	Stone: (1) B/W Neg.: DHF R/78/07.09-10
<i>Publication</i>	Ramsay 1906a, 234 (notice only) Callander 1906, 173 (notice only) Ramsay 1926, 105 (notice only) Ballance 1958, 232 n.16 (notice only) French 1981, 167 no. 13 AE 1986. 683 (text of French) Christol and Drew Bear 1987, 19 no. 2 and photos Pls 5-9 AE 1987. 938 a-c (text of Christol and Drew Bear) SEG 44. 1029 (notice of Christol and Drew Bear 1987 and comments on l. 15) RRMAM 2, 1. 043 (notice only)
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. Top flat; round tenon under base. Letters: worn
<i>Dimensions</i>	Ht 1.76; diam. (top) 0.41. Letters: (text 1) (line 5) E 0.03; (text 3) O of INO 0.06
<i>Text</i>	(1) [Imp Cae]s·L·Sept[imius Sev]- [erus] Pius·Perti [nax] [Aug] Arab·Adia [beni]- 4 [cu]s· Parthicu s [max] [pon]tifex max [tr] [pot] VI·imp·XI cos [II] [pro]cos et Imp Cae s] 8 [M Aur]el Antoninus Au ⟨g⟩ (vac) Part·max (vac) (vac) restituerunt [per T A]tticium [N]- 12 orbanum St/r/a [bo]- (vac) bonem leg (vac) Augg pr pr mil /p/ass VIII

line 8: ligature **AV**line 9: (?) **P Septimius Geta Caes** once inscribed underneath **PartMax**,

cp. 72. Tilki Han
 line 12: **P** for **R** in **STR**
 line 14: **Aug** (French 1981)
 lines 14, 15: **MIL I CAΠΤ** (Christol and Drew Bear 1987); for **mil I**
 /p/ass(uum), cp. 72. Tilki Han

(2) (underneath text [3])
 (?)

(3) (partly covers the l. side of text [1])

	(vac) DD n[n]
	F<small>l</small> V<small>al</small> Constantino
	[[et Val Liciniano]]
4	[[Licinio]] pp ff in-
	yict Augg et Fl
	Val Crispo et Val'
	Constantini Licini
8	et [Cl Val Const]antini
	[nobb] Caesss
	M

(sic)

(sic)

line 1: **DDN[N]** overlies letters of text (2), cf. Christol and Drew Bear
 lines 6-9: added to lines 1-5 by a second hand
 line 9: **AB** and **CAES** of **CAESSS** not seen by DHF but copied by
 Christol and Drew Bear
 line 10: **M** not seen by DHF but copied by Christol and Drew Bear

(4) (underneath, and obscured by, text [5])

2	ppp fff
	(vac)
	invict·Augg

line 3: (?) letters underneath **AUGGG**

(5) (partly covers the r. side of text [1] and l. side of text [3])

	ddd n[nn]
2	Fl Grati[an]o et
	Fl Valen[ti]niano et
4	Fl Theodosio
	ppp fff
6	(vac)
	[- - -]is Auggg

line 2: the letters **OET** were cut over an earlier **FLVAL**

There are a few unexplained letters embedded in texts (3) and (5); consult the drawings, Figs 6.2.6-7

<i>Caput Viae</i>	(Apollonia)
<i>Date</i>	<p>(1) AD 197/198, 10.xii-09.xii Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with Geta (names erased) <i>Caesar</i></p> <p>(2) (?)</p> <p>(3) AD 317 or 318 (Christol and Drew Bear) Constantinus I and Licinius I <i>Augusti</i> with Crispus, Licinius I and Constantinus II <i>Caesares</i></p> <p>(4) (?)</p> <p>(5) AD 379, 19.i-383, 19.i Gratianus, Valentinianus II and Theodosius I <i>Augusti</i> [after the elevation of Theodosius I (AD 379, 19.i) and before the elevation of Arcadius (AD 383, 19.i)]</p>

Comments There are pertinent differences between the texts presented by Christol and Drew Bear and by DHF. For elucidation of texts (3), (4) and (5), cp. the printed text and the facsimile given by Christol and Drew Bear (1987, 20, and 21 Fig. 3, reproduced here, 6.1.4-5 [p. 263]) and the DHF drawings (Figs 6.2.5-7 [pp. 277-278]).

16(B). Çapalı 2

Province, Sub-Province + Admin. Code, Map and Location As 016(A)

Copy Ramsay (W.M.) 1905; DHF 22.vii.1978; Drew Bear (? date). DHF squeeze (drawings, Figs 6.2.8-9 [p. 278]) and photo. (Pl. 7.1.4 [p. 307]) in BIAA. Texts here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 03. Afyon 98, Çapalı 2

Stone: (1) B/W Neg.: DHF R/78/07.07

Publication Ramsay (W.M.) 1906a, 234 (notice only)

French 1981, 168 (notice only)

Christol and Drew Bear 1987, 22 no. 3, facsimile Fig. 3 and photos Pls 10-13
AE 1987, 939 (a) and (b) (text of Christol and Drew Bear)

RRMAM 2, 1.044 (notice only)

Conti 2004, 92 no. 48 (text [3] and comment on text)

Description

A simple cylinder. Broken above and below. Hard, pale limestone. Above, a wreath. Letters: worn

Dimensions

Ht (ex.) 0.84; diam. 0.52. Letters: (text 1) c. 0.02-0.025; (text 2) (line 2) E of ET 0.03; (text 3) (line 2) U 0.040, dI of CLAUDI 0.055

Text

(1) (at the top: a wreath; the text under the wreath was erased; on the left both of [2] and of [3]; some small letters [c. 0.025 high] visible on l. of lines 1-4 of text [3])

(2) (on the l. of the wreath)

dd NN

2 [Fl] **Val** Constantino et [[Val Liciniano Licinio]]

4 [pp ff in]vict Augg et Fl

⁶ [V]al Crispo et Val Constantini [[Licinio]] et Cl Val Constantini

[nnnblbb Caesss]

(sic)

[?]

- line 1: **dd** for **DD**
 line 6: [[Lici]]**nio** Christol and Drew Bear
 line 7: [N]**OB** Christol and Drew Bear
 line 8: **m p** [V]**III** Christol and Drew Bear

(3)	Δ N
2	Fl' Claudi(o)
	Iuliano
4	pio felici vict
	max semp Aug
	(vac)
6	μι [-]

- line 2: d for D; “**I** of **CLAUDI** survives from text (1)” (Christol and Drew Bear 1987, 23)
 line 4: **VICT** *om.* Christol and Drew Bear
 line 5: **MAX** “survives from text (1)” (Christol and Drew Bear 1987, 23). On the other hand, there are traces of earlier letters at the beginning of line 5, thus [[**ORIAC**]]**SEMPAVG**. These were remodelled and replaced by the word **MAX**.
 line 6: ligature **MI**, **μι**(λια)

<i>Caput Viae</i>	[Apollonia]
<i>Date</i>	(1) AD (?)
	(2) AD 317 or 318 (Christol and Drew Bear) Constantinus I and Licinius I <i>Augusti</i> with Crispus, Licinius and Constantinus <i>Caesares</i>
	(3) AD 361, 03.xi-363, 26/27.vi Iulianus <i>Augustus</i>
<i>Comment</i>	Lines 4-5 vict max : cp. [princip]lum(?) max CIL 3. 10648b lines 2-3 = ILS 3. 8946, where, on the basis of the Çapalı 2 text (2) here, these lines could perhaps be restored (line 2 of CIL 3. 10648b with a more appropriate number of letters) Fl Cl Iuliano [vict]lori*** max (imo) etc. Christol and Drew Bear (1987, 23 and n.36) comment on the lack of epithets such as VICTOR and TRIUMFATOR in the Çapalı 2 text (2) here.

16(C). Çapalı 3

<i>Province, Sub-Province + Admin. Code, Map and Location</i>	As 016(A)
<i>Copy</i>	Ramsay (W.M.) 1905; DHF 22.vii.1978; Drew Bear (? date). DHF squeeze (drawing, Fig. 6.2.10 [p. 279]) and photo. (Pl. 7.1.5 [p. 307]) in BIAA. Texts here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 03. Afyon 99, Çapalı 3
	Stone: (1) B/W Neg.: DHF R/78/07.06
<i>Publication</i>	Ramsay (W.M.) 1906a, 234 (notice only) French 1981, 168 (notice only)
	Christol and Drew Bear 1987, 24 no. 4 and photos Pls 14-15 AE 1987, 940 (text of Christol and Drew Bear) RRMAM 2, 1. 045 (notice only)
<i>Description</i>	A simple cylinder. Broken below. Hard, pale limestone. Above, a wreath. Note the letters A and L and the two forms of E. Letters: worn
<i>Dimensions</i>	Ht (ex.) 0.85; diam. (top) 0.51. Letters: (text 1) (line 2) N of CON 0.045

Text(1) (on the full face of the cylinder)
(wreath)**DD nn**2 **Fl Val Constantino**

[[et Val Liciniano]]

4 [[Licinio]] **pp ff**[i]n*vict A*ugg*et Fl*6 [V]al Crisp*o et Va*[l]

[Const]antini Li[ci]-

(sic)

8 [nio] **et Cl Val** [Con]-
[stantino nobb Caesss]

[-]

line 2: note the reversed S

line 4: **DO** (Christol and Drew Bear) = **PP** (DHF)(2) (on r. of text [1]; the end letters of text [1] line 2 overlap the beginning of
text [2] line 8)

2 [- - - -]

[- - - -]

[- -]**NO**4 [- -]**IMI**

[- - - -]

6 [- - - -]

[- - - -]

8 [- - - -]

(vac)

μι ζ'line 9: ligature **MI**, **μι**(λια)*Caput Viae*

[Apollonia]

Date

(1) AD 317 or 318 (Christol and Drew Bear) Constantinus I and Licinius I

Augusti with Crispus, Licinius II and Constantius II *Caesares*

(2) (?)

C. IN PONTUM ET BITHYNIAM

C.2 ANCYRA - GANGRA (- Hadrianopolis)

17(A). Balıkhisar 1

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Çubuk 06-08-1
<i>Map</i>	Gerede 60-t
<i>Location</i>	“Beside the stream which flows through the village” (Macpherson). Now set up in front of the village school (11.xi.1974)
<i>Copy</i>	Macpherson 1953; DHF 11.xi.1974. Macpherson squeeze in the Faculty of Classics, Cambridge (Box IWM VIII no. 181); DHF squeeze (photo., Pl. 7.2.5 [p. 336]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 60, Balıkhisar 1 (= B/W Neg.: Squ. M/15.03-04)
<i>Publication</i>	Macpherson 1954, 119 no. 18 and Pl. 10 no. 4 Macpherson 1958, 180 no. 252 RRMAM 2, 1. 113 (notice only)
<i>Description</i>	A simple cylinder. Complete. Grey limestone. Top flat. Letters: very slightly worn
<i>Dimensions</i>	Ht 1.95; diam. 0.54. Letters: (line 1) P 0.05, (line 2) T 0.047, (line 8) P of PR 0.04
<i>Text</i>	(1)(underneath text [2]) traces of letters
	(2)(on the face of the shaft)
	Imp Caesar (vac) i
2	divi Traiani Par(t)hi-
	ci f div(i) Nervae nepoti
4	Traiano Hadriano
	Aug pont max tr po(t) VI
6	cos III per A Larcium
	M (vac) acedonem leg Aug
8	pr (vac) pr (vac) m (vac) li
	XVI
10	ie'
	(sic)
	(sic)
	line 2: Par(t)h[i] (Macpherson 1954)
	line 3: ligature NE (twice); nepot[i] (Macpherson 1954)
	line 5: ligature NT
	line 7: ligature NE
<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	(1) (?)
	(2) AD 121/122, 10.xii-09.xii Hadrianus Augustus
<i>Comment</i>	Was the damage to the letter X (lines 5 and 9) intentional? obliterated perhaps during the Ottoman period?

17(B). Balıkhisar 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 17(A)																		
<i>Location</i>	“In field about 1 mile west of village, near the Ankara-Çubuk road” (Macpherson). Present whereabouts not established (DHF visit 11.xi.1974).																		
<i>Copy</i>	Macpherson 1953. Macpherson squeeze in the Faculty of Classics, Cambridge (Box IWM VIII no. 192). The stone has not been examined by DHF. Text here of Macpherson 1954 and from Macpherson squeeze																		
<i>Publication</i>	Macpherson 1954, 119 no. 19 and Pl. 10 no. 5 Macpherson 1958, 181 no. 253 RRMAM 2, 1. 114 (notice only)																		
<i>Description</i>	“Grey limestone” (Macpherson 1954)																		
<i>Dimensions</i>	“H. 1.86 Diam. 0.47; letters 0.0035-0.04” (Macpherson 1954)																		
<i>Text</i>	<table> <tr> <td></td> <td>Imp Ner[va] Trai-</td> </tr> <tr> <td>2</td> <td>anus Caesar Aug</td> </tr> <tr> <td></td> <td>Germanicus pont</td> </tr> <tr> <td>4</td> <td>max trib pot p p cos [?]</td> </tr> <tr> <td></td> <td>restituit per T</td> </tr> <tr> <td>6</td> <td>Pomponium Bassum</td> </tr> <tr> <td></td> <td>leg pro pr-</td> </tr> <tr> <td>8</td> <td>aetore</td> </tr> <tr> <td></td> <td>[-] XV</td> </tr> </table>		Imp Ner[va] Trai-	2	anus Caesar Aug		Germanicus pont	4	max trib pot p p cos [?]		restituit per T	6	Pomponium Bassum		leg pro pr-	8	aetore		[-] XV
	Imp Ner[va] Trai-																		
2	anus Caesar Aug																		
	Germanicus pont																		
4	max trib pot p p cos [?]																		
	restituit per T																		
6	Pomponium Bassum																		
	leg pro pr-																		
8	aetore																		
	[-] XV																		

line 4: **max trib pot III cos [-]** (Macpherson 1954) but all other milestones of Traianus on this road have **p p cos II**
 line 9: **? [m p] XV; [X]XV** (Macpherson 1954)

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 98(?) Traianus <i>Augustus</i>
<i>Commentary</i>	According to Kienast (1996, 123), Traianus began his COS II on AD 01 January 98 but had ended his TR P (I) on 09 December 97: an apparent anomaly, therefore, if the numberless TRP was indeed correctly inscribed. He took the title <i>pater patriae</i> in “Spätherbst” 98 (Kienast).

17(C). Balıkhisar 3

<i>Province, Sub-Province + Admin. Code and Map</i>	As 17(A)				
<i>Location</i>	In the village; beside the mosque				
<i>Copy</i>	DHF 11.xi.1974. DHF squeeze (drawing, Fig. 6.2.11 [p. 279]) in BIAA. Text here from DHF squeeze				
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 61, Balıkhisar 3				
<i>Publication</i>	RRMAM 2, 1. 115 (notice only)				
<i>Description</i>	A simple cylinder. Top flat. Complete. Hard, grey limestone. Top flat. Surface very worn. Letters: very worn				
<i>Dimensions</i>	Not recorded. Letters: (line 5) T of TRIB 0.045, (line 9) T 0.04				
<i>Text</i>	<table> <tr> <td></td> <td>[Imp Nerva]</td> </tr> <tr> <td>2</td> <td>Traianus [Cae]-</td> </tr> </table>		[Imp Nerva]	2	Traianus [Cae]-
	[Imp Nerva]				
2	Traianus [Cae]-				

4 **s a[r A]ug Ge[rma]-**
 4 **n i c u s** [pont max]
 5 **t r i b p o t p p** [cos II]
 6 **r e s t i t u i t p**[er T]
 7 **P o m p o n**[ium Bas]-
 8 **s u m l e g p r**[o pra]-
 9 **e t o r**[e]
 10 **[m XIII t]γ'**

Caput Viae (Ancyra)
Date AD 98(?) Traianus Augustus
Commentary For the date, see the commentary above, no. 17(B)

18. Sünlü

Province, Sub-Province + Admin. Code Ankara, Çubuk 06-08-0
Map Gerede 60-ş
Location In the village; built into the house (no. 50) of Mevlüt Gümüş
Copy SM 1972; DHF 19.ix.1975. SM and DHF squeezes (photo. of DHF squeeze,
 Pl. 7.2.6 [p. 336]) in BIAA. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 06. Ankara 100, Sünlü (= B/W Neg.: Squ. M/15.02)
Publication RRMAM 2, 1. 174 (notice only)
Description (?) A simple cylinder. Broken above, below and behind. Grey limestone.
 Inscribed surface smoothed. Letters: sharp and clear but damaged
Dimensions Ht 0.44; diam. (?) c. 0.50. Letters: (line 7) **E** 0.055

Text [Imp Caesari C]
 2 [Iulio Vero Ma]-
 3 **x i m i n o** [pio fe]-
 4 **l i c i A u g e t** [C Iu]-
 5 **l i o V e r o M a x i -**
 6 **m o n o b i l i s -**
 7 **s i m o C a e s a -**
 8 [r i - - -]
 [- - - -]

Caput Viae [Ancyra]
Date AD 236, 07.i/16.v-238, mid-April Maximinus Augustus with Maximus Caesar
Commentary The dates for Maximinus Augustus with Maximus Caesar are given by Kienast
 (1996, 183-185).

19. Taşpinar

Province, Sub-Province + Admin. Code Ankara, Çubuk 06-08-1
Map Gerede 60-ş
Location In the village cemetery
Copy SM 1972; DHF 11.viii.1974. SM and DHF squeezes (drawing of DHF
 squeeze, Fig. 6.2.12 [p. 279]) in BIAA. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

<i>Publication</i>	Squeeze: 06. Ankara 102, Taşpinar RRMAM 2, 1. 176 (notice only)
<i>Description</i>	A simple cylinder. Hard grey and white limestone. Top flat. Very rough surface. Letters: worn
<i>Dimensions</i>	Ht 1.55; diam. 0.56. Letters: (line 1) N and E 0.067 and 0.055, (line 6) E of RES 0.043
<i>Text</i>	(1) (underneath text [2]) obliterated
	(2) (on top of text [1])
	(vac) Imp·Nerva 2 Traianus·Cae- sar·Aug·Germa- 4 nicus·pont·max· trib·pot·p·p·cos· 6 II·restituit·per T·Pomponium Bas- 8 sum leg·pro praetore 10 m XXII

Caput Viae

(Ancyra)

Date

(1) (?)

(2) AD 98(?) Traianus Augustus

Commentary

For the date, see the commentary above, no. 17(B)

20. Cüçük

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Çubuk 06-08-1
<i>Map</i>	Gerede 60-ş
<i>Location</i>	In a disused cemetery, SSE of the village; beside a <i>türbe</i> (a monumental tomb)
<i>Copy</i>	SM 1972; DHF 14.viii.1974. DHF squeeze (photo., Pl. 7.2.7 [p. 337]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 06. Ankara 67, Cüçük (= B/W Neg.: Squ. M/15.01 and 18.15)
<i>Publication</i>	RRMAM 2, 1. 120 (notice only)
<i>Description</i>	A simple cylinder. Broken above. Grey limestone. Top flat. Letters: slightly worn
<i>Dimensions</i>	Ht 1.01; diam. 0.44-0.48. Letters: (line 5) E 0.052, T of ITV 0.042

<i>Text</i>	[Imp Nerva Traia]-
2	ṇus·Caes̄ar·Aug·
	Germaniçus·pon-
4	t·max·trib·pot·p·p·
	cos·II·restituit
6	per·T·Pomponium
	Bassum·leg·pro
8	praetore

XXIII

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 98(?) Traianus Augustus
<i>Commentary</i>	For the date, see the commentary above, no. 17(B)

21. Ömercik

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Çubuk 06-08-0
<i>Map</i>	Gerede 60-§
<i>Location</i>	In a cemetery, on E side of the village
<i>Copy</i>	DHF 23.ix.1975. DHF photo. (Pl. 7.1.6 [p. 307]) in BIAA
<i>BIAA Collections: Squeeze and Photographs</i>	Stone: (1) B/W Neg.: DHF R/75/07.12
<i>Publication</i>	RRMAM 2, 1. 166 (notice only)
<i>Description</i>	(?) Milestone, in the form of a simple cylinder. Broken above. Grey limestone
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

22. Akkuzulu 1

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Çubuk 06-08-0
<i>Map</i>	Çankırı 61-§
<i>Location</i>	In the village; at the house (no. 97) of Mehmet Kırık
<i>Copy</i>	Anlağan June 1968; seen by RPH, SM and DHF 26.vi.1971 and copied by DHF 23.iv.1975. SM photo. (Pl. 7.1.7 [p. 308]). DHF squeeze (photo., Pl. 7.2.8 [p. 337]) and photos in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 54, Akkuzulu 1 (= B/W Neg.: Squ. M/18.13-14) Stone: (1) B/W Neg.: DHF 35/71/01.05-08 (2) Col. Slide: DHF 079. 27-28
<i>Publication</i>	Anlağan 1968, 6 and Pl. 17 Habicht 1971, 96 (text of Anlağan) Mitchell 1973, 73 (text RPH, SM and DHF 1971) French 1980, 719 no. 15 (text DHF 1975) RRMAM 2, 1. 086 (notice only) Mitchell 1993, 122 and Fig. 22 (photo. of the milestone)
<i>Description</i>	A simple cylinder. Complete. Grey limestone. Top flat; in centre: a boss. Letters: very slightly worn
<i>Dimensions</i>	Ht 1.82; diam. 0.58. Letters: (line 1) P 0.055, (line 6) P 0.04

<i>Text</i>	Imp Caesari
2	divi Traiani Par<t>hi-
	ci f divi Nervae nepoti
4	Traiano Hadriano
	Aug pont max tr pot VI
6	cos III per A /L/arçium
	Mace/d/onem leg Aug
8	pr (vac) pr (vac) m (vac) I

κς' <XX>ΙΙΙΙΙ

line 2: for **Par(t)hi-**, cp. 02. Alacaatlı line 2
 line 3: ligature **NE** (twice)
 line 5: ligature **NT**
 line 6: **IARCIVM** (lapis)
 line 7: **MACECONEM** (lapis); ligature **NE**
 line 9: **KSIIIIII**

Caput Viae (Ancyra)
Date AD 121/122, 10.xii-09.xii Hadrianus Augustus

23(A). Akkuzulu 2

Province, Sub-Province + Admin. Code Ankara, Çubuk 06-08-0
Map Çankırı 61-s
Location In an old cemetery, c. 2 km W of the village
Copy DHF 25.ix.1975. DHF photo. in BIAA
BIAA Collections: Squeeze and Stone Photographs
 Stone: (1) B/W Neg.: DHF R/75/08.01-04
Publication RRMAM 2, 1. 087 (notice only)
Description A simple cylinder. Broken above. Hard, grey limestone
Dimensions Ht (vis.) 1.33; diam. 0.50

Text No visible inscription

23(B). Akkuzulu 3

Province, Sub-Province + Admin. Code and Map and Location As 22(A)
Copy DHF 25.ix.1975. DHF squeeze (drawing, Fig. 6.2.13 [p. 380]) and photo.
 (Pl. 7.1.8 [p. 337]). in BIAA. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 06. Ankara 56, Akkuzulu 3
 Stone: (1) B/W Neg.: DHF R/75/08.05-08
Publication RRMAM 2, 1. 088 (notice only)
Description A simple cylinder. Roughly shaped. Complete. Grey limestone. Top flat.
 Surface and letters: severely worn
Dimensions Ht (vis.) 1.50; diam. 0.47. Letters: (line 6) **R** 0.054, (line 9) **E** 0.045

<i>Text</i>	Imp Ne[rva]
2	Traianu[s] C[ae]-
	sar Aug Germ[a]-
4	nicus po[nt max]
	trib pot p[p] [cos II]
6	restitui[t per]
	T·Pompon[ium]
8	Bassum [leg pro]
	praeto[re]
10	[-]

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	AD 98(?) Traianus <i>Augustus</i>
<i>Commentary</i>	For the date, see the commentary above, no. 17(B)

24. Koyunbaba

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Kalecik 06-13-2
<i>Map</i>	Çankırı 62-r
<i>Location</i>	At a field boundary, c. 3.75 km NW of the village
<i>Copy</i>	DHF 06.x.1974. DHF photo. in BIAA
<i>BIAA Collections: Squeeze and Photograph</i>	Stone: (1) B/W Neg.: DHF R/75/08.05-06
<i>Publication</i>	RRMAM 2, 1. 156 (notice only)
<i>Description</i>	(?) Milestone, in the form of a simple cylinder. Broken above. Grey limestone
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

25. Şemseddin

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Kalecik 06-13-2
<i>Map</i>	Çankırı 62-r
<i>Location</i>	Now buried in the foundations of a mill, c. 1.5 km SW of the village, according to the owner [of the mill]; not verified (DHF visit 13.ix.1974)
<i>Copy</i>	Anderson [1898]. The stone has not been examined by DHF. Text here of CIL (Anderson) (facsimile of the printed text, Fig. 6.1.6 [p. 264])
<i>Publication</i>	CIL 3. 14184 ⁵⁸ (text from Anderson) French 1976a, 52 (notice only) RRMAM 2, 1. 175 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	Imp Caesari
2	divi Tr[ai]ani Par-
	thici f d[ivi] Nervae
4	[n]epoti Traiano
	[Had]riano Aug pont
6	max tri pot IV cos III
	[per] A Larchi[u]m Ma-
8	[ced]onem leg Aug
	[p]r̄ pr m
10	(vac) XXXX
	(vac) μ'

line 3: ligature **TH, NE**

line 5: ligature **NT**

line 8: ligature **NE**

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 119/120, 10.xii-09.xii Hadrianus <i>Augustus</i>

26. Kınık

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Kalecik 06-13-1
<i>Map</i>	Çankırı 63-r
<i>Location</i>	In the village cemetery, on N side of the village şose, c. ½ km NW of the village
<i>Copy</i>	DHF 27.xi.1974. No photo.
<i>Publication</i>	RRMAM 2, 1. 155 (notice only)
<i>Description</i>	A simple cylinder. Broken above. Hard, blue-grey limestone. Very worn.
<i>Dimensions</i>	Ht (vis.) 1.30; diam. (top) 0.33
<i>Text</i>	No visible inscription

[27. Mart

<i>Province, Sub-Province + Admin. Code</i>	Çankırı, Şabanözü 18-08-0
<i>Map</i>	Çankırı 63-p
<i>Location</i>	In the village, according to von Flottwell. Present whereabouts not established (DHF visit 27.xi.1974).
<i>Copy</i>	Kannenberg 1893
<i>Publication</i>	von Flottwell 1895, 42 and Fig. (text of Kannenberg); CIL 3. 13646 (text of Kannenberg); Magie 1950, 2, 1082 n.32 (notice only); French 1976a, 53 (notice only); RRMAM 2, 1. 318 (notice only); Mitchell and French 2012, 178 no. 31 (text and illustration)

The drawing in a letter (dated 7 January 1894) sent to the Königliche Akademie, Berlin, by von Flottwell (information from Stephen Mitchell) indicates that the stone takes the form of a square altar with mouldings above and below the shaft – hence, a dedication (to an unknown 3rd century Emperor by a provincial governor), not a milestone as hitherto (RRMAM 2, 1. 318) claimed.]

28. Yukarı Yanlar

<i>Province, Sub-Province + Admin. Code</i>	Çankırı, Eldivan 18-02-0
<i>Map</i>	Çankırı 64-ö
<i>Location</i>	In the village, at the house owned by Ahmet Kefli. Brought from Türlü Tepe Mevkii, c. 2 km NE of the village. Found in bull-dozing operations June 1987. Probably (as revealed by the bulldozer) <i>in situ</i> . Now in the Archaeological Museum, Çankırı [Inv. no. 2.1.88]
<i>Copy</i>	DHF 04.ix.1987. DHF squeeze in BIAA. Photos of Tuğrul Çakar in BIAA. Text here from DHF squeeze (photos, Pls 7.2.9-10 [pp. 338-339])
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 18. Çankırı 01, Yukarı Yanlar (= B/W Neg.: Squ. M/18.08-12) Stone: (1) B/W Neg.: BIAA (Tuğrul Çakar)
<i>Publication</i>	French 1988a, 275 (notice only) French 1991b, 81 and Figs 7-8 AE 1991. 1498 (text of French 1991) Conti 2004, 189 no. 4 (comment on text [5])
<i>Description</i>	A simple cylinder. Broken below. Hard, grey limestone. Top flat. Very slightly tapering shaft. Letters: no wear on text (1), considerable wear on texts (4)-(6); (text 4) I for L

Dimensions throughout
 Ht (ex.) 1.10; diam. (top) 0.39. Letters: (text 2) (line 1) **P** 0.091, (line 5)
P 0.052; (text 3) (line 2) **P** 0.045, (line 6) **E** 0.032; (text 5) **E** 0.066; (text 6)
 (line 2) **E** 0.039

Text (1) (underneath text [2])
 lost

(2) (vac) **Imp**
 2 **Cæsari divi**
T[rai]anji Par-
 4 **thici f divi Ner-**
vae nepoti Tra-
 6 **iano Hadria-**
no Aug p m t p V[I]
 8 **p p cos III pe[r A]**
Larciu[m Mace]-
 10 **don[em leg Aug]**
 [pr pr]
 12 [-]

line 4: ligature **NE**
 line 5: ligature **NE**
 line 12: [mp V] ?

(3) (underneath text [4])
 lost

(4) (on the l. of text [2])

	B E DD nn	(sic)
2	Imp Caes C Aur Va[]	
	Diocletiano p e in Aug	(sic)
4	et Imp Caes M Aur Val	
	Maximiano p f in Aug	(sic)
6	et Fl Val Constantio	
	et Gal Val Maximiano	
8	n[o]biliss Caess	
	mil p	
10	Aur Prisci⟨a⟩nus v p praes	
	pro[v P]ont d n /m/ q eor[u]m	

line 1: **BE = BF = B(onae) F(ortunae)**
 line 11: **dNNQEOR[V]M = d(evotus) n(umini) /m/(aiestati)q(ue)**
eor[u]m

(5) (on the top, and on the l., of text [2] and on the top of text [4])

	Imp Cæs
2	[- - -] lijanus
	[- - - -] stus

lines 2-3: [Fl Cl Iulia]nus | [p f Augu]s(tus) (ed. pr.) but “Die Abkürzung Augus. ist für Julian sonst nicht bezeugt” (Conti l.c.); [Fl Cl Iu]lianu[s] | [p f Augu]stus (?)

(6) (on the top, and on the l., of text [2] and on the top of text [4] and text [5])

	DD nn	
2	Valentiniani	(sic)
	et Valenti Augg	
4	et Gratiano Aug	

Caput Viae (Gangra Germanicopolis)

Date (1) (?)

(2) AD 121/122, 10.xii-09.xii(?) Hadrianus *Augustus*

(3) (?)

(4) AD 293, 21.v(?)-305, 01.v Diocletianus and Maximianus *Augusti* with Constantius I and Galerius *Caesares*

(5) (?) Iulianus *Augustus* AD 361, 03.xi-363, 26/27.vi

(6) AD 364, 28.iii-367, 24.viii Valentianus I and Valens *Augustus*, then 367, 24.viii-375, 17.xi Gratianus added

Comment (Text [5]): “Die erhaltene Titulatur (das S der Zeile 2 könnte auch *s(emper)* bedeuten, oder, korrekter, *[Augustu]s*) und das Ende des Namens könnten auf fast alle Kaiser des 4. Jh. zutreffen” (Conti l.c.)

D. PER CAPPADOCIAM IN PONTUM ET BITHYNIAM**D.1 ANCYRA per territorium Amasiae (- Amisus)****29(A). Akyurt 1, form. Ravlı**

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Çubuk 06-08-1
<i>Map</i>	Gerede 60-t
<i>Location</i>	In the village of Buğduz, beside the mosque. Formerly in Ravlı (now re-named Akyurt)
<i>Copy</i>	Kannenberg 1893; Macpherson 1953; DHF 19.ix.1975. Macpherson squeeze in the Faculty of Classics, Cambridge (Box IWM VIII no. 180); DHF squeeze in BIAA. No photo. Text here from DHF squeeze (drawing, Fig. 6.2.14 [p. 280]) and from von Flottwell illustration (facsimile, Fig. 6.1.7 [p. 264])
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 67, Buğduz (= Akyurt 1)
<i>Publication</i>	von Flottwell 1895, 42 (text of Kannenberg) CIL 3. 13645 (text of Kannenberg) Bittel 1942a, 16 (notice) Macpherson 1954, 118 no. 17 Macpherson 1958, 180 no. 251 Bosch 1967, 148 no. 122 (text of Kannenberg) RRMAM 2, 1. 089 (notice only)
<i>Description</i>	A simple cylinder. Broken above, below, behind and on both sides. Grey limestone. Surface smoothed. Letters: slightly worn
<i>Dimensions</i>	Ht 1.91; diam. 0.65. Letters: (line 1) R 0.056, (line 2) R 0.047

<i>Text</i>	[Imp Ca]esar[i divi]	
2	[Traia]n <i>i</i> Par[thici]	(sic)
	[f divi N]erva[e nepo]-	
4	[ti Tr]ajan[o Hadr]-	
	[iano]·Au[g [pont]	
6	[max] tri·p[ot VI]	(sic)
	[cos III p]er·A·[Larci]-	
8	[um Ma]ced[onem]	
	[leg Au]g·p[ro pr]	
10	[X]X[-]	

line 2: **NI** (Macpherson)

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 121/122(?) Hadrianus Augustus
<i>Comment</i>	Kannenberg's text was improved by Macpherson. My version does not substantially differ from Macpherson's, although there are minor divergences in the reconstruction of line-endings. For line 6, cp. 25. Şemseddin line 6 tri pot IV cos III and 30. Kalabağ lines 5, 6 tri l pot IV cos III , but cf. 02. Alacaatlı line 6 tri pot VI cos III

29(B). Akyurt 2, form. Ravlı

<i>Province, Sub-Province + Admin. Code and Map</i>	As 29(A)
<i>Provenance</i>	Formerly in a house on the W side of the village; afterwards at the <i>Belediye</i> . Now in the Roman Baths, Ankara [<i>etüdliik</i> ; no Inv. no.]
<i>Copy</i>	SM 1972; DHF 18.ix.1975. DHF squeeze in BIAA. No photo. Text here from DHF squeeze (photo., Pl. 7.2.11 [p. 339])
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 45, Akyurt 2 (= B/W Neg.: Squ. M/18.07)
<i>Publication</i>	RRMAM 2, 1. 090 (notice only)
<i>Description</i>	A simple cylinder. Surface smoothed. Broken above, below and behind. Grey limestone. Letters: (lines 7-8) very slightly worn; (lines 4-6) deliberately erased
<i>Dimensions</i>	Ht (ex.) 0.37; diam. (est.) 0.45. Letters: (line 7) E 0.027

<i>Text</i>	[Imp Caes L Sept]
2	[Severus Pius]
	[Pertinax Aug]
4	[[Arab Adiab P[arth]]]
	[[max pontif·m[ax tr p]]]
6	[[VI imp XI cos [II pp]]]
	p/r/ocos·et Imp C[aes]
8	[M Aur An]toninu[s]
	[Aug et L Septimius]
10	[Geta Caesar]
	[restituerunt]

line 7: ΡΑΟCΟS (lapis)

lines 8-11: for the restorations, see 49(B). Dambasan 2

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	AD 197/198, 10.xii-09.xii Sept. Severus and Caracalla <i>Augusti</i> [with Geta (? name erased)]

30. Kalabağ

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Çubuk 06-08-1
<i>Map</i>	Cankırı 61-t
<i>Location</i>	“Broken up c. 1945 and the pieces thrown into the foundations of the new mosque”, according to villagers; not verified (DHF visit 19.ix.1975)
<i>Copy</i>	Bittel 1939. The stone has not been examined by DHF. Text here of Bittel 1942a
<i>Publication</i>	Bittel 1942a, 16 and 17 n.26 Bittel 1942b, 84 (notice) AE 1946. 178 (text from Bittel) Macpherson 1954, 113 n.3 and 120 (notice) Bosch 1967, 147 no. 118 (text of Bittel) RRMAM 2, 1. 149 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	Imp Caesari divi
2	Traiani Parthici f di-
	vi Nervae nepoti
4	Traiano Hadriano
	Aug pont max tri-
6	pot IV cos III per
	A Larcium Macedo-
8	nem leg Aug pr pr m
	(vac) XX Σ'

Caput Viae (Ancyra)
Date AD 119/120, 10.xii-09.xii Hadrianus *Augustus*

31. Elecik

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Kalecik 06-13-2
<i>Map</i>	Çankırı 62-§
<i>Location</i>	Formerly at the village mosque. Present whereabouts not established (DHF visit 18.ix.1975)
<i>Copy</i>	Anderson [1898]. The stone has not been examined by DHF. Text here of CIL (Anderson) (facsimile of the printed text, Fig. 6.1.8 [p. 264])
<i>Publication</i>	CIL 3. 14184 ⁵⁶ (text from Anderson) Bittel 1942a, 16 and 17 n.27 (notice) Bosch 1967, 91 no. 93 (text of Anderson) RRMAM 2, 1. 131 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	- - - -
2	[- - - - res]-
	[tituit per T Pomp]-
4	[onium] Bassum leg
	(vac) [p]ro p[r]aetore
6	(vac) XXVI

Caput Viae (Ancyra)
Date (?)AD 97 or 98 Nerva *Augustus* or Traianus *Augustus*
Commentary The text can be dated to the reign either of Nerva or of Traianus on the basis of the governor's name.

32(A). Çiftlik 1

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Kalecik 06-13-2
<i>Map</i>	Çankırı 63-§
<i>Provenance</i>	In the village, in front of the house (no. 28) of Ali Rıza Karabulut. Now in the Roman Baths, Ankara [Inv. no. 169.5.76, previously 2.1.76]
<i>Copy</i>	Anderson [1898]; DHF 18.ix.1975. Anderson's text published in CIL is reproduced here, Fig. 6.1.9 [p. 264]). DHF squeeze (drawing, Fig. 6.2.15 [p. 280]) in BIAA. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 73, Çiftlik 1

<i>Publication</i>	CIL 3. 14184 ⁵⁷ (text from Anderson) Bittel 1942a, 17 (notice) Bosch 1967, 91 no. 94 (text of CIL [Anderson]) RRMAM 2, 1. 125 (notice only)
<i>Description</i>	A simple cylinder. Broken above and below. Grey limestone. Slightly tapering shaft. Letters: worn
<i>Dimensions</i>	Ht 0.80; diam. 0.66. Letters: (line 1) E 0.043
<i>Text</i>	Imp·Nerva·Tra- 2 ianus Caesar·Aug Germanicus·pon- 4 t (vac) if·max·trib·pot p·p·cos·II·restitu- 6 it·per·T·Pom·po- nium·Bassum 8 [leg] pro·pr· [-]

line 9: **XXVI** (CIL)

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	No date given in CIL; AD 98(?) Traianus <i>Augustus</i>
<i>Commentary</i>	For the date, see the commentary above, no. 17(B)

32(B). Çiftlik 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 32(A)
<i>Location</i>	In the village; in front of the house (no. 22) of Ahmet Türkmen
<i>Copy</i>	Anderson [1898]; DHF 18.ix.1975. DHF squeeze (photo., Pl. 7.2.12 [p. 341]) in BIAA. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 74, Çiftlik 2 (= B/W Neg.: Squ. M/18.05-06)
<i>Publication</i>	CIL 3. 14184 ⁵⁵ (text from Anderson) Bittel 1942a, 16 (notice) Bosch 1967, 91 no. 95 (text of CIL [Anderson]) RRMAM 2, 1. 126 (notice only)
<i>Description</i>	A simple cylinder. (?) Complete. Grey limestone. Top flat. Inscribed surface smoothed. Letters: slightly worn
<i>Dimensions</i>	Ht 0.90; diam. 0.49. Letters: (line 1) P 0.04, (line 5) P of POM 0.032
<i>Text</i>	Imp·Nerva·Traianus· 2 Caesar·Aug·Germani- cus·pontif·max·trib·pot· 4 p·p·cos·II·restituit·per·T· Pomponium·Bassum· 6 leg·pro praetore (vac) XXXV
<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	No date given in CIL; AD 98(?) Traianus <i>Augustus</i>

Commentary According to Kienast (1996, 123), Traianus began his COS II on AD 01 January 98 but had ended his TR P (I) on 09 December 97: an apparent anomaly, therefore, if the TRP was indeed correctly inscribed. He took the title *pater patriae* in “Spätherbst” 98 (Kienast).

33(A). Kalecik 1

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Kalecik 06-13-0
<i>Map</i>	Çankırı 63-t
<i>Location</i>	“Dans le cimetière” (Perrot et al.). Present whereabouts not established (DHF visit 10.ix.1975); perhaps built into NE corner of the Pazaryeri Cami (DHF 10.ix.1975)
<i>Copy</i>	Perrot 30 October 1861. The stone has not been examined by DHF. Text here of CIL (Perrot)
<i>Publication</i>	Henzen 1862, 66, 67 (copy from Perrot) Perrot 1867, 111 Le Bas and Waddington 1870, 2, 428 no. 1805a (text of Perrot) Perrot et al. 1872, 286 no. 148 CIL 3. 309 (text of Perrot) and 6898 (add. Perrot) Mommsen 1884a, 35 no. 71 (text of Perrot) Bittel 1942a, 17 (notice) Bosch 1967, 91 no. 96 (text of Perrot) RRMAM 2, 1. 150 (notice only)
<i>Description</i>	Not given
<i>Dimensions</i>	“Lettres 0 ^m ,045” (Perrot et al. 1872)

<i>Text</i>	Imp·Nerva{e}·Traia-
2	nus·Caesar·Aug·Ger-
	mani[cus p]untifex
4	max·trib·pot·p·p·cos·II
	restituit·per·[T]·Pom-
6	ponium [Bas]sum [leg]
	pro praetore m [p]
8	(vac) XXX
	(vac) VIII
10	(vac) I

lines 0/1: [Imp] | **divi·Nervae·[f]·Traia** (Perrot 1861)

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	“p.C. 98/99” (CIL); AD 98(?) Traianus Augustus
<i>Commentary</i>	For the date, see the commentary above, no. 32(B)

33(B). Kalecik 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 33(A)
<i>Location</i>	“In the Armenian burial-ground” (Hamilton). Present whereabouts not established (DHF visit 10.ix.1975)
<i>Copy</i>	Texier 1833-37; Hamilton 31 August, 1836; Mordtmann (A. D.) 1858 (see CIL 3. 771); Perrot 30 October 1861. The stone has not been examined by DHF. Text here of CIL (Hamilton, Perrot and Mordtmann) (the printed text of

<i>Publication</i>	Hamilton is reproduced here, Fig. 6.1.10 [p. 264]) Texier 1839-49, 1, 190 Hamilton 1842, 1, 413 no. 99 and 2, 416 no. 99 Henzen 1862, 67 (copy of Perrot) Le Bas and Waddington 1870, 2, 428 no. 1806 (text of Hamilton and of Perrot) Perrot et al. 1872, 1, 286 n.1 (improvements to Hamilton's text, lines 6-7) CIL 3. 310 (texts of Hamilton, Perrot and Mordtmann) Bittel 1942a, 17 (text not given) Bosch 1967, 148 no. 121 (text of Perrot and of Le Bas and Waddington from CIL) RRMAM 2, 1. 151 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	Imp·Caesari
2	divi·Traiani·Parthi-
	ci·f·divi·Nervae·nepoti
4	Traiano·Hadriano
	Aug·pont·max·tr·p·VI
6	cos·III·per·A·Larcium
	Macedon<e>m·leg·Aug
8	pr·pr·m·p
	XXXV

NB. The stop-marks between words (printed in CIL) were not recorded either by Texier or by Hamilton

- line 1: **Caesar** (Perrot)
- line 5: ligature **NT**
- line 7: **Macedon<e>m** (Texier and Hamilton)
- line 8: **m·[p]** (Hamilton and Perrot , thence CIL); **m p** (Texier)

A full summary of the text-variations in the copies of Hamilton, Perrot and Mordtmann is given (by Mommsen) in CIL.

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 121/122, 10.xii-09.xii Hadrianus Augustus

34. İskilip

<i>Province, Sub-Province + Admin. Code</i>	Çorum, İskilip 19-03-0
<i>Map</i>	Osmancık 72-m
<i>Location</i>	“Built into a bridge over the stream which flows through the town” (Anderson). Now set up in the Municipal tea-garden at the town-centre
<i>Copy</i>	Hirschfeld (?1882); Anderson 02.vi.1899; DHF 14.vii.1977. DHF photo. (Pl. 7.1.9 [p. 308]) and squeeze (photo., Pl. 7.2.13 [p. 340]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 19. Çorum 94, İskilip (= B/W Neg.: Squ. M/18.03-04) Stone: B/W Neg.: DHF R/77/10.12
<i>Publication</i>	Mommsen 1884a, 39 no. 81 (text from Hirschfeld)

CIL 3. 6897 (text of Hirschfeld)
 ILS 2. 5840 (text of CIL [Hirschfeld])
 St. Pont. 1 (Anderson), 3 and n.1 (notice only)
 French 1980, 717 no. 11 (text of CIL [Hirschfield])
 RRMAM 2, 1. 342 (notice only)

Description A simple cylinder. Complete. Pale limestone. Inscribed surface finely smoothed. Letters: very slightly worn
Dimensions Ht 1.45; diam. (top) 0.48. Letters: (line 1) **P** 0.055, (line 8) **P** 0.08

Text

[I]mp·Nerva·Caes·
2 Aug·pontif·max·
trib·potest·cos·III
4 p·p·restituit per
Pomponium
6 Bassum leg·
Aug·pro·pr·
8 mil·p·LXXX
(vac) π'

line 3: horizontal bar over the numeral
 lines 8-9: horizontal bar over the numerals

Caput Viae (Gangra Germanicopolis)
Date AD 97, 01.i-17.ix Nerva *Augustus*
Commentary Nerva began his COS III on AD 01 January 97 and ended his TR P (I) on 17 September 97.

F. IN CAPPADOCIAM

F.2 ANCYRA (- Amasia)

35. Ankara, Siteler

<i>Province, Sub-Province + Admin. Code</i>	Ankara 06-00-0										
<i>Map</i>	Ankara 59-ii										
<i>Provenance</i>	Not known. Now in the Roman Baths, Ankara [Inv. no. 113.504.99]										
<i>Copy</i>	DHF 09.iii.1974. DHF squeeze (drawing, Fig. 6.2.16 [p. 281], and photo., Pl. 7.2.14 [p. 341]) and photo. in BIAA. Text here from DHF squeeze										
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 99, Siteler (= B/W Neg.: Squ. M/17.14-15 and 18.01-02) Stone: B/W Neg.: DHF 35/73/07.10										
<i>Publication</i>	RRMAM 2, 1. 107 (notice only) French 2003, 186 no. 73 (text, commentary and photo.) AE 2006. 1483 (text of French 2003)										
<i>Description</i>	A simple cylinder and base. Broken at top left. Grey limestone. Top flat. Roughly squared base. Letters: slightly worn										
<i>Dimensions</i>	Ht 2.16; diam. 0.50. Letters: (line 1) E 0.076, (line 2) E 0.052, (line 6) E of PER 0.047										
<i>Text</i>	<table style="margin-left: 20px;"> <tr><td>[I]mp Nerva</td></tr> <tr><td>Traianus·Cae-</td></tr> <tr><td>sar·Aug·G(e)rma-</td></tr> <tr><td>4 nicus·pont·max·</td></tr> <tr><td>trib·pot·p·p·cos·II</td></tr> <tr><td>restituit·per</td></tr> <tr><td>T·Pompon[i]um</td></tr> <tr><td>8 Bassum leg pro</td></tr> <tr><td>praetore</td></tr> <tr><td>(vac) III (vac)</td></tr> </table>	[I]mp Nerva	Traianus·Cae-	sar·Aug·G(e)rma-	4 nicus·pont·max·	trib·pot·p·p·cos·II	restituit·per	T·Pompon[i]um	8 Bassum leg pro	praetore	(vac) III (vac)
[I]mp Nerva											
Traianus·Cae-											
sar·Aug·G(e)rma-											
4 nicus·pont·max·											
trib·pot·p·p·cos·II											
restituit·per											
T·Pompon[i]um											
8 Bassum leg pro											
praetore											
(vac) III (vac)											

line 5: horizontal bar over the numeral

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 98(?) Traianus Augustus
<i>Commentary</i>	According to Kienast (1996, 123), Traianus began his COS II on AD 01 January 98 but had ended his TR P (I) on 09 December 97: an apparent anomaly, therefore, if the TRP was indeed correctly inscribed. He took the title <i>pater patriae</i> in "Spätherbst" 98 (Kienast).

36. Kayas

<i>Province, Sub-Province + Admin. Code</i>	Ankara 06-00-0
<i>Map</i>	Ankara 60-ii
<i>Location</i>	"Kayaş, bahçe. In cemetery to east" (Macpherson quoting Calder 1911). Present whereabouts not established (DHF visit 16.ix.1975)
<i>Copy</i>	Calder 1910. The stone has not been examined by DHF. Text here of Calder 1911 <i>apud</i> Macpherson
<i>Publication</i>	Calder 1911, (page not numbered) no. 2

<i>Description</i>	Macpherson 1954, 117 no. 13 (text of Calder)
<i>Dimensions</i>	Macpherson 1958, 184 (text of Calder)
	RRMAM 2, 1. 154 (notice only)
	“On a small thin milestone” (Macpherson 1954)

<i>Text</i>	Imp Caes M [Aur]
2	Severo [[Alexand]]-
	[[ro]] pio fel in-
4	victo Aug trib
	pot II cos I
6	m p
	[-]

line 1: **Imp Caes[ar]i** [M Aur] (Calder); **Imp Caes M** [Aur] (DHF), cp.
the initial line of 37. Ortaköy and ll. 2-3 of 119(A). Ahlatlibel 1
line 5: (?) **pot II cos I** [p p], cp. 49(C). Haydarbeyli 3

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	AD 222/223, 10.xii/09.xii Severus Alexander <i>Augustus</i>

37. Ortaköy

<i>Province, Sub-Province + Admin. Code</i>	Ankara 06-00-0
<i>Map</i>	Ankara 60-ü
<i>Location</i>	“In the cemetery” (Sterrett). Present whereabouts not established (DHF visit 16.ix.1975)
<i>Copy</i>	Barth 1858; Sterrett 11 September, 1884. The text published by Sterrett is reproduced here, Fig. 6.1.11 [p. 264]). The stone has not been examined by DHF. Text here of CIL (Barth; Sterrett)
<i>Publication</i>	CIL 3. 311 (text of Barth from Mordtmann) Sterrett 1883-84, 321 no. 378 CIL 3. 6901 (text of Sterrett) Bittel 1942a, 18 (notice) Bosch 1967, 335 no. 274 (text of CIL [Barth] and of Sterrett) RRMAM 2, 1. 165 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	Imp Caes M Au[r]
2	Severo [Alexand]-
	ro pio fel in-
4	victo Aug trib
	pot·II cos I
6	(vac) m p
	(vac) [-]

line 2: ? an erasure, [[Alexand]], cp. 119(A). Ahlatlibel 1 line 5
line 5: (?) **pot·II cos I** [p p], cp. 49(C). Haydarbeyli 3

Caput Viae [Ancyra]
Date AD 222/223, 10.xii/09.xii Severus Alexander *Augustus*
Commentary It is perhaps legitimate to ask whether or not these two milestones (nos 36 and 37) of Severus Alexander may be one and the same. Possibly, in error, the “cemetery” at Kayaş has been confused with the “cemetery” at Ortaköy. The two villages, Kayaş and Ortaköy, are only 6.5 km apart.

38(A). Hasanoğlan 1

Province, Sub-Province + Admin. Code Ankara, Elmadağ 06-10-0
Map Keskin 61-u
Location In the village; in front of the mosque at SE corner of the courtyard
Copy Macpherson 1953; DHF 16.ix.1975. Macpherson squeeze in the Faculty of Classics, Cambridge (Box IWM VI no. 143 [H2]; DHF squeeze (photo., Pl. 7.2.15 [p. 341]) in BIAA. No DHF photo. Texts here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
Squeeze: 06. Ankara 81, Hasanoğlan 1 (= B/W Neg.: Squ. M/17.10-13)
Publication Macpherson 1954, 115 no. 8 and Pl.10 no. 2
Macpherson 1958, 177 no. 245
McCrumb and Woodhead 1961, 136 no. 417 (text of Macpherson 1954)
French 1980, 718 no. 14 and map 3 (site no. 21)
RRMAM 2, 1. 143 (notice only)
Description A simple cylinder. Complete. Grey limestone. Top flat. Letters: worn
Dimensions Ht (vis.) 2.15; diam. c. 0.60. Letters: (text 1) (line 7) **E** of **DIAE** 0.057, (line 10) **T** of **STR** 0.073; (text 2) (line 1) **E** 0.056, (line 4) **E** of **PER** 0.056

Text (1) (underneath, and below, text [2])
(vac) [Imp Caesar]
[divi Vespasi]āni
[f Domitianus] Āu[g]
4 [pont max trib pot]
[p p cos VIII imp II]
[per A Caesennium]
[Gall]ū[m]·leg·Aug·pr·pr·vias
8 provinciar·Galat·Cappadociae·
Ponti·Pisidiaē·Paphlagoniae·
Lycaoniaē·Armeniae·Mino-
ris (vac)
12 (vac) stravit (vac)
[XXII]

lines 1-6: restorations *exempli gratia*

(2) (on the top of, and above, text [1])
Imp·Nerva Traianus
2 **Caes<a>r Aug German<i>**cus
ponti max trib·pot·p p cos II (sic)
4 **restituit·per·Pomponium**
Bassum·leg·pro praetore

6 ab Ancyra XXII νβ'

line 1: {IMP} at the end of the line (Macpherson) = **NI** of text (1) line 2
 line 3: **cos II; cos III** (Macpherson 1954)

<i>Caput Viae</i>	Ancyra
<i>Date</i>	(1) AD 81 or 82 Titus or Domitianus (2) AD 98 (?) Traianus <i>Augustus</i>
<i>Commentary</i>	For the date of text (2), see the commentary above, no. 35

38(B). Hasanoğlan 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 38(A)
<i>Location</i>	In the village; at the İlköğretim Okulu
<i>Copy</i>	(?) Dr Nimet Dinçer (Prof. Dr Nimet Özgürç) and Doc. Azra Erhat 1943; Macpherson 1953; DHF 16.ix.1975. Macpherson squeeze in the Faculty of Classics, Cambridge (Box IWM VI no. 143 and 144 [H3]); DHF squeeze (drawing, Fig. 6.2.17 [p. 281]) in BIAA. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 82, Hasanoğlan 2
<i>Publication</i>	Rohde 1943/44, 807 (notice of Dinçer and Erhat copies at Hasanoğlan) Macpherson 1954, 116 no. 9 Macpherson 1958, 177 no. 246 RRMAM 2, 1. 144 (notice only)
<i>Description</i>	A simple cylinder. Broken above. Grey limestone. Letters: worn
<i>Dimensions</i>	Ht (vis.) 1.54; diam. c. 0.60. Letters: (lines 3 and 6) E 0.05

<i>Text</i>	[Imp Nerva]
2	Traian[us C]aes[a]r]
	Aug·Germanicus·ponti
4	max·trib·pot·p·p·cos II
	restituit per Pompo-
6	nium Bassum leg·pro
	praetore ab Ancyra
8	XXVI kΞÄ

line 2: not read by Macpherson 1954
 line 4: **f max** (Macpherson 1954); horizontal bar above **PP** and **II**
 line 5: **Pompon** (Macpherson 1954)

<i>Caput Viae</i>	Ancyra
<i>Date</i>	AD 98 (?) Traianus <i>Augustus</i>
<i>Commentary</i>	For the date, see the commentary above, no. 35

38(C). Hasanoğlan 3

<i>Province, Sub-Province + Admin. Code and Map</i>	As 38(A)
<i>Location</i>	In the village; at the İlköğretim Okulu
<i>Copy</i>	Dr Nimet Dinçer (Prof. Dr Nimet Özgürç) and Doc. Azra Erhat 1943;

Macpherson 1953; DHF 16.ix.1975. Macpherson squeeze in the Faculty of Classics, Cambridge (Box IWM VI no. 143 and 144 [H4]); DHF squeeze in BIAA (photo., Pl. 7.2.16 [p. 342]). No DHF photo. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 06. Ankara 83, Hasanoğlan 3 (= B/W Neg.: Squ. M/17.07-09)

Publication Rohde 1943/44, 807 (notice of Dinçer and Erhat copy)

Macpherson 1954, 116 no. 10

Macpherson 1958, 178 no. 247

RRMAM 2, 1. 145 (notice only)

Description A simple cylinder. Complete. Grey limestone. Top flat. Letters: slightly worn

Dimensions Ht (vis.) 1.90; diam. 0.58. Letters: (line 1) **E** 0.042, (line 7) **E** of **NEM** 0.037

Text

	Imp Cæsari
2	divi Trai{i}ani Parthi-
	ci f ḋivi Nervae nepoti
4	Traiano Hadriano
	Aug pont max tr pot VI
6	cos III per A Larcium
	Mac<e>donem leg Aug
8	pr (vac) pr (vac) mi
	XXVI ξει'

(sic)

line 2: ligature **TH**

line 3: ligature **NE** (twice)

line 5: ligature **NT**

line 7: **Macedonem** (Macpherson 1954); ligature **NE**

line 8: **pr pr M** (Macpherson 1954)

Caput Viae (Ancyra)
Date AD 121/122, 10.xii-09.xii Hadrianus *Augustus*

38(D). Hasanoğlan 4

Province, Sub-Province + Admin. Code and Map As 38(A)

Location In the village; in front of the mosque, at NE corner of the courtyard

Copy Dr Nimet Dinçer (Prof. Dr Nimet Özgürç) and Doc. Azra Erhat 1943;

Macpherson 1953; DHF 16.ix.1975. Macpherson squeeze in the Faculty of Classics, Cambridge (IWM Box VI no. 143 and 144 [H4]); DHF squeeze (drawing, Fig. 6.2.18 [p. 281]) in BIAA. No DHF photo. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 06. Ankara 84, Hasanoğlan 4

Publication Rohde 1943/44, 807 (notice of Dinçer and Erhat copy)

Macpherson 1954, 116 no. 11 and Pl.10 no. 3

Macpherson 1958, 178 no. 248

RRMAM 2, 1. 146 (notice only)

Description A simple cylinder. Complete. Grey limestone. Top flat. Letters: very slightly worn

Dimensions Ht (vis.) 2.13; diam. 0.65. Letters: (line 1) **E** 0.053, (line 6) **E** 0.042

Text

2	Imp Caesa/r/[i]
4	divi Trai<ani> Parthi-
6	ci f /d/ivi Nervae nepoti
8	Traiano Hadriano
	Aug pont max tr pot VI
	cos III per A Larcium
	Macedonem leg Aug
	pr·pr /m/i
	XXIIII ȝð'

line 1: **CAESAP** (lapis)

line 2: ligature **TH**

line 3: **CIFCIVI** (lapis); ligature **NE** in **NEPOTI** (twice)

line 5: ligature **NT**

line 7: ligature **NE**

line 8: **pr pr M** (Macpherson 1954); **PRPRHI** (lapis), **HI** for **mi(lia)**

Caput Viae (Ancyra)
Date AD 121/122, 10.xii-09.xii Hadrianus

39(A). Elmadağ 1, form. Asi Yozgat

Province, Sub-Province + Admin. Code Ankara, Elmadağ 06-10-0
Map Keskin 62-ü
Location In the village; in front of the Yenipınar Cami
Copy Calder 1910; DHF 16.ix.1975. DHF squeeze (photo., Pl. 7.2.17 [p. 342]) in BIAA. No DHF photo. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
Squeeze: 06. Ankara 77, Elmadağ 1 (= B/W Neg.: Squ. M/17.05-06)
Publication Calder 1911, (page not numbered) no. 5
Macpherson 1954, 118 no. 14 (text of Calder)
Macpherson 1958, 185 (top) (text of Calder)
RRMAM 2, 1. 132 (notice only)
Description A simple cylinder. Broken above and behind. Grey limestone. Top flat; round tenon under base. Letters: slightly worn
Dimensions Ht (max.) 2.11; diam. 0.64. Letters: (line 1) **E** 0.05, (line 6) **E** 0.045, (line 7) **E** of **NEM** 0.036

Text

2	Imp Cæsari
4	divi·Traiani Parthi-
6	ci f divi·Nervae nepo
8	Traiano Had/r/iano
	Aug·pont·max tr pot VI
	cos·III per·A·Larcium
	Macedonem·leg·Aug
	pr (vac) pr (vac) mi
	XIX ȝθ'

lines 1-4: not seen by Calder, here bracketed by Macpherson 1954
 line 2: ligature **TH**
 line 3: ligature **NE** (twice)
 line 4: **HADPIANO** (lapis)
 line 5: ligature **NT**; horizontal bar over the numeral
 line 5: [max tr pot VI] (Calder *apud* Macpherson 1954)
 line 6: **Larci[um]** (Calder *apud* Macpherson 1954)
 line 7: ligature **NE**
 line 8: **p[r] p[r] M P** (Calder *apud* Macpherson 1954)
 line 9: **H** for **M**

Caput Viae (Ancyra)
Date AD 121/122, 10.xii-09.xii Hadrianus *Augustus*

39(B). Elmadağ 2, form. Asi Yozgat

Province, Sub-Province + Admin. Code and Map As 39(A)
Location Not given. Present whereabouts not established (DHF visits 16 and 17.ix.1975)
Copy Calder 1910. The stone has not been examined by DHF. Text here of Macpherson 1954
Publication Calder 1911, (page not numbered) no. 6
 Macpherson 1954, 118 no. 15 (text of Calder)
 Macpherson 1958, 185 (bottom) (text of Calder)
Description RRMAM 2, 1. 133 (notice only)
Dimensions “Milestone broken above” (Macpherson 1954)

<i>Text</i>	[Imp Caesari]
2	[divi Traiani Parthici f]
	[divi Nervae nepoti]
4	[Traiano Hadriano]
	[Aug pont max tr pot VI]
6	cos III per A Larcium
	Macedonem leg Aug
8	pr pr m p
	XXV ηε'

Caput Viae (Ancyra)
Date AD 121/122, 10.xii-09.xii(?) Hadrianus *Augustus*
Commentary The text can be dated to the reign of Hadrianus on the basis of the governor's name.

39(C). Elmadağ 3, form. Asi Yozgat

Province, Sub-Province + Admin. Code and Map As 39(A)
Location Not given. Present whereabouts not established (DHF visits 16 and 17.ix.1975)
Copy Calder 1910. The stone has not been examined by DHF. Text here of

Publication Macpherson 1954
 Calder 1911, (page not numbered) no. 7
 Macpherson 1954, 118 no. 16 (text of Calder)
 Macpherson 1958, 185 (middle) (text of Calder)
 RRMAM 2, 1. 134 (notice only)

Description & Dimensions Not given

Text [Imp Caesari]
 2 **divi Traiani Parthi-**
ci f divi Nervae nepoti
 4 **Traiano Hadriano**
Aug pont max tr pot VI
 6 **cos III per A Larcium**
Macedonem leg Aug
 8 **pr pr m p**
XXVII ηζ'

Caput Viae (Ancyra)
Date AD 121/122, 10.xii-09.xii Hadrianus Augustus

40. Sungurlu

Province, Sub-Province + Admin. Code Çorum, Sungurlu 19-08-0
Map Çorum 71-§
Location “Il est”, dit le correspondant de notre confrère, ‘situé dans un quartier de Soungourlu qu’on appelle Bach-Pynar” (Cagnat). Now in the Çorum Museum [Inv. no. 6.500.68]
Copy Text sent (? date) to Perrot from a “correspondant de notre confrère” (Cagnat); DHF 10.x.1974. DHF squeeze (drawing, Fig. 6.2.19 [p. 281]) and photo. (Pl. 7.1.10 [p. 308]) in BIAA. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 19. Çorum 135, Sungurlu
 Stone: (1) B/W Neg.: DHF R/74/17.08
Publication Cagnat 1903a, 193 (text from Perrot)
 AE 1903. 261 (text of Perrot *apud* Cagnat)
 Anderson 1910, 164 n.4 (notice)
 French 1976a, 53 (notice only)
 RRMAM 2, 1. 352 (notice only)
Description A simple cylinder. Complete. Grey limestone. Irregular oval in section. Top flat. Letters: worn to very worn
Dimensions Ht 1.31; wi. (front) 0.52; depth (side) 0.45. Letters: (line 1) **P** 0.063, (lines 2 and 6) **E** 0.045

Text (vac) **Imp**
 2 [Nerva C]æsar•Aug
pont•max•trib•potest
 4 **cos•III•p•p•restituit•per**
Pomponium•Bassum
 6 **leg•pro•pr**
(v) **m** [XVIII] (v) **ηζ'**

line 7: **m** for **m**(ilia)

Caput Viae (Ad Fines Ancyrae)
Date AD 97, 01.i-17.ix Nerva Augustus
Commentary According to Kienast (1996, 120), Nerva began his COS III on AD 01 January 97 and ended his TR P (I) on 17 September 97.

41. Cevheri, form. Merkepli

Province, Sub-Province + Admin. Code Çorum, Sungurlu 19-08-0
Map Çorum 72-ş
Location “ . . . située dans une vallée à dix pas de la route qui conduit du village de Mérképli à Sungurlu” (Cagnat); on the N bank of the Digi Deresi; c. 2 km W of the village, on N side of the track to Sungurlu. Now in the Çorum Museum [Inv. no. 29.1.87]
Copy Text (? date) from Perrot, “à qui on l'avait communiqué” (Cagnat); DHF 11.ix.1983. DHF squeeze (drawing, Fig. 6.2.20 [p. 282]) and photos (Pl. 7.1.11 [p. 309]) in BIAA. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 19. Çorum 30, Cevheri
 Stone: (1) B/W Neg.: DHF M/83/10.14-15 and 11.01-02
 (2) Col. Slide: DHF 240.05-06
Publication Cagnat 1903b, 169-170 (text from Perrot)
 AE 1903, (p.) 48 (notice)
 Bittel 1957, 92 no. 1b (notice)
 Loriot 1978, 81 no. 5 (text of Perrot *apud* Cagnat)
 French 1984d, 123 and Fig. 4
 RRMAM 2, 1. 326 (notice only)
 Christol and Loriot 1993, 217-218 (citation of text and of DHF l.c. Fig. 4)
Description A simple cylinder. Complete. Hard, pale limestone. The shaft tapers sharply towards the top. Round tenon under base. Note the lunate E. Letters: worn
Dimensions Ht 1.68; diam. (base) 0.49; (tenon) ht 0.10; diam. 0.19. Letters: (line 1) **P** 0.046, (line 10) **P** 0.037

Text

4	[I]mp Caes M Antonio Gordiano Semproni- ano Romano Afri- cano seniori pio fe-
8	lici invic̄to Aug et Imp Caes M Anto- nio Gordiano Se- mproniano Ro-
12	mano (A)frikanī i- uniori pio felici i- nvict/o/ Aug domi- nis indulgentiss-
	(vac) imis
	(vac) mi p

(vac) **LE'**

lines 2, 11 and 12: **d** for **D**
 line 7: **Δ** for **D**
 line 11: **INVICTC** (lapis)
 line 14: ligature **MI**, **mi(lia)** **p(assuum)**

Caput Viae (Ad Fines Ancyrae)
Date AD 238, Jan(?) Gordianus I and Gordianus II *Augusti*

42. Demirşeyh

Province, Sub-Province + Admin. Code Çorum, Sungurlu 19-08-0
Map Çorum 73-§
Provenance In the village; used as support for the *musalla tas* (coffin-table) beside the village cemetery. Now in the Çorum Museum [Inv. no. 27.1.87]
Copy DHF 13.ix.1983. DHF squeeze (drawing, Fig. 6.2.21 [p. 282]) in BIAA.
 No photo. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 19. Çorum 72, Demirşeyh
Publication RRMAM 2, 1. 330 (notice only)
Description A simple cylinder. Chipped; left side of inscription lost. Now in two pieces. Hard, pale limestone. The shaft tapers slightly towards top. Inscription on a smoothed panel. Letters: slightly worn
Dimensions Ht 0.90 + 0.80 (top); diam. (base) 0.45. Letters: (line 1) **E** of **CAES** 0.046, (lines 5 and 6) **E** 0.056, (line 8) **E** 0.05

<i>Text</i>	(vac) [Imp]
	(vac) Ner̄va·Caes
	Aug·pontif·max·
4	trib·potest̄
	cos·III·p·p·re-
	stituit per
	Pomponium
8	[B]assum leg.
	[Au]g·pro pr·
	(vac)
	m[-]

line 5: horizontal bar over the numeral

Caput Viae [Ad Fines Ancyrae]
Date AD 97, 01.i-17.ix Nerva *Augustus*
Commentary According to Kienast (1996, 120), Nerva began his COS III on AD 01 January 97 and ended his TR P (I) on 17 September 97.

43. Hacılarhanı

Province, Sub-Province + Admin. Code Çorum, Sungurlu 19-08-0
Map Çorum 73-r

<i>Provenance</i>	Recovered in 1982 from the <i>TCK Şantiyesi</i> [Turkish State Highways work-yard] (c. 3 km NE of the village) by the Sungurlu Kaymakamı and the German Excavation at Boğazköy. Now in the Boğazköy Museum					
<i>Copy</i>	Bittel 1982; DHF 12.ix.1983. DHF squeeze (drawing, Fig. 6.2.22 [p. 282]) in BIAA. No DHF photo. Text here from DHF squeeze					
<i>BIAA Collections: Squeeze and Stone Photographs</i>						
Squeeze: 19. Çorum 93, Hacılarhanı						
<i>Publication</i>	Bittel 1985, 26-27 and Fig. 34 AE 1985. 814 (text of Bittel) RRMAM 2, 1. 340 (notice only)					
<i>Description</i>	A simple cylinder. Chipped above. Hard blue+white limestone. Irregular shape. Longitudinal fault on front. Inscription very worn, especially below. Letters: very worn					
<i>Dimensions</i>	Ht (vis.) 1.34; diam. 0.45. Letters: (line 2) E 0.05					
<i>Text</i>	(Bittel)	Imp Ca(e)s Tr 2 ebonio Gallo 4 (I)nvicto Aug oi P P constr(uxit) ST				
	(DHF)	Imp Caes Vibio T- 2 reboni(an)o Gallo [p f i]- nvicto Aug (vac) tri- 4 b pot p p cons procons [?] EST				
		line 5 et seqq.: (?) [milia r]est[ituta] [per - - -]				
<i>Caput Viae</i>	[Ad Fines Ancyrae]					
<i>Date</i>	AD 251, mid-June(?)–Aug.(?) Trebonianus Gallus <i>Augustus</i>					

F.3 ANCYRA - TAVIUM (- Zela - Neocaesaria)

44. Zincir

<i>Province, Sub-Province + Admin. Code</i>	Yozgat, Yerköy 66-08-1
<i>Map</i>	Yozgat 71-ü
<i>Location</i>	“ . . . in dem Dorf Zincir, das sich heute in Hof des Sadik Özayar befindet” (Strobel and Gerber)
<i>Copy</i>	Strobel (?)date. Text here of Strobel and Gerber
<i>Publication</i>	Strobel and Gerber 2007, 618 no. 2 and photo., Fig. 54 AE 2007. 1458 (text of Strobel and Gerber)
<i>Description</i>	“ . . . ein Meilensteinbruchstück aus rötlich-grauem Konglomeratgestein (»Konglomeratmarmor«) regelmäßig gearbeitete Säule ” (Strobel and Gerber)
<i>Dimensions</i>	“ . . . einen Durchmesser von 0,31 m und eine erhaltene Länge von 1,02 m. Die Buchstabenhöhe beträgt in Z 3-5 4,5 cm, der Zeilenabstand einheitlich 2 cm.” (Strobel and Gerber)
<i>Text</i>	[[- - -]] 2 [[- - -]] testāte 4 consu[1] p mil 6 (v) θ'
<i>Caput Viae</i>	(Tavium)
<i>Date</i>	Severus Alexander ? (Strobel and Gerber)

45(A). Büyük Nefes 1

<i>Province, Sub-Province + Admin. Code</i>	Yozgat, Yozgat 66-00-1
<i>Map</i>	Yozgat 73-ü
<i>Location</i>	“In a cemetery between Büyük Nefezkivei and Assar, and immediately W of the acropolis of Büyük Nefezkieve” (Sterrett). Presents whereabouts not established (DHF visits 16 and 17.ix.1975)
<i>Copy</i>	Sterrett 04 September, 1884. The stone has not been examined by DHF. Text here of CIL (Sterrett) (facsimile of Sterrett’s text, Fig. 6.1.12 [p. 264])
<i>Publication</i>	Sterrett 1883-84, 309 no. 356 Sterrett 1885, 43 no. 60 CIL 3. 6899 (text of Sterrett) Ramsay (W.M.) 1941, 94 no. 61 (text of Sterrett) Bittel 1942a, 6 (notice) Bittel 1955, 24 n.7 (notice) RRMAM 2, 1. 970 (notice only) Strobel in Strobel and Gerber 2003, 164 no. A 1a (text of Sterrett and in CIL) Strobel 2007, 1411 no. A 1 (text of Sterrett and in CIL)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	(vac) Imp
2	Nerva Caesar Au[g]

	4	pont max trib potest II	
	6	cos III p p restituit	
		per Pompon[iu]m	
		Bassum leg pro pr	
		(vac) p m I α'	(sic)

line 3: POTES VII (Sterrett)

Caput Viae (Tavium)
Date AD 97, 18.ix-09.xii Nerva Augustus

45(B). Büyük Nefes 2

Province, Sub-Province + Admin. Code As 45(A)
Map As 44(A)
Location “ . . . wurde im Jahre 2000 im Haus Nr. 84 in Büyük Nefes gefunden und in das Depot des Grabungshauses gebracht (Fundnr. BN 280)” (Strobel and Gerber)
Copy Strobel and Gerber (? date). Text here of Strobel and Gerber
Publication Strobel and Gerber 2007, 619 no. 3
Description AE 2007. 1459 (text of Strobel and Gerber)
Dimensions “Der aus einer Säulentrommel schräg, vermutlich einer natürlichen Bruchlinie folgend, herausgetrennte, oben und unten nur groß abgeschlangene Block aus rötlich-grauem Konglomeratmarmor . . . Nur an der Vorderseite ist noch der originale, gut geglättete Oberfläche der Säule vorhanden. Hier sind leicht schräg aufsteigend drei Zeilen ganz bzw. Teilweise erhalten” (Strobel and Gerber)
Text - - -
[- - -] N . . [- - -]
[- - Str] abonem [- -]
(vac)
(vac) α'

Caput Viae (Tavium)
Date AD 193-211 Septimius Severus, on the basis of the governor's name

45(C). Büyük Nefes 3

See below, 3.F.6 Tavium (- Melitene) / 3.F.7 Tavium (- Caesaria)

46. Bicikler

Province, Sub-Province + Admin. Code Yozgat, Yozgat 66-00-1
Map Yozgat 73-v
Location “Das Meilensteinfragment wurde am 31.7.2001 in Bicikler am Lesesteinrand eines Feldes direkt am nördlichen Dorfrand gefunden . . . ” (Strobel). Now in

	the courtyard of the Yozgat Museum
<i>Copy</i>	Strobel 2001. Text here of Strobel and Gerber
<i>Publication</i>	Strobel in Strobel and Gerber 2003, 167-168 no. A 3 and photo., Fig. 19
	AE 2003. 1711 (text of Strobel)
<i>Description</i>	Strobel 2007, 1413 no. A 3 and Fig. 3
	“Erhalten ist nur der obere, schrifttragende Teil der relativ kleinen Meilensäule, die unten direkt an der letzten Zeile abschlagen ist. Grauer basalt, relativ unebene, z. T. porige Oberfläche. . . . Die Schrift ist relativ grob und unregelmäßig.” (Strobel)
<i>Dimensions</i>	“Die Höhe des erhaltenen Teiles beträgt 0,64 m, der Durchmesser nur ca. 0,30 m.” (Strobel)

Text

	[Im]p Caes M
2	[Iul]io Philippo
	[p f] Aug p p et
4	nob Caes Iuli-
	o Philippo
6	p f
	μ β'

line 7: μ(ιλια)

<i>Caput Viae</i>	(Tavium)
<i>Date</i>	AD 244, July/Aug-247, July/Aug Philippus <i>Augustus</i> with Philippus <i>Caesar</i>

47. Eski Karaağıl

<i>Province, Sub-Province + Admin. Code</i>	Yozgat, Yozgat 66-00-1
<i>Map</i>	Yozgat 73-ü
<i>Location</i>	“Der Meilenstein wurde am 2.8.2001 südlich der Wüstung von Eski Karaağıl Köyü (nordnordöstlich von Dereçik) gefunden und zwar in Bachthal unterhalb des erhaltenen römischen Staßendammes der nördlichen Straßenroute Tavium-Ekkobriga-Ankara.” (Strobel)
<i>Copy</i>	Strobel 2001. Text here of Strobel and Gerber
<i>Publication</i>	Strobel in Strobel and Gerber 2003, 162-164 no. A 1 and Fig. 17
	AE 2003. 1708 (text of Strobel)
<i>Description</i>	Strobel 2007, 1409 no. A 1 and photo., Fig. 1
	“. . . ; aus metamorphem Kalkstein grau, weiß geädert. Erhaltungszustand gut” (Strobel)
<i>Dimensions</i>	“Gesamthöhe 2,05 m; Querschnitt etwas oval 0,60 x 0,54 m;” (Strobel)

Text

	Imp
2	Nerva Caesa[r Aug]
	pont maxim [trib potest II]
4	cos III p p restitu[it per]
	Pomponium B[assum]
6	leg propri (vac) (gap 10 cm)
	p m III

line 8: **p m** for **m p**

Caput Viae (Tavium)
Date AD 97, 18.ix-09.xii (?), Nerva Augustus

48. Körpeli

Province, Sub-Province + Admin. Code Yozgat, Yozgat 66-00-1
Map Yozgat 72-ü
Location “Dieser obere Teil eines Meilensteins wurde am 14.8.2001 in Körpeli an der rechten Seite der Hofeinfahrt des Kaplan Evi auf der Nordseite des Dorfplatzes gefunden” (Strobel)
Copy Strobel 2001-2002. Text here of Strobel and Gerber
Publication Strobel in Strobel and Gerber 2003, 168-169 no. A 4 and Fig. 20
Description AE 2003. 1712 (text of Strobel)
Dimensions Strobel 2007, 1414 no. A 4 and photo., Fig. 4
Text “Relativ dünne Meilensäule aus grauem Kalkstein, unten abschlagen. . . . Am rechten Rand der 1. Zeile sind arabische Zahlen sekundär eingemeißelt. Wenig oberhalb der 1 Zeile springt die Säule um 1,5 vor. Die Oberfläche ist grob gepickt und nur im Bereich der Inschrift feiner geglättet. Links vor den Zeilen des Inschriftfeldes ist die ursprünglich grob gepickte Oberfläche besonders stark ausgewaschen. Der Buchstabe A ist wie kursive A geschrieben, die Buchstabe L wie sonst die Abkürzung für Centurio. E ist durchgehend als rundes E ausgeführt” (Strobel).
Letters: lunate E
Dimensions “Erhaltene Höhe 0,58 m; Durchmesser 0,36m. Buchstabenhöhe 4-4,5 cm; ” (Strobel)

Text	Imp Caes L D-
2	omitiō Au-
4	reliano pi-
4	o fel Aug
6	[-]ā[- - -]
6	- - - -

Caput Viae (Tavium)
Date AD 270, Sept.-275, Sept./Oct. Aurelian Augustus

49(A). Haydarbeyli 1

Province, Sub-Province + Admin. Code Yozgat, Yozgat 66-00-1
Map Yozgat 72-u
Location In the village; at the Özpinar Çeşmesi
Copy DHF 03.vii.1977. DHF squeeze (drawing, Fig. 6.2.23 [p. 283]) and photo. (Pl. 7.1.12 [p. 309]) in BIAA. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
Squeeze: 66. Yozgat 05, Haydarbeyli 1
Stone: (1) B/W Neg.: DHF R/77/08.12
Publication RRMAM 2, 1. 976 (notice only)
Publication Strobel in Strobel and Gerber 2003, 177 no. B 6

<i>Description</i>	Strobel 2007, 1419 no. B 6 (notice only)
<i>Dimensions</i>	A simple cylinder. Complete. Hard, grey limestone. Top flat. Round tenon under base. Letters: very worn
	Ht 1.97; diam. (top) 0.62; (tenon) ht 0.18; diam. 0.52. Letters: (lines 1 and 6) P 0.06, (line 3) P of PON 0.05

<i>Text</i>	(vac) Imp
2	Nerva·Caesar·Aug
	pont·max·trib·p[-]
4	cos·III·p·p·restituit·per
	Pomponium·Bassum
6	leg·pro·pr·
	p·m X (vac) t'

line 7: **p m** for **m p**; horizontal bar over **X**

<i>Caput Viae</i>	(Tavium)
<i>Date</i>	AD 97, 01.i-17.ix (TR.P., COS III) [or AD 97, 18.ix-09.xii (= TR.P.II)] Nerva Augustus
<i>Commentary</i>	Nerva began his COS III on AD 01 January 97 and ended his TR P (I) on 17 September 97. His COS IV began on 01 January 98.

49(B). Haydarbeyli 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 49(A)
<i>Location</i>	In the village; at the house of Çelebi Aslanoğlu
<i>Copy</i>	DHF 03.vii.1977. DHF photos (Pl. 7.1.13-14 [p. 309]) and squeeze (photo., Pl. 7.2.18) [p. 343] in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 66. Yozgat 06, Haydarbeyli 2 (= B/W Neg.: Squ. M/17.01-04) Stone: (1) B/W Neg.: DHF R/77/08.10-11
<i>Publication</i>	French 1981, 168 (notice only) RRMAM 2, 1. 977 (notice only) Strobel in Strobel and Gerber 2003, 176 no. B 5 Strobel 2007, 1419 no. B 5
<i>Description</i>	A simple cylinder. (?) A re-used column. Broken above, below and rear. Hard, pink+white limestone. Surface smoothed. Letters: sharp and clear
<i>Dimensions</i>	Ht (ex.) 0.675; diam. (below) 0.315. Letters: (text 1) 0.015-20; (text 2) (line 8) E 0.06, (line 10) E 0.05, (line 11) E 0.065
<i>Text</i>	(1) (underneath and below text [1]) 7+ lines of tiny letters; not deciphered
	(2) (on face of shaft)
	[Imp Caes L Septi]- [mius Severus Pi]- [us Pertinax Aug] 4 [Arab Adiaben Pa]- [rthic max ponti]- flex m[ax t]rib pot

	VI·imp [XI cos] II·pi·p·	(sic)
8	proco[s et I]mp Cae (vac) - sar·Mar[cus] Aur An- tonin[us <Aug> e]t L·Septim- ius [[Geta]] [C]aes[ar] (vac)	
12	[restitu]erunt [per Attic]ium Str- [abonem le]g Aug[g pr pr] [-]	
<i>Caput Viae</i>	[Tavium]	
<i>Date</i>	(1) (?) (2) AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (the name Geta erased) <i>Caesar</i>	

49(C). Haydarbeyli 3

<i>Province, Sub-Province + Admin. Code and Map</i>	As 49(A)
<i>Provenance</i>	Brought from the village. Now in the Yozgat Museum [Inv. no. 291] “Im Jahre 2003 wurde bei der Räumung des alten Depots des Museums in Yozgat die Meilensäule wiedergefunden, die am 7.10.1982 vom Muhtar des Dorfes Haydarbeyli nach Abriss des alten Moschee in das Museum gebracht worden war (Inv. 291)” (Strobel and Gerber)
<i>Copy</i>	DHF 06.viii.1986. DHF squeeze (photo., Pl. 7.2.19 [p. 343]) in BIAA. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 66. Yozgat 07, Haydarbeyli 3 (= B/W Neg.: Squ. M/12.14-15)
<i>Publication</i>	French 1987a, 194 (notice only) Strobel and Gerber 2007, 617 no. 1 and photo., Fig. 53 AE 2007. 1457 (text of Strobel and Gerber)
<i>Description</i>	A simple cylinder. Re-used column. Complete. Hard, pink-white limestone. Top and bottom flat; square dowel hole in top. Letters: very slight wear
<i>Dimensions</i>	Ht 1.54; diam. (top) 0.31. Letters: (line 1) E 0.037, (line 6) E of ALE 0.04, (line 7) E 0.04

<i>Text</i>	Imp Caes divi	
	Severi nepos	
	divi Antonini	
4	magni filius	
	M·Aurel·Severus	
	Alexander pius	
	felix·Aug	
8	tribuniciae pō-	
	testatīs (vac) II	
	consul (vac) I	
	p·p mil (vac) p	
12	[?]	

lines 8-9: tribunicia | potestate C (Strobel and Gerber)
line 10: I om. Strobel and Gerber

Caput Viae [Tavium]
Date AD 222/223, 10.xii/09.xii Severus Alexander *Augustus*

50(A). Dambasan 1

Province, Sub-Province + Admin. Code Yozgat, Yozgat 66-00-1
Map Yozgat 73-u
Location “The stone is partly embedded in the ground in the cemetery” (Sterrett). Seen in this location by DHF (02.vii.1997). Seen in the courtyard of the village mosque by Strobel [NB On the basis of the photograph (Strobel Fig. 24), it seems that the milestone has been erected, in the courtyard of the village mosque, upside down]
Copy J. H. Haynes 05 September, 1884; DHF 02.vii.1977; Strobel 8.8.2002.
Haynes’ text published by Sterrett is reproduced here, Fig. 6.1.13 [p. 265]).
DHF squeeze (drawing, Fig. 6.2.24 [p. 283]) and photo. (Pl. 7.1.15 [p. 310]) in BIAA. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
Squeeze: 66. Yoxgat 03, Dambasan 1
Stone: (1) B/W Neg.: DHF R/77/08.05
Publication Sterrett 1883-84, 320 no. 377 (text of Haynes)
CIL 3. 6899a (text of Haynes *apud* Sterrett)
Ramsay (W.M.) 1941, 95 no. 64 (text of Haynes *apud* Sterrett)
RRMAM 2, 1. 973 (notice only)
Strobel in Strobel and Gerber 2003, 175-176 no. B 4 and photo., Fig. 24
(revision, from a copy and photo., of Sterrett’s text)
AE 2003. 1716 (revised text of Strobel, with additional comments on ll. 2 and 3) (“On ne voit pas pourquoi D. French propose de le dater d’Hadrien” *editor*)
Strobel 2007, 1418 no. B 4 and photo., Fig. 8
Description A simple cylinder. Round tenon under base. Complete. Hard, pale limestone.
Letters: very worn
Dimensions Ht 1.98; diam. (top) 0.40; (tenon) ht 0.13; diam. 0.30. Letters: (line 1) **I** 0.031, (line 2) **I** of **DI** 0.045

Text

		(vac) Imp
2	Ca/e/sari divi·	
	T̄raiani f·divi·	
4	Nerva·nepote	(sic)
	T̄raiano·Hadriano	
6	Aug pont·ma[x]	
	[trib p]o[t VI]	

restoration of text after line 7:

		8 [cos III]
		[per A Larcium]
		[Macedonem]

12 [leg Aug pr pr]
[m p -]

line 2: **CAISAR** (lapis)
line 6: ligature **NT**

Caput Viae [Tavium]
Date (?)AD 121/122 Hadrianus Augustus
Commentary For the text of Sterrett, see the facsimile (Fig. 6.1.13 [p. 265]). Sterrett's text passed into CIL and thence to Ramsay (1941). The text given by Strobel follows the text of CIL; Strobel reads:

[- - -]ISSI[- - -]
[- - -]AVR[- - -]
[- - -].NVI[- - -]
[- - -]MENERO[- - -]
[- - -]O.A.[- - -]
[- - -].POS[- - -]
[- - -]O[- - -]

I believe that the letters recorded by Sterrett can be traced on my squeeze in approximately the same positions, as follows:

ISSI = IMP
CAISARDIVI
TRAIANIFDIVI
NERVAENEPOTE
TRAIANOHADRIA
NOAVCPONT Sterrett did not record the ligature NT
O

50(B). Dambasan 2

Province, Sub-Province + Admin. Code and Map As 50(A)

Location “In the cemetery” (CIL). Seen there by DHF (02.vii.1977). Now in the courtyard of the village mosque (Strobel)

Copy Anderson c. 08-12 June, 1899; DHF 02.vii.1977; Strobel 8.8.2002. DHF squeeze (drawing, Fig. 6.2.25 [p. 283], and photo. of lines 10-14, Pl. 7.2.20 [p. 344]) and photo. (Pl. 7.1.16 [p. 310]) in BIAA. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 66. Yozgat 04, Dambasan 2 (= B/W Neg.: Squ. M/03.11-13 and DHF M/85/10.09)

Stone: (1) B/W Neg.: DHF R/77/08.06

Publication CIL 3.14184⁴¹ (text from Anderson)

St. Pont. 1 (Anderson), 19 (notice)

Bittel 1942a, 8 (notice of CIL text)

Bittel 1942a, 8 (notice of CIE text);
Bittel 1955, 24 and n.7 (notice of CIL text).

	French 1981, 168-169 (Dambasan ‘1’)
	RRMAM 2, 1. 974 (notice only)
	Strobel in Strobel and Gerber 2003, 173-174 no. B 3 and photo., Fig. 23 (text from copy and photo.)
	AE 2003. 1715 (text of Strobel)
	Strobel 2007, 1417 no. B 3 and photo., Fig. 7
<i>Description</i>	A simple cylinder. Complete. Hard, pink+white limestone. The shaft tapers very slightly towards top. Letters: very worn
<i>Dimensions</i>	Ht 1.90; diam. (top) 0.47, (base) 0.50. Letters: (line 7) E of CAE 0.037
<i>Text</i>	(1) (underneath text [2]) slight traces
	(2) (on the top of text [1])
	[Imp Caes L] Septimius
	[Severus] Pius Pertinax
	Aug Arab Adiabenic
4	Parthic max ponti-
	fex m̄xim̄ trib pot
	VI imp XI cos·II·p·p·
	procos·et·Imp·Cae-
8	sar Marcus Aur Añ-
	toninus Augustus cos
	Parth·maxim
	[restitu]er[unt] SV
12	per Atticum Stra-
	bun̄em leg Aug(g) pr pr
	(vac) V
	(sic)

line 6: horizontal bar over the numerals

lines 9-11: **et P | Septimius Geta Caelsar** once inscribed under **cos I**

Parth maxim, cp. 72. Tilki Han

line 10: ligature **TH**

line 11: the final letters, **SV**, belong to text (1)

lines 12-13: [per L Petron]iu[m Velr]um (Anderson, thence CIL)

<i>Caput Viae</i>	(Tavium)
<i>Date</i>	(1) (?)
	(2) AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i>
<i>Commentary</i>	Anderson restored ll. 12-13 on the basis of the Severan text (at İncesu: RRMAM 3.4 [Pontus et Bithynia]. İncesu 2) which indubitably recorded the name of Petronius Verus (CIL 3. 14184 ³⁴). Strobel’s text confirms the revised reading (French 1981, 168) of the governor’s name on the Dambasan stone, not Petronius Verus (Anderson’s text, CIL 3. 14184 ⁴¹ , cited by Marek [1993, 73 n.505] and by Thomasson [2009, 1, 104 28.034]) but Atticius Strabo.

51(A). Karakeçili 1

Province, Sub-Province + Admin. Code

Corum, Sungurlu 19-08-1

<i>Map</i>	Çorum 73-t
<i>Provenance</i>	Brought from the village by the German Excavation at Boğazköy. Now in the Boğazköy Museum
<i>Copy</i>	Bittel 29 August, 1975; DHF in Boğazköy Museum 16.vii.1977. DHF squeeze (drawing, Fig. 6.2.26 [p. 284]) and photo. (Pl. 7.1.17 [p. 311]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	19. Çorum 99, Karakeçili 1
	Stone: (1) B/W Neg.: DHF R/77/11.07
<i>Publication</i>	French 1981, 168 (notice only) Bittel 1985, 13 and Fig.16 AE 1985. 810 (text of Bittel) RRMAM 2, 1. 343 (notice only)
<i>Description</i>	A simple cylinder. Broken above. Hard, pink+white limestone. Letters: sharp and clear
<i>Dimensions</i>	Ht 1.03; diam. (top) 0.39. Letters: (line 4) E of LEG 0.042

<i>Text</i>	-----
	2 [- restitueru]-
	nt·per·Attic·Stra-
	4 bonem legatum
	Augg p/r/ p⟨r⟩
	6 (vac) m XIII
	(vac) IV'

line 3: [eru]n[t] (Bittel)
 line 5: AVGGPAP (lapis)
 line 6: horizontal bar over the numeral

<i>Caput Viae</i>	(Tavium)
<i>Date</i>	(?)AD 197/198 Sept. Severus and Caracalla <i>Augusti</i> with Geta <i>Caesar</i>
<i>Commentary</i>	The text can be dated to the reign of Septimius Severus on the basis of the governor's name.

51(B). Karakeçili 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 51(A)
<i>Provenance</i>	Found on 30.ix.1981 and brought from the village by the German Excavation at Boğazköy. Now in the Boğazköy Museum
<i>Copy</i>	Bittel 17 October, 1981; DHF in Boğazköy Museum 12.ix.1983. DHF squeeze (drawing, Fig. 6.2.27 [p. 284]) in BIAA. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 19. Çorum 98, Karakeçili 2
<i>Publication</i>	Bittel 1985, 14 and Fig. 18, a-b AE 1985. 811 (text of Bittel) RRMAM 2, 1. 344 (notice only)
<i>Description</i>	A simple cylinder. Broken below and lower right. Hard, blue+white limestone. Letters: slightly worn
<i>Dimensions</i>	Ht (ex.) 1.00; diam. 0.25. Letters: (line 2) E 0.05

<i>Text</i>	(vac) B F
	Imp Caes
	G Messio
4	Quinto
	Traian[o]
	Decio
	p fel A[ug]
8	(vac) NI
	(vac) II
	(vac) IY'

line 5: **Traian(o)** (Bittel)
 line 8: **A ?NI** (Bittel); the letters are both clear and undamaged; perhaps N is a malformed version of **M**, i.e. **MI**[LP]. The stone is broken immediately on the right of **I**.
 line 9: (?) [X]**II**[I]; there is perhaps a faint trace of **X** before **II**; the stone is broken immediately on the right of the second **I**.

<i>Caput Viae</i>	(Tavium)
<i>Date</i>	AD 249, Sept/Oct(?) - 250, May/June Traianus Decius <i>Augustus</i>
<i>Commentary</i>	It may be assumed that the stone was erected under Traianus Decius before his elder son became <i>Caesar</i> . Decius' elder son, Herennius Etruscus, is not named here; he was not elevated to <i>Caesar</i> before May/June, 250 according to Kienast (1996, 206).

51(C). Karakeçili 3

<i>Province, Sub-Province + Admin. Code and Map</i>	As 51(A)
<i>Provenance</i>	Formerly <i>in situ</i> , beside the Roman road; then rolled down into the <i>dere</i> below the Roman road. Brought to the Boğazköy Museum in autumn 1986 by the German Excavation at Boğazköy
<i>Copy</i>	DHF in Boğazköy Museum 09.vii.1987. DHF squeeze (drawing, Fig. 6.2.28 [p. 284]) and photo. (Pl. 7.1.18 [p. 311]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 19. Çorum 97, Karakeçili 3 Stone: (1) B/W Neg.: DHF M/87/11.05
<i>Publication</i>	French 1988a, 274 (notice only)
<i>Description</i>	A simple cylinder. Complete. Top roughly flat. The shaft tapers slightly towards top. Large, round tenon under base. Inscription on a prepared panel.
<i>Dimensions</i>	Letters: worn Ht 1.92; diam. (top) 0.64. Letters: (line 1) P 0.062, (line 5) P of PON 0.045

<i>Text</i>	(vac) Imp (vac)
2	Nerva·Caesar·Aug
	pont·max·trib·potest
4	cos·III·p·p·restituit·per
	Pomponium·Bassum
6	leg·pro·pr
	p (vac) m ·(vac) XIII·IY'

lines 4 and 7: horizontal bar over the numerals

<i>Caput Viae</i>	(Tavium)
<i>Date</i>	AD 97, 01.i-17.ix Nerva Augustus
<i>Commentary</i>	According to Kienast (1996, 120), Nerva began his COS III on AD 01 January 97 and ended his TR P (I) on 17 September 97.

52(A). Yazır 1

<i>Province, Sub-Province + Admin. Code</i>	Corum, Sungurlu 19-08-1
<i>Map</i>	Çorum 74-t
<i>Provenance</i>	Formerly in the cemetery at Yazır. Now in the Boğazköy Museum [Inv. no. 2.5.66]
<i>Copy</i>	Bittel September 1967; DHF in Boğazköy Museum 09.x.1974. DHF squeeze (drawing, Fig. 6.2.29 [p. 285]) and photo. (Pl. 7.1.19 [p. 311]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 19. Çorum 143, Yazır 1
	Stone: (1) B/W Neg.: DHF R/74/16.12
<i>Publication</i>	French 1981, 168 (notice only) Bittel 1985, 11-12 and Fig. 14, a-c AE 1985. 809 (text of Bittel) RRMAM 2, 1. 353 (notice only)
<i>Description</i>	A simple cylinder. Broken above right. Hard, pink+white limestone. Letters: worn
<i>Dimensions</i>	Ht (vis.) 0.88; diam. 0.40. Letters: (line 12) T 0.04

<i>Text</i>	(Bittel)
	[Imperator Caesar]
	[Septimius Severus Pertinax Augustus]
3	[Arabicus] (A)diab(enicus) [Parthicus ponti] fex·max·trib·pot·
	XI c(onsul?) p(at)er p(atriae) proco(nsul)
6	et·Imp·[Caesar]·Aur·Ant oninus·et·Septim
	(i)u(s) Comodus
9	Caesar·restitu erunt·per·Attic(ium) Strabonem·lega
12	tum·Aug(ustorum) (pro praetore) M XII

<i>(DHF)</i>	
	[Imp Caes L Sept]-
	[imius Severus]
	[Pius Pertinax Aug]
4	Arāb·Ādiāb·<Parthic max> pōnti- /f/ex·max·trib·pot·<VI> i[mp] XI·c[os II]·p·p·proco[s]

	et·Imp [C⟨aes⟩] M·Aur Ant-	
8	[o]ninus ⟨Aug⟩·et·Septim·	(sic)
	[[Geta]] Com/modu/s	(sic)
	Caesar·restitu-	
	erunt·per·Attic·	
12	Strabonem·lega-	
	tum·Augg p/r/ p⟨r⟩	
	(vac) m XII	
	(vac) τβ'	

line 5: **EEX** (lapis)

line 9: **COMOMDYS** (lapis)

line 13: **TVMAVGGPAP** (lapis)

lines 14 and 15: horizontal bar over the numerals

<i>Caput Viae</i>	(Tavium)
<i>Date</i>	L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with Septimius Geta (the name Geta erased) <i>Caesar</i> , (?) AD 197/198
<i>Commentary</i>	On the use of <i>Comomdys</i> (= Commodus) in line 9, see now Leschhorn on bronze coins of Geta at Tavium (1992, 324-325 “... könnte man an den Namen Commodus denken, der aber für Geta nirgends bezeugt ist, obwohl sich sein Vater Septimius Severus gelengentlich als Bruder des Commodus bezeichnete”; and 1993, 411). The coins in question are inscribed ΓΕΤΑΣ ΚΟΝ(?) (or ΚΟΜ) ΚΑΙΣΑΡ and ΓΕΤΑΣ·ΚΟΜ·ΚΕΣΑΡ·

52(B). Yazır 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 52(A)
<i>Location</i>	Brought from Findıklı to Yazır. Taken to the Boğazköy Museum [Inv. no. 2.2.66] in 1962
<i>Copy</i>	Bittel 10 November, 1962; DHF in Boğazköy Museum 09.x.1974. DHF squeeze (drawing, Fig. 6.2.30 [p. 285]) and photo. in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 19. Çorum 144, Yazır 2
	Stone: (1) B/W Neg.: DHF R/74/17.03
<i>Publication</i>	Bittel 1985, 10-11 and Fig.13, a-c AE 1985. 808 (text of Bittel) RRMAM 2, 1. 354 (notice only)
<i>Description</i>	A simple cylinder. Hard, pink+white limestone. Shaft tapers slightly towards top. Note the influence of Greek letters: lunate epsilon for E, the Γ-form S; note also the forwards tilted L. Surface and letters: worn
<i>Dimensions</i>	Ht (vis.) 1.66; diam. (top) 0.29. Letters: (line 9) T of ITU 0.04
<i>Text</i>	(1) (underneath text [2]) obliterated
	(2) (on the top of text [1]) (Bittel)

1	Imp Caesar
	[Divi] Severi nepo-
	s Divi Antonini
	filius M Aur[elius] A-
5	ntoninus Pius
	Felix Aug trib
	potest cos pro-
	cos pp rest-
9	ituit
	[v jia[s]
	MP

(DHF)

4	Imp Caes di-
	yi Seve/r/i nepo-
	s divi Antonini
8	filius M Aur A-
	ntoninus piu-
	s fel Aug trib
	potest cos pr-
	ocos p p res-
	[t]ituit
	(vac)
	(vac) ια'

- line 1: Δ for **D**
 line 2: Γ for **S**; SEVEPI (lapis)
 line 3: δ for **D**
 line 4: alteration of **A**
 line 7: **P** of **POT** is very thin

Caput Viae (Tavium)
Date (1) (?)
 (2) AD 218, 16.v-09.xii Elagabalus *Augustus*

53(A). Yekbaş 1

<i>Province, Sub-Province + Admin. Code</i>	Çorum, Sungurlu 19-08-1
<i>Map</i>	Çorum 74-t
<i>Provenance</i>	Found in 1981 by the German Excavation at Boğazköy. Now in the Boğazköy Museum
<i>Copy</i>	Bittel 18 October, 1981 and 09 September, 1983; DHF in Boğazköy Museum 12.ix.1983; Strobel (? date). DHF squeeze (drawing, Fig. 6.2.31 [p. 286]) in BIAA. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 19. Çorum 145, Yekbaş 1
<i>Publication</i>	Bittel 1985, 15-16 and Fig.19, a-c AE 1985. 812 (text of Bittel) RRMAM 2, 1. 355 (notice only) Strobel in Strobel and Gerber 2003, 166 (citation of Bittel's text)

<i>Description</i>	AE 2003. 1710 (text of Strobel)
<i>Dimensions</i>	A simple cylinder. Broken into two pieces. Hard, pale limestone. Inscription on a prepared panel. Letters: worn Ht (vis.) 1.70; diam. (top) 0.55. Letters: (line 1) E of CAE 0.053, (line 2) E of SEV 0.045
<i>Text</i>	(1) (underneath text [2]) lost
	(2) (on the top of text [1]) (Bittel)
	<p style="text-align: center;">Imp·Caes·L·Septimi-</p> <p style="text-align: center;">us Severus Pius Felix</p> <p style="text-align: center;">Aug·Arab·Adiaben(icus)</p> <p style="text-align: center;">Parthic·Max·ponti-</p> <p style="text-align: center;">5 fex maximus tr·pot·</p> <p style="text-align: center;">VII Imp·XI cos II pp</p> <p style="text-align: center;">procos et Imp·Cae-</p> <p style="text-align: center;">sar Marcus Aur·An-</p> <p style="text-align: center;">toninus et L·Septimi-</p> <p style="text-align: center;">10 us ////////////</p> <p style="text-align: center;">Caesar restitu(it)</p> <p style="text-align: center;">per Atticum</p> <p style="text-align: center;">Strabone(m) legatum</p> <p style="text-align: center;">A K</p>
	(DHF)
	<p style="text-align: center;">Imp Caes·L·Septimi-</p> <p style="text-align: center;">us Severus Pius Pertin</p> <p style="text-align: center;">Aug·Arab·Adiabenic</p> <p style="text-align: center;">4 Parthic max ponti-</p> <p style="text-align: center;">/f/ex maxim trib·pot</p> <p style="text-align: center;">VI imp·XI cos II p p</p> <p style="text-align: center;">(vac)</p> <p style="text-align: center;">procos et Imp Cae-</p> <p style="text-align: center;">8 sar Marcus Aur An-</p> <p style="text-align: center;">toninus <Aug>·et /L/ Septi<mi></p> <p style="text-align: center;">us [[Geta]] Com<m>odus</p> <p style="text-align: center;">Caesar restituerunt</p> <p style="text-align: center;">12 per Atticum</p> <p style="text-align: center;">Stra/b/one<m> legatum</p> <p style="text-align: center;">(vac)</p> <p style="text-align: center;">(vac) u</p> <p style="text-align: center;">(vac) x'</p>

line 5: **EEXMAXIMTRIBPOT** (lapis)

line 9: **TONINVSETISEPTI** (lapis)

line 13: **STRARONEM** (lapis)

line 14: **μ(iλια)**

<i>Caput Viae</i>	(Tavium)
<i>Date</i>	(1) ? (2) AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with Geta (name erased) <i>Caesar</i>
<i>Commentary</i>	On Com<m>odus in line 10, see comment above, 52(A). Yazır 1

53(B). Yekbaş 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 53(A)
<i>Location</i>	In the village; at the house of Şevket Koldemir, used as a post for the balcony. Provenance not known
<i>Copy</i>	DHF 29.vi.1986. DHF squeeze (drawing, Fig. 6.2.32 [p. 287]) in BIAA. No photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 19. Çorum 146, Yekbaş 2
<i>Publication</i>	French 1987a, 191 (notice only)
<i>Description</i>	A simple cylinder and plinth. Complete, but chipped and cut on face. Andesite. Top flat; shaft tapers slightly towards top; square, shaped base. Letters: worn at edge, lost in centre of inscription
<i>Dimensions</i>	Ht (top base) 1.66; diam. (top) 0.28. Letters: (line 6) M 0.045

<i>Text</i>	Imp
	[- - - -]
	[- - -] i ano
4	[- - -] IG
	[- - - -]
	[- - -] M
	[- - - -]
8	[- - - -]
	[- - - -]
	[- - - -] I
	(?) [- - - -]

<i>Caput Viae</i>	[Tavium]
<i>Date</i>	(?)

54(A). Kaymaz 1

<i>Province, Sub-Province + Admin. Code</i>	Çorum, Sungurlu 19-08-1
<i>Map</i>	Çorum 74-t
<i>Location</i>	“Village of Eskiypar, one hour (five miles) west of Alaja. Probably the ‘Alty Yapan’ of Kiepert’s map, , on the road from Sungurlu to Alaja (Etonea?)” (Garstang). Now in the village of Kaymaz; inside the house of Zeki Gürhan; c. 1937 brought from an old <i>mezarlık</i> (cemetery), Baş bağlı, c. 2 km NNW of Emirler and 3.5 km SSE of village on road to Emirler
<i>Copy</i>	Winckler 15 August, 1906; Bittel 04 September, 1956; DHF 16.vii.1977. DHF photo. (Pl. 7.1.20 [p. 311]) and squeeze (photo., Pl. 7.2.21 [p. 345]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	

<i>Publication</i>	Squeeze: 19. Çorum 103, Kaymaz 1 (= B/W Neg.: Squ. M/12.12-13) Stone: (1) B/W Neg.: DHF R/77/11.08 Garstang 1908, 9 (text of Winckler from Riggs) Bittel 1957, 90 no. 1a and Pl.11 AE 1961. 127 (notice of Bittel's text) Loriot 1978, 72 n.6 and 81 no. 6 (text of Winckler <i>ex</i> Riggs <i>apud</i> Garstang, and of Bittel) RRMAM 2, 1. 345 (notice only)
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. Top flat. Letters: worn
<i>Dimensions</i>	Ht (vis.) 1.62; diam. (top) 0.40. Letters: (line 1) T 0.047, (line 5) T of ET 0.037

<i>Text</i>	Imp Caes M Antonio 2 Gordiano Semproni- ano Rōmano Africa- 4 no seniori pio fel- i/ci/ invicto Aug et I- 6 mp (Caes M Antonio Gordiano - - - - - - - -)
-------------	---

line 5: **IOINVICTO** (lapis)

lines 6 et seqq.: not completed by stone-cutter; (?) text intended to be as
41. Cevheri

<i>Caput Viae</i>	[Tavium]
<i>Date</i>	AD 238 Gordianus I and (? Gordianus II) <i>Augusti</i>
<i>Commentary</i>	"It was Mr. Riggs who first kindly communicated to us the fact of this inscription, and a note from his pocket-book, in the train from Aleppo. The revised reading is due again to Professor Haverfield" (Garstang). Bittel (1957, 90) gives a detailed account of this episode wherein the copy of Winckler was transmogrified, apparently ("offenbar"), into a note from Riggs' pocket-book.

54(B). Kaymaz 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 54(A)
<i>Location</i>	In the village, outside the house of Zeki Gürhan. Said by the owner [of the house] to have been brought from the same <i>mezarlık</i> (cemetery), Bağbaşı NNW of Emirler, as 54(A).
<i>Copy</i>	Bittel 04 September, 1956; DHF 16.vii.1977. DHF squeeze (drawing, Fig. 6.2.33 [p. 287]) and photo. in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 19. Çorum 104, Kaymaz 2 Stone: (1) B/W Neg.: DHF R/77/11.09
<i>Publication</i>	Bittel 1957, 92 no. 2 AE 1961. 127 (notice of Bittel's text) RRMAM 2, 1. 346 (notice only)
<i>Description</i>	A simple cylinder. Broken on left, otherwise complete. Hard pink+white limestone. Top flat. Letters: slightly worn
<i>Dimensions</i>	Ht 1.56; diam. (top) 0.63. Letters: (line 1) I 0.062, (line 2) E of ER 0.047, E of

CAE 0.04, (line 4) E of RES 0.037

<i>Text</i>	(vac) Imp
2	[N]erva·Caesar·Aug
	[p]ont·max·trib·potest
4	[c]os·III·p·p·restituit·per
	[Po]mponium·Bassum
6	[leg] pro (vac) pr
	(vac) m·XXIII·xγ'

lines 4 and 7: horizontal bar over the numerals

line 7: **m** for **m**(ilia passuum)

a cross was incised below line 7 (? in early Byzantine period)

<i>Caput Viae</i>	(Tavium)
<i>Date</i>	AD 97, 01.i-17.ix Nerva Augustus
<i>Commentary</i>	According to Kienast (1996, 120), Nerva began his COS III on AD 01 January 97 and ended his TR P (I) on 17 September 97.

55. Gökçam

<i>Province, Sub-Province + Admin. Code</i>	Çorum, Sungurlu 19-08-0
<i>Map</i>	Çorum 73-ş
<i>Location</i>	In the village, in front of the house (no. 94) owned by Hüseyin Saçın. Brought from Assar Mevkii, c. 1 km below the village ('köy altı'), below the Ortaokul (which is situated on the S side of the main road).
<i>Copy</i>	DHF 10.x.1995. DHF squeeze and photo. (Pl. 7.1.21 [p. 312]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 19. Çorum 87, Gökçam
	Stone: (1) B/W Neg.: DHF M/95/03.07
	(2) Col. Slide: DHF 412.04-05
<i>Description</i>	A simple cylinder. Broken above, buried below. Hard, pale limestone. The shaft is straight. Letters: slightly worn
<i>Dimensions</i>	Ht (vis.) 0.86; diam. (top) 0.41. Letters: c. 0.025-30

<i>Text</i>	[Imp Caes L Septimius]
	[Severus Pius Pertinax]
	[Aug Arab Adiabenic]
4	[Parthic maxim p]on.
5	[tifex max] trib·pot
	VI·imp·XI·cos II·ppp·pro-
	cos·et·Imp Caesar Mar-
8	cus Aur Antoninus·⟨Aug⟩
	et L Septimius [[Geta]]
	Caesar restitue-
	runt·per Atticum
12	Strabonem leg·Aug
	pr pr.

mil. XXV
κε'

lines 1-4: restorations *exempli gratia*

56. Ekmekçi

<i>Province, Sub-Province + Admin. Code</i>	Çorum, Sungurlu 19-08-0
<i>Map</i>	Çorum 74-ş Bü. Ekmekci
<i>Location</i>	In the village, at the village mosque. Brought, c. 30 years ago (i.e. 1965), from 'İncegiriş' Mevkii, c. 3-4 km W of the village
<i>Copy</i>	DHF 10.x.1995. DHF squeeze and photos (Pl. 7.1.22-24 [pp. 312-313]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
Squeeze:	19. Çorum 16, Ekmekçi
Stone:	(1) B/W Neg.: DHF M/95/03.01-04 (2) Col. Slide: DHF 412.01-03
<i>Description</i>	A simple cylinder. Chipped at the top and scored by dragging. Hard, pale limestone. Top: flat; shaft: poorly shaped; under the base: a round tenon. The inscription is cut on a prepared surface, the edges of which are much wider than the area of the text (c. 0.25 on the l. of the Nervan text there is a ridge)
<i>Dimensions</i>	Ht (max.) 2.20, (tenon) 0.18; diam. (top) 0.62, (base) 0.62, (tenon) 0.42. Letters: (line 1) P of IMP 0.084, (line 2) E of NER 0.045, (line 7) X 0.05
<i>Text</i>	(1) (underneath text [2]) obliterated
	(2) (on top of text [1])
	(vac) Imp
2	Nerva·Caesar·Aug
	pont·max·trib potest
4	cos·III·p·p·restituit·per
	Pomponium·Bassum
6	leg pro·pr
	p·m·XXIIIX κη'

Caput Viae (Tavium)
Date AD 97, 01.i-17.ix Nerva Augustus
Commentary According to Kienast (1996, 120), Nerva began his COS III on AD 01 January 97 and ended his TR P (I) on 17 September 97.

57. Comar

Province, Sub-Province + Admin. Code Map Çorum, Alaca 19-01-0
Çorum 74-s

<i>Location</i>	In the village; at the house of Ahmet Güneş, beside and right of the entrance door															
<i>Copy</i>	Bittel 02 September, 1968; DHF 29.vi.1986. DHF squeeze (drawing, Fig. 6.2.34 [p. 287]) in BIAA. No DHF photo. Text here from DHF squeeze															
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 19. Çorum 32, Çomar															
<i>Publication</i>	Bittel 1985, 24 and Fig. 33 a-d AE 1985. 813 (text of Bittel) RRMAM 2, 1. 328 (notice only) French 1989a, 39 Christol and Loriot 1993, 217 (citation of Bittel text and the text in French 1989a)															
<i>Description</i>	A simple cylinder. (?) Complete. Hard, pale limestone. Shaft irregularly and unevenly shaped. Note the form of the letters A, E, F and L. Letters: worn															
<i>Dimensions</i>	Ht c. 1.50. Letters: (line 7) O and B of NOB 0.028 and 0.046															
<i>Text</i>	(Bittel) <table border="0"> <tr> <td style="vertical-align: top; padding-right: 20px;">5</td> <td>Imp Caes O Vero Maximi no Pio (fel)i c(i A)v(g) et Vero Ma ximo nobiliis</td> <td style="vertical-align: bottom;">(sic)</td> </tr> <tr> <td style="vertical-align: top; padding-right: 20px;">10</td> <td>imo Caesari PP Restitu(erunt) Per Licinniu m Cerenianum Leg Avg pr.pr.</td> <td></td> </tr> </table> (DHF) <table border="0"> <tr> <td style="vertical-align: top; padding-right: 20px;">4</td> <td>Imp Caes- ari G I Vero Maximi-</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 20px;">8</td> <td>no pio feli- ci Aug et G I Vero Ma- ximo nobilliss-</td> <td style="vertical-align: bottom;">(sic)</td> </tr> <tr> <td style="vertical-align: top; padding-right: 20px;">12</td> <td>imo Caesari re- sstitu- it per Licinniu- m Serenianum le- e Aug pr pr</td> <td style="vertical-align: bottom;">(sic)</td> </tr> </table>	5	Imp Caes O Vero Maximi no Pio (fel)i c(i A)v(g) et Vero Ma ximo nobiliis	(sic)	10	imo Caesari PP Restitu(erunt) Per Licinniu m Cerenianum Leg Avg pr.pr.		4	Imp Caes- ari G I Vero Maximi-		8	no pio feli- ci Aug et G I Vero Ma- ximo nobilliss-	(sic)	12	imo Caesari re- sstitu- it per Licinniu- m Serenianum le- e Aug pr pr	(sic)
5	Imp Caes O Vero Maximi no Pio (fel)i c(i A)v(g) et Vero Ma ximo nobiliis	(sic)														
10	imo Caesari PP Restitu(erunt) Per Licinniu m Cerenianum Leg Avg pr.pr.															
4	Imp Caes- ari G I Vero Maximi-															
8	no pio feli- ci Aug et G I Vero Ma- ximo nobilliss-	(sic)														
12	imo Caesari re- sstitu- it per Licinniu- m Serenianum le- e Aug pr pr	(sic)														
<i>Caput Viae</i>	[Tavium]															
<i>Date</i>	AD 236, 07.i/16.v-238, mid-April Maximinus <i>Augustus</i> with Maximus <i>Caesar</i>															

58(A). Eskyapar 1

Province, Sub-Province + Admin. Code Çorum, Alaca 19-01-0

<i>Map</i>	Çorum 75-§
<i>Provenance</i>	In the village. Now in Çorum Museum [Inv. no. 6.504.68]
<i>Copy</i>	Munro c. 17 August, 1899 (St. Pont. 3, 1: 20); DHF 10.x.1974. DHF squeeze (drawing, Fig. 6.2.35 [p. 288]) and photo. (Pl. 7.1.25 [p. 313]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 19. Çorum 76, Eskişapar 1
	Stone: (1) B/W Neg.: R/74/17.04-05
<i>Publication</i>	CIL 3. 14184 ⁴² (text from Munro) St. Pont. 1 (Anderson), 20 (notice) Bittel 1955, 24 (notice) French 1976a, 53 (notice only) RRMAM 2, 1. 334 (notice only) French 1989a, 38 AE 1989. 730 (notice of text in French 1989) Christol and Loriot 1993, 214 (citation of text and comment on the governor) Christol and Loriot 2001, 100 no. 7 (comment on the governor)
<i>Description</i>	A simple cylinder. Broken above. Grey limestone. Letters: very slightly worn
<i>Dimensions</i>	Ht (vis.) 1.06; diam. 0.54. Letters: (line 9) I of RESTIT 0.042, (line 10) E 0.047

Text :

	<u>Imp Caesar</u>	
	<u>pius felix</u>	
	<u>Aug M Aur</u>	
4	<u>Severus Alexan-</u>	
	<u>der nobillssim-</u>	(sic)
	<u>us Caesar viam</u>	
	<u>yetustate</u>	
8	<u>comla/p/sam</u>	(sic)
	<u>[r]estituit per</u>	
	<u>[A]ur Basileum·</u>	
	<u>[l]eg Aug pr pr</u>	
12	(vac) xy'	

line 8: **COMLAISAM** (lapis); cp. below, 61. Bolatçık, line 8

<i>Caput Viae</i>	(Tavium)
<i>Date</i>	AD 222 Severus Alexander
<i>Commentary</i>	For the date of this milestone, see Christol and Loriot (1993, 214)

58(B). Eskişapar 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 58(A)
<i>Provenance</i>	In the village; “Used as a gate-post” (Munro <i>apud</i> CIL). Seen there by DHF 23.viii.1984. Now at the Eskişapar dig house
<i>Copy</i>	Munro c. 17 August, 1899 (St. Pont. 3, 1, 20); DHF 23.viii.1984. DHF squeeze (drawing, Fig. 6.2.36 [p. 288]) and photo. in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 19. Çorum 77, Eskişapar 2

<i>Publication</i>	Stone: (2) Col. Slide: DHF Col. 244.38 CIL 3. 14184 ⁴³ (text from Munro) St. Pont. 1 (Anderson), 20 (notice) RRMAM 2, 1. 335 (notice only) French 1989a, 38, 39 AE 1989, 730 (text of French 1989) Christol and Loriot 1993, 219 (citation of text in CIL)
<i>Description</i>	A simple cylinder. Chipped at top and sides, otherwise complete. Hard, pale limestone. Top flat. Note the letter-forms: Γ for G and the lunate E . Letters: very worn
<i>Dimensions</i>	Ht (vis.) 1.07; diam. (mid.) 0.40. Letters: (line 6) E 0.05

<i>Text</i>	Imperat[ori] Coāesar(i) Treb- oni(an)o Gallo et	(sic)
4	[I]mper Coāesar(?) Vo-	(sic)
	/lu/siano [Au]-	
	[gu]stis per M	
	EUMΛAM	
8	[l]ega[tum Augg]	
	(vac) pr pr	

line 5: **SON** for **LU**

<i>Caput Viae</i>	[Tavium]
<i>Date</i>	AD 251, Aug.(?)–253, Aug.(?) Trebonianus Gallus and Volusianus <i>Augusti</i>
<i>Commentary</i>	I have made minor changes to the text published in the ed. pr.

59(A). Alaca 1

<i>Province, Sub-Province + Admin. Code</i>	Çorum, Alaca 19-01-0
<i>Map</i>	Çorum 75-s
<i>Location</i>	“Formerly exposed to view but now built face inwards into the bottom of a wall in the stream bed” (Anderson). Present whereabouts not established (DHF visit 10.vii.1987)
<i>Copy</i>	Anderson c. 09 June, 1899
<i>Publication</i>	St. Pont. 1 (Anderson), 21 (notice) RRMAM 2, 1. 320 (notice only)
<i>Description & Dimensions</i>	Not given
<i>Text</i>	Not given

59(B). Alaca 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 59(A)
<i>Location</i>	“Bei der Hüseyin Gazi Türbe (Şahmaspurtekkesi), rd. 3 km. südsüdwestlich von Alaca” (Bittel). Present whereabouts not established (DHF visit 10.vii.1987)
<i>Copy</i>	Bittel (?date). The stone has not been examined by DHF. Text here of Bittel
<i>Publication</i>	Bittel 1955, 22-23 and Pl. 3 no. 1

RRMAM 2, 1. 321 (notice only)

Description & Dimensions “Die aus grauem Kalkstein bestehende Saule ist noch 1.78 m. hoch. Die Buchstabenhöhe beträgt 4.5 cm., die der Zahlen 5.6 cm.” (Bittel)

<i>Text</i>	(vac) Imp (vac)
2	Nerva Caesar Aug
	pont max trib potest
4	cos III p p restituit per
	Pomponium Bassum
6	leg pro pr
	(v) p (v) ma XXVII κζ' (sic)

line 4: **cos II** (Bittel); **cos III** (Bittel photo.)line 7: **p m XXVII KZ** (Bittel); **p ma XXVII KZ** (Bittel photo.)*Caput Viae* (Tavium)*Date* AD 97, 01.i-17.ix Nerva Augustus*Commentary* According to Kienast (1996, 120), Nerva began his COS III on AD 01 January 97 and ended his TR P (I) on 17 September 97.

60. Akören

Province, Sub-Province + Admin. Code Çorum, Alaca 19-01-0*Map* Çorum 76-s*Location* In the village; at the corner of the house owned by Kemal Darıcılı*Copy* DHF 10.vii.1987. DHF photos (Pl. 7.1.26 [p. 313]) and squeeze (photo., Pl. 7.2.22 [p. 345]) in BIAA. Text here from DHF squeeze*BIAA Collections: Squeeze and Stone Photographs*

Squeeze: 19. Çorum 03, Akören (= B/W Neg.: Squ. M/12.10-11)

Stone: (1) B/W Neg.: DHF M/87/12.01

(2) Col. Slide: DHF 275.14-15

Publication French 1988a, 274 (notice only)*Description* A simple cylinder. Broken below. Hard, grey limestone. The shaft tapers slightly towards top. Letters: slightly worn*Dimensions* Ht 0.57; diam. (max.) 0.52. Letters: (line 1) **P** 0.083, (line 3) **R** 0.063

Text (1) (underneath texts [2] and [3])
 completely obliterated; above line 1 of text (2) can be seen the erasure of two lines

(2) (original Nervan text)

	(vac) Imp
2	[[Nerva]] Caes Au[g]
	[p]· max·trib·po [t cos III]
4	p p restitui [t per]
	[Pomponium Bassum]
6	[leg pr pr]

(3) (original Nervan text, re-cut)

(vac) **Imp**

2	Traiano Caes Au[g]
	[p]·max·trib·po [t cos III]
4	p p restitui [t per]
	[Pomponium Bassum]
6	[leg pr pr]

line 2: **Traiano** cut over **Nerva**

<i>Caput Viae</i>	[Tavium]
<i>Date</i>	(1) AD 97, 01.i-17.ix(?) Nerva
	(2) re-cut AD 98-100 Traianus Augustus

61. Çoprasık

<i>Province, Sub-Province + Admin. Code</i>	Corum, Alaca 19-01-0
<i>Map</i>	Çorum 77-ş
<i>Location</i>	At the house of Durak Gündoğan, on S side of Alaca-Zile road
<i>Copy</i>	DHF 15.vii.1987. DHF squeeze (drawing, Fig. 6.2.37 [p. 288]) in BIAA. No photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 19. Çorum 33, Çoprasık
<i>Description</i>	A simple cylinder. Hard, pale limestone. Top flat; the shaft is roughly shaped and tapers slightly towards top. Surface very worn. Letters: extremely worn
<i>Dimensions</i>	Ht 1.65; diam. (base) 0.56

<i>Text</i>	-----
	[- - -]FI(?)
	[- - - -]
4	[- - - -]
	[- -]LO[-]
	[ma]ximo PHE
	[-]ICI[- -]
8	P[- - -]
	[-]A procos

<i>Caput Viae</i>	[Tavium]
<i>Date</i>	(?)

62. Bolatçık

<i>Province, Sub-Province + Admin. Code</i>	Corum, Alaca 19-01-0
<i>Map</i>	Çorum 77-ş
<i>Location</i>	In the village; at the school
<i>Copy</i>	Süel (? date); DHF 07.viii.1989. DHF squeeze (photo., Pl. 7.2.23 [p. 346]) and photo. (Pl. 7.1.27 [p. 314]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 19. Çorum 17, Bolatçık (= B/W Neg.: Squ. M/12.07-08) Stone: (1) B/W Neg.: DHF M/89/14.03 (2) Col. Slide: DHF 303.18-19

<i>Publication</i>	Süel 1989, 344 (notice) French 1990a, 231 (notice) and Fig. 3
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. Top flat; the shaft tapers strongly to top; base flat. Inscribed surface roughly smoothed. Complete. Hard, pale limestone. Surface and letters: slightly worn Letters: broken-bar A and diagonal-bar L throughout; E but lunate E in AE (line 1), in TE (line 2) and in TE (line 7), (line 11) <i>delta</i> -form D, (line 8) <i>gamma</i> -form S
<i>Dimensions</i>	Ht 1.60; diam. (base) c. 0.458, (top) 0.43. Letters: (line 1) I of IMP 0.047, (line 2) V of PIVS 0.02, (line 4) V of RVS 0.028
<i>Text</i>	(1) (underneath text [2]) obliterated
	(2) (on the top of text [1])
	Imp·Caesar
	pius·felix·Aug
	M·Aur·Seve-
4	rus·Alexan-
	der·nob̄illissimu⟨s⟩
	(sic)
	Caesar·viam
	vettu⟨s⟩tatte
	(sic)
8	comla/p/sam
	restituit per
	Asinnium Le-
	pidum leg
12	Aug pr·pr·

line 8: mal-formed **P** (lapis); cp. 58(A). Eskiyapar 1, line 8

<i>Caput Viae</i>	[Tavium]
<i>Date</i>	(1) (?)
	(2) AD 222 or 223(?), Severus Alexander <i>Augustus</i>
<i>Commentary</i>	For the text and date of this milestone, cp. above, 58(A). Eskiyapar 1 and the comments of Christol and Loriot (1993, 214) on the date of the Eskiyapar milestone and on the beginning of Asinius Lepidus' governorship ("from 10/12/222 AD").

F.6 TAVIUM (- Melitene per Basilika Therma)**or F.7 TAVIUM (- Caesaria per Therma)**

Two milestones have been assigned to the shared portion of the above-named routes. Both texts, 45(C) Büyük Nefes 3 and 64. Musabeyli, date to the same year (AD 118/119) of Traianus; they record consecutive distance-figures from Tavium, namely, I and II. Both inscriptions were cut with identical line-arrangement, letter-formation, spelling (e.g. Adriano for Hadriano), mis-spelling (e.g. the praenomen and nomen of the legate) and phrase (curo . . .).

These idiosyncracies suggest the possibility that the two milestones are part of the same series along the same road. Tentatively it is proposed here to separate both road and milestones from the Ancyra - Tavium - Zela route (3.F.3) to which an earlier milestone (45[A]. Büyük Nefes 1; Nerva, AD 97; numbered MP I) has been assigned. It cannot be excluded, however, that milestones 45(C) and 64 replaced or augmented the record of Nervan activity (repair to road or milestone?) on the Ancyra - Tavium road.

45(C). Büyük Nefes 3

<i>Province, Sub-Province + Admin. Code</i>	Yozgat 66-00-1
<i>Map</i>	Yozgat 73-ü
<i>Location</i>	“Partially buried on acropolis of ancient city” (Macpherson). Now (erected upside down at the head of a grave) in the village cemetery of Kırıkalıfaklı, on W edge of the village; bought c. 1975 from Bü. Nefes (for TL 6!)
<i>Copy</i>	Macpherson 1953; Bittel 16 September, 1954 and 13 August, 1955; DHF 23.xi.1976 and 01.vii.1977; Strobel 16.8.2001. Macpherson squeeze in the Faculty of Classics, Cambridge (Box IWM XIII); DHF squeeze (drawing, Fig. 6.2.38 [p. 289]) and photo. (Pl. 7.1.28 [p. 314]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 66. Yozgat 01, Büyük Nefes 2 (but here re-numbered to 3)
	Stone: (1) B/W Neg.: DHF R/77/08.02-03
<i>Publication</i>	Macpherson 1954, 117 no. 12 Bittel 1955, 24 n.7 and Pl. 3 nos 2-3, and 119-120 Macpherson 1958, 194 no. 277 RRMAM 2, 1. 971 (notice only) Strobel in Strobel and Gerber 2003, 169-171 no. B 1 and photo., Fig. 21 (text from Bittel copy and photo.) AE 2003. 1713 (text of Strobel) Strobel 2007, 1415 no. B 1 and Fig. 5
<i>Description</i>	A simple cylinder. Hard, pale limestone. Round tenon under base. Letters: very worn
<i>Dimensions</i>	Ht 1.87; diam. (top) 0.40. Letters: (lines 2 and 9) E 0.045

<i>Text</i>	(vac) Imp
	Caesari [Tra]-
	iāno Adriān[o]
4	Aug pon·ma-
	ximo·tribu-
	nicio·p·III cos
	III curo·A /Lar/-
	(sic)
	(sic)
	(sic)

8 **cio Macedone**
 /l/eg·Aug p ⟨p⟩
 milia p·II

- line 2: **Caesari Tra** (Macpherson 1954), **Caesar T[ra]** (Bittel; Strobel, thence AE)
 line 3: **iano Adri** (Macpherson 1954)
 line 4: **no pon ma** (Macpherson 1954)
 lines 6 and 7: horizontal bar over the numerals
 line 6: **nicia pot III** (Macpherson 1954), **nic pot III cos** (Bittel; Strobel, thence AE)
 line 7: **IICVROΔΜΑ** (lapis), **CVRD** (Strobel, thence AE)
 line 9: **SEG** (lapis), **SEC** (lapis *apud* Strobel, thence AE); **p** ⟨p⟩ for **p(r)** ⟨pr⟩
 line 10: **milia p II** [β'] (?); **milia I α'** (Strobel)
 lines 6, 8 and 10: line over the numeral
 lines 7-10: Macpherson 1954 reads
 per A Larc-
 ium Macedonem
 leg Aug pr
 pr milia I
 Bittel reads:
 III curant[e] A [Lar]-
 cio Macedo[ne]
 leg Aug p[r pr]
 milia I

Caput Viae (Tavium)
Date AD 119. 01.i-09.xii Hadrianus *Augustus*

63(A). Küçük Nefes 1

<i>Province, Sub-Province + Admin. Code</i>	Yozgat, Yozgat 66-00-1
<i>Map</i>	Yozgat 73-v
<i>Location</i>	“Der Meilenstein wurde am 4.8.2001 in Küçük Nefes im Haus Nr. 24 (Haus von Salih und Çelebi Mahir) gefunden” (Strobel)
<i>Copy</i>	Strobel 04.08.2001. Text here of Strobel and Gerber
<i>Publication</i>	Strobel in Ströbel and Gerber 2003, 165-166 no. A 2 and photo., Fig. 18 AE 2003. 1708 (text of Ströbel)
<i>Description</i>	Strobel 2007, 1411 no. A 2 and photo. Fig. 2 “Roter Konglomeratmarmor, als regelmäßige Äale hergestellt, Der untere, original erhaltene Fläche der Säule ist grob geglättet, die Oberfläche der Säle ist durchgehend geglättet. Oben endt die Säule heute unmittelbar oberhalb der ersten Schriftzeile. . . . Da ein Zapfen unten fehlt, war der Meilenstein offensichtlich als Säule auf einer Basis aufgestellt. Die Inschrift selbst ist nur durch wenige Oberflächenschäden beeinträchtigt; am rechten Rand setzt eine stärkere Verwitterung ein.” (Strobel)
<i>Dimensions</i>	“ . . . Durchmesser 0,52 m, erhaltene Höhe 1,67 m. . . . Buchstabenhöhe Z. 1: 5 cm; Z. 2: 4,5-5 cm; Z. 3-8: 4-4,5 cm; Z. 9-10: 3,5-4 cm; Z. 11-12: 4,5 cm; Z.

13: 6 cm; Z. 14: 5,5 cm" (Strobel)

<i>Text</i>	[Imp Cae]s L Septimi (vac)
2	[us Sever]us Pius Pertinax
	[Aug Ara]b Adiabe[n]ic (vac)
4	[Parthic] max ponti (vac)
	[fex m] axim trib pot
6	[VI imp] XI cos II {p} p p (vac)
	[proco]s et Imp Cae-
8	[sar M]arcus Au/r/ An-
	[tonin]us Augustus cos
10	[Par]t maxim resti-
	[tu]erunt per Atti[ciu]m
12	[Str]abonem legatum
	p m III
	γ'

line 8: **AVP** (lapis)

lines 9-10: (?) **et L Septimilus Geta Caes** (or Caesar) once inscribed underneath **ustus cos** | [Par]t **maxim**, cp. 72. Tilki Han; Strobel (l.c.) restores ll. 9-10 **tonin Aug et P Septimius / Geta nobil Caes resti**] but cp. above no. 55 Gökc̄am and also the undamaged text from Uluköy in Amasya province (AE 1986. 664): **et·L·Septimius Geta Caesar | restituerunt**

<i>Caput Viae</i>	(Tavium)
<i>Date</i>	(?) AD 197/198, 10.xii-09.xii [L. Septimius Severus] and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta <i>Caesar</i> (the names and title erased)

63(B). Küçük Nefes 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As no. 62 (A)
<i>Location</i>	As no. 62 (A)
<i>Copy</i>	Strobel 04.08.2001
<i>Publication</i>	Strobel in Ströbel and Gerber 2003, 165 Strobel 2007, 1412 no. A.2a
<i>Description</i>	"Der Meilenstein" [= no. 63 (A)] "ist mit einer zweiten, unbeschrifteten, in Größe und Art identischen Meilensäule als Stützmauer der vorderen Hausterasse verbaut" (Strobel)

64. Musabeyli

<i>Province, Sub-Province + Admin. Code</i>	Yozgat 66-00-1
<i>Map</i>	Yozgat 74-u
<i>Location</i>	In the village cemetery
<i>Copy</i>	DHF 01.vii.1977; Strobel 14.8.2002. DHF squeeze (photo., Pl. 7.2.24 [p. 346]) and photo. (Pl. 7.1.29 [p. 315]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 66. Yozgat 09, Musabeyli (= B/W Neg.: Squ. M/12.09) Stone: (1) B/W Neg.: DHF R/77/08.01

Publication RRMAM 2, 1. 981 (notice only)
 Strobel in Ströbel and Gerber 2003, 171-172 no. B 2 and photo., Fig. 22
 AE 2003. 1714 (text of Strobel)
 Strobel 2007, 1416 no. B 2 and Fig. 6

Description A simple cylinder. Complete. Hard, pale limestone. Top flat; round tenon under base. Letters: worn

Dimensions Ht 1.45; diam. (top) 0.40. Letters: (line 1) **I** 0.049, (line 6) **O** of **CIO** 0.026

Text

(vac)	Imp (vac)	
	Caesari T/ra/-	
	iano Adria<no>	
4	Aug pon ma-	(sic)
	ximo t[rib]u-	
	nicio p III cos	(sic)
	III curo /A Lar/-	(sic)
8	cio Macedone	
	leg Aug p <p>	
	milia p	
	I α' (leaf ?)	

line 2: **CAESARTM** (lapis); **Caesar(i) Tra** (Strobel)

line 5: **TRIBV** (Strobel)

line 7: **IIICVROΛAIAP** (lapis); **CVRD** (lapis *apud* Strobel)

lines 7-8: **A Lar[ci]lo** (Strobel)

lines 6, 7 and 11: line over the numeral

Caput Viae (Tavium)
Date AD 119, 01.i-09.xii Hadrianus Augustus

F.8 ANCYRA (- Caesaria per Aquas Saruvenas)

65(A). Tol 1

65(B). Tol 2

Province, Sub-Province + Admin. Code and Map As 65(A)
Location Near the village; at a *çeşme* (fountain) called Tozbağ or Tozukbağ, c. 1.50 km
 WSW of the village
Copy Calder 1910; DHF 01.x.1975. DHF squeeze (photo., Pl. 7.2.25 [p. 347]) and

photo. (Pl. 7.1.31 [p. 315]) in BIAA. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs

<i>Publication</i>	Squeeze: 06. Ankara 105, Tol 2 (= B/W Neg.: Squ. M/12.05-06) Stone: (1) B/W Neg.: DHF R/75/09.11
<i>Description</i>	Calder 1911, (page not numbered) no. 12
<i>Dimensions</i>	Macpherson 1954, 115 no. 6 ('Köseli') (text of Calder) Macpherson 1958, 186 (lower) (text of Calder) RRMAM 2, 1. 178 (notice only)
	A simple cylinder. Top flat. Complete. Grey limestone. Letters: worn Ht 1.90; diam. (top) 0.53. Letters: (line 1) E 0.068, (line 3) E of NER 0.035

<i>Text</i>	(1) (underneath text [2]) (?)
	(2) (on top of text [1])
	Imp Caesari
	2 divi Traiani Parthici
	f diyi Neryae nepoti
	4 Traiano Hadriano Aug
	pont max tr pot VI cos
	6 III per A Larcium Mace-
	d[on]jem leg Aug pr pr
	8 XXVII xz'
	line 2: ligature TH
	line 3: ligature NE (twice), VA
	line 4: TRAINO (Macpherson 1954); ligature AV
	line 5: ligature NT, MA
	line 6: ligature VM
	line 7: ligature AV

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	(1) (?)
	(2) AD 121/122, 10.xii-09.xii Hadrianus Augustus

66. Köseli

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Balâ 06-05-1
<i>Map</i>	Keskin 61-z
<i>Location</i>	At a çeşme (fountain) in middle of the village. Now built into the right-hand end of the facade and barely visible
<i>Copy</i>	Calder 1910; DHF 01.x.1975. Text here from DHF notes
<i>Publication</i>	Calder 1911, (page not numbered) no. 9
	Macpherson 1954, 114 no. 5 (text of Calder)
	Macpherson 1958, 186
	RRMAM 2, 1. 157 (notice only)
<i>Description</i>	The main text is not visible
<i>Dimensions</i>	Not visible

Text - - - -

2 **XXXV**
 λε'

Caput Viae (Ancyra)
Date (?)

67. Abazlı 1

Province, Sub-Province + Admin. Code Ankara, Balâ 06-05-0
Map Ankara 60-Ia
Location In the village; on the left-hand side of the gate into the courtyard of the cami.
Brought from Bağdere, c. 3 km SE of village
Copy DHF 02.x.1975. DHF photo. (Pl. 7.1.32 [p. 315]) and squeeze (photo.,
 Pl. 7.2.26 [p. 347]) in BIAA. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 06. Ankara (not numbered), Abazlı 1 (= B/W Neg.: Squ. M/12.01-04)
 Stone: (1) B/W Neg.: DHF R/75/10.01-06
Publication French 1980, 728 map 3 (site no. 20) (notice)
 RRMAM 2, 1. 076 (notice only)
Description A simple cylinder. Grey limestone. Top flat. Letters: slightly worn
Dimensions Ht 2.08; diam. (top) 0.52. Letters: (line 1) **E** of **CAE** 0.047, (line 6) **E** 0.03,
 (line 11) **L** 0.048

Text

4	Imp Caesar·divi·Vespa- sian[i f] [[Domitianus]] Aug pont max·trib·pot·p·p·cos·IIIX des·IX·imp·II (vac) per· A·Caesen·njum·Gallum· cos·XV·vir·s·f·leg·pro·pr· vias·provinciař·Galatiae·
8	Cappadociae·Ponti·Pisidiaę Paphlag·Lycaoniae·Arme- niae·Minoris·stravit· (vac) mil·XXXIX
12	(vac) λθ'

Caput Viae (Ancyra)
Date AD 82, “seit Mitte Marz”-13.ix Domitianus Augustus

68. Karakeçili, Burun Mevkii

Province, Sub-Province + Admin. Code Ankara, Balâ 06-05-0
Map Keskin 64-Ia
Provenance Found, in 1999, on the l. bank of the Kızılırmak, lying partly on the mud and
 partly in the water at the river's edge, c. 8 km due S of Karakeçili. In 2009 a
 search failed to locate the stone; it can be assumed that the stone is now lost.
Copy Seen by the authorities in Karakeçili and reported to the Ankara Museum. It
 was noted that the stone was cylindrical and carried a multi-line inscription in
 Latin characters.

69(A). Çağırkan 1

<i>Province, Sub-Province + Admin. Code</i>	Kırşehir, Kaman 40-02-0
<i>Map</i>	Keskin 67-Ic
<i>Provenance</i>	Found <i>in situ</i> , in the field of İsmail Özer, c. 3-4 km N of village and c. 2 km N of the main road. Now in the Kırşehir Museum [Inv. no. 1412]
<i>Copy</i>	DHF 03.ix.1991; DHF squeeze (drawing, Fig. 6.2.40 [p. 289]) and photos (Pl. 7.1.33-34 [p. 316]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 40. Kırşehir 01, Çağırkan 1
	Stone: (1) B/W Neg.: DHF M/91/18.06-09
	(2) Col. Slide: DHF 345.16-22
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. The top surface is flat, the shaft straight. Under base: a large, round tenon. The surface of the stone was roughly dressed. On the face of the shaft an area was prepared for the inscription; the text was then inscribed on a smooth area framed by an incised line. Letters: slightly worn
<i>Dimensions</i>	Ht 2.00 + 0.155, diam. (top) c. 0.56. (Tenon) ht 0.155, diam. c. 0.40. Letters: (line 1) I of IMP 0.051, O of POM 0.035, (line 6) E of IEG 0.044

<i>Text</i>		Imp·Nerva·Caes-
		ar·Aug·pont
	4	max·trib·potest·co-
		s·III·p p restituit pe-
		r Pomponium·Bass-
		um·leg·pro·pr·p·m·
		(vac) LXXXIXIIII
		(vac)
	8	(in a panel)
		qδ'

lines 2, 3 and 4: **I** for **T**

line 6: **I** for **L**

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 97, 01.i-17.ix Nerva Augustus
<i>Commentary</i>	According to Kienast (1996, 120), Nerva began his COS III on AD 01 January 97 and ended his TR P (I) on 17 September 97.

69(B). Çağırkan 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 69(A)
<i>Provenance</i>	As 62(A). Now in the Kırşehir Museum [Inv. no. 1413]
<i>Copy</i>	DHF 03.ix.1991; DHF squeeze (drawing, Fig. 6.2.41 [p. 290]) and photo. (Pl. 7.1.35-36 [p. 316]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 40. Kırşehir 02, Çağırkan 2
	Stone: (1) B/W Neg.: DHF M/91/18/10-12
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. The top surface is flat, the shaft irregular. Large, round tenon (now broken) under base. Note the

form of the letters E and L.
 Letters: slightly worn
Dimensions Ht 2.06 + 0.035 (ex.), diam. (top) 0.47; (tenon) ht (ex.) 0.35, diam. 0.30.
 Letters: (line 1) **P** of **IMP** 0.062, (line 11) **T** of **ET** 0.034.

<i>Text</i>	Imp Caes P Ael
	Licinnio Va-
	leriano p f Aug
4	et Imp Caes P Li-
	cinnio Egnat-
	tio Gallieno
8	p f Aug et P Li-
	cinnio Egnati-
	o Valeriano Sa-
	loniano indulgen-
12	tissimo Caes Aug
	et Saloninae matri
	Augg et castror
	ux A p f Aug
16	[-]

line 11: **LONIANO** (lapis)
 line 14: **Aug(ustorum)** **et castror(um)**
 line 15: **ux(ori)** **A(ugusti)** **p(iae)** **f(elicis)** **Aug(ustae)**

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	Valerianus and Gallienus <i>Augusti</i> and Salonina <i>Augusta</i> either (?)AD 255-257/258 with Valerianus Iunior <i>Caesar Augustus</i> or AD 257/258-260 Spring with Saloninus <i>Caesar</i>
<i>Commentary</i>	For Valerianus Iunior as <i>Augustus</i> , see Kienast (1996, 221).

F.9 COLONIA ICONIUM (- Colonia Archelaïs - Caesaria)**70(A). Konya 1**

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-0
<i>Map</i>	Konya 57-Ip
<i>Provenance</i>	“In cemetery of Seidiler, E of Konya” (Cronin); brought from the Sedirler Mahalle cemetery to the Konya Museum [Inv. no. 801]
<i>Copy</i>	Ramsay (W.M.), Cronin and Wathen 1901; DHF 26.vii.1974; ASH (? date); Houston (? date). ASH photo. (Pl. 7.1.37 [p. 317]). DHF squeeze (drawing, Fig. 6.2.42 [p. 290]) in BIAA. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 42. Konya 19, Konya 1
<i>Publication</i>	CIL 3. 14402 (text from Ramsay, Cronin and Wathen) Cronin 1902, 119 no. 46 and Fig. Ramsay (A.M.) 1909, 20 no. 1 (comment) Ballance 1958, 230 no. 10 (notice) French 1976a, 52 (notice) RRMAM 2, 1. 641 (notice only) RECAM 4 (ed. McLean). 237 and Figs 276-277 (text and commentary by George Houston)
<i>Description</i>	A re-used column. The shaft is round. Mouldings at top but lost below (cp. 73[A]. Obruk 1); below the top mouldings and on the face of the shaft: a raised, flat, rectangular panel; at the top of the raised panel there is a wreath. Below the wreath there is a prominent <i>tabula</i> ; both the wreath and the <i>tabula</i> are surrounded by a band in relief. At the edge of the <i>tabula</i> there is a raised frame. Broken below. White marble. Letters: slightly worn
<i>Dimensions</i>	Ht 1.40; diam. (top) 0.44; (panel) wi. 0.38. Letters: (line 1) P of IMP 0.0375, (line 9) I of MIL 0.075
<i>Text</i>	(on the panel) <p style="text-align: center;"> Imp·Caesar·divi 2 Traiani·Parthici f·divi Nerva·ne - 4 pos·Traianus Ha - drianus·Aug pon (sic) 6 max·trib·pot·XIII cos·III (vac) p·p 8 (vac) IIII </p> (on the shaft, below the panel) <p style="text-align: center;"> mil (vac) p X </p>

line 8: the numerals are shallowly cut; they have the appearance of a later addition

<i>Caput Viae</i>	(Colonia Iconium)
<i>Date</i>	AD 128/129, 10.xii-09.xii Hadrianus Augustus
<i>Commentary</i>	One of a number of milestones in this form; see also 79(A). Obruk 1; for the raised, rectangular panel, see 73(B). Kulak Murat Han 2, 78. Divanlar, 79(E). Obruk 5 and 83. Ağsaklı

70(B). Konya 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 70(A)
<i>Location</i>	“In the streets of Konia” (Cronin). Present whereabouts not established (DHF visit 31.v.1977)
<i>Copy</i>	Ramsay (W.M.) and Cronin 1901. The stone has not been examined by DHF.
<i>Text here of Cronin</i>	
<i>Publication</i>	CIL 3. 14399a (text from Ramsay and Cronin) Cronin 1902, 121 no. 48 Ballance 1958, 230 no. 11 (notice) RRMAM 2, 1. 642 (notice only)
<i>Description & Dimensions</i>	Not given

Text

[I]mp·C[aes]ari divi	
Tra[iani·Par]thic[i]	
nep[o]ti div[i] Nerv-	
4 ae [pronepot]i [*] _* divi	
Hadır[iani f T] [*] _* Aelio	
Hadri[ano A]nto-	
nino Au[g pio po]ntif	
8 max t[rib pote]st IIII	
cos III (vac) mil [p]	
[-]	

<i>Caput Viae</i>	(Colonia Iconium)
<i>Date</i>	AD 140/141, 10.xii-09.xii Antoninus Pius <i>Augustus</i>

70(C). Konya 3

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-0
<i>Map</i>	Ilgın 57-Iö (Dikili Han)
<i>Location</i>	“In a cemetery to the North” (Cronin). Seen (31.v.1977) at the Dikilihan, in the grounds of the (former) Aslim Talı İstasyonu, Toprak Su Araştırma Enstitüsü (the building now destroyed); c. 0.90 km S of the Aksaray junction on Ankara-Konya highway. Now (since 1991) at the Faculty of Science and Humanities, Selçuk University, Konya
<i>Copy</i>	Ramsay (W.M.) 1901; DHF 31.v.1977. DHF squeeze (drawing, Fig. 6.2.43 [p. 291], and photos, Pls 7.2.27-28 [p. 348]) and photo. (Pl. 7.1.38 [p. 317]) in BIAA. Texts here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 42. Konya 20, Konya 3 (= B/W Neg.: Squ. M/15.09-13) Stone: (1) B/W Neg.: DHF R/74/02.07-11 (2) Col. Slide: DHF 115. 26-28
<i>Publication</i>	CIL 3. 14402a (text of Ramsay) Cronin 1902, 121 no. 49 Ramsay (A.M.) 1909, 21 no. 2 (notice) Ballance 1958, 230 no. 12 and n.10 (notice) French 1976a, 52 (notice) RRMAM 2, 1. 643 (notice only)

<i>Description</i>	A simple cylinder. Broken into two pieces (1977). Hard, pale limestone. Letters: slightly worn
<i>Dimensions</i>	Ht c. 2.34; diam. (top) 0.44. Letters: (text 1) (line 1) P 0.053, (line 3) R of TRA 0.055, (line 6) P of PRO 0.05, (line 12) (numerals) 0.06, (text 2) T of PET 0.04
<i>Text</i>	(1) (on one side of the shaft) (vac) Imp Caesari·divi Ḥa- driani·filio·div[i] 4 Traiani Parthic[i] nepoti·divi Nery- ae pronepoti T·Ae- lio Ḥadriano Anto- 8 nino Aὔgusto pio pontif·maximo trib·p[ο]t·III·cos·III mil·passu(u)m·(vac) 12 (vac) XXVIII

(2) (on the other side of the shaft, towards the base)

et Graťiano
pe(r)petu(i)s Augg

<i>Caput Viae</i>	(Colonia Iconium)
<i>Date</i>	(1) AD 141/142, 10.xii-09.xii Antoninus Pius <i>Augustus</i> (2) (?) AD 367-375 [Valentinianus I, Valens] and Gratianus <i>Augusti</i>

70(D). Konya 4

<i>Province, Sub-Province + Admin. Code and Map</i>	As 70(A)
<i>Location</i>	“Garden by road to Obruk, about 2 mp from Amphilochius” (Calder); “NE of Konya” (Ballance). Present whereabouts not established (DHF visit 31.v.1977)
<i>Copy</i>	Calder 1910. The stone has not been examined by DHF. Text here from MHB(allance) notes of Calder’s notebook for 1910 (the note is reproduced here, Fig. 6.1.14 [p. 266])
<i>Publication</i>	Ballance 1958, 230 no. 7 (notice) RRMAM 2, 1. 644 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	(vac) [Im]p (vac) Ca[esar di]vi Traia- n[i Parthici f di]vi 4 Nε[rvae nep]os Tra- ia[nus Had]rianus A[u]g pontif]ex max
-------------	--

8 **‡[ribunici]ae pote-**
s[t -] cos III
p [p] [-]
 (vac) [-]
 (vac) [-]
 12 (vac) [-]
 (vac) [m]p III

Caput Viae (Colonia Iconium)
Date AD 128/129(?), Hadrianus Augustus

70(E). Konya 5

Province, Sub-Province + Admin. Code Konya 42-00-0
Map Konya 56/57-Ip
Location In the courtyard of the Ala-ed-din Cami
Copy Eyice 21.06.1970; DHF 23.viii.1974. Eyice photo. (Pl. 7.1.39 [p. 318]); DHF squeeze (drawing, Fig. 6.2.44 [p. 291]) in BIAA. No DHF photo. Texts here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 42. Konya 21, Konya 5
Publication Eyice 1970-71, 271 and Fig. 8
 French 1976a, 52 (notice)
 RRMAM 2, 1. 645 (notice only)
Description A simple cylinder. Soft, pale limestone. Re-cut (?recently) at top and sides.
 Letters: slightly worn
Dimensions Ht 1.93; wi. 0.37. Letters: (line 7) **O** of **COS** 0.068, (line 8) **I** 0.08

Text (1) (underneath text [2])
 2 [Imp Caesar divi]
 2 [Traiani Parthici]
 4 [filius divi Nervae]
 4 [ne]pos Tr[aianus Hadri]-
 6 [an]us Aug p[on]t max]-
 6 [im]us trib[us] p[on]t
 8 [XIII] cos III p p
 (vac)
 8 (vac) mil V

(2) (on the top of text [1])
 - - -
 2 Fl Consta[n]tino et]
 Fl Iul C[on]stantio et]
 4 [Fl Constanti]
 [nobb Caess]
 6 [-]

Caput Viae (Colonia Iconium)
Date (1) AD 128/129(?), Hadrianus Augustus

(2) AD 333, 25.xii-335, 18.ix [Constantinus I *Augustus*] with Constantinus II,
Constantius II [and Constans *Caesares*]

70(F). Konya 6

<i>Province, Sub-Province + Admin. Code and Map</i>	As 70(E)
<i>Location</i>	In the courtyard of the Ala-ed-din Cami
<i>Copy</i>	DHF 23.viii.1974. DHF squeeze (drawing, Fig. 6.2.45 [p. 292]) in BIAA. No photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 42. Konya 22, Konya 6
<i>Publication</i>	French 1976a, 52 (notice) RRMAM 2, 1. 646 (notice only)
<i>Description</i>	A simple cylinder. Broken at top. Soft, pale limestone. Letters: slightly worn
<i>Dimensions</i>	Ht (ex.) c. 1.00; diam. 0.60. Letters: 10.07
<i>Text</i>	----- 2 ços [- -] VI ș'
<i>Caput Viae</i>	(Colonia Iconium)
<i>Date</i>	(?)Hadrianus

71. Konya, Dikilitas

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-0
<i>Map</i>	Konya 57-Ip(?)
<i>Location</i>	“Half-way between them” (sc. the milestones at Kulak Murat Han) “and Konia we found a milestone, broken and obliterated, still standing in its original position, and marking the line of the Roman road to the north, connecting Iconium with Ancyra. The <i>milliarium</i> is called Dikeli-Tash, the ‘standing stone’, and is shown on Kiepert’s map as a village” (Ramsay [A.M.] 1909, 5). Present whereabouts not established (DHF visit 31.v.1977)
<i>Copy</i>	Ramsay (A.M.) 1909
<i>Publication</i>	Ramsay [A.M.] 1909, 5 and 21 no. 3 Ballance 1958, 230 no. 37 (notice) RRMAM 2, 1. 647 (notice only)
<i>Description & Dimensions</i>	Not given
<i>Text</i>	“Obliterated” (Ramsay [A.M.] 1909: 5)
<i>Date</i>	(?)
<i>Commentary</i>	“ . . . about the eighth mile” (Ramsay [A.M.] 1909, 21)

72. Tilki Han

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-8
<i>Map</i>	Ilgin 58-In
<i>Location</i>	In the <i>han</i> , formerly a <i>mandira</i> (sheep-shelter), where it is used as a roof-pillar; c. 50 m W of the Ankara-Konya highway, c. 0.90 km S of the turning for

	Eğribayat and c. 32.50 km N of Konya. The area around the han is now given over to quarrying operations
<i>Copy</i>	Ramsay (W.M.) 1907 and 1908; DHF 27.v.1973, 22.vi.1973, 18.x.73, 23.x.73 (photo., Pl. 7.1.40 [p. 318]) and 23.v.1977. DHF squeeze (drawing, Fig. 6.2.46 [p. 292], and photo., Pl. 7.2.29 [p. 349]) and photos in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 42. Konya 34, 35, Tilki Han (= B/W Neg.: Squ. M/13.13-15)
	Stone: (1) B/W Neg.: DHF 35/73/05.25-26
<i>Publication</i>	Ramsay (W.M.) 1907, 449 n.19 (notice)
	Ramsay (A.M.) 1909, 24 no. 7
	Ballance 1958, 230 no. 18 (notice)
	RRMAM 2, 1. 666 (notice only)
<i>Description</i>	A simple cylinder. Complete except for surface damage. Hard, pale limestone. Letters: slightly worn
<i>Dimensions</i>	Ht (ex.) 1.45; diam. 0.52. Letters: (line 1) E of CAE 0.032, E of SEP 0.028, (line 12) E of RES 0.034

<i>Text</i>	Imp Caes·L Septim[ius]
	Severus·Pius Pertī-
	nax Augustus·Arabi-
4	cus Ädiabenicus Par-
	thicus maximus·ponti-
	fex maximus·trib pot VII
	imp XI cos II·p p procos
8	et Imp Caesar Marçus
	Aurelius Anton[i]nus
	[A]ug cons Par-
	thic[u]s maxi-
12	mus restituerunt
	mil pass
	[-]

line 7: horizontal bar over the numerals

lines 10-11: **et L Septimius | Geta Caesar** was once inscribed
underneath **cons Parthicus maximus**

"Lines 10, 11 and part of 12, are written in different style over an erasure. Originally these lines contained the name of P. Septimius Geta Caesar; but, after Geta had been murdered in AD 212 by his brother Caracalla, his name was erased on all monuments throughout the Empire.

Erasures are very common in Imperial inscriptions of Emperors or Caesars whose memory had been condemned. Usually, the erasure is left as a blank space; but sometimes it is filled up: here and in this whole series of milestones titles of Caracalla are added. It is not quite certain whether the title Aug(ustus) is original or in the erasure, but probably it belongs to the later addition, as do Co(n)s(ul), and Parthicus Maximus" (Ramsay [A.M.] 1909, 26)

<i>Caput Viae</i>	(Colonia Iconium)
<i>Date</i>	AD 198/199, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i>
<i>Commentary</i>	Almost universally on milestones in Asia Minor the name of Geta was erased;

for an exception, at Uluköy near Amasya (in Cappadocia) (see RRMAM 2, 1.072 = French 1986b, 77 no. 3 = AE 1986, 664 = RRMAM 3.3 (Cappadocia), 149[A]. Uluköy 1). The erased lines were then inscribed with the titles of Caracalla, viz. *consul* and *Parthicus maximus* [16(A), 50(B), 74(A) & (C), 77, 72(A), 79(E) and 89(B)] or with other Imperial titles: *Invict Augg* [no. 86].

73(A). Kulak Murat Hanı 1

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-8
<i>Map</i>	Ilgın 59-In (Hacımurat Hanı)
<i>Location</i>	“In front of Kulak-Murad Khan” (Ramsay A.M.). Present whereabouts not established (DHF visit 27.v.1973 and 22.vi.1973)
<i>Copy</i>	Ramsay (A.M.) 1909. The stone has not been examined by DHF. Texts here of Ramsay (A.M.) (her text and drawing are reproduced here, Figs 6.1.15, 17 [p. 266])
<i>Publication</i>	Ramsay (A.M.) 1909, 22 no. 6 and Fig. 7 Ballance 1958, 230 nos 16 and 31 (notice) RRMAM 2, 1. 648 (notice only)
<i>Description</i>	“ . . . , on a small round cippus. The inscription is in a bad condition and much worn; but also it was scratched rather than incised by an unskilled engraver in very coarse crowded, small letters, of extremely bad shape. The inscription is very long; but only a part of a word here and there could be read, sufficient to show to one who was familiar with the epigraphy of the Province, Sub-Province and its milestones that it was one of the series (discovered during the last five years) raised in honour of Septimius Severus and Caracalla (with Geta erased) by Gaius Atticius Strabo, governor of Galatia in AD 198. The number was unfortunately illegible; the milestones of Atticius were generally measured from Ancyra. ... At a later time an inscription of [Valens, Gratian] and Valentinian was inscribed higher upon the cippus, identical with that which appears in no. 5” [= here, 72(C)] “.... The arrangement of the letters inside and outside of a rectangle, which was marked out for a much shorter inscription, shows that the masons used an older milestone, of which they must have obliterated the inscription. This stone, therefore, had as complicated a history as the preceding. It bore first an inscription of some earlier Emperor in the rectangular space marked out by lines. This was erased, and a dedication to Severus, Caracalla and Geta was substituted. Then Geta's name was erased and anachronistic titles of Caracalla were inserted AD 212. Finally, in the blank space above this dedication, the inscription of the three Emperors was engraved between AD 375 and 378” (Ramsay [A.M.] 1909, 23 and 24).
<i>Dimensions</i>	Not given
<i>Text</i>	(1) (in the framed panel) erased
	(2) (in the middle of the shaft)
	[Imp Caesar L Septimi]- [us Severus Pius Pert]- nax [Augustus Arabic]-
4	[us] Adiabenicus [Part]- hi[c]us maximus po[ntif]- ex max[imus tribunic]- [i]ae [pot]e[statis VI]

- 8 [imp XI consul] **II** [p p]
 (vac) [p]r[ocos et]
 [Imp C]aesār Ma[r]cus
 [Au]relius Anton[inus]
 12 [Aug] (vac) **cōn[s]**
 [Par]t[hicus maximus]
 r[estituerunt]
 [p]er Caium Att[ici]-
 16 [um] Strabonem [lega]-
 tu[m] Augg [pr pr]
 [mi]lia passu[um -]
SAR A

(3) (above text [2], at the top of the shaft)

- [DDD nnn]
 2 [Fl Valente]
 [et Fl Gratiano]
 4 **et Fl V**[alentiniano]
 per[p]e[t]uis ac [victo]-
 6 **rio**[si]si[mi]s sen- (sic)
 [per Aug]gg

Caput Viae [Colonia Iconium]

Date (1) (?)

(2) L. Septimius Severus and M. Aurelius Antoninus (Caracalla) *Augusti* with
 L. Septimius Geta (names erased) *Caesar*, (?)AD 197/198, 10.xii-09.xii
 (3) AD 375, 17.xi-378, 09.viii Valens, Gratianus and Valentinianus II *Augusti*

73(B). Kulak Murat Hanı 2

Province, Sub-Province + Admin. Code and Map As 73(A)

Location “In the Kulak-Murad Khan, ... This and the following two milestones” (sc. nos 5 and 6 = here nos 73[A] and [C]) “were evidently carried to be used building the Khan. Two serve as columns to support the roof” (Ramsay [A.M.] 1909, 21). Inside the *han*, now used as a *mandira* (sheep-shelter); employed as the lower half of a roof-pillar, on the left of the entrance

Copy Ramsay (A.M.) 1909; DHF 27.v.1973 and 22.vi.1973. DHF squeeze and photo. (Pl. 7.1.41 [p. 318]) in BIAA. Text here as Ramsay (A. M.)

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 42. Konya 23, Kulak Murat Han 2

Stone: (1) B/W Neg.: DHF M/94/13.06 and 08, and 16.12-13

Publication Ramsay (A.M.) 1909, 21 no. 4

Ballance 1958, 230 no. 19 (notice)

RRMAM 2, 1. 649 (notice only)

Description A simple cylinder. (?) Complete. Pale limestone. At the top of the shaft: a double, convex moulding. On face of the shaft: a raised, flat, rectangular panel. “ . . . ; the surface of the projecting panel has been worked smooth in modern time and nothing of the inscription remains except the number at the bottom” (Ramsay [A.M.] 1909, 21). On the shaft on the left of the panel and

Dimensions slightly below the lowest moulding there is an incised cross.
 Ht (vis.) 1.62; (panel) ht 0.89, wi. 0.47. Letters: (numerals) c. 0.08

Text (in the panel)
 - - -
 (on the shaft, below the panel)
mil p XVI

The numeral belongs to the main text (now lost) on the panel above

Caput Viae (Colonia Iconium)
Date (?)Hadrianus
Commentary For the shape and form of the milestone and for the location of the distance-figure not on the panel but on the shaft, see the Hadrianic milestone above, 70(A). Konya 1. Ballance (l.c.) suggested Valens, Gratianus and Valentinianus II (Ballance), presumably on the basis of the intact text on the milestone below, 73(C). Kulak Murat Hanı 3 (2)

73(C). Kulak Murat Hanı 3

Province, Sub-Province + Admin. Code and Map As 73(A)
Location “In Kulak-Murad Khan . . .” (Ramsay [A.M.] 1909, 21). Inside the *han*, now used as a *mandira* (sheep-shelter); set upside down and employed as the lower half of a roof-pillar, on the right of the entrance
Copy Ramsay (A.M.) 1909; DHF 27.v.1973 and 22.vi.1973. The drawing published by Ramsay is reproduced here (Fig. 6.1.16 [p. 266]). DHF squeeze (drawing, Fig. 6.2.47 [p. 292]) and photo. (Pl. 7.1.42 [p. 318]) in BIAA. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 42. Konya 24, Kulak Murat Han 3
 Stone: (1) B/W Neg.: DHF M/94/16.14-15
Publication Ramsay (A.M.) 1909, 21 no. 5
 Ballance 1958, 230 nos 30 and 36 (notice)
 RRMAM 2, 1. 650 (notice only)
Description “The original inscription has been carefully erased in ancient time and an inscription in honour of Valens, Gratian and Valentinian substituted. The traces are so slight, that I could not have made anything out of this inscription except through my father's knowledge of the formula. The original number of Hadrian's milestone was left at the foot. . . Underneath are traces of the foot of a large cross, and letters of which we could make no sense; the stone was used at a later time for some other purpose, probably as a gravestone. On the back are rude letters scratched, which also were unintelligible to us” (Ramsay [A.M.] 1909: 21).
 A simple cylinder. On the face of the shaft: a raised, flat, rectangular panel.
 (?) Complete. Pale limestone. Letters: extremely worn
Dimensions Ht (vis.) 1.28; (panel) ht 0.85, wi. 0.42. Letters: c. 0.045, (numerals) c. 0.075
Text (1) (underneath text [2])
 lost
 (2) (on top of text [1]).

(in the panel)

2 **DDD nn[n]**
 2 **Fl Valente**
 4 [e]t **Fl Gratia[no]**
 4 **et Fl Valentini-**
 6 **ano perpet[uis]**
 6 [ac victoriosim]-
 8 [is semper] **Au-**
 8 (vac) **ggg**

(on the shaft, below the panel)

mil p XVII

line 9: the numeral probably belongs to the original (? Hadrianic) text
erased for text (2)

<i>Caput Viae</i>	(Colonia Iconium)
<i>Date</i>	(1) Hadrianus (Ramsay [A.M.]) (2) AD 375, 17.xi-378, 09.viii Valens, Gratianus and Valentinianus II <i>Augusti</i>
<i>Commentary</i>	For the shape and form of the milestone and for the location of the distance-figure not on the panel but on the shaft, see the Hadrianic milestone above, 70(A). Konya 1

73(D). Kulak Murat Hanı 4

<i>Province, Sub-Province + Admin. Code and Map</i>	As 73(A)
<i>Location</i>	“Kulak Murat Hanı (near)” (Ballance). Present whereabouts not established (DHF visit 27.v.1973 and 22.vi.1973)
<i>Copy</i>	Ballance 1957
<i>Publication</i>	Ballance 1958, 230 no. 35 (notice) RRMAM 2, 1. 651 (notice only)
<i>Description & Dimensions</i>	Not given
<i>Text</i>	Not given
<i>Date</i>	(?) AD 375-378 Valens, Gratianus and Valentinianus II (Ballance)

73(E). Kulak Murat Hanı 5

<i>Province, Sub-Province + Admin. Code and Map</i>	As 73(A)
<i>Location</i>	Inside the <i>mandira</i> (sheep-shelter); the shaft has been cut into two sections, each then used as a capital above the roof-pillars (milestones nos 73[B] and [C])
<i>Copy</i>	DHF 27.v.1973 and 22.vi.1973. DHF squeeze (drawing, Fig. 6.2.48 [p. 292]) and photo. [shaft section above 73 (B)] (Pl. 7.1.43 [p. 319]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 42. Konya 25, Kulak Murat Han 5 Stone: (1) B/W Neg.: DHF M/94/13.07
<i>Publication</i>	RRMAM 2, 1. 652 (notice only)
<i>Description</i>	A simple cylinder. Now cut into two pieces. Pale limestone. Letters: very worn

Dimensions Ht 0.72 (left-hand capital) + 0.70 (right-hand capital). Letters: (line 1) **I** 0.04

<i>Text</i>	(l. capital)	Imp [- - -] S[- - -] [- - - -] [- - - -]
	5	M [- - -] AV [- - -] [- - - -] [- - - -] IV [- -]
	(r. capital)	T [- - -] [-] I [- -] ER [- -]

Caput Viae [Colonia Iconium]
Date (?)

74(A). Eğribayat 1

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-8
<i>Map</i>	Ilgin 59-In
<i>Location</i>	In the village; at the house of Nuri Özdemir. Now used as a gate-post
<i>Copy</i>	Calder 1910; Ballance 1956; DHF 02.vi.1977. DHF squeeze (drawing, Fig. 6.2.49 [p. 293]) and photo. (Pl. 7.1.44 [p. 319]) in BIAA. Text here from DHF squeeze and from MHB(allance) notes of Calder's notebook for 1910 (MHB's note is reproduced here, Fig. 6.1.18 [p. 267])
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 42. Konya 08, Eğribayat 1 Stone: (1) B/W Neg.: DHF R/77/03.12 and 04.01
<i>Publication</i>	Ballance 1958, 230 no. 21 (notice) RRMAM 2, 1. 615 (notice only)
<i>Description</i>	A simple cylinder. (?) Complete. Hard, pale limestone. Round tenon on top. Letters: worn
<i>Dimensions</i>	Ht 1.32; diam. (top) 0.41 Letters: (text 1) (line 11) T 0.038, (text 2) (line 2) T of STA 0.045, (text 3) P of PP 0.068

<i>Text</i>	(1) (on the face of the shaft)
	[Imp Caes L Septimius] [Severus Pius Pertinax]- [Aug Arabicus Adiabe]-
4	nicu [s Parth]ic[u]s·ma-
	x̄imū [s pon]tife[x ma]-
	xim [us trib pot] VII
	im [p XI cos II p p pro]-
8	cos [e]t Imp·Caesar Marcus·Aure [l]ius [A]ntoninus·Au[g e]t [c]ons·Parthicus

12 [m]aximus·resti-
tuerunt·mil·pās[s]
[-]

lines 1-7: restored from the text of 71. Tilki Han; underlined letters seen by Calder 1910
 line 6: XII (Calder, Ballance), XIM (DHF)
 lines 11-12: L Septimius Geta | Caesar once inscribed underneath
cons·Parthicus | maximus, cp. 72. Tilki Han

(2) (below and upside down to text [1])

	[DDDD] nnnn
2	[Fl Val Con]stāntīno Au[g et]
	[Fl Co]nstāntīno et
4	[Fl Consta]ntīo et
	[Fl Consta]nti
6	[nobb Caess]

(3) (upside down to text [1] and on the r. of text [2])

	IM[-]
2	M[-]
	M[-]
4	PP[-]

Caput Viae [Colonia Iconium]

Date (1) AD 198/199, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) *Augusti* with L. Septimius Geta (names erased) *Caesar*, not AD 204 *pace* Ballance, who interprets the letters at the beginning of line 7 (here = line 6) in Calder's copy as [TR P] XII
 (2) AD 333, 25.xii-335, 18.ix Constantinus I *Augusti* with Constantinus II, Constantius II and Constans *Caesares*
 (3) (?)

74(B). Eğribayat 2

Province, Sub-Province + Admin. Code and Map As 74(A)

Location Not given. Present whereabouts not established (DHF visit 02.vi.1977)

Copy Calder 1910. The stone has not been examined by DHF. Text here from MHB(allance) notes of Calder's notebook for 1910 (MHB's note is reproduced here, Fig. 6.1.19 [p. 267])

Publication Ballance 1958, 230 no. 24 (notice)

RRMAM 2, 1. 614 (notice only)

Description “Flat stone, roughly cut” (Calder)

Dimensions Not given

Text Imp Cae[sarem]
 P·L·Valerian[um]
 et P·Licin·
 4 Gallienum

et P Corne-
lium [Salonium]
Valerianum
nobilissimu[m]
Caesarem
Augustos

line 6: [Saloninum], cp. 100(B). Kavak 2, lines 8-10: **Cor[n]e[lio]**
Salonino [Valeri]ano
line 7: “**VINCENNIVM, N** of **NIVM** doubtful” (Calder)
line 10: **Augustos**, sc. Valerianus and Gallienus, but cf. **indulgentissimo**
Caes Aug on 69(B). Çağırkan 2

<i>Caput Viae</i>	[Colonia Iconium]
<i>Date</i>	AD 257/258-260, Spring Valerianus and Gallienus <i>Augusti</i> with Saloninus <i>Caesar</i>
<i>Commentary</i>	“Perhaps not a milestone” (Ballance)

74(C). Eğribayat 3

<i>Province, Sub-Province + Admin. Code and Map</i>	As 74(A)
<i>Location</i>	At a çeşme (fountain) on N side of the village; said to have been brought from Seyitler (? = Sedirler) Mahallesi, Konya
<i>Copy</i>	DHF 02.vi.1977. DHF squeeze and photo. in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 42. Konya 09, Eğribayat 3
	Stone: (1) B/W Neg.: DHF R/77/04.01
<i>Publication</i>	RRMAM 2, 1. 613 (notice only)
<i>Description</i>	A simple cylinder. Hard, pale limestone. Now re-cut as a water-trough. Letters: very worn
<i>Dimensions</i>	Ht 1.40; diam. (base) 0.49. Letters: T of ITV 0.035

<i>Text</i>	(1)	[Imp C]aes
	Sep[- -]	
	[- - -]	
	[- - -]	
5	[- - -]	
	[- - -]	
	[- - -]	
	[- - -]	
	[- - -]	
	[-]cos [Parthi]-	
10	çus maxim[us]	
	restituerunt mil	
	pass CVI [- -]	
	ITRIO [- -]	
	[- - - -]	
15	[-]	

lines 9-10; et L. Septimius | Geta Caesar once inscribed underneath cos

[Parthi]çus maxim[us], cp. 72. Tilki Han
 lines 12-13: the letters are nearly illegible; ? X for C. Perhaps a
 governor's name has been lost here? or an earlier inscription?

(2)	DDDD nnnn
2	Fl Val Constanti[no]
	- - -
4	- - -
	- - -
6	- - -
	- - -

cp. 74(A). Eğribyat 1, text (2)

- Caput Viae* [Colonia Iconium]
Date (1) L. Septimius Severus and M. Aurelius Antoninus (Caracalla) *Augusti* with
 L. Septimius Geta (names erased) *Caesar*, (?)year
 (2) (?) AD 333-335 Constantinus I *Augustus* with Constantinus I, Constantius I
 and Constans *Caesares*

74(D). Eğribyat 4

- Province, Sub-Province + Admin. Code and Map* As 74(A)
Location In the village; beside the house of Rıza Koçak
Copy DHF 02.vi.1977. DHF squeeze (drawings, Figs 6.2.50-51 [p. 293]) and photo.
 (Pl. 7.1.45 [p. 319]) in BIAA. Texts here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 42. Konya 10, Eğribyat 4
 Stone: (1) B/W Neg.: DHF R/77/04.03
Publication RRMAM 2, 1. 616 (notice only)
Description A simple cylinder. Broken on the right; (?)broken below. Hard, pale
 limestone. Letters: extremely worn
Dimensions Ht 1.54; diam. 0.47. Letters: (text 2) (line 2) **C** 0.065, (line 6) **I** 0.060, (text 3)
V of AVG 0.035, **M** 0.085

- Text* (1) (underneath text [2])
 traces
 (2) (from the top to the centre)
 (vac) **I**[-]
C[. . .]|[-]
|[- - -]|
4 **.V. .E**[-]
I..SI[-]
M.XI[- -]
PVIIIIC[-]
8 **XIIIIC**[-]
[. . .]**I**[-]
(vac) **P**[-]
(vac) **M**[-]

Possible restoration:

	(vac) I [mp]
	C [aes] [divi f]
	[Domitianus]
4	[A]u[g G]e[rman]-
	i [cu]s p[ont]
	m [a]x [trib]
	p VIII c[os]
8	XIII c[ens]
	[per]p[etuus]
	(vac) p [p]
	(vac) m [p]
	(vac) [-]

line 8: horizontal bar over the numeral

line 9: (?) [p] **p**, i.e. **p**(ater) **p**(atriae)

line 10: (?) [m] **p**, i.e. [m(il)] **p**(ass)

(3) (below, and upside down to, text [2])

	- - - -
2	[- - m]ax·ac
	[- -]t·Aug·
4	(vac) m [-]

line 4: (?) **m**(il) [p(ass)]

Caput Viae [Colonia Iconium]

Date (1) (?)

(2) AD 89/90, 14.ix-13.ix Domitianus Augustus

(3) (?)

Commentary The restorations in text (2) above are suggested by the text of the Domitianic milestones found (1) at İsmail near Afyon (CIL 3. 14200¹ [AD 90-91]) and (2) at Balçova near İzmir (IK 24, 1. 826 [AD 92/3]).

74(E). Eğribayat 5

Province, Sub-Province + Admin. Code and Map As 74(A)

Location In the village, at a *çeşme* (fountain); said to have been brought from Muşki Yayla

Copy DHF 02.vi.1977. DHF photo. in BIAA
Stone: (1) B/W Neg.: DHF R/77/04.02

Publication RRMAM 2, 1. 617 (notice only)

Description A simple cylinder. Pale limestone. Now re-cut as a water-trough.

Dimensions Not recorded

Text No visible inscription

75. Muşki Yayla

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-1
<i>Map</i>	Ilgin 59-Io
<i>Location</i>	Not given. Present whereabouts not established (DHF visit 02.vi.1977)
<i>Copy</i>	Calder 1910. The stone has not been examined by DHF. Text here from MHB(allance) notes of Calder's notebook for 1910 (MHB's note is reproduced here, Fig. 6.1.20 [p. 267]).
<i>Publication</i>	Ballance 1958, 230 no. 6 (notice) RRMAM 2, 1. 653 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	Imp Caesare di- vi Traiani Par- thici f̄ divi Ner- *	(sic)
4	vae nepoti Tra- iano Hadrian[o] [Au]g p[on]t max [tr pot] IV̄ cos III	
8	[per A Larcijum] Macedonem [leg] p̄ro pr [-]	

line 3: ligatures **TH, NE**

<i>Caput Viae</i>	[Colonia Iconium]
<i>Date</i>	AD 119/120, 10.xii-09.xii Hadrianus Augustus

76(A). Kızılcakuyu 1, form. Sarayköyü Yayla

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-1
<i>Map</i>	Ilgin 60-Io
<i>Location</i>	In the village cemetery; c. 1 km S of the village
<i>Copy</i>	Ballance 1957; DHF 27.v.1977. DHF photo. (Pl. 7.1.46 [p. 319]) and squeeze (photo., Pl. 7.2.30 [p. 349]) in BIAA. Texts here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 42. Konya 16, Kızılcakuyu 1 (= B/W Neg.: Squ. M/13.11-12) Stone: (1) B/W Neg.: DHF R/77/02.05-06
<i>Publication</i>	Ballance 1958, 230 no. 2 ('Sarıköy') (notice) RRMAM 2, 1. 637 (notice only)
<i>Description</i>	A simple cylinder and plinth. Broken into two pieces. Pale limestone. Plinth square. Letters: (text 1) slightly worn; (text 2) extremely worn
<i>Dimensions</i>	Ht 2.24; diam. 0.45; (plinth) ht 0.57; wi. 0.61. Letters: (text 1) (line 6) T 0.033, (text 2) (line 5) E of SEM 0.043

<i>Text</i>	(1) (below text [2])
	I(m)perato(r)i Nerva
2	Caesari A[ug] p̄onti- fici /maximo/

4 /t/ribuniciā
 potestate patri
 6 patriae cos III
 [?]

line 3: **ATIXIAD** (lapis)

line 4: **I** (lapis)

(2) (above text [1])

[- - -]
 [- - -]
 3 [- - -]
 [- - -] I
semper
 6 [Au]g[gg]

Caput Viae [Colonia Iconium]

Date (1) AD 97, 01.i-17.ix Nerva Augustus

(2) (?)AD 375-378 Valens, Gratianus and Valentinianus II, cp. below, 76(C)

Commentary (Text 1) According to Kienast (1996, 120), Nerva began began his TR P (I) on 18 September 96 and ended the same on 17 September 97; he did not began his COS III until AD 01 January 97.

76(B). Kızılçakuyu 2, form. Sarayköyü Yayla

Province, Sub-Province + Admin. Code and Map As 76(A)

Location In the village cemetery; c. 1 km S of the village

Copy Ballance 1957; DHF 27.v.1977. DHF squeeze (drawing, Fig. 6.2.52 [p. 293]) and photo. (Pl. 7.1.47 [p. 320]) in BIAA. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 42. Konya 17, Kızılçakuyu 2

Stone: B/W Neg.: DHF R/77/02.07-08

Publication Ballance 1958, 230 no. 3 ('Sarıköy') (notice)

RRMAM 2, 1. 638 (notice only)

Description A simple cylinder and plinth. Broken at top. Pale limestone. Plinth square. Letters: (text 1) faint traces only; (text 2) worn on l.

Dimensions Ht 2.16; diam. 0.53; (plinth) ht 0.46; wi. 0.54. Letters: (text 2) T of **TIF** 0.033

Text (1) (below text [2])
 inscription erased

(2) (above text [1])

I(m)perato(ri) Nervae Caes[ari]
 2 Aug pontifici /maximo/ tri-
 bunicia potestate patri
 4 patriae cos III
 [?]

line 2: **AIXIAD** (lapis)

<i>Caput Viae</i>	[Colonia Iconium]
<i>Date</i>	(1) (?)Titus or Domitianus (2) AD 97, 01.i-17.ix Nerva <i>Augustus</i>
<i>Commentary</i>	(Text 2) According to Kienast (1996, 120), Nerva began his TR P (I) on 18 September 96 and ended the same on 17 September 97; he did not begin his COS III until AD 01 January 97.

76(C). Kızılcakuyu 3, form. Sarayköyü Yayla

<i>Province, Sub-Province + Admin. Code and Map</i>	As 76(A)
<i>Location</i>	In the village; at the house (no. 4) of Seyit Ertuğrul
<i>Copy</i>	DHF 27.v.1977. DHF photo. (Pl. 7.1.48 [p. 320]) and squeeze (photo., Pl. 7.2.31-32 [p. 350]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 42. Konya 18, Kızılcakuyu 3 (= B/W Neg.: Squ. M/13.03-10) Stone: (1) B/W Neg.: DHF R/77/03.04 (2) Col. Slide: DHF 153. 05-06
<i>Publication</i>	RRMAM 2, 1. 639 (notice only)
<i>Description</i>	A simple cylinder. Broken below. Pale limestone. Letters: (text 1) faint traces only; (texts 2 and 3) very slightly worn
<i>Dimensions</i>	Ht 1.10; diam. (top) 0.50. Letters: (text 2) (line 2) T of TIF 0.045; (text 3) (line 2) T of RAT 0.045
<i>Text</i>	(1) (above text [2]) inscription erased
	(2) (below text [1]) /Imp/ Nerva Caesari 2 Aug pontifici /maximo/ tribunicia potestate 4 patri patriae cos III [V]
	line 1: ΙΑΝ (lapis) line 2: ΑΤΙΧΙΑΝ (lapis)
	(3) (on the r. of texts [1] and [2]) ddd nnn Valente 2 Gratiano et Valen[t]- iniano perse- 4 tuis Augg μι ε'
	line 5: ligature ΜΙ , μι(λια)

<i>Caput Viae</i>	(?)
<i>Date</i>	(1) (?)Titus or Domitianus (2) AD 97, 01.i-17.ix Nerva <i>Augustus</i>
<i>Commentary</i>	(3) AD 375, 17.xi-378, 09.viiii Valens, Gratianus and Valentinianus II <i>Augusti</i> (Text 2) According to Kienast (1996, 120), Nerva began his TR P (I) on

18 September 96 and ended the same on 17 September 97; he did not begin his COS III until AD 01 January 97.

77. Akbaş Yayla

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-1
<i>Map</i>	İlgın 60-Io (Eskihan Hr.)
<i>Location</i>	“At the Kutudelik Han” (Ramsay). Present whereabouts not established (DHF visit 26.v.1977)
<i>Copy</i>	Cousin 1898; Ramsay 1904; Calder 1908. The stone has not been examined by DHF. Text here of Ramsay, Callander and MHB(alliance) notes of Calder’s notebook for 1908 (MHB’s note is reproduced here, Fig. 6.1.21 [p. 268])
<i>Publication</i>	Ramsay (W.M.) 1905, 415 no. 7 Cousin 1904, 401-402 AE 1906. 21 (text of Ramsay) Callander 1906, 172 no. 56 (text of Ramsay) Ballance 1958, 230 no. 14 (notice) Robert 1965, 73 (reference to Cousin) RRMAM 2, 1. 594 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	[Imp Caes L Septimius] [S]eve⟨rus⟩ Pius Pertin⟨ax⟩ [A]ug Arab Adiab Par-
	4 thicus maxi⟨mus⟩ pont-
	ifex maximus tribu-
	nicia potestatis VI imp
	[X]I cos pr pr procos et
	8 Imp Cae⟨s⟩ Mar Aur Anto-
	ni⟨nus⟩ Aug cons Parthic⟨us⟩
	max r̄es̄titueru/nt/ per
	[Atticium S]trabonem le-
	12 g Aug⟨g⟩ pr pr milem pass
	ω

- line 5: **IPEX** (Ramsay); **IFEX** (Calder's notebook)
- line 6: **NICIA** (Calder's notebook)
- line 7: **pr pr** (Calder's notebook)
- line 9: ligature **TH**
- lines 9-10: **et L Septimius Geta Caes** once inscribed underneath **cons Parthic⟨us⟩** | **max**, cp. 72. Tilki Han
- line 10: **PE TITUERUMPER** (Ramsay); **[R]E[S]TITUERU[NT]** (Callander); **RESTITUEBUMPER** (Calder)
- line 11: **[-]STRABONEMLE** (Calder)
- line 12: **//////TRMILEMPASS** (Calder's notebook)

<i>Caput Viae</i>	(?)
<i>Date</i>	AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i>

78. Divanlar

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-8
<i>Map</i>	Ilgin 60-Iö
<i>Location</i>	“In the porch of a house” (Ballance 1960). Present whereabouts not established (DHF visit 26.v.1977)
<i>Copy</i>	Ballance 1957. The stone has not been examined by DHF. Text here of Ballance 1960
<i>Publication</i>	Ballance 1958, 230 no. 13 (notice) Ballance 1960, 184 no. 165 RRMAM 2, 1. 612 (notice only)
<i>Description</i>	“Greyish-white limestone column with flat panel projecting from one side, buried below” (Ballance 1960)
<i>Dimensions</i>	“H. 142 plus, diam. 38 (panel 90 x 45), lett. 3.0-3.5 above the panel, wreath of leaves and fruit” (Ballance 1960)
<i>Text</i>	<p>[I]mp Caesar L Se- [pt]imius Severu[s] [P]ius Per̄tinax Aug</p> <p>4 [A]rabicus Adiabē- [ni]cus Par̄thicus [m]aximus pon[t]- [i]fex maxim[us]</p> <p>8 trib potest[ati]- [s V]I imp XI [cons]- [ul] II p p p[rocos] [et] Imp Ca[esar]</p> <p>12 [M]arcus Aū[rel]- [ius] Antonin[us] [Au]g cos Par̄[thi]- [cus m]aximus [res]-</p> <p>16 [tit]uerunt p[er] [.] A[t]ticium S[tr]- [ab]onem legatu[m] Auḡ p̄ p̄ m</p> <p>20 passus (vac) (sic) [?]</p>

line 17: [C] A[t]ticium (Ballance)

lines 14-15: (?) et L. Septimius Geta Caes once inscribed underneath cos
Parthicus maximus, cp. 72. Tilki Han

<i>Caput Viae</i>	(?)
<i>Date</i>	AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) Augusti with L. Septimius Geta (names erased) Caesar

79(A). Obruk 1

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-6
---	---------------

<i>Map</i>	Aksaray 62-In
<i>Location</i>	In the cemetery
<i>Copy</i>	Ramsay 1908; Calder 1908; DHF 01.vi.1977. DHF squeeze (drawing, Fig. 6.2.53 [p. 294]) and photo. (Pl. 7.1.49 [p. 321]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 42. Konya 26, Obruk 1
	Stone: B/W Neg.: DHF R/77/03.09
<i>Publication</i>	Ramsay (W.M.) 1909b, 8 (reference to distance-figure) Ballance 1958, 230 no. 9 (notice) MAMA 8. 261 and Pl. 11 (text of Ballance?) RRMAM 2, 1. 654 (notice only)
<i>Description</i>	A re-used column. Broken above. Grey limestone. The shaft is round. Mouldings at the bottom of the shaft. On the face of the shaft, a flat, raised, rectangular panel. Letters: extremely worn in centre, worn on edges of inscription
<i>Dimensions</i>	Ht 1.15; diam. (base) 0.53; (panel) ht 0.38; wi. 0.35. Letters: (line 6) P of PON 0.033
<i>Text</i>	(on panel)
	[Imp Caesar Divi] [Traiani Parthi]- [ci f divi Nervae]
4	nepos Trajanus Hadrianus Aug pon max trib pot
	(sic)
	XIII cos III
8	(vac) p p (vac) m (vac) [?]
	(below the panel, on the shaft)
10	mil [p] VII
	line 6: ligature IB ; pont (MAMA); pote (MAMA)
	line 7: cos [III] (MAMA)

<i>Caput Viae</i>	(?)
<i>Date</i>	AD 128/129, 10.xii-09.xii Hadrianus Augustus
<i>Commentary</i>	For the shape and the form of this milestone, see above, 70(A). Konya 1

79(B). Obruk 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 79(A)
<i>Location</i>	In the cemetery
<i>Copy</i>	Ramsay 1908; Calder 1908; DHF 01.vi.1977. DHF squeeze (photos, Pl. 7.2.33-34 [p. 351]) in BIAA. No DHF photo. Texts here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 42. Konya 27, Obruk 2 (= B/W Neg.: Squ. M/19.08-15)
<i>Publication</i>	Ramsay (W.M.) 1909b, 8-9 (reference to distance-figure) Ballance 1958, 230 nos 4 and 32 (notice) RRMAM 2, 1. 655 (notice only)

79(C). Obruk 3

<i>Province, Sub-Province + Admin. Code and Map</i>	As 79(A)
<i>Location</i>	In the cemetery
<i>Copy</i>	Ramsay (W.M.) 1908; Calder 1908; DHF 01.vi.1977. DHF squeeze (drawing, Fig. 6.2.54 [p. 294]) in BIAA. No DHF photo. Texts here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 42. Konya 28, Obruk 3
<i>Publication</i>	Ballance 1958, 230 no. 1 (notice) RRMAM 2, 1. 656 (notice only)
<i>Description</i>	A simple cylinder and plinth. Complete. Hard, grey limestone. Plinth square . Letters: very worn
<i>Dimensions</i>	Ht (vis.) 1.90; diam. (top) 0.42; (plinth) wi. 0.48. Letters: (text 1) (line 4) T of TI 0.043
<i>Text</i>	(1) (underneath, on the r. of, and below text [2]) [- - ? - -] [- - - - -] I [- - - - -] TI 4 [- - - - -] A . R

[- - - - -]**I**
[- - -]
[- - - - -]**A**
8 [- - - - -]**A** (vac)
[- - - - -]**PSSAI**
[- - - - -]**IV**
VRM[- -]VM
12 **POMVVIRTF**
l̄eg Aug p[r]o pr
14 **SIIR[- - ? - -]**
(vac)
N&N . . . (?)

(2) (above, on the top, and on r., of text [1])

(vac) **Imp Nerva**
2 **Caesar Aug pont**
max trib pot p p re[s] -
4 **tituit cos III per Pom-** (sic)
ponium Bassum
6 **leg pr pr**
[?]

Caput Viae [?]

Date (1) Domitianus, (?) year

(2) AD 97, 01.i-17.ix *Nerva Augustus*

Commentary Text (1) is clearly earlier than text (2). Even in its present state, however, text (1) does not resemble, in style and form, the known texts of Caesennius Gallus (whether under Titus or under Domitianus). It is difficult to restore the name of Pomponius Bassus in lines 11-12; the date of the milestone, therefore, falls in the middle years of Domitianus' rule, i.e. after the final year of Gallus (AD 82) and before the first year (AD 94) of Bassus.

For the date of text (2), see the commentary above, no. 79(B)

79(D). Obruk 4

Province, Sub-Province + Admin. Code and Map As 79(A)

Location Not given. Present whereabouts not established (DHF visit 01.vi.1977)

Copy Calder 1908. The stone has not been examined by DHF. Text here from

MHB(allance) notes of Calder's notebook for 1908 (MHB's note is reproduced here, Fig. 6.1.22 [p. 268])

Publication Ballance 1958, 230 no. 5 (notice)

RRMAM 2, 1. 657 (notice only)

Description & Dimensions Not given

Text [I]**mp** **N**[erva]e **Caesare Aug** (sic)
2 [pontifici m]aximo **tr**[ib]
[pot]estat[e] pa[tri]
4 [pa]triae [cos III]
[?]

<i>Caput Viae</i>	[?]
<i>Date</i>	Nerva Augustus, (?)AD 97
<i>Commentary</i>	For the date of the text, see the commentary above, no. 79(B)

79(E). Obruk 5

<i>Province, Sub-Province + Admin. Code and Map</i>	As 79(A)
<i>Location</i>	In the cemetery
<i>Copy</i>	(?)Ramsay (W.M.) 1908; Calder 1908; DHF 01.vi.1977. DHF squeeze (drawing, Fig. 6.2.55 [p. 294]) and photo. (Pl. 7.1.50 [p. 321]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 42. Konya 29, Obruk 5 Stone: (1) B/W Neg.: DHF R/77/03.10 (2) Col. Slide: DHF 153. 26-27
<i>Publication</i>	Ballance 1958, 230 no. 17 (notice) RRMAM 2, 1. 658 (notice only)
<i>Description</i>	A re-used column. Broken below. Grey limestone. The shaft tapers slightly towards top. At the top of the shaft: a moulding; on face of shaft: a raised, flat, rectangular panel, above which there is a wreath. Letters: note the bar-less A, the lunate E, the tilted L and the Γ-form S. Letters: very faint traces at top, worn below
<i>Dimensions</i>	Not recorded. Letters: (line 12) T 0.032

<i>Text</i>	[ImpCaesar] [L Septimius] [SeverusPius] 4 [PertinaxAug] [- - -] [- - -] [- - -] 8 [- - -] [- - -] [- - -] [- - -]pr.pr.pro-	(sic)
	12 [c]os·et·Imp·Cae- [s]ar·Marcus Au- relius·Anto[n]- [i]nus·Augus[t]-	
	16 [us cons] Parth[- [icus maximus]	
	- - -	

lines 1-4: faint traces visible
line 13: ligature AV
lines 16, 17: **L. Septimius Geta Caesar** once inscribed underneath **cons Parthicus maximus**, cp. 72. Tilki Han

<i>Caput Viae</i>	[?]
<i>Date</i>	L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i>

with L. Septimius Geta (names erased) *Caesar*, (?) year

79(F). Obruk 6

<i>Province, Sub-Province + Admin. Code and Map</i>	As 79(A)
<i>Location</i>	In the cemetery
<i>Copy</i>	Calder 1908 (“not copied by R(amsay)’); DHF 31.v.1977. DHF squeeze (drawing, Fig. 6.2.56 [p. 295]) in BIAA. No DHF photo. Texts here from DHF squeeze and from MHB(allance) notes of Calder’s notebook for 1908
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 42. Konya 30, Obruk 6
<i>Publication</i>	Ballance 1958, 230 no. 33 and n.11 (notice) RRMAM 2, 1. 659 (notice only)
<i>Description</i>	A simple cylinder and plinth. Complete. Hard, grey limestone. Plinth square. Letters (both texts): very worn
<i>Dimensions</i>	Ht 2.12, diam. (top) 0.50; (plinth) ht 0.50; wi. 0.52. Letters: (text 1) (line 1) I 0.035; (text 2) (line 4) T 0.04
<i>Text</i>	(1) (underneath text [2]) almost entirely obliterated
	(2) (on the l. of, and partly underneath, text [3])
	Imp N̄er[va]e Caesare (sic)
2	Aug p̄o[ntifici] maximo
	tribun[icia potestate]
4	patri [patri]a[e cos III] [I]
	(3) (on the r., and partly on top of, text [2])
	DDD nn̄n
	F (vac) I Valente (sic)
	et Fl Gratiano
4	et Fl Valentiniano
	perpetuis ac victo-
	riosissimis semper
	Auggg
8	μ α'
	line 8: μ(iλια)
<i>Caput Viae</i>	(?)
<i>Date</i>	(1) Titus or Domitianus (2) Nerva Augustus, (?)AD 97 (3) AD 375, 17.xi-378, 09.viii Valens, Gratianus and Valentinianus II Augusti
<i>Commentary</i>	For the date of text (2), see the commentary above, no. 79(B)

79(G). Obruk 7

<i>Province, Sub-Province + Admin. Code and Map</i>	As 79(A)
---	----------

79(H). Obruk 8

<i>Province, Sub-Province + Admin. Code and Map</i>	As 79(A)
<i>Location</i>	“To right of road running south, just outside the town” (Calder's notebook for 1908). Present whereabouts not established (DHF visit 31.v.1977)
<i>Copy</i>	Calder 1908. The stone has not been examined by DHF. Text here from MHB(alliance) notes of Calder's notebook for 1908 (MHB's note is reproduced

here, Fig. 6.1.24 [p. 268])

Publication Ballance 1958, 230 no. 39 (notice) (wrongly assigned to no. 34)

Description & Dimensions Not given

Text (1) (above text [2])
(see Fig. 021)

(2) (below text [1])

- - - -
[-] **se[m]per Augg[g]**
(vac) **M ..**
III

Caput Viae (?)

Date (1) (?)

(2) (?) AD 375-378 Valens, Gratianus and Valentinianus II *Augusti*

F.10 COLONIA ICONIUM (- Sidamaria - Tyana)

80(A). Abuditolu 1

<i>Province, Sub-Province + Admin. Code</i>	Konya, Çumra 42-05-0
<i>Map</i>	Konya 59-Is
<i>Provenance</i>	Brought from the village. Now in the Konya Archaeological Museum [Inv. no. 1994.8.1]
<i>Copy</i>	Drew Bear (? date); Mclean (? date). Texts here from a majuscule copy (in RECAM 4) of Drew Bear, checked by Mclean and edited by George Houston
<i>Publication</i>	RECAM 4 (ed. McLean). 238 and Fig. 278 (text and commentary of Houston) AE 2002. 1446 (text in RECAM 4)
<i>Description</i>	“Column of orangey limestone with three inscriptions; broken at both ends ; surface badly scarred, holed and pitted, especially at the ends. Inscription A, the earliest, wraps around the column at one end; inscription B is at the opposite end, upside down in relation to A; inscription C is about 0.30 below B, oriented in the same direction.” (RECAM 4)
<i>Dimensions</i>	“H. 1.90 (broken); circumference, 0.99 (end with inscr. B), 1.045 (end with inscr. A); lettering: 0.04–0.05 (inscr. A), 0.04 (inscr. B), 0.05 (inscr. C)” (RECAM 4)

<i>Text</i>	(1) (at upper face of shaft)
	dddd nnn[n]
2	Fl Val Constantino A⟨u⟩g [e]t
	Fl Cl Constantino et
4	Fl Constantio et
	Fl Iul Constante
6	nobbb CCC[C]
	[-]

(2) (at lower end of shaft; upside down to text [1])

2 [D] n Fl
 [Vale]ntiniano
 [e]t Fl Valentи tr-

4 [ium]fatoribus s
 [.] A[u]gg

line 4: "the reading of line 4 is quite uncertain" (RECAM 4)
lines 4-5: s | [.] A[u]gg, sl[s] A[u]gg?, i.e. s(emper) Augusti ?
line 5: "presumably AAGG, i.e. Augustis" (RECAM 4)

(3) (at lower end of shaft and below text [2]; upside down to text [1])
et Gratia-
2 no perpe-
tuo A[u]g

Caput Viae [Colonia Iconium]
Date (1) AD 333, 25.xii-335, 18.ix Constantinus I *Augustus* with Constantinus II,
Constantius II and Constans *Caesares*
(2) AD 364, 28.iii-367, 24.viii Valentinianus I and Valens *Augusti*

(3) AD 367, 24.viii-375, 17.xi Gratianus *Augustus* (added to text [2])**80(B). Abditolu 2**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 80(A)										
<i>Provenance</i>	Brought from the village. Now in the Konya Archaeological Museum [Inv. no. 1994.8.2A]										
<i>Copy</i>	Drew Bear (? date); Houston (? date). Text here from a majuscule copy (in RECAM 4) of Drew Bear, checked by George Houston against the stone										
<i>Publication</i>	RECAM 4 (ed. McLean). 239 and Figs 279-280 (text and commentary of Houston)										
<i>Description</i>	AE 2002. 1447 (text in RECAM 4) “Orangey limestone column, badly pitted, tapering slightly, with two inscriptions. Originally erected as a gravestone (no. 138), the stone was subsequently turned upside down for reuse as a milestone (no. 239). Dowel hole on top. Appears to be complete at both ends.” (RECAM)										
<i>Dimensions</i>	“H. 1.68, 0.35 (upper diameter), 1.28 (lower circumference); lettering:” [text A?] “0.35–0.04; lettering:” [text B?] “0.04–0.045” (RECAM 4)										
<i>Text</i>	<p style="text-align: center;">dddd nnnn</p> <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 20%;">2</td> <td>Fl Val Constantino A<u>g</u> [e]t</td> </tr> <tr> <td></td> <td>Fl Cl Constantino et</td> </tr> <tr> <td style="width: 20%;">4</td> <td>Fl Constantio et</td> </tr> <tr> <td></td> <td>Fl Iul Constante</td> </tr> <tr> <td style="width: 20%;">6</td> <td>nobbbb CCCC</td> </tr> </table> <p style="text-align: right;">(sic)</p>	2	Fl Val Constantino A<u>g</u> [e]t		Fl Cl Constantino et	4	Fl Constantio et		Fl Iul Constante	6	nobbbb CCCC
2	Fl Val Constantino A<u>g</u> [e]t										
	Fl Cl Constantino et										
4	Fl Constantio et										
	Fl Iul Constante										
6	nobbbb CCCC										
<i>Caput Viae</i>	[Colonia Iconium]										
<i>Date</i>	AD 333, 25.xii-335, 18.ix Constantinus I <i>Augustus</i> with Constantinus II, Constantius II and Constans <i>Caesares</i>										

80(C). (?) Abditolu

<i>Province, Sub-Province + Admin. Code and Map</i>	As 80(A)										
<i>Provenance</i>	“Unknown provenance” (RECAM 4). Now in the Konya Archaeological Museum [Inv. no. 1996.8.20]										
<i>Copy</i>	McLean (? date). Texts here from RECAM 4										
<i>Publication</i>	RECAM 4 (ed. McLean). 240 and Fig. 281 (text and commentary of Houston)										
<i>Description</i>	AE 2002. 1448 (text in RECAM 4) “Short limestone column. Badly worn inscription is inscribed around almost the entire column. Dowel hole on top. Appears to be complete at top and broken at bottom.” (RECAM 4). A re-used column (RECAM 4. Fig. 281)										
<i>Dimensions</i>	“H. 1.68, 0.35 (upper diameter), 1.28 (lower circumference); lettering: 0.03–0.06” (RECAM 4)										
<i>Text</i>	<p style="text-align: center;">(1) (on the upper face, below the collar)</p> <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 20%; text-align: right;">[DDDD NNNN]</td> <td style="width: 60%; text-align: center;">?</td> </tr> <tr> <td style="width: 20%;">2</td> <td>Fl Val [Constant]ino Aug</td> </tr> <tr> <td></td> <td>et Fl Cl [Constantin]o</td> </tr> <tr> <td style="width: 20%;">4</td> <td>et Fl [Consta]ntio</td> </tr> <tr> <td></td> <td>[et Fl Iul Cons]tante</td> </tr> </table> <p style="text-align: right;">(sic)</p>	[DDDD NNNN]	?	2	Fl Val [Constant]ino Aug		et Fl Cl [Constantin]o	4	et Fl [Consta]ntio		[et Fl Iul Cons]tante
[DDDD NNNN]	?										
2	Fl Val [Constant]ino Aug										
	et Fl Cl [Constantin]o										
4	et Fl [Consta]ntio										
	[et Fl Iul Cons]tante										

6 **LLL**
 (vac)
 mp XI

line 3: “the P at the end is uncertain” (RECAM)
 line 6: LLL for [nobi]III [CCC] (RECAM)?
 line 7: “the M is quite uncertain but seems to be required” (RECAM)

(2) (on top of lines 1-5, and below line 5, of text [1])

	ddd nn[n]
2	Fl Vale[nti et]
	Fl Gr[atiano]
4	et Fl Vale[nti]
	niano PP
6	LLL
	maxim(is)
8	semp(er) Aug

line 5: PP for *perpetui* (Dušanić in AE)
 line 6: LLL for SSS?, i.e. PP|SSS, per|petuis

Caput Viae (Colonia Iconium)

Date (1) AD 333, 25.xii-335, 18.ix Constantinus I *Augustus* with Constantinus II,
 Constantius II and Constans *Caesares*
 (2) AD 375, 17.xi-378, 09.viii Val[ens], Gr[atianus] and Vale[nti]nianus II
 Augusti

Commentary “Since the inscription continues around virtually the entire stone, it is difficult to tell where a given line begins and ends.” (RECAM 4)

The texts here differ from the arrangement of the surviving inscriptions published in RECAM 4. The second text is interpreted as a partial re-use of suitable letters in the first text, particularly at the beginning of each line

81. Karkin

Province, Sub-Province + Admin. Code Konya 42-05-0

Map Konya 60-Is

Provenance In the village

Copy Konya Plain Survey directed by Dr Douglas Baird, 1999

Description Not given

Dimensions Ht 0.80; diam. c. 0.50

<i>Text</i>	D DDD nn[nn]
2	[Fl V]a[l] Cons[tantino Avg
	[et Fl Cl] Const[antino]
4	[et Fl Val] Const[antio]
	[et] Fl Iul[ianus] Const[ante] (sic)
6	NObbb CCC
	[?]

Caput Viae [Colonia Iconium]

Date AD 333, 25.xii-335, 18.ix Constantinus I *Augustus* with Constantinus II,
Constantius II and Constans *Caesares*

F.11 SAVATRA - CANA (- Sidamaria)**82(A). Ennek 1**

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-6
<i>Map</i>	Aksaray 62-Iö
<i>Location</i>	“In the cemetery” (Callander). Present whereabouts not established (DHF visit 01.vi.1977)
<i>Copy</i>	Ramsay 1905; Calder 1908. The stone has not been examined by DHF. Text here from MHB(alliance) notes of Calder’s notebook for 1908 (MHB’s note is reproduced here, Fig. 6.1.25 [p. 268])
<i>Publication</i>	Callander 1906, 160 no. 11 (text from Ramsay) Ballance 1958, 230 no. 20 and n.15 (notice) RRMAM 2, 1. 618 (notice only)
<i>Description</i>	“Round pillar” (Calder)
<i>Dimensions</i>	Not given

<i>Text</i>	- - - -
	[. . . restit]-
	[uerunt] p̄r̄
4	C Atticium
	[Str]abonem
	[legat]um [Au]-
	[gg p]r̄ p̄r̄
8	[- - -]

<i>Caput Viae</i>	[?]
<i>Date</i>	[L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta <i>Caesar</i>], (?) year
<i>Commentary</i>	The text can be dated to the reign of Septimius Severus on the basis of the governor’s name.

82(B). Ennek 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 82(A)
<i>Location</i>	Not given. Present whereabouts not established (DHF visit 01.vi.1977)
<i>Copy</i>	Callander 1904; Calder 1908. The stone has not been examined by DHF. Text here of Callander and from MHB(alliance) notes of Calder’s notebook for 1908 (MHB’s note is reproduced here, Fig. 6.1.26 [p. 269])
<i>Publication</i>	Callander 1906, 160 no. 10 Ballance 1958, 230 no. 23 (notice) RRMAM 2, 1. 619 (notice only)
<i>Description</i>	“Round pillar” (Calder)
<i>Dimensions</i>	Not given

<i>Text</i>	Imp Caes
	M·Iulius
	Filippus
4	p f Aug

et M Iul
Filippus
Caesar
8 **filius eius**
[**r]est[i]tuerunt**]
[per - - -]
- - -

line 1: **IM CES** (Calder)
line 3: **Philippus** (Callander)
line 5: **ETMAUL** (Calder)
line 6: **Philippus** (Callander)
line 9: from Calder's notebook

Caput Viae [?]
Date AD 244, July/Aug.-247, July/Aug. Philippus *Augustus* with Philippus *Caesar*

83. Ağsaklı

Province, Sub-Province + Admin. Code Konya 42-00-6
Map Aksaray 62-Iö
Location In the village; in an *ahır* (byre) at the house (no. 7) of Ahmet Ari, where it is used as the base for a wooden column
Copy DHF 01.vi.1977 and 13.vi.1977. DHF photo. (Pl. 7.1.51 [p. 321]) and squeeze (photo., Pl. 7.2.35 [p. 352]) in BIAA. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
Squeeze: 42. Konya 01, Ağsaklı (= B/W Neg.: Squ. M/13.01-02)
Stone: (1) B/W Neg.: DHF R/77/06.01
Publication French 1981, 170 no. 14
AE 1986. 684 (text of French 1981)
RRMAM 2, 1. 593 (notice only)
Christol and Loriot 2001, 106 no. 1b) (comment on ll. 10-11)
AE 2001. 1915 (notice of Christol and Loriot)
Description A simple cylinder. Pale limestone. The shaft tapers slightly; the top is moulded (?re-used column). On the face of shaft: a raised, flat, rectangular panel; above the panel: a wreath and ties. Letters: worn
Dimensions Ht (vis.) 1.02; diam. (top) 0.33; (panel) ht (ex.) 0.54; wi. 0.26. Letters: (line 5)
T of CTV 0.018

Text **I**mpe/ra/tor C[ae]-
 sar M Aureliu[s]
 [[Antoninus]] [p]ius
4 [f]elix Augustus
 [i]nvictus divi Seve-
 ri nepos divi Anto-
 nini filius rest<itui>-
8 /t/ per L Egnatiu-
 m Lollianum le-
 gatum eius /pr/

12 /pr/ **praesidem p-**
 [r]ovinc⟨i⟩ae Galā-
 (vac) **tiae** (vac)

line 1: **IMPEMTO** (lapis)

line 8: **SPER** (lapis)

lines 10, 11: **PΛ | PΛ** (lapis)

Caput Viae

Date

[?]

AD 218, 16.v-09.xii M. Aurelius Antoninus (Elagabalus) *Augustus*

G. GALATIA

G.1 ANCYRA - COLONIA ICONIUM

84(A). Altinekin 1, form. Zivarık

<i>Province, Sub-Province + Admin. Code</i>	Konya, Cihanbeyli 42-04-1
<i>Map</i>	Ilgın 60-II
<i>Location</i>	“... carried to the cemetery from its original site” (Callander). Present whereabouts not established (DHF visit 03.vi.1977)
<i>Copy</i>	Callander 1904; Ramsay (W.M.) 1905. The stone has not been examined by DHF. Text here of Callander
<i>Publication</i>	Ramsay (W.M.) 1905, 416 (notice) Callander 1906, 173 no. 58 AE 1907. 58 (text of Callander) Ramsay (A.M.) 1909, 27 no. 9 (notice) Ballance 1958, 230 no. 15 (notice) RRMAM 2, 1. 598 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	- - - -
2	restituerunt per C
	Atticum Strabonem leg
4	Aug(g)·pr·pr·mil passu(um)
	(vac) PE
	(sic)

line 2: for **C**(aium), see above. 72(A). Kulak Murat Hanı 1 and 81(A).

Ennek 1

line 5: **PE** (Callander), i.e. ፩, 105 miles; PE here = XL ?

<i>Caput Viae</i>	(?)
<i>Date</i>	[L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with <i>Geta Caesar</i>], (?) year
<i>Commentary</i>	The text can be dated to the reign of Septimius Severus on the basis of the governor's name.

The distance figure, **PE**, i.e. 105 Roman miles (= c. 156 km), is curious. From what *caput viae* was the distance measured? If from Iconium, the “original site” of the milestone would be located c. 156 km N of Konya, at a point 85 km S of Ankara, i.e. c. 100 km N of Altinekin (c. 55 km N of Konya). Perhaps unlikely. If from Ancyra, the “original site” would be situated in the neighbourhood of Cihanbeyli, c. 156 km S of Ankara and c. 45 km N of Altinekin. This latter explanation could be a more reasonable solution. On the other hand, **PE**, a Greek number, is most probably a mis-reading of a Latin figure, (?) **XL**, i.e. 40 MP or c. 60 km; the “original site” of the milestone would then lie a mere 5 km N of Altinekin. It should be noted that the usual practice on Severan stones of Galatia is for the Latin to precede a Greek figure (if any), cp. 123(A). Karaali 1 and 126(B). Yöreli 2, and, on the *Via Sebaste*, 90(B) Gencalı 2.

84(B). Altinekin 2, form. Zivarık

<i>Province, Sub-Province + Admin. Code and Map</i>	As 84(A)
---	----------

Location “In the cemetery” (Callander). Present whereabouts not established (DHF visit 03.vi.1977)

Copy Ramsay (W.M.) 1905. The stone has not been examined by DHF. Text here of Callander

Publication Callander 1906, 173 no. 59 (text from Ramsay [W.M.])
Ramsay (A.M.) 1909, 28 no. 10 (text of Ramsay [W.M.])
MAMA 1. 20 (text of ?)
RRMAM 2, 1. 599 (notice only)

Description & Dimensions Not given

Text

- - - -
[-]P[-]
DIVIV[-]
- - - -

Date (?)
Commentary “The last letter in line 2 is V, not X” (MAMA)

Not a milestone?; see the Calder’s comment in MAMA: “This quarry mark(?) carved close to the r. edge of the lateral band on an ‘engaged’ column, appears to be identical with the inscription published as a milestone in *Stud. E.R.P.*, p.174, no. 59”

84(C). Altinekin 3, form. Zivarık

Province, Sub-Province + Admin. Code and Map As 84(A)

Location In the cemetery

Copy Ramsay (W.M.) 1905; Calder 1910; DHF 03.vi.1977. DHF squeeze (drawing, Fig. 6.2.58 [p. 296]) and photo. (Pl. 7.1.52 [p. 321]) in BIAA. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs
Squeeze: 42. Konya 05, Altinekin 3
Stone: (1) B/W Neg.: DHF R/77/04.05

Publication Callander 1906, 173 no. 60 (text from Ramsay [W.M.])
Ramsay (A.M.) 1909, 28 no. 11 (notice)
Ballance 1958, 230 no. 28 (notice)
RRMAM 2, 1. 600 (notice only)

Description A simple cylinder and plinth. Complete. Hard, pale limestone. Plinth square. Letters: very worn

Dimensions Ht (vis.) 2.00; diam. 0.48; (plinth) wi. 0.60. Letters: (text 2) (line 2) **E** 0.045

Text

(1) (underneath text [2])
traces of an earlier text

(2) (on the top of text [1])

	DDDD nnnn
2	Fl Val Constantino Aug et
	F[[l Constantin]o] et
4	Fl Constan[t]io et
	Fl Iul Cons[t]ante
6	[nobb Caess] A(?)

[-]

<i>Caput Viae</i>	[?]
<i>Date</i>	(1) (?)
	(2) AD 333, 25.xii-335, 18.ix Constantinus I <i>Augustus</i> with Constantinus II, Constantius II and Constans <i>Caesares</i>

84(D). Altınekin 4, form. Zivarık

<i>Province, Sub-Province + Admin. Code and Map</i>	As 84(A)
<i>Location</i>	“In the cemetery at Severek” (Callander); “Suwerek, in the cemetery” (Calder in MAMA). Present whereabouts not established (DHF visit 03.vi.1977)
<i>Copy</i>	Ramsay (W.M.) 1905; Calder 1910. The stone has not been examined by DHF. Texts here of MAMA
<i>Publication</i>	Callander 1906, 173 no. 61 (text from Ramsay [W.M.]) Ramsay (A.M.) 1909, 29 no. 12 (notice) MAMA 1. 17 (text of Calder?) Ballance 1958, 230 no. 25 (notice) RRMAM 2, 1. 601 (notice only)
<i>Description & Dimensions</i>	Not given

Text (1) (below text [2])

- - -
N[.]TI
[- - -]**I O S I S**

lines 1, 2: perhaps one line, not two
line 3: [victor]**iosis**[simis] (MAMA); **IU**[- -]**OΙΠΓ** (Callander)

“In the last line perhaps **M.[P. I]ΠΓ**” (Callander); **M[- -]ΙΠΓ** as one line (Calder’s notebook for 1910)

(2) (above text [1])

	Imp C M Aur Caro
2	p f invicto Aug
	et M Aur Carino
4	[- - - -]
	[- - - -]
6	[- - - -]
	[- - - -]
8	[- - - -]
	et Nomeriano

(sic)

<i>Caput Viae</i>	[?]
<i>Date</i>	(1) (?)
	(2) AD 282, end-283, early Carus <i>Augustus</i> with Carinus and Numerianus <i>Caesares</i>

85. Yazibelen, form. Tutup

Province, Sub-Province + Admin. Code Konya 42-00-8

<i>Map</i>	Ilgin 59-II
<i>Location</i>	"In the cemetery of a village, Tutup, . . ." (Ramsay [A.M.] 1909, 26); still at the cemetery. Used in the foundations of the E wall but visible in the outer face. The inscription is mostly obscured; neither Ballance nor DHF saw the left-hand side of the text.
<i>Copy</i>	Ramsay (W.M.) 1908. Ramsay's drawing, published by Ramsay (A. M.) (1909, Fig. 8), is reproduced here (Fig. 6.1.27 [p. 269]); Ballance 1956; DHF 02.vi.1977. No DHF squeeze. DHF photo. (Pl. 7.1.53 [p. 322]) in BIAA. Text here of Ramsay (A.M.) and (right-hand side only) of Ballance and of French
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Stone: (1) B/W Neg.: DHF R/77/04.04
<i>Publication</i>	Ramsay (A.M.) 1909, 26 no. 8 and Fig. 8 (text of Ramsay [W.M.] 1908) Ballance 1958, 230 no. 8 (notice) RRMAM 2, 1. 669 (notice only)
<i>Description</i>	A simple cylinder and plinth. Complete. Hard, pale limestone. Plinth square. "As the shading shows, almost the whole inscription has been destroyed by the mutilation of the stone; but from the few letters that remain, the whole can be restored with absolute and perfect certainty (except that the numbers of the Tribunician Authority and the Consulship are doubtful). All that can be said is that the inscription, being in honour of Hadrian, probably belongs to the same year as No.1 on this road. The most important point of the whole is the measurement, which fortunately is legible" (Ramsay [A.M.] 1909, 26)
<i>Dimensions</i>	Ht 2.50; (plinth) ht. 0.55; "diam. c.40; letters v(ery) g(ood), 5-6 cm." (Ballance)

<i>Text</i>	[Imp Caesar] [divi Trai]an- [i Parthici f]il di[vi Nerv]ae n- 5 epo[s Tr]ajanu- s Had[rian]us Au- g p[ontife]x m- ax[imus tri]bu- nici[ae pot]es- 10 tat[is XIII] cos (vac) III p [p] (vac) (vac) [-]
-------------	---

The line-endings have been recorded as follows:

	(MHB)	(DHF)
	...AN	...AN
	...IL	...IL
	...AEN	... (vac)
5	...AN[.]	5 ... (vac)
	...VSAV	...AV
	...XM	...M
	...BV	...BV
	...TES	...S
10	...OS	10 ... (vac)

(vac) ?
lines 8-10: for the genitive . . . tribulniciae potestatis . . . , cp. 70(D).
Konya 4
line 10: **COS III** (Ramsay [W.M.]); neither Ballance nor DHF saw
numerals after the **S** of **COS**
line 11: **HIP** (Ramsay [W.M.])

Caput Viae [?]

Date (Ballance) AD 129 Hadrianus

Comment In Hadrianic texts of the same year (AD 129) the imperial titulature is closed with the abbreviation **P P**; accordingly **HIP** (line 11) is here interpreted not as the distance figure but as the remains of **IIIPP**. Other Hadrianic milestones of the year AD 128/129 give the distance-number in Latin alone, never solely in Greek, cp. 70(A). Konya 1, 70(D). Konya 4, 70(E). Konya 5 and 79(A). Obruk 1, all from the Konya region.

H. DE LYCIA ET PAMPHYLIA IN GALATIAM

H.1 VIA SEBASTE

86. Uluborlu

<i>Province, Sub-Province + Admin. Code</i>	Isparta, Uluborlu 32-08-0
<i>Map</i>	Dinar 38-Io
<i>Location</i>	“Near Uluborlu, at a fountain in the valley, about 3 km W of the town” (MAMA). Present whereabouts not established (DHF visit 13.xi.1976)
<i>Copy</i>	Buckler et al. 1930. The stone has not been examined by DHF. Texts here of MAMA
<i>Publication</i>	MAMA 4. 148 (text of ?) and Pl. 38 Christol and Drew Bear 1987, 37 n.87 (comment) RRMAM 2, 1. 404 (notice only)
<i>Description</i>	“Milestone, broken at top, the inscription beginning directly below the break” (MAMA)
<i>Dimensions</i>	“H. (vis.) 0.55; diam. 0.48; letters: 0.03 to 0.04” (MAMA)
<i>Text</i>	<p>(1) [Imperator Caesar] [Lucius Septimius] [Severus Pius]</p> <p>4 [Pertinax Augustus] [Arabicus Adiaben]- cus Parthicus [max ponti]fex max</p> <p>8 [t]rib [p]ot VI imp XI cos [II procos et] Imp Caes M Aurel Antoninus Au[g] invict·Augg</p> <p>12 (vac) restituerunt M III δ'</p>
	line 8: [t]rib [p]ot XI (MAMA)
	line 11: <i>om.</i> MAMA but visible in photo, Pl. 38; (?) et L Sept Geta Caes originally inscribed underneath invict·Augg , cp. 72. Tilki Han
(2)	- - - ppp fff invict Augg
<i>Caput Viae</i>	(Apollonia)
<i>Date</i>	(1) AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i> (2) (?) Constantinus I and sons, cp. 87(A). Yassören 1, text (2), AD 333-335, then 337-340

87(A). Yassören 1

<i>Province, Sub-Province + Admin. Code</i>	Isparta, Senirkent 32-05-0
<i>Map</i>	Dinar 40-Io
<i>Location</i>	“In the corner of the street, diagonally opposite the inscribed Dibek Tashü” (Sterrett). Present whereabouts not established (DHF visit 13.xi.1976)
<i>Copy</i>	Sterrett 22 September, 1885; Ramsay (W.M.) 1888. The stone has not been examined by DHF. Texts here of CIL (Sterrett and Ramsay)
<i>Publication</i>	Sterrett 1884-85, 387 nos 560, 561 CIL 3. 6970/1 (text of Sterrett and copy from Ramsay) RRMAM 2, 1. 405 (notice only)
<i>Description</i>	“Columna miliaria” (CIL)
<i>Dimensions</i>	“Alta ped. 5, diam. ped. 1 1/2” (CIL), i.e. ht 1.52, diam. 0.46

<i>Text</i>	(1) [Imp Caesari divi]
	2 [Traiani f divi Ner]-
	[vae] nepoti [Trai]-
	4 [an]o A[d]rian[o pont]
	[max] trib p [ot VI]
	6 (vac) c [os] III [p p]
	(vac) [-]

the text is here restored after 88(A). Esendere 1

(2)	(vac) DD
2	FL VAL CONST
	MAX C
4	C
	ET FL
6	PPP FFF
	INVICT[I]S

(possible restoration)	
	(vac) DD [nn]
2	Fl Val Const [antino]
	max [Au]g [et Fl Constant]-
4	[in]o [et Fl Constantio]
	et Fl [Constanti]
6	ppp fff
	inv[i]ctis
	[Auggg]

line 1: **DD** [nn], cp. 94(A). Dedeçam 1, text (6)

line 2: **max** [Au]g, cp. 88(C). Esendere 3, text (2)

line 8: [Auggg], cp. 86. Uluborlu, text (2)

<i>Caput Viae</i>	[Apollonia]
<i>Date</i>	(1) Hadrianus (?) or (possibly) Antoninus Pius
	(2) (?) Constantinus I <i>Augustus</i> with Constantinus II, Constantius II and Constans <i>Caesares</i> , AD 333-335, then 337-340 Constantinus II, Constantius II and Constans <i>Augusti</i>

87(B). Yassören 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 87(A)
<i>Location</i>	Not given. Present whereabouts not established (DHF visit 13.xi.1976)
<i>Copy</i>	Ramsay (W.M.) 1888. The stone has not been examined by DHF. Text here of CIL (Ramsay)
<i>Publication</i>	CIL 3. 6972 (copy from Ramsay) RRMAM 2, 1. 406 (notice only)
<i>Description</i>	“Columna miliaria parva, quales solent esse positae saeculo quarto, ...” (CIL)
<i>Dimensions</i>	Not given
<i>Text</i>	- - - [- - -]to Augusto
<i>Caput Viae</i>	[Apollonia]
<i>Date</i>	(?)

88(A). Esendere 1, form. Bü. Kabaca

<i>Province, Sub-Province + Admin. Code</i>	Isparta, Senirkent 32-05-0
<i>Map</i>	Dinar 40-In
<i>Location</i>	“In the cemetery” (Sterrett; MAMA). Present whereabouts not established (DHF visit 13.xi.1976)
<i>Copy</i>	Sterrett 22 September, 1885; Ramsay (W.M.) 1888; Buckler et al. 1930. The text published by Sterrett is reproduced here (Fig. 6.1.28 [p. 269]). The stone has not been examined by DHF. Text here of MAMA
<i>Publication</i>	Sterrett 1884-85, 400 no. 587 CIL 3. 6968 (texts of Sterrett and copy from Ramsay) MAMA 4. 234 (text of Buckler et al.) and Pl. 50
<i>Description</i>	“Limestone miliarium” (MAMA)
<i>Dimensions</i>	“H. (vis.) 1.30; diam. 0.55; letters: 0.025” (MAMA)

<i>Text</i>	Imp Caesare divi	(sic)
2	Traiani·f·divi Nervae	
	nepoti Traiano	
4	Adriano Aug·pont [max]	
	trib·p·VI·cos III [p p]	
6	(vac) XII (vac)	

line 5: **VI** (MAMA); **VII** (CIL); **cos III** [p p] restored after 90(A).
Gençali 1, text (1)

<i>Caput Viae</i>	(Apollonia)
<i>Date</i>	AD 121/122, 10.xii-09.xii Hadrianus <i>Augustus</i>

88(B). Esendere 2, form. Bü. Kabaca

<i>Province, Sub-Province + Admin. Code and Map</i>	As 88(A)
---	----------

<i>Location</i>	“In the northern cemetery” (Sterrett). Present whereabouts not established (DHF visit 13.xi.1976)
<i>Copy</i>	Sterrett 22 September, 1885; Ramsay (W.M.) 1888; Buckler et al. 1930. The text published by Sterrett is reproduced here (Fig. 6.1.29 [p. 269]). The stone has not been examined by DHF. Texts here of MAMA
<i>Publication</i>	Sterrett 1884-85, 401 no. 588 CIL 3. 6969 (text of Sterrett and copy from Ramsay) MAMA 4. 233a (text of Buckler et al.) and Pl. 50 Christol and Drew Bear 1986, 45 (comment on text) Christol and Drew Bear 1987, 20 n.31 (comment) RRMAM 2, 1. 388 (notice only)
<i>Description</i>	“Limestone miliarium, broken above and below” (MAMA)
<i>Dimensions</i>	“H. 0.91; diam. 0.43; letters: 0.02 to 0.04; figures at bottom 0.09” (MAMA)

<i>Text</i>	(1) (vac) dd nn Fl Val Constantino [[et Val Licinniano]]
	4 [[Licinnio]] [pp ff inv]ic- [tis A]ug[g et] Fl Val Cr(i)spo
	et Val Constantino
	Licinnio et Fl Val
	8 Constanti<no> nobb
	Caess
	[?Ab Apol]lonia
	[XX]
	line 1: ddNN (photo. MAMA 4. Pl. 50)
	line 4: [Licinio pa] tri·ff·f·invict[i]s (CIL); here restored on the basis of the photo. MAMA 4. Pl. 50
	lines 4-5: here INV]IC [TIS; traces of IC visible in photo. MAMA 4. Pl. 50; space for TIS available before AUGG
	line 5: [A]ugg et F·Val· etc. (CIL)
	line 6: Fl Val Constantino (MAMA)
	(2) DD nn Fl Constantino 2 invict Aug et Fl Iul Crispo <et> 4 Fl Constantino nobb Caess 6 (vac) XX (vac)
	line 1: DDNN (photo. MAMA 4. Pl. 50)

<i>Caput Viae</i>	Apollonia
<i>Date</i>	(1) AD 317 or 318 (Christol and Drew Bear) Constantinus I and Licinius I Augusti with Crispus, Licinius II and Constantinus II <i>Caesares</i>
	(2) AD 324, 19.ix- 326, (?)March Constantinus I <i>Augustus</i> with Crispus and Constantinus II <i>Caesares</i>

88(C). Esendere 3, form. Bü. Kabaca

<i>Province, Sub-Province + Admin. Code and Map</i>	As 88(A)
<i>Location</i>	Formerly in the cemetery on S side of the village; now in front of the mosque (in Orta Mahalle)
<i>Copy</i>	DHF 13.xi.1976. DHF squeeze (drawing, Fig. 6.2.59 [p. 296]) and photo. (Pl. 7.1.54 [p. 322]) in BIAA. Texts here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 32. Isparta 33, Esendere 3
	Stone: (1) B/W Neg.: DHF R/76/23.04
<i>Publication</i>	RRMAM 2, 1. 390 (notice only)
<i>Description</i>	A simple cylinder. Complete. Pale limestone. Inscribed face smoothed and recessed. Letters: worn
<i>Dimensions</i>	Ht 1.70; diam. (bottom) 0.60. Letters: (line 6) T of STA 0.033
<i>Text</i>	(1) (underneath text [2]) [Impe]ṛā[tori] Cae[s] [- - - -]II cos
	(2) (on the top of text [1]) dd[n]n 2 [Fl Va]l Cōnstantino (vac) max (vac) Aug 4 [[et Fl Cl Constantino]] et Fl Iul Constantio 6 et Fl Iul Constanti - - -
	line 4: line erased

<i>Caput Viae</i>	(Apollonia)
<i>Date</i>	(1) (?)
	(2) AD 333, 25.xii-335, 18.ix Constantinus I <i>maximus Augustus</i> with Constantinus II, Constantius II and Constans <i>Caesares</i>

88(D). Esendere 4, form. Bü. Kabaca

<i>Province, Sub-Province + Admin. Code and Map</i>	As 88(A)
<i>Location</i>	Lying on N side of a concrete irrigation channel in the field of Hüseyin Erdem; at a place called Boda Kırı Mancarlı, c. 3 km SSE of the village, c. 500 m S of the main road and c. 100 m W of a track to/from the village
<i>Copy</i>	DHF 13.xi.1976. DHF photo. (Pl. 7.1.55 [p. 323]) and squeeze (photo., Pl. 7.2.36 [p. 352]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 32. Isparta 34, Esendere 4 (= B/W Neg.: Squ. M/19.06-07)
	Stone: (1) B/W Neg.: DHF R/76/23.05
<i>Publication</i>	French 1980, 727 map 2 (site no. 5) (notice)
<i>Description</i>	RRMAM 2, 1. 391 (notice only) A simple cylinder (re-cut from an [earlier] semi-fluted column). Broken below; now in two pieces. White marble. Letters: sharp and clear

Dimensions Ht 0.68 + 0.97; diam. (top) 0.495. Letters: (line 1) **I** of **IMP** 0.082, **E** of **CAE** 0.05, (line 3) **E** 0.033

Text

2	Imp·Caesar·Divi·f· Augustus·pont·maximus· cos·XI·desig·XII·imp [XV]
4	trib·potest·XIX [viam] (vac) Sebaste[n curante]
6	Cornut[o Aquila leg suo] (vac) [pro pr fecit] (vac) [-]

Caput Viae (Apollonia)
Date 6 BC, 26.vi-31.xii Augustus

88(E). Esendere 5, form. Bü. Kabaca

Province, Sub-Province + Admin. Code and Map As 88(A)

Location Found together with 88(D)

Copy DHF 13.xi.1976. DHF squeeze (drawing, Fig. 6.2.60 [p. 296]) and photo.
(Pl. 7.1.56 [p. 323]) in BIAA. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 32. Isparta 35, Esendere 5
Stone: (1) B/W Neg.: DHF R/76/23.06

Publication RRMAM 2, 1. 392 (notice only)

Description A simple cylinder. Complete. Pale limestone. Shaft oval in section. Letters: worn

Dimensions Ht 1.18; wi. (top) 0.39. Letters: (line 1) **E** 0.035

Text (1) (underneath text [2])
faint traces only

(2) (on top of text [1])

2	Imp·Caes· M·Aur·Caro Aug·et
4	M·Aur·Carino nob Caes Aug
6	et M·Aur·Numeriano nobilissimo Caesari [-]

line 6: **O** for **U**

Caput Viae (Apollonia)
Date (1) (?)
(2) AD 282, end-283, early(?) M. Aurelius Carus *Augustus* with M. Aurelius Carinus and M. Aurelius Numerianus *Caesares*

89. “Sarıyar”

<i>Province</i>	Isparta, Senirkent ?
<i>Map</i>	Akşehir 41-In ?
<i>Location</i>	“«Sariyar dans un champ à trois heures d’Uluborlu» . . . c’est-à-dire sur le versant septentrional du Barla Dağ” (IK). Sariyar: possibly a local toponym in the region W of Gençalı ?
<i>Copy</i>	Ramsay 1924/25. The text with a facsimile, p. 150 (reproduced here, Fig. 6.1.30 [p. 269]), from Ramsay’s <i>Note-book</i> (1924/25 no. 3) is published in IK IK 67. 158 (text of Ramsay)
<i>Publication</i>	
<i>Description</i>	“Broken but no traces of letters below” (Ramsay quoted in IK)
<i>Dimensions</i>	Not given

Text

	Imp C[aes] P [L]
2	Valeriano
	[p] f Aug
4	et Imp Caesar(i)
	P L Gallieno
6	p f Aug filio
	eius (v) mp

lines 1 and 5: **P(ublius) L(icinius)**

lines 3 and 6: **p(io) f(elici)**

Caput Viae

<i>Date</i>	AD 253, Sept./Oct-255 Valerianus and Gallienus <i>Augusti</i>
<i>Commentary</i>	The date here assumes that Valerianus <i>iunior</i> had not yet been named <i>Caesar</i> . He became <i>Caesar</i> in AD 255; see Kienast (1996, 221).
	According to Kienast (1996, 218), Gallienus became <i>Caesar</i> Sept./Okt. 253 and <i>Augustus</i> “vor Okt. 23 253.”

90(A). Gençali 1

<i>Province, Sub-Province + Admin. Code</i>	Isparta, Senirkent 32-05-0
<i>Map</i>	Akşehir 41-In
<i>Location</i>	“In its burial ground” (Hamilton). Present whereabouts not established (DHF visit 15.xi.1976)
<i>Copy</i>	Hamilton 19 August, 1837; Ramsay (W.M.) (? 1888). The stone has not been examined by DHF. Texts here of CIL (Hamilton; Ramsay)
<i>Publication</i>	Hamilton 1842, 2, 360 and 489 no. 448 Le Bas and Waddington 1870, 2, 337 no. 1385 <i>ter</i> (text of Hamilton; Hamilton’s caption mis-read by Le B. and W. and assigned to “Isaura”) CIL 3. 319 (text of Hamilton) CIL 3. 6965-6967 (copy from Ramsay) CIL 3. 12216 (note on 6965-6967) Christol and Drew Bear 1987, 20 n.31 (comment) RRMAM 2, 1. 393 (notice only)
<i>Description & Dimensions</i>	Not given
<i>Text</i>	(1) (6967) [Imp] Caesar

2 [divi Traian]i f·divi
Nervae nep
4 **Traia[n]us Hadr[i]-**
anus Aug pon[t]
6 **max tri[b p]ot XII**
cos III p p
8 (vac) **XXIX** (vac)

line 6: (?) **max tri[b p]ot VI**, cp. 88(B). Esendere 2
lines 6-8: line over numerals

(2) (6965) **DD nn**
Fl Val Constantino
et [[Val Licin]niā[no Lici]]-
4 **nnio pp [f]f invictis Augg**
et Fl Va⟨l⟩ Crispo et Val (sic)
Constantino Licinnio
7 (?vac) **CILNOBB** (sic)
7a (?vac)
8 **Apollonia**
m p (vac)
(vac) **XVIII** (sic)

line 1: **DDNN** (CIL 3. 6965)
line 3: *[Val Licin]niō [piis]* (CIL 3. 6965)
line 4: *[felicibus]* invictis Augg (CIL 3. 6965)
lines 3-4: ET [- - -] | **PRCCIK** | **INVICTIS** ('exemplum' [from
Ramsay?] CIL 3. 6965)
lines 7-7a: [et Fl Cl Constantino] | [nobb Caess] ?
line 10: [X]**XVIII** ? (CIL)

(3) (6966) **DDD nnn**
2 **Constantino p f invīc**
Aug et F[l] Iul Crispo Fl
4 **C C Cons**
- ? -

line 1: (?) **DDD nnn** [Fl]
lines 3-5: (?) **Aug et F[l] Iul Crispo** ⟨et⟩ | **Fl Cl** * **Cons** [tantino nobb] |
[Caess], cp. 88(A). Esendere 1, text (2)

<i>Caput Viae</i>	Apollonia
<i>Date</i>	(1) Hadrianus <i>Augustus</i> , AD 127/128, 09.xii-10.xii or 121/122 if line 6: tri[b p]ot VI cp. 88(A). Esendere 1
	(2) AD 317 Constantinus I and Licinius I <i>Augusti</i> with Crispus, Licinius II [and ? Constantinus] <i>Caesares</i>
	(3) AD 324, 19.ix- 326, (?)March Constantinus I <i>Augustus</i> with Crispus and Constantinus II <i>Caesares</i>
<i>Comment</i>	Pace reported another Latin text nearby (1916-1920, 51 no. 40 "A poco

distanza da questo cippo” [= here 90(B). Gençali 1] “ho visto un frammento simile (cm. 48 x 18) di marmo, rotto di recente, con resti insignificanti di iscrizione imperiale latina”.

**IVPOTX
OSIIIPP
AVIV**

It is possible that this fragment is part of CIL 3. 6967 = here text (1).

90(B). Gençali 2

	<i>Province, Sub-Province + Admin. Code and Map</i>	As 90(A)
<i>Location</i>	“Poco lungi dal villaggio sulla via, in una piccola vigna di Osmanoglu Osman, esiste in parte intatta, un’antica pietra miliare” (Pace). Now in the village; used as a support for the gate into garden of the mosque	
<i>Copy</i>	Pace May-September, 1914; Ballance 1956; DHF 15.xi.1976. The drawing published by Pace is reproduced here (Fig. 6.1.31 [p. 270]). DHF squeeze (photo., Pl. 7.2.37 [p. 353]) in BIAA. No DHF photo. Texts here from Pace and from DHF squeeze	
<i>BIAA Collections: Squeeze and Stone Photographs</i>		
<i>Publication</i>		Squeeze: 32. Isparta 36, Gençali 2 (= B/W Neg.: Squ. M/19.04-05)
		Pace 1916-20, 51 no. 29
		AE 1922. 5 (text of Pace)
		Ballance 1958, 232 n.16 (notes on text)
		Ballance 1960, 138 no. 137
		French 1976a, 53 (notice)
		RRMAM 2, 1. 394 (notice only)
<i>Description</i>	“Miliare informa di cippo cilindrico di pietra . . .” (Pace). A simple cylinder. Complete except for chips. Pale limestone. Upper lines damaged and worn. Letters: slightly worn	
<i>Dimensions</i>	“Diametro di 59 cm. scritto per 29 cm. con lettere molto regolari di cent. 3” (Pace). Letters: (line 11) E 0.03	
<i>Text</i>	(1) (underneath, and on the l. of, text [2])	

Imp·Caes·Sept
 Sever[u]s [Pius] P[ertinax]
 Aug·Arabicus [Adiabe]-
 4 nicus Parthicus·ma-
 ximus·pontifex·maximus
 trib·pot·VI·imp·XI·cos II
 p·p·procos·et·Imp
 8 Caes·M·Aur·Antoni-
 nu[s] Aug·cos·Parthicus
 maxi[m]us·restituerunt
 run[t]·per·T·Atticiu-
 12 m·No[rba]num·S(t)rabonem
 leg·Aug(g)·pr·pr·mil·pass
XXIX

lines 9-10: **et L Septimius Geta Caesar** once inscribed underneath **cos**

Parthicus I maximus, cp. 72. Tilki Han

(2) (on the r., and on the top, of text [1])

Fl Iovi[ano] (?)**perp Aug (?)**

<i>Caput Viae</i>	(Apollonia)
<i>Date</i>	(1) AD 198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i> (2) (?)AD 363, 27.vi-364, 17.ii Flavius Iovianus <i>Augustus</i>

90(C). Gençali 3*Province, Sub-Province + Admin. Code and Map* As 90(A)*Location* In the Polatdede Türbesi in the cemetery on SE of the village*Copy* Waldmann 1973; DHF 23. vii. 1974. Waldmann squeeze in Vienna (schedae Gençali 6); DHF squeeze (drawing, Fig. 6.2.61 [p. 296]) in BIAA. No DHF photo. Text here from DHF squeeze*BIAA Collections: Squeeze and Stone Photographs*

Squeeze: 32. Isparta 37, Gençali 3

Publication French 1976a, 53 (notice only)

French 1980, 727 map 2 (site no. 6) (notice only)

Waldmann 1981, 99 no. 7 and Pl. 10

Christol and Drew Bear 1986, 52, facsimile Fig. 2 and photo. Pl. 1 no. 2

RRMAM 2, 1. 395 (with DHF text)

Christol, Drew-Bear and Özsait 1993, 168 n.54 (comment on 1. 5: -TEM, not -TEN)

Description A simple cylinder. Complete. Pale limestone. Inscribed face smoothed and recessed. Letters: very worn*Dimension* Ht (vis.) 1.80; diam. (top) 0.55. Letters: (line 1) **I** of **IMP** 0.065, **E** 0.053, (line 3) **E** 0.035, (line 8) numerals 0.085*Text* **Imp·Caesar·Diyi f**

2	Auguſtuſ·pont·m̄axim̄
	cōns XI desig·XII·im[p XV]
4	t[r]ib p[o]teſt·XIIIX·yiam
	[Seba]ſten curant[e]
6	Cornuto Aqui[l]a leg
	suo pro·pr·fecit
8	XXIII

line 2: ligature **NT**line 3: horizontal bar over **XII**line 4: horizontal bar over **XIIIX**line 5: [Seba]**ſtem** (Christol and Drew Bear 1986 and Christol et al.);
ligature **NT***Caput Viae* (Apollonia)*Date* 6 BC, 26.vi-31.xii Augustus

Comment Waldmann's copy is poor, as perhaps was his squeeze (examined by Drew Bear; see the commentary by Christol and Drew Bear [1986, 52]). The DHF squeeze (drawing, Fig. 6.2.61 [p. 297]) clearly shows letters which perhaps, on the Waldmann squeeze, either are obscure or were not impressed on the squeeze paper. Following the re-edition of Christol and Drew Bear, I have indicated the status of certain readings by the use of additional marks not employed for the text given in RRMAM 2, 1. 395.

90(D). Gençali 4

<i>Province, Sub-Province + Admin. Code and Map</i>	As 90(A)
<i>Location</i>	In the village; in an <i>ahur</i> (byre) at the house of Ali Aslan
<i>Copy</i>	Waldmann 1973; DHF 23.vii.1974 and 15.xi.1976. Waldmann squeeze in Vienna (schedae Gençali 7); DHF squeeze (photo., Pl. 7.2.38 [p. 355]) in BIAA. No DHF photo. Texts here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 32. Isparta 38, Gençali 4 (= B/W Neg.: Squ. M/19.02-03)
<i>Publication</i>	Waldmann 1981, 100 no. 8 and Pl. 11 Christol and Drew Bear 1986, 47 n.30 (revision of Waldmann text) RRMAM 2, 1. 396 (with DHF text)
<i>Description</i>	A simple cylinder. Broken above and below. Pale limestone. Letters: slightly worn
<i>Dimensions</i>	Ht 0.33; diam. (bottom) 0.44. Letters: (text 1) (line 4) E 0.03, (text 2) U 0.033
<i>Text</i>	(1) [- - et Val Constan]- [tino] L<small>i</small>cinnio et Cl [Val] Constantino nobb (vac) Caess 5 (?vac) Apollo' - ? -

line 3: “**noobb** (sic!)” (Waldmann, followed by Christol and Drew Bear)
 line 5: (?) [Civ(itas)] **Apoll**(oniensium), cp. 09 Ertuğrul: **civitat·Pess**, and RRMAM 6 (Lycia et Pamphylia). 32(A) İğdecik 1: [A] **civitat(e)**
Conanensium

(2)	----
	Augg
	MX[-]

<i>Caput Viae</i>	Apollonia
<i>Date</i>	(1) AD 317 or 318 (Christol and Drew Bear) rather than AD 317-324 (DHF), [Constantinus I and Licinius I <i>Augusti</i> with Crispus,] Licinius II and Constantinus II <i>Caesares</i>
	(2) (?)

90(E). Gençali 5

<i>Province, Sub-Province + Admin. Code and Map</i>	As 90(A)
<i>Location</i>	In the cemetery on SE of the village; just to E of the Polatdede Türbesi
<i>Copy</i>	DHF 16.xi.1976. DHF squeeze (drawing, Fig. 6.2.62 [p. 297]) and photo.

(Pl. 7.1.57 [p. 323]) in BIAA. Texts here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 32. Isparta 39, Gençali 5

Stone: (1) B/W Neg.: DHF R/77/01.01

Publication RRMAM 2, 1. 397 (notice only)

Description A simple cylinder. Complete but surface worn. Pale limestone. Letters: worn

Dimensions Ht (vis.) 1.45; diam. 0.47. Letters: (text 3) **E** of **TE** 0.04, (text 4) **T** 0.035

Text (1) (below, and on the r. of, text [3] line 8)

XXIX

(2) (underneath both texts [3] and [4])
letters visible

(3) (below text [4]; line 1 underneath line 5 of text [4])

[DD nn]

2	Fl [V]al Constantino
	max Aug
4	et [Fl [Cl Constantino]]
	et Fl Iul Constantio
6	et Fl Iul Constante
	[- - - - -]
8	[- - - - -]

ui uθ'

line 2: the line was erased and **MAX AVG** substituted

line 3: erasure, **[Fl** [Cl Constantino]**]**

lines 7-8 erased; perhaps **[[et Fl Dalmatio] | nobbbb Caessss]**

line 9: **ui(λια)**

(4) (above text [3]; line 5 on top of line 1 of text [3])

Ddot D (v) **nn**

2	Fl Valentinian[o]
	et Fl Valente
4	et Fl Gratiano
	A[ugg]g

Caput Viae (Apollonia)

Date (1) (?)

(2) (?)

(3) AD 333-335, Constantinus I *Augustus* with Constantinus, Constantius and Constans *Caesares*, and AD 335-337 with Dalmatius

(4) AD 367, 24.viii-375, 17.xi Valentinianus I, Valens and Gratianus *Augusti*

Commentary In text [3] there are traces of erasure, certainly of Constantinus II, probably of Dalmatius.

90(F). Gençali 6

<i>Province, Sub-Province + Admin. Code and Map</i>	As 90(A)
<i>Location</i>	Lying beside and below the new main-road (from Uluborlu to Yalvaç) as seen by SM in 1974; c. 2.90 km E of the Gençali cemetery (and the Polatdede türbesi). Brought up by bulldozers in road-widening operations; as found, probably <i>in situ</i>
<i>Copy</i>	SM 1974; DHF 03.viii.1983. SM and DHF squeezes (drawing of DHF squeeze, Fig. 6.2.63 [p. 297]) in BIAA. DHF photo. in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 32. Isparta 40 (DHF) & 41 (SM), Gençali 6
	Stone: (2) Col. Slide: DHF Col. 236.35
<i>Publication</i>	RRMAM 2, 1. 398 (notice only)
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. Inscribed surface smoothed. Letters: worn
<i>Dimensions</i>	Ht 1.66; diam. (top) 0.55. Letters: (text 1) (line 5) L of MIL 0.033, (text 3) (line 5) O of CON 0.027

Text (1) (on the lower face of the shaft, below text [3]; the top lines were removed by text [2])

- - - -

2	[- - re]st̄i[tue]-
	runt̄ per T [Attici]-
4	um Noranum Št[rabonem]
	leg Aug<g> pr·pr milia
6	(vac) XXVII

(2) (on the upper face of the shaft; obscured by text [3]; above the remains of text [1])

- - - -

2	[[- pp ff i]] nv
	Auḡ et Fl Val [Crispo]
4	et Val Const[antino]
	[Licinnio - -]

- - - -

(3) (on the upper face of the shaft; obscuring text [2]; above the remains of text [1])

	dd̄ n̄n
2	Fl Constantino
	maxi Aug
4	[[-----]]
	et Fl Iul·Cons[t]antio
6	et Fl Iul Constante
	et [[- - -]]]

- - - -

line 2: the line was erased and **MAXI AVG** substituted

line 4: erasure [[et Fl Cl Constanti]no]]

lines 7-8: **et** [[Fl Dalmatio]] | [nobbbb Caessss]

<i>Caput Viae</i>	(Apollonia)
<i>Date</i>	(1) AD 197/198(?), [L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with P. Septimus Geta <i>Caesar</i>] (2) AD 317 or 318 (Christol and Drew Bear) rather than AD 317-324 (DHF), [Constantinus I and Licinius I <i>Augusti</i> with Crispus,] Licinius II [and Constantinus II <i>Caesares</i>] (3) AD 333-335, Constantinus I <i>Augustus</i> with Constantinus, Constantius and Constans <i>Caesares</i> , and AD 335-337 with Dalmatius (4) AD 367, 24.viii-375, 17.xi Valentinianus I, Valens and Gratianus <i>Augusti</i>
<i>Commentary</i>	Text (1) can be dated to the reign of Septimius Severus on the basis of the governor's name. In text [3] there are traces of erasure, certainly of Constantinus II, less clearly of Dalmatius.

90(G). Gençali 7

<i>Province, Sub-Province + Admin. Code and Map</i>	As 90(A)
<i>Location</i>	As 90(F). Gençali 6
<i>Copy</i>	SM 1974. SM squeeze (drawing, Fig. 6.2.64 [p. 298]) in BIAA. Text here from SM squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 32. Isparta 42, Gençali 7
<i>Publication</i>	RRMAM 2, 1. 399 (notice only)
<i>Description</i>	Not known. Letters: slightly worn
<i>Dimensions</i>	Not known. Letters: (text 2) (line 3) O 0.03
<i>Text</i>	(1) (underneath text [2]) almost entirely obliterated
	(2) (on the top of text [1]) Imp·Caes 2 M·Iul Philipp[o] nobilissi- 4 mo Imp filio Aug (vac) (leaf) (leaf) (vac)

lines 3-4: nobillissimo Imp(eratoris) filio Aug(ustus)

<i>Caput Viae</i>	(Apollonia)
<i>Date</i>	(1) (?) (2) AD 247, July/Aug.-249, Sept./Oct. Philippus II <i>Augustus</i>
<i>Comments</i>	A milestone in appearance and form; the mile-figure was perhaps obliterated along with the rest of text (1). It is possible that the stone was a boundary-marker/road-terminus stone on the road between Colonia Antiochia and Apollonia.

90(H). Gençali 8

<i>Province, Sub-Province + Admin. Code and Map</i>	As 90(A)
<i>Location</i>	As 90(F). Gençali 6

<i>Copy</i>	SM 1974. SM squeeze (drawing, Fig. 6.2.65 [p. 298]) in BIAA. Text here from SM squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 32. Isparta 43, Gençali 8
<i>Publication</i>	RRMAM 2, 1. 400 (notice only)
<i>Description</i>	Not known. Letters: worn
<i>Dimensions</i>	Not known. Letters: (text 2) (line 5) P of PON 0.025, (line 6) O 0.015
<i>Text</i>	(1) (underneath text [2]) obliterated
	(2) (on the top of text [1])
	Imp C δivi Šepti[mi]
2	Sey[e]ṛi n̄epos δiyi
	M Aὐ̄rel m[agni] (?) Antonini f]
4	[Marcus Aurelius Ant]oni[n]-
	us pius felax Aug ponti-
6	f[e]x maximus trib potes [co]s p p procons reſtituit
	(sic)

<i>Caput Viae</i>	(Apollonia)
<i>Date</i>	(1) (?)
<i>Comment</i>	(2) AD 218, 16.v-09.xii M. Aurelius Antoninus (Elagabalus) <i>Augustus</i>
	Extremely difficult to read. The text is a mixture of Greek and Latin letters. There are variant forms of the same letter, e.g. S normal and reversed (consult the drawing, Fig. 096)

91(A). Aş. Kaşıkara 1

<i>Province, Sub-Province + Admin. Code</i>	Isparta, Yalvaç 32-09-2
<i>Map</i>	Akşehir 42-Im
<i>Location</i>	In the village; at the school where it is used as a gate-post
<i>Copy</i>	DHF 03.viii.1983. DHF photo. in BIAA (Pl. 7.1.58 [p. 324]). Text and description here from DHF notes
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Stone: (1) B/W Neg.: DHF M/83/03.07
<i>Publication</i>	RRMAM 2, 1. 381 (notice only)
<i>Description</i>	A simple cylinder. Broken above. Hard, pale limestone. The shaft tapers very slightly towards the top. Inscription cut on a smoothed, recessed panel.
<i>Dimensions</i>	Surface: worn. Letters: extremely worn Ht (vis.) 1.57; diam. (top) 0.40

<i>Text</i>	- - - -
	(below panel)
	XIII

<i>Caput Viae</i>	(Antiochia)
<i>Date</i>	(?)

91(B). Aş. Kaşıkara 2

Province, Sub-Province + Admin. Code and Map As 91(A)
Location In the village; at the school where it is used as a gate-post
Copy DHF 03.viii.1983. DHF photo. in BIAA. Text here from DHF notes
BIAA Collections: Squeeze and Stone Photographs
 Stone: (1) B/W Neg.: DHF M/83/03.08
Publication RRMAM 2, 1. 382 (notice only)
Description A simple cylinder. Broken below. Hard, pale limestone. Traces of a recessed panel. Surface: very worn. Letters: extremely worn
Dimensions Ht 1.22; diam. (top) 0.39

Text - - -
 (below panel)
XX or **XV**

Caput Viae (Antiochia)
Date (?)

92. Kumdanlı

Province, Sub-Province + Admin. Code Isparta, Yalvaç 32-09-2
Map Akşehir 43-II
Location “ . . . in a cemetery by the roadside about eleven or twelve miles west of Antioch” (Ramsay 1906). Present whereabouts not established (DHF visit 16.xi.1976)
Copy Ramsay (W.M.) (with Sir Charles Wilson) 1882. The stone has not been examined by DHF. Text here of CIL (Ramsay)
Publication Mommsen 1884b, 584 no. 1368 (text from Ramsay)
 CIL 3. 6964 (text of Ramsay)
 RRMAM 2, 1. 403 (notice only)
Description & Dimensions Not given

Text - - -
XI

Caput Viae (Antiochia)
Date (?)

93(A). Sücüllü 1

Province, Sub-Province + Admin. Code Isparta, Yalvaç 32-09-0
Map Akşehir 45-II
Location “Sidjilli” (Ramsay)
Copy Ramsay 1912/13. The text is published in IK with a facsimile, p. 150 (reproduced here, Fig. 6.1.32 [p. 270]), from Ramsay’s *Note-book* (1912/13 no. 82).
Publication IK 67. 159 (text of Ramsay)
Description & Dimensions Not given

Text [DDD] nnn

2	[Fl Cl] Constant[i]no
	[et Fl Iul] Constantio
4	[et Fl Iul] Constanti
	[vict]oriosissimis semper Auggg
6	HPA

line 2: “2. CONSTANT NO” Ramsay (IK)

line 5: “5: après avoir copié ORIOSSISSIMIS SEMPER AVCCC,
Ramsay écrit «I can read only SIMIS» ” (IK)

line 6: “6: sur le côté de sa copie, Ramsay hésite à écrire MPΛ puisque
M est raturé. On pense évidemment à M(ilia) p(assuum) mais on
ne voit quel chiffre était indiqué. Les restes de ces lettres
correspondent peut-être à ab A[ntiochia]” (IK)

For a near-replicate text, cp. below, 94(A). Dedeçam 1 (6) [also cited in IK]. The version here follows the spacing and line-arrangement indicated in Ramsay’s copy, but cf. the restoration of the text in IK:

2	[DDD] nnn
	[Fl Cl] Constant[i]no [max et]
	[Fl Iul] Constantio [et Fl Cl]
4	Constanti
	[vict]oriosissimi semper Auggg
6	HPA

Caput Viae [Col. Antiochia]

Date 337, 09.ix-340, beg. May Constantinus II, Constantius II and Constans *Augusti*

93(B). Sütçüllü 2

Province, Sub-Province + Admin. Code Isparta, Yalvaç 32-09-0

Map Akşehir 45-II

Location “Sidjilli” (Ramsay). “Sidjilli (Sütçüllü) est le lieu de provenance indiqué en 1912/13, puis «NW or (Northern) Mahalle of Gemen» en 1914”

Copy Ramsay 1912/13. The text is published in IK with a facsimile, p. 150 (reproduced here, Fig. 6.1.33 [p. 270]), from Ramsay’s *Note-book* 1912/13 no. 83 and 1914 A no. 22

Publication IK 67. 10 (text of Ramsay)

Description & Dimensions “La pierre est un «excellent milliarium tall 5 ft, standing on a thin slighting basis» . . . Il signale aussi un espacement entre les lignes 5 et 6” (IK)

Text	[DDD n]nn
2	Fl Gratiano
	Fl Valentiniano
4	Fl Theodosio
	semper Aug[gg]
6	V C
	m p IV

lines 1 and 5: “Ramsay. En 1914, il ajoute ce commentaire:«Calder

reads Valeriano, omits VC, reads IV with note that V has been written over II»" (IK)

line 6: [A]ug ? (as suggested by IK); perhaps from an earlier text? cp. IK comment on 1.5

Caput Viae (Col. Antiochia)

Date AD 379, 19.i-383, 19.i Gratianus, Valentinianus II and Theodosius I *Augusti* [after the elevation of Theodosius I (AD 379, 19.i) and before the elevation of Arcadius (AD 383, 19.i)]

94(A). Dedeçam 1, form. Manarga

Province, Sub-Province + Admin. Code Isparta, Yalvaç 32-09-1

Map Akşehir 42-In

Location In the village; at the Eski Cami

Copy Sterrett 24 June, 1884; DHF 29.vii.1983. The text published by Sterrett is reproduced here, Fig. 6.1.34 [p. 270]). DHF squeeze (drawings, Figs 6.2.66-67 [pp. 298-299] and photo., Pl. 7.2.39 [p. 354]) in BIAA. No DHF photo. Texts here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 32. Isparta 31, Dedeçam 1 (= B/W Neg.: Squ. M/16.11-15 and 19.01)
Publication Sterrett 1883-84, 178 nos 178-181

Sterrett 1885, 12 nos 8, 9

CIL 3. 6962/3 (text of Sterrett)

RRMAM 2, 1. 383 (notice only)

Description A simple cylinder. Chipped below; otherwise complete. Hard, pale limestone. The first inscription was cut on a smoothed, recessed panel. Letters: worn to very worn

Dimensions Ht 1.15; diam. (top) 0.44. Letters: (text 1) (line 7) **P** 0.035, **O** 0.03; (text 2) (line 6) **I** 0.03, (line 8) **E** 0.045; (text 4) (line 2) **T** 0.028

Text (1) (underneath and below text [4])

	[Imp Caesari]
2	[divi Traiani f divi]
	[Nervae nepoti]
4	[Traiano]
	Hadriā[no Au]g
6	pontif max tr̄ib
	pot·XIII·cos III·
8	(vac) p·p·(vac)
	(vac)
	(vac) IIII (vac)

lines 1-4: restored after 88(B). Esendere 2 and 90(A). Gençali 1 text (1)

(2) and (3) (on the back of the stone)

	[Imp C C Aur Val]
2	[Diocletiano]
	[p f invict Aug et]
4	Imp C M Aur Val
	Maximiano

6 [p] **f** **invict Aug**
 [et Flavio Valerio] **Constantio**
 8 [et G]aleri[o Valerio Ma]ximiano
 [no]bilissimis **Caesaribus**

lines 7-9: added later in a different hand

(4) (on the back of the stone, below text [2])

 2 **M A**
et Imp Caes
 4 **M Aur Val** (sic)
Maximino
 6 **p f Aug**

line 5: **MAXIMIANO** Sterrett

(5) (underneath text [6])
 traces of letters

(6) (on the top of, and above, text [1])

DD nn
 2 **Fl Cl Constantino max-**
 (vac) **imo**
 4 **et Fl Iul Constantio et Fl**
Cl Constante (sic)
 6 **victoris semp**
ab Antiochia Augg
 (vac)

(below the last line of text [1])

8 **mi p V**

lines 2-3: after the death of Constantine I in AD 337, the original lines **Fl**
Val Constantino max | vict et Fl Cl Constantino were altered to
Fl Cl Constantino maximo

line 6: **VICTORISSEMP | AUGG** added over an original
NOBBBCAESSS (*vel sim.*); **victoris** for **victori(bu)s** or
victori(osissimi)s, cp. above, 93(A). Sücüllü 1

line 8: ligature **MI**

Caput Viae

Date

Antiochia

- (1) AD 128/129, 10.xii-09.xii Hadrianus *Augustus*
- (2) AD 286, 01.iv-293, 21.v(?) Diocletianus and Maximianus *Augusti*
- (3) AD 293, 21.v(?)-305, 01.v Diocletianus and Maximianus *Augusti* with
 Constantius I and Galerius *Caesares*
- (4) (?)
- (5) (?)
- (6) AD 333, 25.xii-335, 18.ix Constantinus I *Augustus* with Constantinus II,
 Constantius II and Constans *Caesares*, then 337, 09.ix-340, beg. May
 Constantinus II, Constantius II and Constans *Augusti*

94(B). Dedeçam 2, form. Manarga

<i>Province, Sub-Province + Admin. Code and Map</i>	As 94(A)
<i>Location</i>	In the village; at the Eski Cami
<i>Copy</i>	DHF 29.vii.1983. DHF squeeze (drawing, Fig. 6.2.68 [p. 299]) in BIAA. No DHF photo. Texts here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 32. Isparta 32, Dedeçam 2
<i>Publication</i>	RRMAM 2, 1. 384 (notice only)
<i>Description</i>	A simple cylinder. Complete. Pale limestone. Inscription cut on a smoothed, recessed panel. Letters: worn
<i>Dimensions</i>	Ht (vis.) 1.32; diam. (bottom) 0.44. Letters: (text 2) (line 2) E 0.045, (line 6) E 0.037

Text (1) (underneath, and on the r., of text [2])

	[I]mp Çæsar Divi f
2	[Augustus pont] m̄axim
	[cos XI desig XII] imp XV
4	[trib potest XIIIX] yiam
	Ş[ebasten cur]ante
6	[Cornuto] Aquila
	[leg suo pro p]r f̄ecit
8	(vac) XII

(2) (on the top, and on the l., of text [1])

	(vac) B F
2	Imp Caes
	PP Lic[i]nn
4	Valeriano
	et Gallieno <et>
6	[V]aleriano
	Auggg
8	m p [-]

line 3: **P**(ubliis) **L**(icinniis)

<i>Caput Viae</i>	(Antiochia)
<i>Date</i>	(1) 6 BC, 26.vi-31.xii Augustus
	(2) AD 260 Spring-Autumn Valerianus, Gallienus and Valerianus (Saloninus) <i>Augusti</i>
<i>Commentary</i>	For the date of Valerianus Saloninus as <i>Augustus</i> , see Kienast (1996, 221)

95(A). Kiyakdede 1

<i>Province, Sub-Province + Admin. Code</i>	Isparta, Şarkikaraağaç 32-07-0
<i>Map</i>	Akşehir 48-Iö
<i>Location</i>	Not given. Present whereabouts not established (DHF visit 10.vi.1977)
<i>Copy</i>	Sterrett 1885; Cronin (?with Ramsay [W.M.] and Wathen) 1901
<i>Publication</i>	Sterrett 1884-85, 196

Cronin 1902, 108

RRMAM 2, 1. 633

Description & Dimensions Not given

Text No visible inscription

95(B). Kiyakdede 2

Province, Sub-Province + Admin. Code and Map As 95(A)

Location Now in front of the village mosque

Copy Sterrett 08 August, 1885; Cronin (?) with Ramsay [W.M.] and Wathen) 1901; DHF 10.vi.1977. DHF squeeze and photo. (Pl. 7.1.59 [p. 324]) in BIAA. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 32. Isparta 48, Kiyakdede 2

Stone: (1) B/W Neg.: DHF R/77/05.04

Publication Sterrett 1884-85, 196

Cronin 1902, 108

RRMAM 2, 1. 634 (notice only)

Description A simple cylinder and plinth. Broken above. Hard, pale limestone. Plinth roughly square. Letters: worn

Dimensions Ht (ex.) 1.24; diam. (top) 0.49; (plinth) ht. 0.47, wi. 0.52. Letters: 0.06

Text - - -
mil XXX

Caput Viae (Antiochia)

Date (?)

95(C). Kiyakdede 3

Province, Sub-Province + Admin. Code and Map As 95(A)

Location “At Khiakdede” (Cronin). Present whereabouts not established (DHF visit 10.vi.1977)

Copy Cronin (?) with Ramsay [W.M.] and Wathen) 1901

Publication Cronin 1902, 108

RRMAM 2, 1. 635

Description & Dimensions Not given

Text No visible inscription

95(D). Kiyakdede 4

Province, Sub-Province + Admin. Code and Map As 95(A)

Location In the village; found c. 50 m. SW of the mosque. Now in the Yalvaç Museum

Copy Ballance 1957; DHF 10.vi.1977. DHF squeeze (drawing, Fig. 6.2.69 [p. 299], and photo., Pl. 7.2.40 [p. 354]) and photos (Pl. 7.1.60-61 [p. 324]) in BIAA.

Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 32. Isparta 49 & 50, Kiyakdede 4 (= B/W Neg.: Squ. M/25.01)

<i>Publication</i>	Stone: (1) B/W Neg.: DHF R/77/05.02-03 French 1980, 787 map 2 (site no. 7) (notice) RRMAM 2, 1. 636 (notice only)
<i>Description</i>	A simple cylinder and plinth. Chipped and damaged on all sides. Hard, pale limestone. The top is flat. Plinth roughly square. The inscription is cut on a smoothed, sunken panel. Surface and letters: worn and damaged.
<i>Dimensions</i>	Ht 1.78; diam. 0.61. Letters: (line 5) E of TEN 0.05, (line 8) 0.08
<i>Text</i>	[Imp Caesar] Divi·f·Ayu [gustus] 2 [po]nt max·cons·XI·de[sig] XII·imp·XV·trib·pot·XIX 4 viam·Seba[s]ten·curan- te·Cornuto[Aqui][la leg] 6 suo·pro·pra[et]o[re fecit] (vac) XXXII

<i>Caput Viae</i>	(Antiochia)
<i>Date</i>	6 BC, 26.vi-31.xii Augustus

95(E). Kiyakdede 5

<i>Province, Sub-Province + Admin. Code and Map</i>	As 95(A)
<i>Location</i>	In the village at the mosque. Now brought to the Yalvaç Museum
<i>Copy</i>	DHF 10.vi.1995, 09.xi.1996. DHF squeeze (photo., Pl. 7.2.41 [p. 355]) in BIAA. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 32. Isparta 51, Kiyakdede 5 (= B/W Neg.: Squ. M/30.02-07)
<i>Publication</i>	French 1997, 63 (notice only)
<i>Description</i>	A simple cylinder without plinth. Complete but worn, chipped, pitted and damaged. Hard, pale limestone. The top surface is flat; the edges are chipped. The shaft is simple and straight. There was no attempt to shape a plinth. There are horizontal grooves (? quarry marks) visible on the lower shaft. The inscription was cut within a smoothed, prepared panel which was set almost immediately below the top. Outside the panel, the surface is rough. Surface and letters: worn and pitted.
<i>Dimensions</i>	Ht 2.45; diam. (top) 0.45. Panel: ht 0.60, wi. c. 0.89. Letters: (text 1) c. 0.03

<i>Text</i>	(1) (cut inside the panel)
	Imp·Caesar·Divi·f·Ayu-
2	[gus]tuş·pont·max·cons
4	XI·desig·XII·imp·XV·trib
6	pot·XIX·viam·Şebasten
8	curante·Cornuto·Aqu[i]-
	la·leg·suo·[p]ro·prae-
	tore·fecit·
8	XXXI
	(2) (below, and on the r. of, lines 6-8 of text [1])
	Φλα' Ο[ν]αλ[ερίῳ]

2 Κενήρ[φ] καὶ
 Γαλερί[φ] Οὐαλερίω
 4 [Μαξιμιανού]μείνω τοῖς
 ἐπιφ Καί[καρπ]ιγ

Caput Viae (Antiochia)
Date (1) 6 BC, 26.vi-31.xii Augustus
 (2) AD 305, 01.v-306, 25.vii Severus and Maximinus *Caesares*

96. Kireli

Province, Sub-Province + Admin. Code Konya, Beyşehir 42-02-2
Map Beyşehir 48-İp
Location “In village” (Cronin). Present whereabouts not established (DHF visit 10.vi.1977)
Copy Cronin (with Ramsay [W.M.] and Wathen ?) June 1901
Publication Cronin 1902, 109 and n.4; 110
 Ramsay 1930b, 252 (notice)
 Ramsay (W.M.) 1941, 288 n.1
 RRMAM 2, 1. 640
Description & Dimensions Not given

Text No visible inscription, cp. the comments of Ramsay (1930b, 252)

97(A). Selki 1

Province, Sub-Province + Admin. Code Konya, Beyşehir 42-02-2
Map Beyşehir 49-İp
Location In the village; at the Yeni Mahalle mosque. Now built into the corner of the mosque wall and covered by cement
Copy Sarre 1895; Ramsay (W.M.), Cronin and Wathen 1901; Calder 1932 (inscription no. 17); DHF 10.vi.1977. Calder squeeze (drawing, Fig. 6.2.70 [p. 300]) in BIAA. DHF photo. (Pl. 7.1.62 [p. 325]) in BIAA. Text here from CIL (Ramsay [W.M.] et al.).
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 42. Konya 32, Selki 1 (WMC)
 Stone: (1) B/W Neg.: DHF R/77/05.05
Publication Sarre 1896a, 39
 Sarre 1896b, 122 and 175 no. 24a
 CIL 3. 14185 (text of Sarre)
 CIL 3. 14401a (text from Ramsay [W.M.], Cronin and Wathen)
 Cronin 1902, 105 no. 11 (copy of Ramsay [W.M.], Cronin and Wathen)
 French 1980, 727 map 2 (site no. 8) (notice)
 RRMAM 2, 1. 663 (notice only)
Description A simple cylinder. Broken below? Hard, pale limestone
Dimensions Ht (vis.) 0.75; diam. 0.58. Letters: (line 5) **E** of **SEB** 0.047

Text [I]mp·Caes[ar Divi f]
 2 Aug[u]stu[s p]on[t max]

	(vac) cos XI desig XII [imp]
4	(vac) XV trib pot XIIIX
	viam Sebaste[n] curan[te]
6	Cornuto [A]q[uil]a le[g]
	suo pro praeto[re fecit]
8	(vac) XLIV (vac)

Caput Viae (Antiochia)
Date 6 BC, 26.vi-31.xii Augustus

97(B). Selki 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 97(A)
<i>Location</i>	In the village; at the Eski Cami (now Orta Mahalle Mescidi) where it stands in the street, at the SE corner of the mosque
<i>Copy</i>	Ramsay (W.M.), Cronin and Wathen 1901; DHF 10.vi.1977. DHF squeeze (drawing, Fig. 6.2.71 [p. 300]) and photo. (Pl. 7.1.63 [p. 325]) in BIAA. Text here from CIL and from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 42. Konya 33, Selki 2 Stone: (1) B/W Neg.: DHF R/77/05.06
<i>Publication</i>	CIL 3. 14401b (copy from Ramsay [W.M.], Cronin and Wathen) Cronin 1902, 105 no. 12 (copy of Ramsay [W.M.], Cronin and Wathen) French 1980, 727 Map 2 (site no. 9) (notice) RRMAM 2, 1. 664 (notice only)
<i>Description</i>	A simple cylinder. Broken below. Hard, pale limestone. Top flat. Surface very worn and damaged. Letters: worn and damaged
<i>Dimensions</i>	Ht (ex.) 0.80; diam. (top) 0.60. Letters: (line 6) Ø 0.05, (line 8) c. 0.10

<i>Text</i>	[I]mp C[esar Divi f]
2	(vac) [A]u[g]ustu[s] [pont max]
	con[s] X[I] de[s]i[g XII]
4	[imp XV trib pot XIIIX]
	viam Sebaste[n] curante
6	Cornuto Aq[uil]a leg suo
	pro praetore [fecit]
8	(vac) XLV (vac)

Caput Viae (Antiochia)
Date 6 BC, 26.vi-31.xii Augustus

97(C). Selki 3

<i>Province, Sub-Province + Admin. Code and Map</i>	As 97(A)
<i>Location</i>	In the village; beside the çesme (fountain) (at its NW corner) at the new mosque
<i>Copy</i>	DHF 10.vi.1977. DHF photo. in BIAA
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Stone: (1) B/W Neg.: DHF R/77/05.07
<i>Publication</i>	RRMAM 2, 1. 665

<i>Description</i>	(?) Milestone, in the form of a simple cylinder and plinth. Broken above. Pale limestone
<i>Dimensions</i>	Ht 1.15; diam. 0.58; (plinth) ht. 0.70, wi. 0.55
<i>Text</i>	No visible inscription

98. Yunuslar

<i>Province, Sub-Province + Admin. Code</i>	Konya, Beyşehir 42-02-1
<i>Map</i>	Konya 51-Ip
<i>Location</i>	“Now used as the headstone of a grave in the cemetery a few minutes east of the village” (Cronin). Now in the village; at the house (no. 34) of Ali Diler, in the courtyard, where it is buried upside down beside the wall
<i>Copy</i>	Cousin 1896; Anderson 1900; Ramsay (W.M.), Cronin and Wathen 1901; Calder 1932 (inscription no. 4); MHB, ASH, SM and CSL, and DHF at various intervals. Calder squeeze (drawing, Fig. 6.2.72 [p. 300]) in BIAA. Text here of Cronin and from Calder squeeze
<i>Publication</i>	CIL 3. 14401c (copy from Anderson and from Ramsay [W.M.], Cronin and Wathen) Cronin 1902, 102 no. 7 AE 1902. 169 (text of Cronin) ILS 2. 5828 (text of CIL [Anderson and Ramsay et al.]) Cousin 1904, 408 Ehrenberg and Jones 1949, 129 no. 294 ‘Comama’ (text of ILS 2. 5828) French 1980, 727 map 2 (site no. 10) and 714 no. 3 (text of Cronin) Levick 1985, 103 no. 94 ‘Comama’ (transl. of Ehrenberg and Jones) RRMAM 2, 1. 670 (notice only)
<i>Description & Dimensions</i>	Not given. Letters (from Calder squeeze): (line 1) E 0.05, (line 2) E 0.05, (line 6) E of RAE 0.04

<i>Text</i>	Imp·Caesar̄ Diyi f·Augus-
2	tus·pon̄·max·cos·XI·desig
	XII·imp·XV·trib·potes·XIX·
4	viam·Sebasten·curante
	Çornuto·Aqu[i]la·leg·suo
6	pro·praetore [f]ecit
	[-]

<i>Caput Viae</i>	(?)
<i>Date</i>	6 BC, 26.vi-31.xii Augustus

99. Değirmen

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-7
<i>Map</i>	Konya 55-Ip
<i>Location</i>	Outside the village, on E; c. 50 m N of the cemetery and şose
<i>Copy</i>	Ballance and Hall 1957; DHF 08.vi.1977 but by that date the inscribed area had been destroyed. Ballance squeeze (drawing, Fig. 6.2.73 [p. 301]) in BIAA. DHF photo. in BIAA. Text here from Ballance squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	

<i>Publication</i>	Squeeze: 42. Konya 07, Değirmen Stone: (1) B/W Neg.: DHF R/77/04.11
<i>Description</i>	Ballance in MAMA 8, xi and n.1
<i>Dimensions</i>	RRMAM 2, 1. 611 (notice only) A simple cylinder. Broken above. Hard, pale limestone. Letters: worn Ht (vis.) 0.80; diam. (top) 0.545. Letters: (line 1) I of IMP 0.062

<i>Text</i>	Imp Nervae Caesari
2	Au[g p]ontif max·
	trib̄ po[t] p p
4	(vac) cos (vac) III
	per-T-Pomponium
6	(vac) Bassum leg
	Aug·pro·pr·
8	m·p·XVIII

lines 4 and 8: horizontal bar over the numerals
line 5: ligature **VM**

<i>Caput Viae</i>	(Colonia Iconium)
<i>Date</i>	AD 97, 01.i-17.ix Nerva Augustus
<i>Commentary</i>	According to Kienast (1996, 120), Nerva began his COS III on AD 01 January 97 and ended his TR P (I) on 17 September 97.

100(A-B). Bayat 1-2

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-2
<i>Map</i>	Konya 56-Ip
<i>Location</i>	In the village cemetery
<i>Copy</i>	DHF 08.vi.1977
<i>Publication</i>	RRMAM 2, 1. 608, 609
<i>Description</i>	Two milestones, each in the form of a simple cylinder. Hard, grey limestone. Surfaces very worn.
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

101(C). Hatunsaray 3

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-3
<i>Map</i>	Konya 55-Ih
<i>Location</i>	In the village; now lying in front of the house (no. 392) owned by Bayram Konca. Brought from his field c. 1-1.50 km N of Kocayük (the large mound dominating the site of Colonia Lystra at Zoldera Mevkii on the NE side of Kocayük). Perhaps <i>in situ</i> , on the <i>Via Sebaste</i> , when found
<i>Copy</i>	DHF 03.vii.1992, 18.xi.1993. DHF squeeze (drawing, Fig. 6.2.74 [p. 301]) and photo. (Pl. 7.1.64 [p. 325]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 42. Konya 13, Hatunsaray 3 Stone: (1) BW Neg.: DHF M/93/21.09

<i>Description</i>	A simple cylinder. Broken on left. Hard, pale limestone. The top surface is roughly flattened but has perhaps been broken. The shaft is rounded for the inscription; otherwise the surface is rough and nearly square in section. The bottom is roughly shaped into a plinth. The inscription is cut on a smoothly dressed, sunken panel; top of letters c. 0.05 from the top of the stone. Surface and letters: slightly worn
<i>Dimensions</i>	Ht 1.55; diam. (top) 0.435; (plinth) wi. 0.38; (panel) ht. 0.36, wi. 0.56. Letters: (line 1) E of CAE 0.042, S of CAES 0.05
<i>Text</i>	<p>(1) (underneath text [2]) traces of letters; after REST perhaps ITVIT</p> <p>(2) (on the top of text [1]) Imp·Caes·M·Ant· 2 Gordiano·p·f·Aug· ·mil·p·rest·^(vac) 4 (vac) I (vac)</p>
<i>Caput Viae</i>	(Colonia Lystra)
<i>Date</i>	<p>(1) Perhaps Maximinus (cp. the text of 101[A] Hatunsaray 1)</p> <p>(2) AD 238, Jan./Feb.-244, beg. Gordianus III <i>Augustus</i></p>

J. IN CILICIAM, ISAURIAM ET LYCAONIAM**J.3 COLONIA LYSTRA (- [?] Dalisandus - Laranda)****101(A). Hatunsaray 1**

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-4
<i>Map</i>	Konya 55-Ih
<i>Location</i>	In the village; “protruding through floor of school” (WMC archive). Taken (?) date) from the school to the courtyard of the cami
<i>Copy</i>	Calder 1934; recorded in a notebook in W. M. Calder archive, in the Aberdeen University Library, Special Collections and Archives, box 3286/1, sheet no. 44. Not seen by DHF 07.vi.1977 but subsequently found at the cami 18.xi.1993. DHF squeeze (drawing, Fig. 6.2.75 [p. 301]). Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 42. Konya 11, Hatunsaray 1
<i>Publication</i>	MAMA 8. 7 (text of Calder) and Fig. (p. 125) RRMAM 2, 1. 625 (notice only) Laminger-Pascher 1992, 125 no. 163 (text from MAMA)
<i>Description</i>	A simple cylinder. Broken below. Hard, pale limestone. Top flat. The shaft tapers slightly towards the top. On the face of shaft, “a panel, enclosed within double incised lines” (MAMA). Inscription cut in a double frame; top border begins at c. 0.10 from top of stone. Surface and letters: very slightly worn “H. (vis.) 0.38; diam. 0.39; letters: 0.045 to 0.055” (MAMA). Ht (max. ex.) 1.00; diam. (top) 0.375, (bottom) 0.44. Letters: (line 1) E of CAE 0.045, (line 2) E of VER 0.053
<i>Text</i>	(1) (underneath text [2]) traces of some letters are visible

	(2) (on the top of text [1])
	·Imp·Caes·G·Iu-
2	lius Verus (vac)
	Maximinus
4	pius·fel·Aug
	restituit
6	·mil·I

lines 4-6: not seen by Calder and, therefore, not cited by Laminger-Pascher

<i>Caput Viae</i>	(Colonia Lystra)
<i>Date</i>	(1) (?)
	(2) AD 235, Feb.-March(?) - 236, 07.i/16.v Maximinus Augustus

101(B). Hatunsaray 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 101(A)
<i>Location</i>	In the village; in front of the house (no. 236A) (beside the village <i>kahve</i>) of Kamil Harman, where it is used as a base for the wooden support of a staircase

Copy DHF 07.vi.1977. DHF squeeze (drawing, Fig. 6.2.76 [p. 301]) and photo. (Pl. 7.1.65 [p. 326]) in BIAA. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 42. Konya 12, Hatunsaray 2

Stone: (1) B/W Neg.: DHF R/77/04.09

Publication RRMAM 2, 1. 626 (notice only)

Description A simple cylinder. Hard, pale limestone. Letters: worn

Dimensions Ht (vis.) 0.41; diam. 0.45. Letters: (line 3) **E** 0.04, (line 4) **I** 0.053

Text (1) (underneath text [2])
obliterated

(2) (on the top of text [1])
[Imp Caes M Ant]
2 **Gordiano·p·f·**
 Aug·mil·p·rest
4 (vac) **II** (vac)

Caput Viae (Colonia Lystra)

Date (1) (?)

(2) AD 238-244 [M. Antonius] Gordianus III Augustus

Comment Perhaps, as 101(C) Hatunsaray 3, carried from the *Via Sebaste*

101(C). Hatunsaray 3

See above, 3.H.1 Via Sebaste

101(D). Hatunsaray 4

Province, Sub-Province + Admin. Code and Map As 101(A)

Location Near the village; now built into a field-bridge c. 1.30 km NE of village, at a place called Hendek arası or Kömürcük Köprüsü

Copy DHF 19.xi.1993. DHF squeeze (drawing, Fig. 6.2.77 [p. 302]) and photo. (Pl. 7.1.66 [p. 326]) in BIAA. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 42. Konya 14, Hatunsaray 4

Stone: (1) B/W Neg.: DHF M/93/21.06

Description A simple cylinder. Broken at top and on right. Hard, pale limestone. (?) Flat top; base (?). The inscription is cut in a sunken panel, framed by an incised line (panel c. 0.35, line c. 0.24, from the top). The surface and letters are very worn. For the letter-forms, consult the drawing, Fig. 6.2.77 [p. 302].

Dimensions Ht (vis.) 1.30; diam. c. 0.44. Letters (line 1) **O** of **TOR** 0.03, **R** of **TOR** 0.04

Text [Imp]erator Caes[ar L]
[Sep]timius Sev[erus]
[Pius] Pertinax A[ug]
4 [Arab]icu[s Ad]jabe[nic]
 [Parth]i[c]us maxi[mus]
 [pontifex] maxi[mus]

	[trib pot ... imp ...]
8	[cos .. p p procos]
	[et Im] p erat[or]
	[Caesar M Aur] e ll[ius]
	[Antoninus A] u g [et]
12	[- - - -]
	[- - - -]
	[restitu]erun[t per]
	[. . . c. 9 . . .]ian[um]
16	[. . . c. 9 . . . le]g pr [pr]
	[-]

<i>Caput Viae</i>	[Colonia Lystra]
<i>Date</i>	L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i> , (?) post-AD 198
<i>Commentary</i>	The surviving letters and the space available in lines 15-16 do not seem to be suitable for any of the known governors of Galatia in the period post-AD 198 (the year in which Caracalla became Augustus).

102(A). Kavak 1

<i>Province, Sub-Province + Admin. Code</i>	Konya 42-00-4
<i>Map</i>	Konya 55-It
<i>Location</i>	“In court of a house” (Sterrett). Presents whereabouts not established (DHF visit 07.vi.1977)
<i>Copy</i>	Sterrett 11 July, 1885; (?) Calder (?date). The stone has not been examined by DHF. Text here of CIL (Sterrett)
<i>Publication</i>	Sterrett 1884-85, 155 no. 265 CIL 3. 6958 (text of Sterrett) MAMA 8. 6 (text of Calder?) RRMAM 2, 1. 627 (notice only) Laminger-Pascher 1992, 155 no. 225 (text from Sterrett, CIL and MAMA)
<i>Description</i>	“Miliarium” (MAMA)
<i>Dimensions</i>	“H. 2.39; diam. 0.54 to 0.62; letters: 0.07” (MAMA)

<i>Text</i>	Imp C[aesar d]ivi	cp. 070(A) Konya 1
2	T r[aiani Parthici]	
	[f - - -]	
4	[- - - -]	
or		
	Imp C[aesari d]ivi	cp. 070(B) Konya 2
2	T r[aiani Parthici]	
	[nepoti - -]	
4	[- - - -]	

<i>Caput Viae</i>	[Colonia Lystra]
<i>Date</i>	AD 117-138 Hadrianus or AD 138-161 Antoninus Pius

102(B). Kavak 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 102(A)
<i>Location</i>	In the cemetery
<i>Copy</i>	Sterrett 11 July, 1885; Ramsay (W.M.) and Hogarth 1890; (?) Calder (? date) with squeeze; DHF 07.vi.1977. DHF squeeze (drawings, Figs 6.2.78-79 [p. 302]) in BIAA. No DHF photo. Texts here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 42. Konya 15, Kavak 2
<i>Publication</i>	Sterrett 1884-85, 153-154 nos 261-263 CIL 3. 6956/7 (text of Sterrett) CIL 3. 12215 (text from Ramsay and Hogarth) MAMA 8. 8 (text of Calder?) RRMAM 2, 1. 628 (notice only) Laminger-Pascher 1992, 156 no. 226 (text from Sterrett, CIL and MAMA)
<i>Description</i>	A simple cylinder. Hard, pale limestone. Top flat. Letters: worn. A Christian cross has been inscribed above and r. of text (2).
<i>Dimensions</i>	Ht (vis.) 1.05 (1.20 MAMA); diam. (top) 0.40. Letters: (text 1) (line 12) T 0.045
<i>Text</i>	(1) (underneath text [2]) obliterated; a few letters survive

(2) (on the top of text [1])

	B F
	Imp Caesari P
	Liciñño Valeri-
	ano et P Licinnio
5	Ga(l)ieno et P Cor-
	[nelio] Valeriano
	f[i]l[io] nñ piorum
	[Au]gg et Cor-
	[nelio] Salonino
10	[Valeri]ano iuniori
	Iulia Fel·Aug
	[C]ol Lustrenium
	[-]

line 1: **B F** not recorded by Sterrett, Ramsay and Hogarth, and (?) Calder; hence not in CIL texts; not indicated on the drawing (Fig. 6.2.78 [p. 302])

line 2: **[Im]p** (CIL 12215)

lines 3-4: **Valer|ian]o** (CIL 12215), **Valeria]no** (MAMA)

line 5: **[Ga]l]ieno** (CIL 12215), **[G]alieno** (MAMA)

line 6: **[ne]lio Valeriano** (CIL 12215), **[nel]io [V]aleriano**

line 7: **f[i]l [et] n piorum** (CIL 12215), **piorum** (MAMA)

line 8-9: **Cor|nelio** (CIL 12215), **[Aug]g et Cor[n]** (MAMA)

lines 9-10: **[Valleria]no iunior[i]**

line 11: **[piis] Fel Aug** (CIL 12215), **e[t] Aug** (MAMA)

line 12: **a [Lus]tre[is] IV m** (MAMA)

(3) (on the r. of, and underneath, text [2])
a few letters only; (?)Constantinian

(4) (on the r. of text [2])
DDD nnn

- - -

Caput Viae Colonia Lystra

Date (1) (?)

(2) AD 257/258 Valerianus and Gallienus *Augusti* with Valerianus *filius Augg*
and Salonus *iunior*

(3)-(4) (?)

Commentary For the dates of Valerianus Iunior and Salonus, see Kienast (1996, 220-221). Laminger-Pascher (1992, 156) gives a date, “vielleicht Herbst 253”, on the basis of the MAMA text.

102(C)-(D). Kavak 3-4

Province, Sub-Province + Admin. Code and Map As 102(A)

Location “In the cemetery” (Sterrett). Present whereabouts not established (DHF visit 07.vi.1977)

Copy Sterrett 11 July, 1885

Publication Sterrett 1884-85, 155

RRMAM 2, 1. 629, 630 (notice only)

Description & Dimensions Not given

Text No visible inscription

103. Apa

Province, Sub-Province + Admin. Code Konya, Çumra 42-05-2

Map Konya 58-Iu

Location At a bridge “where the road from Iconium to Old Isaura crosses the Tcharshamba River” near “a village called Appa, half a kilometre” (sc. S) “from the milestone” Ramsay 1909). The bridge is now drowned under the waters of the Apa dam; the new village, Apa, has been moved c. 3 km downstream. It may be presumed that the stone is lost (DHF visit 31.x.1977)

Copy Ramsay (W. M.) and Hogarth 1890; Ramsay (A.M.) 1909. Text here of CIL (Ramsay and Hogarth)

Publication CIL 3. 12218 (text of Ramsay and Hogarth)

Ramsay (A.M.) 1909, 28 (notes after autopsy)

Ramsay (W.M.) 1909a, 277 and Pl. 18 (notice)

Ramsay (W.M.) 1916, 132 (notice)

French 1976a, 52 (notice)

French 1980, 728 map 3 (site no. 23) (notice)

RRMAM 2, 1. 602 (notice only)

Laminger-Pascher 1992, 188 no. 299 “Meilenstein ?” (text from CIL)

Winter 1996, 317 no. 25 (text from CIL)

Description & Dimensions Not given

Text

	[Imp] T Caesar di- vi Vespasiani f Aug pont max trib potest X imp XVII p p cos VIII desig VIII censor (vac) et [Domitia]nus [Cae]sar divi [Vespas]iani f cos VII desig VIII
4	
8	sacerdos omnium collegi- orum princeps iuventutis per A Caesennium Gallum cos XV vir s f leg Aug pro pr
12	(vac) straverunt (vac) [?]

line 4: **IMPXV** (CIL); **IMPXVII** (Ramsay [A.M.] 1909, 28)

line 4: **p p** (vac) (CIL); “ . . . No such space is shown in our copy”
(Ramsay [A.M.] 1909, 28)

Caput Viae [Colonia Lystra]

Date AD 81, “seit Mitte Marz”-30.vi Titus *Augustus* with Domitianus *Caesar*

Commentary (Line 6) Was the name of Domitianus only partly erased? Or not at all? The size of the damage (at the beginning of l. 7) to Vespasian’s name suggests that the loss at the beginning of l. 5 may have been the result of wear or accident, not of partial erasure.

(Line 12) The verb *straverunt* usually indicates the paving of a road (cp. above, the text of 008 Mülk) rather than the building of a bridge, but cf. Winter (1996, 83, 150 and 154 “Bau einer Brücke”) and Laminger-Pascher (1992, 188 no. 299 “Meilenstein ?”).

According to Kienast (1996, 112 and 116), Titus began his TR P XI on 01 July 81, his COS DES IX “seit Mitte Marz” 81; Domitianus became COS VII DES VIII also “seit Mitte Marz” 01.i.81

**P. PER PONTUM ET BITHYNIAM, GALATIAM, CAPPADOCIAM
ET CILICIAM, ISAURIAM ET LYCAONIAM AD SYRIAM USQUE**

**1. [The Pilgrim's Road] (Chalcedon - Nicaea - Iuliopolis) - ANCYRA (- Colonia Archelaïs -
Tyana - *Via Tauri* - Tarsus - Antiochia)**

104. Beypazarı region

Province, Sub-Province + Admin. Code Ankara, Beypazarı 06-06-0

A milestone was reported to have been found by the Tahirler Project directed by Professor Peter Brown

105. Bayram

Province, Sub-Province + Admin. Code Ankara, Ayaş 06-04-0

Map Ankara 54-u

Location In the village; in front of the mosque

Copy Anderson Summer 1898; Macpherson 1953(?); DHF 22.ix.1975. The text published by Anderson is reproduced here, Fig. 6.1.35 [p. 271]. Macpherson squeeze in the Faculty of Classics, Cambridge (IWM Box VI no. 148); DHF squeeze in BIAA. No DHF photo. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 06. Ankara 66, Bayram

Publication Anderson 1897-98, 66 (notice only)

Anderson 1899, 63 no. 10

CIL 3, Suppl. 2. 14184⁶⁴ (text of Anderson)

Macpherson 1954, 113 no. 2

Macpherson 1958, 162 no. 208

Bosch 1967, 364 no. 301 (text from Anderson and CIL)

RRMAM 1. 30 (text only, from DHF copy)

RRMAM 2, 1. 117 (notice only)

Description A simple cylinder. Broken below. Hard, blue limestone. The top surface is flat.

Dimensions Ht c. 1.00; diam. 0.65. Letters: 0.038-48

Text (1) (underneath lines 1-4 of text [2]; at the top of the shaft)

B F

2 **Imperr** [--]

[-----]

4 [-----]

[-----]

(2) (on the front face)

[Imp Caes C Aur Val]

[Diocletiano]

[p f inv Aug et]

4 [Imp Caes M Aur Val]

Maximiano p f

inv Aug·et Fl

8 **Constantio et
Gal Val
Maximian[o]
[nobill Caess]**

Caput Viae [Ancyra]
Date (1) (?)
(2) AD 293, 21.v(?)-305, 01.v Diocletianus and Maximianus *Augusti* with
Constantius I and Galerius *Caesares*

106(A). İlyağut 1

Province, Sub-Province + Admin. Code Ankara, Yenimahalle 06-03-4
Map Ankara 55-u (41.41)
Provenance (Lower fragment) Formerly in the village, in front of house no. 6 but owned by Abdullah Özer (house no 11); brought c. 1945 from the ruins at the mouth of the *dere* c. 2 km E of the village. (Upper fragment) Formerly in the village; it stood in front of the muhtar's house. Now in the collection of the Sincan Belediye (Municipality) [Inv. no. 2002/13]
Copy (Lower fragment) (lines 7-11) SM 1972 (?), DHF 22.ix.1975; (upper fragment) (lines 1-6) DHF notes 16.ix.2005. (Lower fragment) SM and DHF squeezes in BIAA. No DHF photo. Text here from DHF squeeze and notes
BIAA Collections: Squeeze and Stone Photographs
Squeeze: 06. Ankara 85, 86, İlyağut 1
Publication RRMAM 1. 31(A) (text of lower fragment only)
RRMAM 2, 1. 147 (notice only)
Description A simple cylinder. Now in two fragments. (Lower fragment) Broken below and on 1. Grey limestone. The surface was well smoothed.
Dimensions Ht 0.63 + (?); diam. 0.60. Letters: (line 8) P of P (leaf) 0.065

Text (1) (on the full face of the shaft)
[B] F
I[[mp]] (leaf) Cae-
3 [[sari (leaf) C (leaf)]]
 [[Iulio (leaf) Vero]]
 [[Maximino]]
6 [[pio felici]]
 [Au]g [trib]
8 p (leaf) p p
 mp
10 X.XI
 kα'

(2) (on the rear face of the shaft)

m XXI
kα'

Caput Viae (Ancyra)
Date (1) (?) AD 235, Feb/March-236, 07.i/16.v Maximinus *Augustus*
(2) (?)

106(B). İlyağut 2

Province, Sub-Province + Admin. Code and Map As 106(A)
Provenance In the village; built into a garden wall, c. 100 m W of the mosque and on the SW edge of the village. Now in the collection of the Sincan *Belediye* (Municipality) Inv. no. 2002/8]
Copy DHF 22.ix.1975, 16.ix.2005. DHF squeezes in BIAA. No photo. Texts here from DHF squeezes and notes
BIAA Collections: Squeeze and Stone Photographs
Squeeze: 06. Ankara 87, İlyağut 2
Publication RRMAM 1. 31(B) (text only, from DHF copy)
RRMAM 2, 1. 148 (notice only; corrections to texts published in RRMAM 1. 31[B])
Description A simple cylinder. Broken above and below. Grey-blue limestone. The surface was well smoothed.
Dimensions Ht 0.94; diam. 0.58. Letters: (text 1) E of CAE 0.071, (text 2) c. 0.063, (text 3) O of INO 0.08
Text (1) (on the face of the shaft)

[B] F
I [[mp]] (leaf) C ae-
3 [[sari (leaf) C (leaf)]]
 [[Julio (leaf) Vero]]
 [[Maximino]]
6 [[pio felici]]

(2) (on the l. of text 1)

[[Imp Caes·C Aur·Vale·]]
[[Diocle]tianο·p·f·in·y·Aug·]
3 [[et·Imp·Caes·M·Aur·Vale·]]
 [[Maximia]no p f·in·y·Aug·]]
 [[- - - -]]
6 [[- - - -]]

m XXI
κα'

(3) (above and on the top of lines 1-2 of texts [1] and [2] and (line 4) between text [2], lines 4-5)

- - - -
2 Fl Cons[t]a[n]-
tino Augg
(vac)

4 **xa'**(4) (inscribed over the end of text 2, line 6)
 [[---] **p f in(v) Aug**

- Caput Viae* (Ancyra)
Date (1) (?) AD 235 Maximinus
 (2) AD 293-305 Diocletianus and Maximianus *Augusti* [with Constantius I and Galerius *Caesares*]
 (3) AD 307-308 [Galerius and] Constantinus I *Augusti*
 (4) AD (?)

106(C). İlyagut 3

- Province, Sub-Province + Admin. Code* Ankara, Yenimahalle 06-03-3
Map Ankara 56-u
Provenance Not known. Now in the collection of the Sincan *Belediyesi* (Municipality) [Inv. no. 2002/7]
Copy Seen but not copied DHF 16.ix.2005. No squeeze. No photo.
Description A simple cylinder. Hard, pale limestone
Dimensions Ht 0.88; diam. 0.48. Letters: not recorded

<i>Text</i>	(1) & (2)
	Imp·Caes·C·Aur
2	Diocletiano·inv
	Aug·et·Imp·Caes·Fl
4	Val·Constan - -
	Aug·
6	et·Imp·Caes
	Severo - - -
8	M - - -

Two texts of the 1st and 2nd tetrarchies ?

(3)

- - - -
entiniano
 - - - -

Presumably the remains of a 4th century text, incorporating the name of the Emperor Valentinianus

- Caput Viae* [Ancyra]
Date (1) and (2) (?)
 (3) (?) [Val]entinianus, I or II

107(A). Coğlu 1

- Province, Sub-Province + Admin. Code* Ankara, Yenimahalle 06-03-3
Map Ankara 56-u

<i>Location</i>	In the centre of the village; beside a telegraph pole
<i>Copy</i>	DHF 15.vii.1973
<i>Publication</i>	RRMAM 1. 32
	RRMAM 2, 1. 127
<i>Description</i>	A simple cylinder. Hard, pale limestone
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

107(B). Çoḡlu 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 105(A)
<i>Provenance</i>	Not known. Now in the collection of the Sincan <i>Belediyesi</i> (Municipality) [Inv. no. 2002/31]
<i>Copy</i>	Seen but not copied DHF 16.ix.2005. No squeeze. No photo.
<i>Description</i>	A simple cylinder. Hard, pale limestone. The text was cut on a flattened surface (? erasure)
<i>Dimensions</i>	Ht 1.24; diam. 0.45. Letters: not recorded
<i>Text</i>	A text of c. 10+ lines (9 lines) 10 A Larcium Macedonem

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	AD 121/122(?) Hadrianus
<i>Commentary</i>	The text can be dated to the reign of Hadrianus on the basis of the governor's name.

108. Tatlar

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Yenimahalle 06-03-3
<i>Map</i>	Ankara 56-u
<i>Provenance</i>	In the village cemetery. Now in the collection of the Sincan <i>Belediyesi</i> (Municipality) [Inv. no. 2002/27]
<i>Copy</i>	Seen but not copied DHF 16.ix.2005. No squeeze. No photo.
<i>Description</i>	A simple cylinder. Hard, pale limestone.
<i>Dimensions</i>	Ht 1.32; diam. 0.48. Letters: not recorded
<i>Text</i>	(1) A tetrachic text of 9 lines (2) (?)

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	(1) AD 293-305 Diocletianus and Maximianus <i>Augusti</i> , (?)with <i>Caesares</i>
	(2) (?)

109(A). Susuz 1

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Yenimahalle 06-03-1
<i>Map</i>	Ankara 57-u

<i>Location</i>	In the village; beside the mosque
<i>Copy</i>	Seen by DHF 15.vi.1972, 15.vii.1973
<i>Publication</i>	RRMAM 1. 33(A) RRMAM 2, 1. 172
<i>Description</i>	A simple cylinder. Hard, pale limestone
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

109(B). Susuz 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 109(A)
<i>Location</i>	In the village; lying in the stream which runs down the main street
<i>Copy</i>	Seen by DHF 15.vi.1972, 15.vii.1973
<i>Publication</i>	RRMAM 1. 33(B) RRMAM 2, 1. 173
<i>Description</i>	A simple cylinder. Hard, pale limestone
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

110. Erkeksu Çiftlik

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Yenimahalle 06-03-3								
<i>Map</i>	Ankara 55-ü								
<i>Location</i>	“(The road reaches) the foot of the high ridge Ayash Bel beside Irkek-su tchiftlik, where there is another site with a curious ancient cemetery, on the lower slope of the hillock, on which this cemetery lies, we found the following milestone,” (Anderson 1899). Present whereabouts not established (DHF visit 24.ix.1975)								
<i>Copy</i>	Anderson Summer 1898. The text published by Anderson is reproduced here, Fig. 6.1.36 [p. 271]. The stone has not been examined by DHF. Text here from Anderson’s copy (1899, 60 no. 8)								
<i>Publication</i>	Anderson 1897-98, 66 (notice only) Anderson 1899, 60 no. 8) CIL 3. 14184 ^{62,63} (text of Anderson) Bosch 1967, 364 no. 300 (text of Anderson and CIL comments) RRMAM 1. 34 (text only; text of Anderson) RRMAM 2, 1. 136 (notice only)								
<i>Description</i>	“Unfortunately the number is again indecipherable (or possibly it was cut on the lower part of the pillar, which is broken away)” (Anderson)								
<i>Dimensions</i>	Not given								
<i>Text</i>	(1) (above and underneath text [2]) <table style="margin-left: 100px;"> <tr> <td style="text-align: center;">2</td> <td style="text-align: center;">B>F></td> </tr> <tr> <td style="text-align: center;"> </td> <td style="text-align: center;">Imp>Caes></td> </tr> <tr> <td style="text-align: center;"> </td> <td style="text-align: center;">IM[---]</td> </tr> <tr> <td style="text-align: center;"> </td> <td style="text-align: center;">-- ? --</td> </tr> </table> (2) (below and on top of text[1])	2	B>F>		Imp>Caes>		IM[---]		-- ? --
2	B>F>								
	Imp>Caes>								
	IM[---]								
	-- ? --								

Imp·Caes·C [Aur]
Val·Diocletiano [p f]
inv·Aug·et Imp·Caes
 4 **M·Aur·Val·Maximiano**
p·f·inv·Aug·et
Fla·Val·Constanti[o]
et·G·Val·Maximiano
 8 **nobilissimis**
Caesaribus
RLSMV..
(sic)

Caput Viae [Ancyra]
Date (1) AD (?)
 (2) AD 293, 21.v(?)-305, 01.v Diocletianus and Maximianus *Augusti* with
 Constantius I and Galerius *Caesares*
Commentary The separation (of the inscription as copied by Anderson) into two texts, as
 proposed here, was not suggested by Anderson himself.

111(A). Eryaman 1

Province, Sub-Province + Admin. Code Ankara, Yenimahalle 06-03-2
Map Ankara 57-ü
Location In the village. “On a heavy pillar, lying beside the mosque” (Anderson). On
 the left of the gate into the courtyard of the mosque; upside down and largely
 obscured
Copy Anderson Summer 1898; DHF 24.ix.1975. The text published by Anderson is
 reproduced here, Fig. 6.1.37 [p. 271]). No DHF photo. DHF squeeze (lines
 6-10) in BIAA. Text here from Anderson (1899, 59 no. 5) and from DHF
 notes and squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 06. Ankara 78, Eryaman 1
Publication Anderson 1897-98, 65 (notice only)
 Anderson 1899, 59 no. 5
 AE 1899. 183 (text of Anderson)
 CIL 3. 14184 (text of Anderson)
 Bosch 1967, 148 no. 123 (text of Anderson, and comment)
 RRMAM 1. 35(A) (text only, from DHF copy; line 4 corrected here, see
 below)
Description RRMAM 2, 1. 137 (notice only)
Dimensions A simple cylinder. Broken above. Pale limestone
 Ht (ex.) 1.30; diam. (base) 0.65. Letters: 0.035-48

Text **Imp Caesari di-**
 2 **vi Traiani Parthici**
 fil divi Nervae nepo-
 4 **ti Traiano Hadrino**
 Aug pont̄ māx̄ tr pot
 6 **VI cos I[I]I per A Larci-**
 um Macdonem leg Aug
 8 **(vac) pr pr**
(sic)
(sic)

10 (vac) **mi** [-]
 (vac) **III**[-]

- line 2: ligature **TH**
- line 3: ligature **NE** (twice)
- line 7: ligature **NE**
- line 9: ligature **MI**
- line 10: **II**[-], (?)**IH**, i.e. $\text{v}\eta'$

Caput Viae (Ancyra)
Date AD 121/122, 10.xii-09.xii Hadrianus *Augustus*

111(B). Eryaman 2

Province, Sub-Province + Admin. Code and Map As 111(A)
Location Outside the village. At the gate into the cemetery on the W side of the village
Copy Macpherson 1953(?); DHF 24.ix.1975. Macpherson squeeze in the Faculty of Classics, Cambridge (IWM Box VI no. 141); DHF squeeze in BIAA. No DHF photo. Text here from DHF notes and squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 06. Ankara 79, Eryaman 2
Publication Macpherson 1954, 113 no. 1
 Macpherson 1958, 162 no. 207
 RRMAM 1. 35(B) (text only, from DHF copy)
 RRMAM 2, 1. 138 (notice only)
Description A simple cylinder. Broken above and below. White-veined grey limestone.
 Surface: somewhat worn
Dimensions Ht 0.90; diam. 0.24. Letters: 0.033-43

	B	F
2	Imp·Caes·	
	P·Licinn	
4	Valeriano	
	p·f·Aug·	
6	et Imp Caes·	
	P·Licinn	
8	Gallieno	
	p·f·Aug·	

Caput Viae [Ancyra]
Date AD 253, “vor 23 Okt.”-255 Valerianus and Gallienus *Augusti*
Comment The date here assumes that Valerianus *iunior* had not yet been named *Caesar*. He became *Caesar* in AD 255; see Kienast (1996, 221). According to Kienast (1996, 218), Gallienus became *Caesar* Sept./Okt. 253 and *Augustus* “vor Okt. 23 253.”

112. Ankara, Etimesgut

Province, Sub-Province + Admin. Code Ankara, Yenimahalle 06-03-1

<i>Map</i>	Ankara 57-u
<i>Provenance</i>	Not known. Now in the Roman Baths, Ankara [Inv. no. 113.507.99]
<i>Copy</i>	Macpherson 1953(?); SM 10.xi.1971; DHF 10-12.ix.1974. Macpherson squeeze in the Faculty of Classics, Cambridge (IWM Box I nos 1-8); DHF squeeze in BIAA. No DHF photo. Text here from DHF notes and squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 57, Etimesgut
<i>Publication</i>	Macpherson 1958, 166 no. 215 RRMAM 1. 36 (text only, from DHF copy) RRMAM 2, 1. 139 (notice only) French 2003, 194 no. 79 (DHF text, commentary and photo.)
<i>Description</i>	A column re-used as a milestone. Complete. Pale grey, white-veined marble. Surface and letters: some wear.
<i>Dimensions</i>	Ht 1.22; diam. (top) 0.60. Letters: text (1) (line 1) F 0.070, (lines 2-10) 0.06, text (2) (line 1) 0.090-130, (line 6) 0.090-110. Lines 1-7: space between lines 0.055

Text (1) (on the front face)

	B F
	Imp(leaf)Caes
	[Ga]io(leaf)Iulio
4	[V]ero Maximi-
	no pio felici
	Aug(leaf)trib(leaf)p
	p p (vac 0.15)
8	m p (vac 0.135)
	VIII
	η'

(2) (on the left of text [1])

	Imp Caes·C·Aur·Val
2	Diocletiano p f·inv·
	Aug·et Imp·Caes M Aur·Val
4	Maximiano p f·inv·Aug
	et Fla Val·Constantio
6	et Gal·Val·Maximiano nobi-
	lissimis Caesaribus

Caput Viae (Ancyra)

Date (1) AD 235, Feb/March-236, 07.i/16.v Maximinus *Augustus*
(2) AD 293, 21.v(?)-305, 01.v Diocletianus and Maximianus *Augusti* with
Constantius I and Galerius *Caesares*

Commentary It is not known on which road – to Pessinus ? or to Iuliopolis ? – this milestone once stood but most probably it was erected on the road which ran westwards from Ancyra to Iuliopolis and thence to Nicaea, Nicomedia and Chalcedon. On the basis of comparison between the text and lettering of text (2) with the text and lettering of the Batikent milestone – (below, no. 115. text [2]) - it is possible that both may have belonged to the same series, that is to say, both were erected on the same road, the so-called Pilgrim's Road, if the provenance of the Batikent

milestone is an indication of its original location.

113. Yuva

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Yenimahalle 06-03-0														
<i>Map</i>	Ankara 58-ü														
<i>Provenance</i>	At a çeşme, 'Dörtpınar Mevkii', c. 3.50 km S of the village. Now in the Roman Baths, Ankara [Inv. no. 99.113.533]														
<i>Copy</i>	DHF 15.vii.1973. DHF squeeze in BIAA. No DHF photo. Text here from DHF squeeze														
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 108, Yuva														
<i>Publication</i>	RRMAM 1. 37 (text only, from DHF copy) RRMAM 2, 1. 181 (notice only)														
<i>Description</i>	A simple cylinder, on a square plinth. Broken into two pieces. Hard, pale grey limestone. The top surface is flat but is broken all round. The surface and letters are chipped and worn; the letters of text [1] are very regular and well cut but those of text [2] are somewhat irregular and poorly cut; the letters of text [3] are very irregular and very poorly cut														
<i>Dimensions</i>	Ht (vis.) 0.85; diam. 0.47. Letters: (text 1) 0.060-70; (text 2) 0.05-06; text [3] 0.045														
<i>Text</i>	(1) (on the front face of the shaft) <table border="0"> <tr> <td style="vertical-align: top; padding-right: 10px;">Imp·Caes·C·Aur·Valer</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">2 D<small>i</small>o<small>c</small>leti<small>i</small>[a]no·p·f·in[v]</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">4 Aug·et·Imp·Caes·[M·]</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">4 [Aur]·Val·M<small>a</small>[xim]iano·p f</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">5 i[nv·Aug] et Fl [-]</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">6 [-]</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">6 [-]</td> <td></td> </tr> </table>	Imp·Caes·C·Aur·Valer		2 D<small>i</small>o<small>c</small>leti<small>i</small>[a]no·p·f·in[v]		4 Aug·et·Imp·Caes·[M·]		4 [Aur]·Val·M<small>a</small>[xim]iano·p f		5 i[nv·Aug] et Fl [-]		6 [-]		6 [-]	
Imp·Caes·C·Aur·Valer															
2 D<small>i</small>o<small>c</small>leti<small>i</small>[a]no·p·f·in[v]															
4 Aug·et·Imp·Caes·[M·]															
4 [Aur]·Val·M<small>a</small>[xim]iano·p f															
5 i[nv·Aug] et Fl [-]															
6 [-]															
6 [-]															
	(2) (on the lower r. side of text [1] over the top of lines 4-5) <table border="0"> <tr> <td style="vertical-align: top; padding-right: 10px;">Imp Caes</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">Constantino p</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">f [-] et Imp Val Lic[iniano]</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">[- - - -]</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">(?)</td> <td></td> </tr> </table>	Imp Caes		Constantino p		f [-] et Imp Val Lic[iniano]		[- - - -]		(?)					
Imp Caes															
Constantino p															
f [-] et Imp Val Lic[iniano]															
[- - - -]															
(?)															
	(3) (on top of the r. side of text [1] and over text [2]) <table border="0"> <tr> <td style="vertical-align: top; padding-right: 10px;">[Imp Caes F]l Val</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">Constantino p f [max]</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">[- - - -]</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">Constantino et</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">Constantio et</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">Constanti nob[b]</td> <td></td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">[Caess]</td> <td></td> </tr> </table>	[Imp Caes F]l Val		Constantino p f [max]		[- - - -]		Constantino et		Constantio et		Constanti nob[b]		[Caess]	
[Imp Caes F]l Val															
Constantino p f [max]															
[- - - -]															
Constantino et															
Constantio et															
Constanti nob[b]															
[Caess]															
<i>Caput Viae</i>	[Ancyra]														
<i>Date</i>	(1) AD 293, 29.v(?)-305, 01.v Diocletianus and Maximianus <i>Augusti</i> with [Constantius I and Galerius <i>Caesares</i>]														

- (2) AD 317-324 Constantinus I and Licinius I *Augusti*
 (3) AD 333, 25.xii-335, 18.ix Constantinus I *Augustus* with [Constantinus II],
 Constantius II and Constans [*Caesares*]

114. Macun

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Yenimahalle 06-03-2
<i>Map</i>	Ankara 58-ü
<i>Location</i>	In a cemetery, on E of the village
<i>Copy</i>	Macpherson 1953(?); DHF 22.ix.1975. Macpherson squeeze in the Faculty of Classics, Cambridge (IWM Box VI no. 148); DHF squeeze in BIAA. No DHF photo. Text here from DHF notes and squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 06. Ankara 88, Macun
<i>Publication</i>	Macpherson 1954, 114 no. 3 and Pl. 10.1 Macpherson 1958, 179 no. 249 RRMAM 1. 38 (text only, from DHF copy) RRMAM 2, 1. 158 (notice only)
<i>Description</i>	A simple cylinder. Broken behind. Grey limestone. The top surface is flat
<i>Dimensions</i>	Ht (vis.) c. 1.83; diam. c. 0.60. Letters: (line 1) E of CAES 0.086, (line 8) E of NEM 0.033

<i>Text</i>	Imp Caesari divi Traiani Par- thici f divi Nervae
	4 nepoti Traiano Hadri- ano Aug pont max tr̄ pot VI cos III p̄er A Larcium Ma-
	8 c̄edonem leg Aug (vac) pr pr (vac) (vac) m VII (vac) ζ'

line 3: ligatures **TH, NE**

line 4: ligature **NE**

line 5: ligature **NT**

line 8: ligature **NE**

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 121/122, 10.xii-09.xii Hadrianus <i>Augustus</i>

115. Ankara, Batikent

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Yenimahalle 06-03-0
<i>Map</i>	Ankara 58-ü
<i>Provenance</i>	Found in 1990 in Batikent (c. 6 km W of Ulus). Now in the garden, on the lower terrace, of the Museum of Anatolian Civilizations, Ankara [Inv. no. 8.91.90]

Copy DHF 01.viii.1990. DHF squeeze (drawing, Fig. 6.2.80 [p. 303] and photos (Pl. 7.2.42-43 [pp. 356-357]) in BIAA. Photos by Tuğrul Çakar in BIAA (Pl. 7.1.67 [p. 326]). Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 06. Ankara 192, Ankara, Batıkent (= B/W Neg.: Squ. M/11.01-03 and 07-12)

Stone: (1) B/W Neg.: BIAA (Tuğrul Çakar)

Publication French 1990b, 15 and photo., Pl. 10b

AE 1994, 1724 a-d (text of French)

French 2003, 188 no. 76 (text, commentary and photo.)

Conti 2004, 74 no. 21 (text [4] and comment)

Description A column re-used as a milestone. Chipped at the top, otherwise complete. Hard, grey limestone. The mouldings at the base of the column were removed. The column was inverted before being inscribed as a milestone; consequently the shaft now tapers slightly towards the bottom. The top surface is flat. The surface of the shaft is finely smoothed. Surface: some wear. The letters of the first text were very well shaped, of even height, and carefully cut; they remain sharp and clear.

Dimensions Ht 2.20; diam. (top) 0.51. Letters (text 1): (line 1) I of IMP 0.038

Text (1) (on the front face of the shaft)

4	Imp Caesar [L Septi]- mius Sever[us Pius] Pertinax·A[ug Ara]- /b/icus Adia[benicus]
8	Parthicus māximūs fe(lix) trib·potēs<t>atis XVI imp·XII ços·I[II pro-] (vac) ços·p [p] (vac)
12	et Imp Caesar [M Aure]- lius Antoniū[s Pius] Aug·felix·tr[ib potes]- tatis XI imp II [cos III] procōs·Parthi-
16	(vac) çus max·(vac) (vac) cos·II·viam stratām a novo
20	(vac) fecerunt·per·P /P/ Caecilium Urbicum Aimilianum leg·Augg[gl] (sic) pro·pr·cos·designat (vac)
	MP [[X]]VIII (vac) (vac) Θ

line 4: **R** (lapis)

line 5: ligature **TH**

line 6: the numeral XVI can be restored from the Severan milestone

which is better preserved (117[M]. Ankara 13)
line 7: ligature **MP**; **COS I[II]** can be restored from the Severan
milestone below (117[M]. Ankara 13)
lines 9 and 12: ligature **IM**
lines 14, 15 and 16 (partly): the names and title (but not his consulship)
of Geta – et P Septimius Geta nobilissimus Caesar, as on the
Severan milestone below (117[M]. Ankara 13) – were erased and
replaced by the words now present, cp. no. 72. Tilkihan
line 17: ligature **NT**
line 18: **I** (lapis)
lines 18-19: Caecilium (correctly) but Aimilianum instead of
Aemilianum, cp. the variation on the Severan milestone below,
(117[M]. Ankara 13)
line 19: **AUGGG**, the final **G** was erased on the stone

(2) (on the r., and partly over the top, of text [1])

	Imp Cæs C A[ur] Val
2	Diocletiano p f inv
	Aug et Imp Caes M Aur
4	Val [Maximia]no p f inv Aug
	et Flav(io) Val Con(s)tantio et
6	Gal Val Maximiano nobili[s]-simis Caesaribus

(3) (over the top of text [2]; lines 3-5 of text [2] adapted and extended)

	B (vac) F
	(vac)
2	Imp Caes Fl
	Val Co(n)stantino p f inv Aug
4	et Imp Caes Val Licinio p f
	(vac) in(v) Aug
	(vac)
6	M VIII Θ

There was considerable re-use and adaptation of the letters of text (2):

line 1: over the top of line 1 of text (2)
line 2: **IMPCAES** re-used from line 3 of text (2)
line 3: **VAL** and **NOPFINVAUG** re-used from line 4 of text (2)
line 4: **ETFL** re-used as **ETIMP**, and **NTIOET** as **INIOPF**, from line 5
of text (2)
line 5: over the top of line 6 of text (2)

(4) (over the top of text [2], lines 1-3)

	Fl Iuliano maxi-
2	mo victori aç tri-
	umfatori (s)emper
4	Aug

- Date*
- (1) AD 207/208, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) *Augusti* with P. Septimius Geta (names erased) *Caesar*
 - (2) AD 293, 21.v(?)-305, 01.v Diocletianus and Maximianus *Augusti* with Constantius I and Galerius *Caesares*
 - (3) AD 313, Aug./Sept.-317, 28.ii Constantinus I and Licinius I *Augusti*
 - (4) AD 361, 03.xi-363, 26/27.vi Flavius Julianus *Augustus*

Commentary There are 4 overlapping texts on this milestone, the third text (text [3]) re-using and adapting the letters of the previous inscription (text [2]). This practice, when combined with natural weathering and other damage, can make the texts on milestones exceptionally difficult to read; it is by no means uncommon to find 6 or 7 separate texts on a single milestone.

On the basis of its provenance – on the W side of Ankara, as nos 116. Akköprü and 112. Etimesgut, above – this milestone may once have stood on the so-called Pilgrim's Road, the major highway between Byzantium/Constantinoplis, Ancyra, Tarsus and Antiochia (modern Antakya). There is a replicate of text (1) on another Severan milestone, 117(M). Ankara 13. On this second stone the distance figure is MP VI; it is probable that both milestones were erected on the same road, i.e. on the Pilgrim's Road.

116. Ankara, Akköprü

- Province, Sub-Province + Admin. Code* Ankara, Yenimahalle 06-03-0
Map Ankara 58-ü
Provenance Found in 1989 during drain-digging operations on the E side of the bridge at Akköprü (c. 2.5 km NW of Ulus) below Yenimahalle in 1989. Now in the garden, beside the steps to the lower terrace, of the Museum of Anatolian Civilizations, Ankara [Inv. no. 218.1.89]
Copy DHF 05.vi.1989. DHF squeeze (Pl. 7.2.44 [p. 358]) in BIAA. Photos by Tuğrul Çakar in BIAA (Pl. 7.1.68 [p. 326]). Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 06. Ankara 106, Ankara, Yeni Mahalle (= Akköprü) (= B/W Neg.: Squ. M/11.04-06)
 Stone: (1) B/W Neg.: BIAA (Tuğrul Çakar)
Publication French 1990b, 13 and photo., Pl. 10a
 AE 1994. 1723 (text of French)
 French 2003, 188 no. 75 (text, commentary and photo.)
Description A simple cylinder. Complete. Hard, pale limestone. The shaft is straight; the top surface is approximately flat. Under the base there is a large, round tenon. The surface of the shaft is roughly chiselled but the area of the inscription is well smoothed.
Dimensions Ht (plus tenon) c. 2.22, (tenon) 0.11; diam. 0.48 (front face to back 0.57), (tenon) 0.451. Letters: (line 1) E of CAES 0.085, (line 2) T of TRAI 0.057, (line 6) T of POT 0.45

<i>Text</i>	Imp Caesari	
	divi Traiani Par-	
4	thici f divi Nervae	
	nepoti Traiano Ha-	
	driano Aug pont	
	max trib pot VI co⟨s⟩	
	III (vac) per A Larcium	
8	Macedonem leg	

Aug (vac) **pro** (vac) **pr**
M (vac) **II**
 (vac) **β'**

line 3: ligature **TH**
 line 8: ligature **NE**

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 121/122, 10.xii-09.xii Hadrianus <i>Augustus</i>
<i>Commentary</i>	The provenance of this milestone on the W side of Ankara – at Akköprü, c. 2.5 km NW of Ulus at the centre of Ancyra – suggests that – as nos 112. Etimesgut and 115. Batıkent – it may once have stood on the so-called Pilgrim’s Road, the major highway between Byzantium-Constantinopolis and Antiochia (modern Antakya).

117(A). Ankara 1

<i>Location</i>	“Nous leûmes” (lûmes) “au dela de la Tour, où l’on passe pour aller à la porte d’Esset, sur une colonne enchaînée dans la muraille, les mots suivans. Le reste est écrit sir la partie de la colomne qui est engagée dans la muraille” (de Tournefort). For the position of the “Esset” Gate (= Esat Kapısı, on the S side of the Ottoman Outer Castle), see Mamboury (1933, 80). Present whereabouts not established
<i>Copy</i>	de Tournefort between 22 October and 02 November 1701. Text here from the de Tournefort copy in CIL
<i>Publication</i>	de Tournefort 1717a, 2, 453 = 1717b, 3, 324 = 1718, 2, 181 Donati 1765-74, 1, (Classis III) 147 no. 1 (text of de Tournefort 1717b) Le Bas 1853-58 (“livraison 47 [1858]”), 440 no. 1787 (majuscule version of de Tournefort 1718) Le Bas and Waddington 1870, 2, 426 no. 1787 (text of de Tournefort 1718) CIL 3, 1. 246 (text of de Tournefort 1717b; notice of de Tournefort text in Donati and Le Bas) Bosch 1967, 345 no. 281 (de Tournefort text in CIL) RRMAM 1. 39(A) (text only; de Tournefort text in CIL) RRMAM 2, 1. 092 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	Imp Caes
2	[Lic Valeriano]
	[Aug]
4	et Imp [Caes Licin] Gallieno
6	-----

line 4: **IMPRO** (de Tournefort, followed by Donati and by Le Bas [1853-58, 440 no. 1787 = Le Bas and Waddington 1870, 2, 426 no. 1787])

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	AD 253-255 Valerianus and Gallienus <i>Augusti</i>
<i>Commentary</i>	This milestone – if it is a milestone – cannot be attributed, with certainty, to the

Pilgrim's Road.

117(B). Ankara 2

<i>Provenance</i>	Formerly in the Namazgâh Mezarlığı? "Porte de Namazghia" (Perrot 1872). The cemetery – which no longer exists – is now the location of the Ethnographic Museum. Now in the Roman Baths, Ankara [Inv. no. 113.505.99]
<i>Copy</i>	Perrot between 12 August and 29 October 1861; Miltner (H.) Summer 1934; DHF 11.ix.1974. DHF squeeze in BIAA. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 176, Ankara 2
<i>Publication</i>	Henzen 1862, 66 (copy of Perrot) Perrot 1867, 102 Le Bas and Waddington 1870, 2, 425 no. 1784a (text of Perrot in Henzen) Perrot et al. 1872, 1, 227 no. 111 CIL 3, 1. 312 (text of Perrot in Henzen) ILS 1. 268 (text of Perrot in CIL) Sandys 1919, 136 (lines 3-10 of CIL text) Miltner (H. and Fr.) 1936, 20 no. 18 (notice of lines 1-2 and 9 in CIL text) Bosch 1967, 67 no. 68 (text of Perrot) French 1980, 717 no. 10 RRMAM 1. 39(B) (text only, from DHF copy) RRMAM 2, 1. 093 (notice only)
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. The top surface is flat. The shaft is straight; there is no base. The surface of the shaft is roughly dressed. The text is inscribed on a smooth, prepared panel. Surface and letters: slightly worn
<i>Dimensions</i>	Ht 1.68, " . . . haute de 1 ^m ,87" (Perrot); diam. (top) 0.53. Letters: 0.03-04, "0 ^m ,035" (Perrot)

<i>Text</i>	Imp Caes divi Vespasiani f [[Domitianus]] Aug pot·max (sic) trib·potest·cos·VIII desig·VIII(l) p p·per
	4 A·Caesennium Gallum leg pro·pr·vias provinciarum Galatiae Cappadociae Ponti Pisidiae Paphlagoniae
	8 Lycaoniae Armeniæ Minor(is) stravit η' VIII

lines 1-2: **Vespasiani** | [f Domitianus] (Perrot)

line 2: **PonT** (Perrot)

line 8: perhaps **Minor**⟨is⟩

lines 3, 10: line over the top of the numeral **VIII**

Caput Viae (Ancyra)

<i>Date</i>	AD 82, “seit Mitte Marz”-13.ix Domitianus (name erased) <i>Augustus</i>
<i>Commentary</i>	This milestone cannot be attributed, with certainty, to the Pilgrim’s Road.

117(C). Ankara 3

<i>Location</i>	Formerly at the Hacı Musa Mosque; “Dans le porche de la mosquée d’ <i>Hadjı-Moussa</i> ” (Perrot 1872). Present whereabouts not established
<i>Copy</i>	Perrot between 11 August and 29 October 1861. Text here from copy of Perrot (1872, 1, 228)
<i>Publication</i>	Henzen 1862, 68 (copy of Perrot) Perrot 1867, 113 Perrot et al. 1872, 1, 228 no. 112 CIL 3, 1. 313 (text of Perrot) Bosch 1967, 148 no. 120 (text of Perrot in CIL) RRMAM 1. 39(C) (text only; text of Perrot in CIL) RRMAM 2, 1. 094 (notice only)
<i>Description</i>	“Sur une colonne milliaire” (Perrot)
<i>Dimensions</i>	“Hauteur des lettres 0 ^m ,04” (Perrot)
<i>Text</i>	<p style="text-align: center;">Imp·Caes· divi Traia[ni Par]- thici [f]·divi Nervae 4 nepoti Traiano Hadriano Aug pon[t max] tri[b] pot VI cos III per A·Larcium Ma- 8 cedonem leg·Aug· pr·pr·[m p] VII[I]·η'</p>

line 10: line over the top of the numeral VIII

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 121/122, 10.xii-09.xii Hadrianus
<i>Commentary</i>	This milestone cannot be attributed, with certainty, to the Pilgrim’s Road.

115(D). Ankara 4

<i>Location</i>	Formerly in the Armenian cemetery; then at the Milli Eğitim Bakanlığı, “Autour du nouveau Ministère de l’Instruction publique, alors en construction (sur l’emplacement d’anciens cimetières), nous avons vu plusieurs milliaires” (de Jerphanion). Present whereabouts not established
<i>Copy</i>	Mordtmann (A. D.) 1858; de Jerphanion between 1925 and September 1927. Text here from copy of Mordtmann in CIL and from copy of de Jerphanion
<i>Publication</i>	CIL 3, 1. 315 (text of Mordtmann) de Jerphanion 1928, 277 no. 52 (line 5 only) RRMAM 1. 39(D) (text only; text of Mordtmann in CIL) RRMAM 2, 1. 095 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	Imp [---]
2	MC [-----]
	C [-----]
4	via [-----]
	m·XIII iγ'

line 5: **M XIII IE** (CIL), **M XIII IIΓ** (de Jerphanion)

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	(?)
<i>Commentary</i>	This milestone cannot be attributed, with certainty, to the Pilgrim's Road.

117(E). Ankara 5

<i>Location</i>	Seen by de Jerphanion “Autour du nouveau Ministère de l'Instruction publique, alors en construction (sur l'emplacement d'anciens cimetières), . . .”, cp. 117(D) Ankara 4. Present whereabouts not established
<i>Copy</i>	de Jerphanion between 1925 and September 1927. Text here of de Jerphanion
<i>Publication</i>	de Jerphanion 1928, 277 no. 53 Bosch 1967, 365 no. 302 (text of de Jerphanion) RRMAM 1. 39(E) (text only; text of de Jerphanion)
<i>Description</i>	RRMAM 2, 1. 096 (notice only) “ . . . brisé et probablement martelé aussi (ou du moins très usé). Le haut du texte manque. Puis, après deux lignes indéchiffrables . . . ” (de Jerphanion)
<i>Dimensions</i>	Not given
<i>Text</i>	— — — et Gal V[al Maximiano] nobilissi[mis Caess] m VII
<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 293-305 [Diocletianus and Maximianus <i>Augusti</i> with Constantius I] and Galerius [<i>Caesares</i>]
<i>Commentary</i>	This milestone cannot be attributed, with certainty, to the Pilgrim's Road.

117(F). Ankara 6

<i>Provenance</i>	Not known. Seen at the Hacı Bayram mosque by Ramsay in 1927-1928. Now in the Roman Baths, Ankara [Inv. no. 113.501.99]
<i>Copy</i>	Ramsay 1927-1928; Miltner (H.) Summer 1934; DHF 10-12.ix.1974. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 177, Ankara 6
<i>Publication</i>	Miltner (H. and Fr.) 1936, 27 no. 28 Bosch 1967, 365 no. 303 (text of Miltner) RRMAM 1. 39(F) (text only, from DHF copy) RRMAM 2, 1. 097 (notice only)
<i>Description</i>	“Schriftseite arg vertrieben und, da doppelt beschrieben, unleserlich geworden bis auf die Meilenangabe” (Miltner); “Nr. 300 und 303 sind auf ältere Inschriften geschrieben, von denen noch einzelne Spuren erkennbar sind, ohne

dass man jedoch diese rekonstruieren könnte” (Bosch). A simple cylinder. Broken at the top. Hard, pale limestone. The shaft is straight. Surface and letters: worn
Dimensions
 Ht (vis.) 0.96; diam. 0.455. Letters: (line 4) M of VMF 0.06, (line 9) O of NOBB 0.045

Text

(1) (underneath text [2])	
	illegible
(2) (on the front face; on top of text [1])	
	[D n Fl Val]
	[Constantino]
	maximo victori
4	[ac t]riumphatori
	sem̄per Aug et Fl Cl
	Constantino et Fl
	Constantio
8	et Fl Iul Constant <i>(i)</i>
	nobb Caess
	m XXXIII
	λδ'

line 7: “ . . . in der drittletzten Zeile *Constantio*” (Miltner)

Caput Viae (Ancyra)
Date (1) (?)
 (2) AD 333, 25.xii-335, 18.ix Constantinus I *maximus Victor Augustus* with Constantinus II, Constantius II and Constans *Caesares*
Commentary This milestone cannot be attributed, with certainty, to the Pilgrim’s Road. The distance figure, 34 MP (= c. 50.5 km) indicates a location on one of three roads: W of Ankara in the region of Ayaş, S of Ankara in the region of Yöreli or E of Ankara in the region of Elmadağ.

117(G). Ankara 7

Provenance Not known. Now in the Roman Baths, Ankara [Inv. no. 14501]
Copy SM 10.xi.1971; DHF 10-12.ix.1974. SM squeeze and photo. (Pl. 7.1.69 [p. 327]) and DHF squeeze in BIAA. No DHF photo. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 06. Ankara 178 [DHF], 179 [SM], Ankara 7
Publication Mitchell in French (ed.) 1973, 26 photo. (illustration only)
 French 1980, 728 map 3 no. 15 (notice only)
 RRMAM 1. 39(G) (text only, from DHF copy)
 RRMAM 2, 1. 098 (notice only)
 French 2003, 185 no. 72 (text, commentary and photo.)
Description A simple cylinder. Complete. Hard, pale limestone. The top surface is flat. The inscription is cut in a sunken, frameless panel (starting 0.17 below the top), on a smooth surface. Letters: sharp and clear
Dimensions (Shaft) ht 1.68; diam. (top) c. 0.55. (Inset panel) ht 0.715, (wi.) 0.60. Letters:

(line 1) 0.055, (line 2) 0.045-50, (line 5) 0.035, (line 8) 0.03, (line 12) 0.07

Text

	4	Imp·Caes·divi Vespasiani·f [[Domitia]]- [[nūs]] Aug·pont·max·trib
	8	pot·p p·cos·VIII·desig·VIII imp·II·(vac) per· A·Caesennium·Gallum·cos XV·vir·s·f·leg·Aug·pro·pr vias provīciarum·Galatiae Cappa- dociae·Ponti·Pisidiae Paphlago- niae Lycaoniae Armeniae Minoris·
	12	stravit·II·

Caput Viae

[Ancyra]

*Date*AD 82, “seit Mitte Marz”-13.ix Domitianus (name erased) *Augustus**Commentary*

This milestone cannot be attributed, with certainty, to the Pilgrim’s Road.

117(H). Ankara 8*Provenance*

Not known. Now in the Roman Baths, Ankara [Inv. no. 14502]

Copy

SM (?date); DHF 10-12.ix.1974. SM and DHF squeezes in BIAA. No DHF photo. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 06. Ankara 180 [SM], 181 [DHF], Ankara 8

Publication

RRMAM 1. 39(H) (text only, from DHF copy)

RRMAM 2, 1. 099 (notice only)

French 2003, 193 no. 78 (text, commentary and photo.)

AE 2006. 1485 (text of French 2003)

Description

A simple cylinder. Complete. Hard, pale limestone. The top surface is flat. The inscribed area is smoothed; otherwise the surface of the shaft is rough. Surface and letters: slight wear.

Dimensions

Ht 1.62; diam. (top) 0.47. Letters: (line 1) 0.055, (lines 2-10) 0.50

Text

	4	B·F· Imp·Caes·divi Severi [[nepos]]
	8	divi Antonini· [[filius]] M·Aur· [[Antoninus]] pius fel·Aug·tri pote- st·cos·procos p·p·restituit
		m p [–]

Caput Viae

[Ancyra]

*Date*AD 218, 16.v-09.xii M. Aurelius Antoninus (Elagabalus) *Augustus*

Commentary This milestone cannot be attributed, with certainty, to the Pilgrim's Road.

117(I). Ankara 9

<i>Provenance</i>	"From Akkiri" [sic] (CIL); (?) Akkiri = Akköprü, the location of milestone 113. Ankara, Akköprü. Present whereabouts not known
<i>Copy</i>	(? Abbé Vincent Kirmizian) to Mordtmann [J. H.] 1870; Ramsay June 1871.
<i>Publication</i>	Not re-found by DHF. Text here from copy of Mordtmann in CIL CIL 3, 2. 6058 (text from Mordtmann [J. H.] in 1870 from two copies of a local friend), and 6900 (text from a copy of Ramsay 1871 and a photograph of Mordtmann [J. H.]) Mommsen 1884a, 35 no.72 (text from Mordtmann [J. H.] in 1870 from two copies of a local friend), as CIL 6058) ILS 1. 467 (text in CIL) Bosch 1967, 333 no. 273 (text in CIL) RRMAM 1. 39(I) (text only; text of Mordtmann in CIL) RRMAM 2, 1. 100 (notice only) Christol and Loriot 2001, 106 no. 1a) (notice of ll. 10-11) AE 2001. 1915 (notice of Christol and Loriot)
<i>Description</i>	"Columna" (CIL 6058)
<i>Dimensions</i>	Not given

Text

	B	F
	[Imp] Caes divi Antonin[i]	
	[fi]lio divi Severi nepoti	
4	[M Aure]l Antonino pio fel	
	[Au]g trib potest cos	
	[pr]ocos p p domino	
	[in]dulgentissimo dica-	
8	[ti]ssima numini eius	
	[met]ropolis Ancyranorum	
	[per] L Egnatium Victorem	
	(v) Lollianum·leg eius	
12	pr pr	
	m p	
	III	

line 14: line over the numeral III

<i>Caput Viae</i>	Ancyra
<i>Date</i>	AD 218, 16.v-09.xii M. Aurelius Antoninus (Elagabalus) <i>Augustus</i>
<i>Commentary</i>	This milestone cannot be attributed, with certainty, to the Pilgrim's Road.

117(J). Ankara 10

<i>Provenance</i>	Not known. Now in the Roman Baths, Ankara [Inv. no. 113.503.99]
<i>Copy</i>	Miltner (H.) Summer 1934; DHF 10-12.ix.1974. DHF squeeze in BIAA. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 06. Ankara 184, Ankara 10

<i>Publication</i>	Miltner (H. and Fr.) 1936, 21 no. 21 and Fig. 7 AE 1937. 91 (text of Miltner) RRMAM 1. 39(J) (text only, from DHF copy) RRMAM 2, 1. 101 (notice only)
<i>Description</i>	A simple cylinder. Complete? Hard, pale limestone. The top surface is flat. The inscribed area was smoothed; otherwise the surface was only roughly dressed.
<i>Dimensions</i>	Ht (vis.) 1.10; diam. (top) 0.54. Letters: (line 1) E of AES 0.055, (line 8) E of LEG 0.085

<i>Text</i>	Imp Caesari divi Traiani Parthi- ci f divi Nervae nepoti 4 Traiano Hadriano Aug p<small>ont</small>·max trib pot VI cos IIII per A Lar- cium Macedonem 8 leg Aug pr pr m IIII δ'
-------------	---

- line 2: ligature **TH**
 line 3: ligatures **NE** (twice)
 line 5: ligature **NT**
 line 7: ligature **NE**

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 121/122, 10.xii-09.xii Hadrianus <i>Augustus</i>
<i>Commentary</i>	This milestone cannot be attributed, with certainty, to the Pilgrim's Road.

117(K). Ankara 11

<i>Provenance</i>	Not known. Now in the Roman Baths, Ankara [Inv. no. 113.493.99]
<i>Copy</i>	SM 18.xi.1971; DHF 10-12.ix.1974. SM and DHF squeezes and DHF photo. in BIAA
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
<i>Publication</i>	Squeeze: 06. Ankara 182 [DHF], 183 [SM], Ankara 11 RRMAM 1. 39(K) (text only, from DHF copy) RRMAM 2, 1. 102 (notice only) French 2003, 187 no. 74 (text, commentary and photo.) AE 2006. 1484 (text of French 2003)
<i>Description</i>	A simple cylinder. Broken at the top. Hard, pale limestone. The inscribed area was smoothed; otherwise the surface is rough. At the bottom of the shaft there is a roughly shaped base or plinth, c. 0.25 high. Letters: some wear.

<i>Dimensions</i>	Ht 1.90; diam. (top) 0.50. Letters: (line 3) 0.074, (other lines) 0.045-50
-------------------	--

<i>Text</i>	(1) (underneath text [2]) traces of letters
	(2) (on the face of the shaft)

2 [Imp Caesari]
 [divi Traiani Parthi]-
ci f divi Nervae n̄ep.
 4 **Traiano Hadrian**[o]
Aug pont max tr pot VI
 6 **cos III per A Larcium**
Maceeonem leg Aug (sic)
 8 **p r p r**
m I

line 3: ligatures **NE**
 line 5: ligature **NT**
 line 7: ligature **NE**
 line 9: there are indecipherable letters (presumably of text [1]) below the
 second PR (in line 8); in all previous editions of this text these
 letters were interpreted as 'III Γ'

Caput Viae (Ancyra)
Date (1) ?
 (2) AD 121/122, 10.xii-09.xii Hadrianus *Augustus*
Commentary This milestone cannot be attributed, with certainty, to the Pilgrim's Road.

117(L). Ankara 12

Provenance Not known. Now in the Roman Baths, Ankara [Inv. no. 8985]
Copy SM (?date); DHF 10-12.ix.1974. SM and DHF squeezes in BIAA. No DHF photo. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 06. Ankara 186 [SM], 185 [DHF], Ankara 12
Publication RRMAM 1. 39(L) (text only, from DHF copy)
 RRMAM 2, 1. 103 (notice only)
Description A simple cylinder. Damaged around the top. Pale, soft limestone. The top surface is flat. Surface and letters: worn
Dimensions Ht 1.92; diam. (top) 0.57. Letters: (line 1) 0.09 (max.), (other lines) 0.04-05

Text

4	Im[p C]aesari divi Traiani Parthi- ci fil divi Nervae ne- poti Traiano Hadri-
	no Aug pont max tr pot VI
8	cos III per A Larc- um Macedonem
	leg Aug pr pr
	m [VIII]
	(vac)
	η'

Caput Viae (Ancyra)
Date AD 121/122, 10.xii-09.xii Hadrianus *Augustus*

Commentary This milestone cannot be attributed, with certainty, to the Pilgrim's Road.

117(M). Ankara 13

<i>Provenance</i>	Not known. Now in the Roman Baths, Ankara [Inv. no. 113.486.99]
<i>Copy</i>	SM (?date); DHF 10-12.ix.1974. SM and DHF squeezes in BIAA. No DHF photo. Text here from DHF squeeze (drawing, Fig. 6.2.81 [p. 303])
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 06. Ankara 188 [SM], 189 [DHF], Ankara 13 (photo. Col. Slide: DHF 294.35-36)
<i>Publication</i>	RRMAM 1. 39(M) (text only, from DHF copy) RRMAM 2, 1. 104 (notice only)
<i>Description</i>	A simple cylinder. Broken into two pieces. Hard, pale grey limestone. The top surface is damaged. Roughly shaped base; the bottom surface was flat. Slightly tapering shaft. The inscribed area was smoothed; otherwise the surface was only roughly dressed. Surface and letters: little wear; the letters are sharp and clear. Note the lunate E and the top extension of r. diagonal of A.
<i>Dimensions</i>	Ht 0.62 + 1.61; (base) 0.65; diam. (top) 0.46, (base) 0.58. Letters: (lines 1-11) 0.04-05, (other lines) 0.035-45

<i>Text</i>		(leaf) (leaf)
	Imp·Caes·L·Septi-	
	mius Severus Pi-	
4	us Pertinax Aug	
	Arabicus Adiabenicus	
	Parthicus maximus fel trib	
	potest XVI imp·XII cos III	
8	(vac) cos·p·p	(sic)
	et Imp·Caes M Aurelius An-	
	toninus Pius Aug·fel trib potest	
	XI imp·II·cos III procos et [[P Septi]]-	
12	[[mius [Geta] nobilissimus Caesar]]	
	[[cos II]] viam stratam a novo fe-	
	cerunt (v) per P Caecilium	
	Urbicum Aemelianum leg·Aug·g	(sic)
16	pro·pr·cos·designatum	
	mp (leaf) VI	
	ς'	

line 15: **Aemelianum** for **Aemilianum**

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 207/208, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with P. Septimius Geta <i>Caesar</i> (names and titles erased)
<i>Commentary</i>	This milestone cannot be attributed, with certainty, to the Pilgrim's Road.

118(A). Ankara, Çankaya 1

<i>Provenance</i>	Seen by Mordtmann [A.D.] in 1858 at the “Derwisch-kloster” (“prope monasterium Dervisorum” [CIL]) and by Bittel in 1931 at the Erkek Lisesi, Çankaya. Brought from there to the depot at the Çankırı Kapı (Bosch). Now in the Roman Baths, Ankara [Inv. no. 113.502.99]
<i>Copy</i>	Mordtmann [A.D.] 1858; Bittel 1931; Miltner (H.) Summer 1934; SM 11.xi.1971; DHF 10-12.ix.1974. DHF squeeze in BIAA. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 06. Ankara 41, Çankaya 1
<i>Publication</i>	CIL 3. 314 (copy of Mordtmann [A.D.]) Bittel 1932, 260 AE 1932. 49 (text of Bittel) Miltner (Fr. and H.) 1936, 19 no. 15 Bosch 1967, 299 no. 237 (notice of CIL, Bittel and Miltner, and text) French 1980, 722 no. 22 (notice only) RRMAM 1. 40(A) (text only, from DHF copy) RRMAM 2, 1. 105 (notice only) French 2003, 192 no. 77 (text, commentary and photo.)
<i>Description</i>	A simple cylinder. Broken below? Hard, pale limestone. The top surface surface is flat but rough. The inscribed area is smoothed; otherwise the surface of the shaft is rough. The back of the stone has been hollowed towards the base. Surface and letters: slight wear
<i>Dimensions</i>	“H. 1.90 m, Dm. rund 0.50 m; Bh. 0.05 m” (Miltner [H.]); ht (vis.) 1.00; diam. (top) 0.41. Letters: 0.045-50

<i>Text</i>	Imp·Caesar M·Aurelius Severus 4 Antoneinus Aug·pius fe- lix Parthicus Britannicus 8 max·p·trib· put·XV·cos· III viam fieri ius(s)it (vac) mp III 12 (vac) γ'	(sic)
-------------	---	-------

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 211/212, 10.xii-09.xii M. Aurelius Antoninus (Caracalla) <i>Augustus</i>
<i>Commentary</i>	On the basis of its provenance – on the S side of Ankara – this milestone may once have stood on the so-called Pilgrim’s Road, the major highway between Chalcedon and Antiochia (modern Antakya). If the suggested location is correct, this milestone is one of three known to have been erected by order of M. Aurelius Antoninus (Caracalla) on the same road, running S from Ancyra, in the direction of Tarsus (in Cilicia) and Antiochia (in Syria); all three record the same text (though in a different lay-out) and at least two (probably also the third) the same date.
118(B). Ankara, Çankaya 2	

<i>Location</i>	“Trovée à Tchanli-kaia, auprès d’Ancyre, dans une vigne,” (Perrot 1872, 1, 228); “Nous traversâmes les vignes de <i>Tchengi</i> ou <i>Tchanli-aia</i> , où, peu de temps avant notre arrivée à Ancyra, on avait découvert les restes d’une ville romaine du seconde siècle de notre ère; nous avons donné (n°. 113) une inscription qui provient de ces fouilles” (Perrot 1872, 1, 284). Present whereabouts not established
<i>Copy</i>	Perrot between 11 August and 29 October 1861. The stone has not been examined by DHF. Text here from copy of Perrot (1872, 1, 228)
<i>Publication</i>	Perrot et al. 1872, 1, 228 no. 113 CIL 3, 1. 316 (copy of Perrot) Bosch 1967, 335 no. 275 (Perrot text in CIL) RRMAM 1. 40(B) (text only; Perrot text in CIL) RRMAM 2, 1. 106 (notice only)
<i>Description</i>	“. . . . sur une colonne milliaire. Lettres très-négligemment gravées” (Perrot)
<i>Dimensions</i>	Not given

<i>Text</i>	B F
	Imp Caes·M
	Aur Seye[ro]
4	Ale[x]an <u>d</u> ro [pio] felici invicto
	Aug tribunic
	potest II
8	cos I p p m p [-]

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	AD 222/223, 10.xii-09.xii M. Aurelius Severus Alexander (Severus Alexander)
<i>Commentary</i>	Augustus

119(A). Ankara, Ahlatbel 1

<i>Provenance</i>	Found in 1994 during road-widening operations at the <i>yonca</i> (clover-leaf fly-over) [Ankara 58-v (39.20)] on the Ankara-Konya highway; said to have once been standing upright in the METU forest on the W of the highway. Now at the Archaeological Museum of METU (Middle East Technical University), Ankara
<i>Copy</i>	DHF 15.x.1994. DHF squeeze in BIAA. No photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 190, Ahlatlbel 1
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. The top surface is flat. The inscribed area was trimmed with a claw-tooth chisel. Probably the cylinder was intended for a column, since the guide-channels (seven in all) are visible. The inscription begins c. 0.135 from the top. The inscribed area measures c. 0.80 x c. 0.50. The letters were enhanced by red paint.
<i>Dimensions</i>	Ht c. 2.04; diam. (top) 0.50, (base) 0.52. Letters: (line 1) B 0.064, (line 4) E of

SEV 0.051, (line 7) T 0.064

Text

	(v) B (v) F
	Imp·Caes·
	M·Aur·
4	Severo [[· <u>Ale</u>]-
	[[<u>xandro</u>]]
	pio fel·in-
	victo Aug
8	trib·p·II·cos I
	p p (vac) mp·IX

Caput Viae

(Ancyra)

*Date*AD 222/223, 10.xii-09.xii M. Aurelius Severus Alexander (Severus Alexander)
*Augustus***119(B). Ankara, Ahlatibel 2***Provenance*

As above, 119(A)

*Copy*DHF 15.x.1994. DHF squeeze in BIAA. No photo. Text here from DHF
squeeze*BIAA Collections: Squeeze and Stone Photographs*

Squeeze: 06. Ankara 191, Ahlatibel 2

Description

A simple cylinder. Now broken into two pieces. Hard, pale limestone. The top surface is flat. The shaft is straight. The inscribed area was smoothed. The inscription begins c. 0.09 from the top. The inscribed area measures c. 0.65 (ht) x 0.50 (wi.). Text (2) has been erased but some letters survive more-or-less intact.

Dimensions

Ht (upper) 0.79, (lower) 0.60; diam. (top) 0.33. Letters: (line 1) B 0.054

Text(1) (underneath text [2]; erased and the lines re-inscribed)
at least seven lines(2) (inscribed over the top of text [1] but the lines do not occupy the total
erased length of each line of the earlier text)

	(vac) B (vac) F
2	Imp·Caes·M·[Aur]
	Sever[o] Magn[i f]
4	pio (leaf) felici Aug (leaf)
	trib` potes` cos
6	procos p p
	[[---]]

Caput Viae

[Ancyra]

Date

(1) (?)

(2) AD 218, 16.v-09.xii M. Aurelius Severus (Elagabalus) *Augustus***120. Emircöl***Province, Sub-Province + Admin. Code*

Ankara, Çankaya 06-02-1

<i>Map</i>	Ankara 58-v
<i>Location</i>	“In a cemetery opposite the end of Emir Giöl,” (Anderson). Present whereabouts not established (DHF visit 26.ix.1975)
<i>Copy</i>	Anderson Summer 1898. The stone has not been examined by DHF. Text here from copy of Anderson (1899, 101)
<i>Publication</i>	Anderson 1899, 101 no. 86 CIL 3. 14184 ⁴⁶ (text of Anderson) RRMAM 1. 41 (text only; text of Anderson) RRMAM 2, 1. 135 (notice only)
<i>Description</i>	“ , we saw a broken pillar with a worn fragment of an inscription” (Anderson)
<i>Dimensions</i>	Not given

Text -----
 2 **LEG III**
 XIII

line 2: **LEG III** (Anderson), (?) **leg pr** [pr]

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	(?)

121(A). Örencik 1

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Çankaya 06-02-1
<i>Map</i>	Ankara 59-y
<i>Provenance</i>	In the village; lying at the foot of a house wall (at the SE side of the cemetery) c. 10 m N of village street. Now in the Ankara Museum [Inv. no. 1.3.1976]
<i>Copy</i>	Macpherson 1953(?); DHF 29.ix.1976. DHF squeeze and photo. in BIAA
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 95, Örencik 1 Stone: (1) B/W Neg.: DHF R/75/08.11
<i>Publication</i>	Macpherson 1954, 114 no. 4 Macpherson 1958, 179 no. 250 RRMAM 1. 42(A) (text only, from DHF copy) RRMAM 2, 1. 167 (notice only)
<i>Description</i>	A simple cylinder. Broken above. Hard, grey limestone.
<i>Dimensions</i>	Ht (ex.) 1.34; diam. (top) 0.41, (base) 0.425. Letters: c. 0.07

Text -----
 XVI ις'

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	(?)

121(B). Örencik 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 121(A)
<i>Provenance</i>	In the village; in two pieces. One piece lies at the foot of a wall, on the E side of a <i>çeşme</i> (fountain) on the S side of the mosque. The second piece is built

into the outside face of the courtyard (at the SW corner) of the house (no. 20) owned by Abdullah Teke. Now in the Roman Baths, Ankara [Inv. no. 1.4.76] DHF 26 and 29.ix.1975. DHF squeeze and photos (Pl. 7.1.70-71 [p. 327]) in BIAA. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 06. Ankara 96, Örencik 2

Stone: (1) B/W Neg.: DHF R/75/08.07-08

Publication RRMAM 1. 42(B) (text only, from DHF copy)

RRMAM 2, 1. 168 (notice only)

Description A simple cylinder. Broken into two pieces. Hard, pale limestone. The top surface is flat*Dimensions* (upper piece) 0.73 + (lower piece) (ex.) 1.20; diam. (top) 0.40, (bottom) 0.46*Text* (1) (underneath text [2])
illegible

(2) (on top of text [1])

B F
Imp Caesar
M·Aur·Severus
 4 **Antoninus Aug**
 [piu]s felix Parth
 [Brit]annicus max
 p·p·trib·pot·XV
 8 [co]s·I·II·I [vi]am [fieri]
 iussit
 m p XVII
 t̄z'

line 5: ligature TH

line 10: horizontal bar over the numeral

Caput Viae (Ancyra)*Date* (1) (?)(2) AD 211/212, 10.xii-09.xii M. Aurelius Severus Antoninus (Caracalla)
*Augustus***121(C). Örencik 3***Province, Sub-Province + Admin. Code and Map* As 121(A)*Location* In the village; lying in the street, at the NW corner of the mosque, on the outside of the courtyard wall*Copy* DHF 29.ix.1975. DHF photos in BIAA*BIAA Collections: Squeeze and Stone Photographs*

Stone: (1) B/W Neg.: DHF R/75/08.09-10

Publication RRMAM 1. 42(C) (notice only)

RRMAM 2, 1. 169 (notice only)

Description A simple cylinder on a square plinth. Broken above. Hard, grey limestone. Slightly oval in section.*Dimensions* Ht 1.28; ht (base) 0.27; wi./diam. 0.61/0.49

Text no visible inscription

Date (?)

122(A). Oğulbey 1, form. Çakal

Province, Sub-Province + Admin. Code Ankara, Çankaya 06-02-4
Map Ankara 59-z
Provenance “ . . . in the cemetery” (Anderson). Now in the Roman Baths, Ankara [Inv. no. 8984]
Copy Anderson Summer 1898; Miltner (H.) Summer 1934; DHF 10-12.ix.1974. The text published by Anderson is reproduced here (Fig. 6.1.38 [p. 271]). DHF squeeze in BIAA. No DHF photo. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 06. Ankara 90, Oğulbey 1
Publication Anderson 1897-98, 74 (notice only)
 Anderson 1899, 102 no. 87)
 AE 1899. 185 (text of Anderson)
 CIL 3. 14184⁴⁸ (text of Anderson)
 Miltner (H. and Fr.) 1936, 19 no. 16
 AE 1937. 90 (notice of Miltner’s revisions)
 Bosch 1967, 67 no. 69 (text of Anderson, and comments)
 RRMAM 1. 43(A) (text only, from DHF copy)
 RRMAM 2, 1. 160 (notice only)
Description A simple cylinder. Hard, pale limestone. Complete but worn. The top surface is flat but damaged all round the edge. Text (1) was cut on the smoothed face of a prepared panel; otherwise the rest of the shaft was roughly dressed.
Dimensions Surface and letters: very worn
 Ht c. 2.00; diam. (top) c. 0.57. Letters: (lines 1-5) 0.05, (others) 0.03

Text (1) (in a panel, on the face of the shaft)

	Imp·Caes·divi·Vespasia-
	ni·f [[Domitianus]] Aug·pont
	max trib pot [p p cos] IIIX des
4	IX·imperatoř II per
	A·Caesennium Gallum
	cos·XV vir [s f leg Aug pro] pr
	vias p[rovinciaru]m Galatiae
8	Cappadociae Ponti·Pisidiae
	Paphlagoni[ia]e Lycœniae
	Armen[i]æ Minœ[ri]ss[tr]avit
	mil XX

line 2: ligature NT

line 3: tr[ib pot II cos] (Miltner)

line 4: [III] per (Miltner)

line 6: vir s f l[eg (Miltner)

line 11: mil X[I]X (Miltner)

(2) (over the right-hand end of lines 2-6, text [1])

dd nn Fl
 2 **Valentiniano**
 e(t) Fl Valente
 4 **triumfatoris**
 semper Augg

Caput Viae (Ancyra)*Date* (1) AD 82, “seit Mitte Marz”-13.ix Domitianus (name erased) *Augustus*
 (2) AD 364, 28.iii-367, 24.viii Valentinianus I and Valens *Augusti***122(B). Oğulbey 2, form. Çakal***Province, Sub-Province + Admin. Code and Map* As 122(A)*Location* “ . . . in the cemetery” (Anderson). Now (26.ix.1975) at the S side of the cemetery*Copy* Anderson Summer 1898; DHF 26.ix.1975. The text published by Anderson is reproduced here (Fig. 6.1.39 [p. 271]). DHF squeeze in BIAA. No DHF photo. Text here from DHF squeeze*BIAA Collections: Squeeze and Stone Photographs*

Squeeze: 06. Ankara 91, Oğulbey 2

Publication Anderson 1897-98, 74 (notice only)

Anderson 1899, 103 no. 88

CIL 3. 14184⁴⁷ (text of Anderson)

Bosch 1967, 151 no. 126 (text of Anderson, and comments)

RRMAM 1. 43 (B) (text only, from DHF copy)

RRMAM 2, 1. 161 (notice only)

Description A simple cylinder. Broken above. Hard, pale limestone. The underside of the base is flat.*Dimensions* Ht (vis.) 1.47; diam. (base) 0.57. Letters: (line 3) **F** 0.045, (line 7) **E** 0.035, (line 10) **X** 0.055

Text

4	Imp Çä[esari] divi Traian[i P]är- t(h)ici f divi Nervae nepoti Traiano Hadriano Aug pont max tr pot VI cos III per A Larcjum
8	Macedonem leg Aug pr pr XXV næ'

line 3: ligature **NE**line 4: ligature **NE**line 5: ligature **NT**line 8: ligature **NE**

Caput Viae (Ancyra)
Date AD 121/122, 10.xii-09.xii Hadrianus *Augustus*

122(C). Oğulbey 3, form. Çakal

Province, Sub-Province + Admin. Code and Map As 122(A)
Location “ . . . in the cemetery” (Anderson); inside the gate on the N side of the cemetery (26.ix.1976)
Copy J. W. Crowfoot Summer 1898; DHF 26.ix.1975. The text published by Anderson is reproduced here (Fig. 6.1.40 [p. 272]). DHF squeeze in BIAA. No DHF photo. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
Publication Squeeze: 06. Ankara 92, Oğulbey 3
 Anderson 1897-98, 74 (notice only)
 Anderson 1899, 103 no. 89 (copy of Crowfoot)
 CIL 3. 14184⁴⁹ (text of Anderson)
 Bosch 1967, 358 no. 295 (text of Anderson, and comments)
 RRMAM 1. 43 (C) (text only, from DHF copy)
 RRMAM 2, 1. 162 (notice only)
Description A simple cylinder. Complete. Hard, grey limestone. The top surface is flat.
Dimensions Ht (vis.) 2.05; diam. (top) 0.49. Letters: (3) E of REL 0.055, O of NO 0.035

Text (1) (underneath text [2])
 B F
 traces of letters

(2) (on the face of the shaft)
 B F D n
 Imp Caes L Dom
 Aureliano
 4 p·f·invicto
 (vac)
 Aug
 (vac)
 8 V

line 8: [XX]V (Bosch)

Caput Viae (Ancyra)
Date (1) (?)
 (2) AD 270, Sept-275, Sept/Oct L. Domitius Aurelian Augustus

122(D). Oğulbey 4, form. Çakal

Province, Sub-Province + Admin. Code and Map As 122(A)
Provenance Brought in 1973 from the ‘Yayla semti’, from the field of Zeynullah Özyahar, opposite the TCK Kantari (Highways Ministry weighing station) on the main highway. Now at the Museum of Anatolian Civilizations, Ankara, in the Sera dépôt [Inv. no. 48.1.73]
Copy DHF 29.v.1973. DHF squeeze (drawing, Fig. 6.2.82 [p. 304]) in BIAA. No DHF photo. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

<i>Publication</i>	Squeeze: 06. Ankara 93, Oğulbey 4 RRMAM 1. 43(D) (text only, from DHF copy)
<i>Description</i>	RRMAM 2, 1. 163 (notice only)
<i>Dimensions</i>	A simple cylinder. Broken below. Hard, grey limestone. The top surface is flat. The front face is smooth, the rear face rough. Roughly oval in section. Ht 0.82; wi./diam. 0.32/0.23. Letters: (line 1) P of IMP 0.65, (line 8) O of ANO 0.04

Text

	Imp Caes	
	G Vibiō Treb	
	ΟΑΠΙΟ Callō piō	(sic)
4	felici Aug·et I-	
	mp Caes·G·A-	
	finiō Callō Vel-	
	dumnianō V-	
8	ōlusianō Aug	

line 3: ΟΑΠΙΟ for ΟΝΙΟ

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	AD 251, (?)Aug-253, (?)Aug Trebonianus Gallus and Volusianus <i>Augusti</i>

122(E). Oğulbey 5, form. Çakal

Province, Sub-Province + Admin. Code and Map As 122(A)

<i>Location</i>	In the village; in the cemetery, inside the gate at the N side of the cemetery.
<i>Copy</i>	DHF 26.ix.1975. DHF squeeze in BIAA. No DHF photo. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

<i>Publication</i>	Squeeze: 06. Ankara 94, Oğulbey 5 RRMAM 1. 43(E) (text only, from DHF copy)
<i>Description</i>	RRMAM 2, 1. 164 (notice only)
<i>Dimensions</i>	A simple cylinder. Complete. Hard, grey limestone. The top surface is flat.
	Ht (vis.) 1.90; diam. (top) 0.44. Letters: (text 1) c. 0.075, (text 2) 0.045-50

Text

(1) (on the face of the shaft)

	Imp·Caes·C·Aur·Val	
2	Diocletiano·p f inv	
	[A]ug·et·Imp·Cae[s·Gal]	
4	[V]al [Maximiano·p f]	

(2) (on the top of text [1] lines 3-4 and below)

	[-----]	
2	[Constantino maxi]-	
	mo victori ac triumf-	
4	[atori sem]per Aug [et]	
	[Fl Constantin]o et Fl Consta-	

6 [ntio et Fl Constanti]
[nobb Caess]

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	(1) AD 286-293 Diocletianus and Maximianus <i>Augusti</i> or AD 293-305 Diocletianus and Maximianus <i>Augusti</i> with Constantius I and Galerius <i>Caesares</i> (2) AD 333-335(?) [Constantinus I] <i>maximus vicit Augustus</i> with Constantinus I, Constantius I [and Constans ?] <i>Caesares</i>

123. Beynam Çiftlik

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Çankaya 06-05-1
<i>Map</i>	Ankara 60-z
<i>Location</i>	In the village cemetery, on the S side of the road, below the çiftlik
<i>Copy</i>	Seen DHF 15.v.1983
<i>Publication</i>	RRMAM 2, 1. 118
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. Rough surface
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

124(A) April 1

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Çankaya 06-02-1
<i>Map</i>	Ankara 59-Ia
<i>Provenance</i>	In the village; at the gate of the village school. "Reported to have been excavated in 1951" (Macpherson). Now in the Roman Baths, Ankara [Inv. no. 1.2.1976]
<i>Copy</i>	Macpherson 1953(?); DHF 29.ix.1975. DHF squeeze and photos (Pl. 7.1.71-72 [pp. 327-328]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 06. Ankara 51, Ahiboz 1
	Stone: (1) B/W Neg.: DHF R/75/08.12 and 09.01
<i>Publication</i>	Macpherson 1954, 120 no. 7a Macpherson 1958, 192 no. 275 RRMAM 1. 44(A) (text only, from DHF copy) RRMAM 2, 1. 084 (notice only)
<i>Description</i>	A simple shaft. Complete. Hard, grey limestone. The top surface is flat; the back of the shaft has been flattened.
<i>Dimensions</i>	Ht (vis.) 1.15; diam. (top) 0.32. Letters: (line 2) P of IMP 0.06, C of CAES 0.04

Text A F (sic)
Imp Caes
P Licinnio
4 Valeriano
p f Augusto

et Imp Caes
P Licinnio
8 **Gallieno p**
felici Aug
 (vac)
 m
 [-]

Caput Viae [Ancyra]
Date AD 253, “vor Okt. 23”-255 Valerianus and Gallienus *Augusti*
Comment The date here assumes that Valerianus *iunior* had not yet been named *Caesar*.
 He became *Caesar* in AD 255; see Kienast (1996, 221).
 According to Kienast (1996, 218), Gallienus became *Caesar* Sept./Okt. 253 and *Augustus* “vor Okt. 23 253.”

124(B). Ahiboz 2

Province, Sub-Province + Admin. Code and Map As 124(A)
Provenance In the village; at the gate (on the E side) of the village school. Now in the Roman Baths, Ankara [Inv. no. 1.1.1976]
Copy DHF 29.ix.1975. DHF squeeze and photo. (Pl. 7.1.71 [p. 327]) in BIAA. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 06. Ankara 52, Ahiboz 2
 Stone: (1) B/W Neg.: DHF R/75/09.01
Publication RRMAM 1. 44(B) (text only)
 RRMAM 2, 1. 085 (notice only)
Description A simple cylinder. Complete. Hard, grey limestone. The top surface is flat. Slightly thickened base. The inscribed surface is smooth, the back rough.
Dimensions Ht 1.64; diam. (top) 0.36. Letters: (line 5) **S** 0.055, (line 6) **L** 0.035, (line 7) **L** 0.042

Text

	dd nn
	Const [antino]
	maxim [o victori]
4	ac tri [mfatori]
	sempe [r Aug et]
	[F]l Co[nstantino]
	et Fl C [onstantio]
8	et Fl C [onstanti]
	[-----]
	[-----]

line 1: the first line is inscribed **dd NN**

Caput Viae [Ancyra]
Date AD 333, 25.xii-335, 18.ix Constantinus I *maximus Victor Augustus* with Constantinus II, Constantius II and Constans *Caesares*

125(A). Günalan 1, form. Holoz

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Çankaya 06-02-1
<i>Map</i>	Ankara 59-z
<i>Location</i>	“Brought from Ahiboz, now in bridge foundation” (Macpherson). Brought (date ?) from Ahiboz. Said to have been built into the bridge/culvert at the entrance to the village; no longer visible
<i>Copy</i>	Macpherson 1953(?). Not examined by DHF 29.ix.1975. Text here from Macpherson (1954, 120)
<i>Publication</i>	Macpherson 1954, 120 no. 7b Macpherson 1958, 193 no. 276 RRMAM 1. 45(A) (text only) RRMAM 2, 1. 141 (notice only)
<i>Description</i>	“White marble miliarium, broken above” (Macpherson)
<i>Dimensions</i>	“H 1·75 Diam 0·35. Letters 0·055 to 0·06” (Macpherson)

<i>Text</i>	B F
	Imp Caes C Aur [Val]
	Diocletiano p f
4	inv Aug et Imp
	Caes M Aur Val
	Maximiano p f
	inv Aug ab Ancyra
8	m XXVIII
	zn'

<i>Caput Viae</i>	Ancyra
<i>Date</i>	AD 286, 01.iv-293, 21.v(?) Diocletianus and Maximianus <i>Augusti</i>

125(B). Günalan 2, form. Holoz

<i>Province, Sub-Province + Admin. Code and Map</i>	As 125(A)
<i>Location</i>	In the village. In the street, at the NW corner of the house (no. 10) of Yusuf Aksaya
<i>Copy</i>	DHF 29.ix.1975. DHF squeeze and photo. (Pl. 7.1.73 [p. 328]) in BIAA. Texts here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 80, Günalan 2 Stone: (1) B/W Neg.: DHF R/75/09.02-03
<i>Publication</i>	RRMAM 1. 45(B) (text only, from DHF copy) RRMAM 2, 1. 142 (notice only)
<i>Description</i>	A simple cylinder. Broken above. Hard, grey limestone. The top surface is flat but chipped around the rim
<i>Dimensions</i>	Ht (vis.) 0.80; diam. (top) 0.48. Letters: (text 1) (line 1) 0.05-06, (lines 2-4) 0.03-04, (text 2) 0.03-05

<i>Text</i>	(1) (on the face of the shaft; below text [2])
	Imp Caesari
2	divi Traiani Pa[r]-
	thici f divi Ne[rvae]
4	ne[p]oti T[raiano]

(2) (above text [1])

2	DD nn Fl	
4	Valentiniano	
	et Fl Valente	
	triunfatoris sen-	(sic)
	per Augg	

Caput Viae

[Ancyra]

Date

(1) AD 121/122(?) Hadrianus

(2) AD 364, 28.iii-367, 24.viii Valentinianus I and Valens *Augusti***126(A). Karaali 1**

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Balâ 06-05-1
<i>Map</i>	Ankara 60-z
<i>Location</i>	Not given. Present whereabouts not established (DHF visit 29.ix.1975)
<i>Copy</i>	Anderson Summer 1898. The text published by Anderson is reproduced here, Fig. 6.1.41 [p. 272]). Not re-found by DHF 29.ix.1975. Text here from Anderson (1899, 104)
<i>Publication</i>	Anderson 1897-98, 74 (notice only) Anderson 1899, 104 no. 90 CIL 3. 14184 ⁵⁰ (text of Anderson) RRMAM 1. 46(A) (text only; text of Anderson) RRMAM 2, 1. 152 (notice only)
<i>Description</i>	“On a small column” (Anderson)
<i>Dimensions</i>	Not given
<i>Text</i>	[Imp Caes] [L Septimius Severus] [-----] [-----] 5 [-----] [et Imp Caesar] M Aure Anton[i]nus Aug {cos III} [[et L Septimius Geta Caesar]] restituerunt 10 m XXXIII λδ' line 7: ligature S, encircled by the O of COS

Anderson (loc. cit.) restored the text as a milestone of Antoninus Pius and Marcus Aurelius:

[Imp. Caes. T. Aelius
Hadrianus Antoninus
Aug pius cos IIII
et Imp. Caes.]
M. Aur[e](lius) Anton[in]us Aug. cos. III
restituerunt

M(ilia)
XXXIII. λδ

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	“The date is probably Jan.-March, 161 A.D.” (Anderson); AD 208 (Mommsen in CIL); AD 198 [L. Septimius Severus and] M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i> (DHF)

Commentary There is a similar milestone at Yörenli, c. 14 km S of Karaali; for the date (AD 198) of this and of the Karaali milestone, see below, no. 129(B). Yörenli 2 *Commentary*

126(B). Karaali 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 126(A)
<i>Location</i>	Not given. Present whereabouts not established (DHF visit 29.ix.1975)
<i>Copy</i>	Anderson Summer 1898. The text published by Anderson is reproduced here, Fig. 6.1.42 [p. 272]). Not re-found by DHF 29.ix.1975. Text here from Anderson (1899, 104)
<i>Publication</i>	Anderson 1897-98, 74 (notice only) Anderson 1899, 104 no. 91 CIL 3. 14184 ⁵¹ (text of Anderson) Bosch 1967, 363 no. 299 (text of Anderson) RRMAM 1. 46(B) (text only; text of Anderson) RRMAM 2, 1. 153 (notice only)
<i>Description</i>	“Worn and faint” (Anderson)
<i>Dimensions</i>	Not given

<i>Text</i>	D N
2	Imp Caes C Aur Val
	Diocletianus p f inv
4	Aug et Imp Caes M
	[[Aur Val Maximianus]]
6	p f inv Aug ab Ancyra m XXXVIII

<i>Caput Viae</i>	Ancyra
<i>Date</i>	AD 286, 01.iv-293, 21.v(?) Diocletianus and Maximianus (name erased) <i>Augusti</i>

127(A). Abazlı 2

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Balâ 06-05-0
<i>Map</i>	Ankara 60-Ia
<i>Location</i>	In an old cemetery, situated at the junction of three village territories (Yörenli, Abazlı and Deliler Çiftliği); c. 5.60 km W of Abazlı and c. 4.20 km N of Yörenli
<i>Copy</i>	DHF 02.x.1975. DHF squeeze and photos (Pl. 7.1.74-75 [pp. 328-329]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 46, Abazlı 2 Stone: (1) B/W Neg.: DHF R/75/10.02-04

<i>Publication</i>	RRMAM 1. 47(A) (text only, from copy of DHF) RRMAM 2, 1. 077 (notice only)
<i>Description</i>	A simple cylinder. Complete. Hard, grey limestone. The top surface is flat. Surface and letters: very worn
<i>Dimensions</i>	Ht 1.90; diam. (top) 0.48, (bottom) 0.55. Letters: (line 6) O of COS 0.03, (line 7) O of EDO 0.038, (line 8) G of AVG 0.05

<i>Text</i>	[Imp Caes] [divi Traia]ni [Parth]- [ici f divi] Ner[vae ne]- 4 [poti Trajano Had- [riano Aug] pont max [trib pot VI] cos III per [A Larcium] Macedo- 8 [nem leg A]ug pr pr [- - -]
-------------	--

line 3: ligature **NE**

line 5: ligatures **NT**, **MA**

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	AD 121/122(?) Hadrianus <i>Augustus</i>

127(B). Abazlı 3

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Balâ 06-05-0
<i>Map</i>	Ankara 60-Ia
<i>Location</i>	In the village; at the house of (no. 88) of Mevlüt Yılmaz
<i>Copy</i>	DHF 02.x.1975. DHF photo. in BIAA
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Stone: (1) B/W Neg.: DHF R/75/10.01
<i>Publication</i>	RRMAM 1. 47(B) (notice only) RRMAM 2, 1. 078 (notice only)
<i>Description</i>	A simple cylinder, on a round base. Broken above. Hard, grey limestone
<i>Dimensions</i>	Ht 0.91; diam. (top) 0.29, (base) 0.31

<i>Text</i>	No visible inscription
<i>Date</i>	(?)

128(A). Bağıçı 1, form. Zivre

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Balâ 06-05-1
<i>Map</i>	Ankara 59-Ia
<i>Location</i>	In the village cemetery (c. 0.5 km E of the village)
<i>Copy</i>	Macpherson 1953 (?); DHF 30.ix.1975. DHF squeeze and photo. (Pl. 7.1.76 [p. 329]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 62, Bağıçı 1 Stone: (1) B/W Neg.: DHF R/75/09.04

<i>Publication</i>	Macpherson 1954, map Fig. 1 RRMAM 1. 48(A) (text only, from DHF copy) RRMAM 2, 1. 109 (notice only)
<i>Description</i>	A simple cylinder. Complete. Pale grey limestone. The top surface is flat. Surface and letters: very worn, pitted and lichen covered
<i>Dimensions</i>	Ht (vis.) 1.60; diam. 0.47. Letters: (line 1) C of CAES 0.05, (line 2) D of DIV 0.0.03, (line 4) O of ANO 0.027
<i>Text</i>	[Im]p Caesari divi Traiani Par- [thici] f divi Nervae 4 nepoti Traiano Hadriano Aug pont max tr pot VI cos II per A 8 Larcium Mace- donem leg Aug pr pr XXXIII λγ'
	line 6: ligature NT line 9: ligature NE

Caput Viae (Ancyra)
Date AD 121/122, 10.xii-09.xii Hadrianus Augustus

128(B). Başıçı 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 128(A)
<i>Location</i>	At the <i>türbe</i> (built tomb, mausoleum), on a hill E of village; lying on the E slope
<i>Copy</i>	DHF 30.ix.1975. DHF squeeze and photo. (Pl. 7.1.77 [p. 329]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 63, Başıçı 2 Stone: (1) B/W Neg.: DHF R/75/09.06
<i>Publication</i>	RRMAM 1. 48(B) (text only, from DHF copy) RRMAM 2, 1. 110 (notice only)
<i>Description</i>	A simple cylinder, on a square plinth. Complete. Hard, grey limestone. The top surface is flat. The inscribed area was smoothed, the rest roughly dressed.
<i>Dimensions</i>	Ht 1.57, (plinth) 0.40; Wi. (plinth) 0.40, diam. 0.34. Letters: (text 2) E 0.03, OYC 0.035, IO 0.030, (text 3) 0.037-42
<i>Text</i>	(1) (underneath text 3, especially on the r. of text 3, at the end of line 3 and between lines 6-7) (at end of l. 3 of text [3]) --]E[-- (between ll.6-7 of text[3]) --]O[. . .]OYC[-- (between ll.7-8 of text[3]) --]IO[-- -----

(2) (underneath text 3, especially on the r. of text 3, line 3)
A few letters

(3) (on front face, on top of texts 1 and 2)

dd nn Fl

Constantino ma-

ximo victori ac tri-

4

umfatori semper

Aug et Fl Constantino

et Fl Constantio

et Fl Consta' nobb

(sic)

8

Caess

mil [-]

line 1: the beginning of the first line is inscribed **dd NN**

Caput Viae [Ancyra]

Date (1) (?)

(2) (?)

(3) AD 333, 25.xii-335, 18.ix Constantinus I *maximus victor Augustus* with
Constantinus II, Constantius II and Constans *Caesares*

128(C). Bağıçı 3

Province, Sub-Province + Admin. Code and Map As 128(A)

Location In the village; beside the mosque

Copy DHF 30.ix.1975. DHF squeeze and photo. (Pl. 7.1.78 [p. 330]) in BIAA. Text
here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 06. Ankara 64, Bağıçı 3

Stone: (1) B/W Neg.: DHF R/75/09.07-08

Publication RRMAM 1. 48(C) (text only, from DHF copy)

RRMAM 2, 1. 111 (notice only)

Description A simple cylinder. Complete. Hard, grey limestone. The top surface is flat

Dimensions Ht (vis.) 1.60; diam. 0.53. Letters: 0.028-33

Text **Imp Caes̄ar d̄ivi Vespasian̄i·**
f·Domitianus Auḡ pont·max·
tr·pot̄ cos VIII desig·VIII·imp·II
4 **per (vac)**

·A·Caesen̄nium Gallum cos XV vir
s f·pro pr̄ vi[as] provinciar·Galatiae
[Cappad]ociae [Po]nt Pisidiae Paphl-
8 **[a]goniae Lycaoniae Armeniae [Mi]-**
noris stravit
mil [XXX]III λγ'

Caput Viae (Ancyra)

Date AD 82, “seit Mitte März-13.ix” Domitianus *Augustus*

128(D). Bağıçı 4

<i>Province, Sub-Province + Admin. Code</i>	As 128(A)
<i>Location</i>	In the village; the stone is owned by Salih Taştan
<i>Copy</i>	DHF 30.ix.1975
<i>Publication</i>	RRMAM 1. 48(D) (notice) RRMAM 2, 1. 112 (notice)
<i>Description</i>	A simple cylinder. Complete. Hard, grey limestone. The top surface is flat. The inscribed area was smoothed
<i>Dimensions</i>	Ht 1.94; diam. (top) 0.38, (bottom) 0.44
<i>Text</i>	No visible inscription
<i>Date</i>	(?)

129(A). Yöreli 1

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Balâ 06-05-1
<i>Map</i>	Ankara 60-Ib
<i>Location</i>	In the village; formerly “beside the Köy Odası” (Macpherson), then at a <i>çeşme</i> (fountain) at the W end of the village. Now (30.ix.1975) in front of a house (no. 1) owned by Süleyman Çalışkan
<i>Copy</i>	Calder 1911; Macpherson 1953(?); DHF 30.ix.1975. DHF squeeze and photo. (Pl. 7.1.79 [p. 330]) in BIAA. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	
	Squeeze: 06. Ankara 107, Yöreli 1
	Stone: (1) B/W Neg.: DHF R/75/09.09
<i>Publication</i>	Calder 1911, (page not numbered) no. 13 Macpherson 1954, 115 no. 7 Macpherson 1958, 187 RRMAM 1. 49(A) (text only, from DHF copy) RRMAM 2, 1. 179 (notice only)
<i>Description</i>	A simple cylinder. Broken above and below. Hard, grey limestone
<i>Dimensions</i>	Ht (ex.) 0.50; diam. 0.39. Letters: 0.040-45

<i>Text</i>	B·F
	⟨Imp Caes⟩
	M·Aur·Severus
4	Antoninus ⟨Aug⟩
	pius felix Part-
	hicus Brit[an]-
	nicus m[ax]
8	p p·trib pot
	[XV cos IIII]
	[viam fieri]
	[iussit]
12	[mp - -]
	[- -]

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	AD 211/212, 10.xii-09.xii (?), M. Aurelius Severus Antoninus (Caracalla)
<i>Commentary</i>	“Calder’s note indicates that the stone was superscribed” (Macpherson). The text given above varies, in details but not in essentials, from Calder’s version (quoted by Macpherson). The omissions (lines 2 and 4) and the restorations (lines 9-11) of the text here are based on the complete example (118[A]. Çankaya 1), and the near-complete example (121[B]. Örencik 2), of Caracallan milestones in the year AD 211/212.

129(B). Yörenli 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 129(A)
<i>Location</i>	Not given. Present whereabouts not established (DHF visit 30.ix.1975)
<i>Copy</i>	Calder 1910. Not re-found by DHF 30.ix.1975. Text here from Buckler et al. (1924, 77)
<i>Publication</i>	Buckler, Calder and Cox 1924, 77 no. 111 (copy of Calder in 1910) RRMAM 1. 49(B) (text only; text of Buckler et al.) RRMAM 2, 1. 180 (notice only)
<i>Description & Dimensions</i>	Not given

<i>Text</i>	Imp Caesar
	L Septimius Severus
	Pius Pertinax Aug Arab
4	Adiab Parth max pon-
	tif trib pot VI imp XI cos
	(sic)
	III procos et Imp Caesar
	M Aure Antoninus Aug {cos III}
8	[[et L Septimius Geta]]
	[[Caesar]] restituerunt
	m
	XXXVII λξ'

lines 4-5: **pon|tif** (max)
line 5: (X)VI (Buckler et al.)
line 8: [[et P Septimius Geta Caesar]] (Buckler et al.)

<i>Caput Viae</i>	(Ancyra)
<i>Date</i>	AD 207/208 [Severus TR·P·XVI] (Buckler et al.); AD 197/198, 10.xii-09.xii [Severus TR·P·VI] L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i> , as no. 124(A) (DHF)

Commentary There is some uncertainty over the date of this text. Buckler et al. (l. c.) comment: “The inscription as it stands (l. 5) dates the third consulships both of Septimius Severus and of M. Aurelius Antoninus (Caracalla) in the year of the former’s sixth tribunician power, i.e. in A.D. 198. Clearly the engraver had XVI in his copy, i.e. A.D. 208”. In that year (AD 208), Severus would have been IMP·XII (XIII, Kienast 1996, 157), not IMP·XI. In AD 208 the imperial titles of Severus were TR·P·XVI·IMP·XII·COS·III and of M. Aurelius Antoninus (Caracalla) TR·P·XI IMP·II·COS III, cp. above, 117(M). Ankara 13. The Yörenli milestone, on the other hand, is unlike the Ankara milestone in three aspects: (1) in the fullness

and completeness (on the Ankara text) of the imperial titles for the year AD 207-208, (2) in the omission (on the Yöreli stone) of the governor's name – P. Caecilius Urbicus Aemelianus – and (3) in the omission (on the Yöreli stone) of the phrase *viam stratam a novo fecerunt*, for which there is certainly no room.

Nor, confusingly, do the imperial titles on the Yöreli milestone wholly conform to the standard Severan text for the year 197/198, namely, TR·P·VI·IMP·XI·COS·II (French 1986, 88). Severus did not become COS·III until AD 202 (Kienast 1996, 157), M. Aurelius Antoninus (Caracalla) not until AD 208 (Kienast 1996, 163).

In the text above Caracalla's COS·III has been bracketed on the supposition that the letters are the result of dittography.

For a fragmentary but similar text, see above, no. 126(A). Karaali 1, probably of the year, AD 198 (Severus TR·P·VI) and in the same series of milestones erected on the Pilgrim's Road – note, in both texts, the spelling, Aurelius and the arrangement of the final lines; cp. no. 131(G). Afşar 7, perhaps also in the same series.

130. Bezirhane

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Cankaya 06-02-1
<i>Map</i>	Ankara 59-Ib
<i>Location</i>	In the village; beside the mosque. Said to have been brought from Yöreli
<i>Copy</i>	DHF 30.x.1975
<i>Publication</i>	RRMAM 1. 50 (notice) RRMAM 2, 1. 119 (notice)
<i>Description</i>	A simple cylinder
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription
<i>Date</i>	(?)

131(A). Afşar 1

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Balâ 06-05-0
<i>Map</i>	Keskin 61-Ib
<i>Location</i>	"At the village . . ." (Anderson). The text published by Anderson is reproduced here, Fig. 6.1.43 [p. 272]). Present whereabouts not established (DHF visit 01.x.1975)
<i>Copy</i>	Anderson Summer 1898. The stone has not been examined by DHF. Text here from Anderson (1899, 106 no. 93)
<i>Publication</i>	Anderson 1899, 106 no. 93 CIL 3. 14184 ⁵² (text of Anderson) Bosch 1967, 341 no. 278 (text of Anderson in CIL) RRMAM 1. 51(A) (text only; text of Anderson) RRMAM 2, 1. 079 (notice only)
<i>Description</i>	" . . . a very badly cut and exceedingly worn <i>miliarium</i> of Gordian" (Anderson)
<i>Dimensions</i>	Not given
<i>Text</i>	B E Imp Caes (sic)

4	M Antonio
	Gordiano
	felici
	invicto Au
	SOS. .OCOP (?)
8	-----

line 7: **c_{*}os [pr]ocos_{*} (?)**

Caput Viae [Ancyra]
Date AD 238-244 M. Antonius Gordianus III *Augustus*

131(B). Afşar 2

Province, Sub-Province + Admin. Code and Map As 131(A)
Location In the village; beside the mosque
Copy DHF 01.x.1975. DHF squeeze in BIAA. No DHF photo. Text here from DHF squeeze
BIAA Collections: Squeeze and Stone Photographs
 Squeeze: 06. Ankara 48, Afşar 2
Publication RRMAM 1. 51(B) (text only, from DHF copy)
 RRMAM 2, 1. 080 (correction of text of RRMAM 1. 51[B])
Description A simple cylinder. Broken below. Hard, grey limestone. The top surface is flat
Dimensions Ht 0.84; diam. (bottom) 0.43. Letters: (line 4) ET 0.046, (line 5) CAES 0.05

4	B F
	Imp·Caes·C·Aur·
	Val·Diocletiano
	p·f·iny·Aug·et·
	Imp·Caes·M·Aur·
	Val·Maximiano
	p·f·iny·Aug·et·
8	Fl·Val·Constantio
	et·Gal·Val·
	[M]aximiano
	[nobb·Caess]
12	-----

Caput Viae [Ancyra]
Date AD 293, 21.v(?)-305, 01.v Diocletianus and Maximianus *Augusti* with Constantius I and Galerius *Caesares*

131(C). Afşar 3

Province, Sub-Province + Admin. Code and Map As 131(A)
Location In the village; at the house formerly of İhsan Küçük, now (03.x.1991) of Hacı Veli Küçük; brought from a field, c. 100 m N of Tekağil, the property of Hasan Küçük

<i>Copy</i>	DHF 01.x.1975. DHF squeeze in BIAA. No DHF photo. Text here from DHF squeeze
<i>BIAA Collections: Squeeze and Stone Photographs</i>	Squeeze: 06. Ankara 47, Afşar 3
<i>Publication</i>	RRMAM 1. 51(C) (text only, from DHF copy)
<i>Description</i>	RRMAM 2, 1. 081 (notice only)
<i>Dimensions</i>	A simple cylinder. Broken below. Hard, grey limestone. The top surface is flat, the shaft oval in section. The inscribed area was smoothed, the rest and the back roughly dressed
<i>Dimensions</i>	Ht 0.65; diam./wi. 0.30. Letters: (line 2) O of BIO 0.055, (line 7) O of VOL 0.04

<i>Text</i>	Imp Caes
	G Vibio Treb-
	ΑΠΟ Gallo bio
4	felici Aug e(t) Imp
	Caes G Afinio
	Gallo Veldu-
	[m]nianq Volu-
8	[siano Aug]

<i>Caput Viae</i>	[Ancyra]
<i>Date</i>	AD 251, (?)Aug-253, (?)Aug Trebonianus Gallus and Volusianus Augusti

131(D). Afşar 4

<i>Province, Sub-Province + Admin. Code and Map</i>	As 131(A)
<i>Location</i>	In the village; standing beside the mosque, at the left-hand side of the gate on the E side of the mosque courtyard
<i>Copy</i>	DHF 01.x.1975
<i>Publication</i>	RRMAM 1. 51(D) (notice)
	RRMAM 2, 1. 082 (notice)
<i>Description</i>	The plinth of a simple cylinder
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription
<i>Date</i>	(?)

131(E). Afşar 5

<i>Province, Sub-Province + Admin. Code and Map</i>	As 131(A)
<i>Location</i>	Inside the courtyard of a <i>ağıl</i> (pen or sheepfold) called 'Müslü Aras <i>ağılı</i> ', in an area called Aydinoğlu Mevkii, c. 4 km S of village
<i>Copy</i>	DHF 01.x.1975
<i>Publication</i>	RRMAM 1. 51(E) (notice)
	RRMAM 2, 1. 083 (notice)
<i>Description</i>	A simple cylinder, on a square plinth. Broken above. Hard, grey limestone. The surface was smoothed

Dimensions Ht 1.20 + (plinth) 0.30; wi. (plinth) 0.46; diam. 0.40

Text No visible inscription

Date (?)

131(F). Afşar 6

Province, Sub-Province + Admin. Code and Map As 131(A)

Location Found in a field (owned by Osman Ballidere) at the entrance to the village, on the NW side; now lying in front of the village *atölyeleri* (workshops)

Copy DHF 03.x.1991. DHF squeeze and photos (Pl. 7.1.80 [p. 330]) in BIAA. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 06. Ankara 49, Afşar 6
Stone: (1) B/W Neg.: DHF M/91/22.07

Description A simple cylinder. Complete. Hard, pale limestone. The top surface is flat. The base is roughly shaped. The area for the inscription was smoothed; the rest of the stone was rough and unworked. Surface and letters: worn and damaged

Dimensions Ht (total) 1.68, (base) 0.64; diam. (top) 0.32. Letters: P and O of PIO 0.05 and 0.043 respectively

<i>Text</i>	Imp Caes
2	[[---]]
	[[---]]
4	et Imp
	[[---]]
6	pio MPP

Caput Viae [Ancyra]

Date (?)

131(G). Afşar 7

Province, Sub-Province + Admin. Code and Map As 131(A)

Location Found at a place called Yanacak Öz or Çayırlar, near the boundary with Çiğdem village; now in Afşar, at the house of Durmuş Üner

Copy DHF 03.x.1991. DHF squeeze and photos in (Pl. 7.1.81 [p. 330]) BIAA. Text here from DHF squeeze

BIAA Collections: Squeeze and Stone Photographs

Squeeze: 06. Ankara 51, Afşar 7
Stone: (1) B/W Neg.: DHF M/91/22.08-09

Description A simple cylinder. Broken below; chipped around the top edge. Hard, grey limestone. The top surface is flat. The inscription was cut inside a panel, on a smoothed surface; the rest of the stone was rough and unworked. Surface and letters: sharp and clear; all letters with pronounced apices

Dimensions Ht 0.54; diam. (bottom) 0.435. Letters: (text 1) (line 1) E 0.063, (line 2) E of SEPT 0.037; (text 2) E 0.032

Text

(1) (below and partly underneath text [2])

	Imp Caesar
2	L Septimius Severus
	Pius Pertinax Aug Arab
4	Adiab Parth max pon-
	tif·trib·pot·VI·imp·XI cos
6	III pro[cos·p·p·et --]

(sic)

lines 4-5: **ponltif <max>**, cp. above, no. 129(B). Yörenli 2

(2) (above and partly on top of text [1])

n[obi]lissimis Caesa-
ribus

Caput Viae

[Ancyra]

Date(1) AD 197/198, 10.xii-09.xii L. Septimius Severus [and M. Aurelius Antoninus (Caracalla) *Augusti*, (?) with L. Septimius Geta *Caesar*]

(1) (?)

Comment This milestone possibly belongs to the same series as nos 124(A). Karaali 1 and 127(B). Yörenli 2, all three erected on the same road, namely, the Pilgrim's Road.

132. Sarıhüyük, form. Şedithüyük*Province, Sub-Province + Admin. Code* Ankara, Balâ 06-05-2*Map* Kırşehir 63-Iç*Location* Outside the village; in an old cemetery on the W side of the village*Copy* Anderson Summer 1898; DHF 02.x.1975. The text published by Anderson is reproduced here (Fig. 6.1.44 [p. 272]). DHF squeeze in BIAA. No DHF photo. (of Text [2]). Text here from DHF squeeze*BIAA Collections: Squeeze and Stone Photographs*

Squeeze: 06. Ankara 98, Sarıhüyük

Publication Text (1) Anderson 1899, 107 no. 95
RECAM 2. 403

Mitchell and French 2012, 171 no. 20

Text (2) Anderson 1897-98, 74 (notice only)

Anderson 1899, 106 no. 94

CIL 3. 14184⁵³ (text of Anderson)

RRMAM 1. 52 (text only, from DHF copy)

RRMAM 2, 1. 170 (notice only)

Description A simple cylinder; a column (?), re-used as a milestone. Broken above. Hard, grey limestone. The top surface is flat, the surface smooth.*Dimensions* Ht 1.85; (diam.) 0.54. Letters: 0.05-07*Text*

(1) (on the front face of the shaft)

Dedication by Ancyra, metropolis of Galatia, to Cornelia Salonina

(2) (on the rear face of the shaft)

Imp [Caes] Fl Val(e)rio
Constantino p f inv Aug et
3 Imp Caes Va[ll] Liciniano]]
[[Licinio]] p f in(v) Aug
m LXV
6 μ ε'

line 2: ligatures AV, ET

line 6: μ(iλια)

Caput Viae

(Ancyra)

Date

(2) AD 313, Aug/Sept-317, 28.ii Constantinus I and Licinius I *Augusti*

**4.5 CONCORDANCES
4.6 INDICES**

4.5 CONCORDANCES

4.5.1 Topographic. Old and New Place-Names

(Old)

(New)

Altıyapan	- Eskiypar
Ası Yozgat	- Elmadağ
Büyük Kabaca	- Esendere
Büyük Zengi	- Bakırpinar
Çerkez Atlandı	- Mahmudiye
Demirşeyh	- Demirşih
Manarga	- Dedeçam
Merkepli	- Cevheri
Meidan	- Meydan
Nevenne	- Bahçesaray
Nevine	- Bahçesaray
Ravlı	- Akyurt
Suwerek	- Altınekin
Sarayköy Yaylası	- Kızılçakuyu
Saraiköy	- Kızılçakuyu
Zivarık	- Altınekin

4.5.2 Epigraphic

1. Collections

CIL

246	- 117(A)	6958	- 102(A)	14184 ⁵⁰	- 126(A)
309	- 33(A)	6962/3	- 94(A)	14184 ⁵¹	- 126(B)
310	- 33(B)	6964	- 92	14184 ⁵²	- 131(A)
311	- 37	6965-7	- 90(A)	14184 ⁵³	- 132
312	- 117(B)	6968	- 88(A)	14184 ⁵⁵	- 32(B)
313	- 117(C)	6969	- 88(B)	14184 ⁵⁶	- 31
314	- 118(A)	6970/1	- 87(A)	14184 ⁵⁷	- 32(A)
315	- 117(D)	6972	- 87(B)	14184 ⁵⁸	- 25
316	- 118(B)	12215	- 102(B)	14184 ⁵⁹	- 02
317	- 04	12216	- 90(A)	14184 ⁶⁰	- 05
318	- 08	12218	- 103	14184 ^{62,63}	- 110
319	- 90(A)	13645	- 29(A)	14184 ⁶⁴	- 105
6058	- 117(I)	13646	- (27)	14185	- 97(A)
6897	- 34	14184	- 111(A)	14399a	- 70(B)
6898	- 33(A)	14184 ⁴¹	- 50(B)	14401a	- 97(A)
6899	- 45(A)	14184 ⁴²	- 58(A)	14401b	- 97(B)
6899a	- 50(A)	14184 ⁴³	- 58(B)	14401c	- 98
6900	- 117(I)	14184 ⁴⁶	- 120	14402	- 70(A)
6901	- 37	14184 ⁴⁷	- 122(B)	14402a	- 70(C)
6902	- 03	14184 ⁴⁸	- 122(A)		
6856/7	- 102(B)	14184 ⁴⁹	- 122(C)		

IK 66 (Pessinus)		33(A)	- 109(A)	51(D)	- 131(D)
		33(B)	- 109(B)	51(E)	- 131(E)
41	- 10	34	- 110	52	- 132
183	- 09	35(A)	- 111(A)		
		35(B)	- 111(B)		
IK 67		36	- 112		RRMAM 2, 1
		37	- 113	043	- 16(A)
158	89	38	- 114	044	- 16(B)
159	93(A)	39(A)	- 117(A)	045	- 16(C)
160	93(B)	39(B)	- 117(B)	076	- 67
		39(C)	- 117(C)	077	- 127(A)
ILS 1		39(D)	- 117(D)	078	- 127(B)
		39(E)	- 117(E)	079	- 131(A)
263	- 08	39(F)	- 117(F)	080	- 131(B)
268	- 117(B)	39(G)	- 117(G)	081	- 131(C)
467	- 117(I)	39(H)	- 117(H)	082	- 131(D)
		39(I)	- 117(I)	083	- 131(E)
ILS 2		39(J)	- 117(J)	084	- 124(A)
		39(K)	- 117(K)	085	- 124(B)
5828	- 98	39(L)	- 117(L)	086	- 22
5840	- 34	39(M)	- 117(M)	087	- 23(A)
		40(A)	- 118(A)	088	- 23(B)
MAMA 1		40(B)	- 118(B)	089	- 29(A)
		41	- 120	090	- 29(B)
17	- 84(D)	42(A)	- 121(A)	091	- 02
20	- 84(B)	42(B)	- 121(B)	092	- 117(A)
		42(C)	- 121(C)	093	- 117(B)
MAMA 4		43(A)	- 122(A)	094	- 117(C)
		43(B)	- 122(B)	095	- 117(D)
148	- 86	43(C)	- 122(C)	096	- 117(E)
233a	- 88(B)	43(D)	- 122(D)	097	- 117(F)
234	- 88(A)	43(E)	- 122(E)	098	- 117(G)
		44(A)	- 124(A)	099	- 117(H)
MAMA 7		44(B)	- 124(B)	100	- 117(I)
		45(A)	- 125(A)	101	- 117(J)
9	- 11	45(B)	- 125(B)	102	- 117(K)
		46(A)	- 126(A)	103	- 117(L)
MAMA 8		46(B)	- 126(B)	104	- 117(M)
		47(A)	- 127(A)	105	- 118(A)
6	- 102(A)	47(B)	- 127(B)	106	- 118(B)
7	- 101(A)	48(A)	- 128(A)	107	- 35
8	- 102(B)	48(B)	- 128(B)	108	- 07
261	- 79(A)	48(C)	- 128(C)	109	- 128(A)
		48(D)	- 128(D)	110	- 128(B)
RRMAM 1		49(A)	- 129(A)	111	- 128(C)
		49(B)	- 129(B)	112	- 128(D)
30	- 105	50	- 130	113	- 17(A)
31(A)	- 106(A)	51(A)	- 131(A)	114	- 17(B)
31(B)	- 106(B)	51(B)	- 131(B)	115	- 17(C)
32	- 107(A)	51(C)	- 131(C)	116	- 05

117	- 105	173	- 109(B)	406	- 87(B)
118	- 123	174	- 18	593	- 83
119	- 130	175	- 25	594	- 77
120	- 20	176	- 19	598	- 84(A)
124	- 01	177	- 65(A)	599	- 84(B)
125	- 32(A)	178	- 65(B)	600	- 84(C)
126	- 32(B)	179	- 129(A)	601	- 84(D)
127	- 107(A)	180	- 129(B)	602	- 103
129	- 03	181	- 113	604	- 11
130	- 04	318	- (27)	608	- 100(A)
131	- 31	320	- 59(A)	609	- 100(B)
132	- 39(A)	321	- 59(B)	611	- 99
133	- 39(B)	326	- 41	612	- 78
134	- 39(C)	328	- 57	613	- 74(C)
135	- 120	330	- 42	614	- 74(B)
136	- 110	334	- 58(A)	615	- 74(A)
137	- 111(A)	335	- 58(B)	616	- 74(D)
138	- 111(B)	340	- 43	617	- 74(E)
139	- 112	342	- 34	618	- 82(A)
141	- 125(A)	343	- 51(A)	619	- 82(B)
142	- 125(B)	344	- 51(B)	625	- 101(A)
143	- 38(A)	345	- 54(A)	626	- 101(B)
144	- 38(B)	346	- 54(B)	627	- 102(A)
145	- 38(C)	352	- 40	628	- 102(B)
146	- 38(D)	353	- 52(A)	629	- 102(C)
147	- 106(A)	354	- 52(B)	630	- 102(D)
148	- 106(B)	355	- 53(A)	633	- 95(A)
149	- 30	368	- 10	634	- 95(B)
150	- 33(A)	369	- 09	635	- 95(C)
151	- 33(B)	375	- 08	636	- 95(D)
152	- 126(A)	381	- 92(A)	637	- 76(A)
153	- 126(B)	382	- 92(B)	638	- 76(B)
154	- 36	383	- 94(A)	639	- 76(C)
155	- 26	384	- 94(B)	640	- 96
156	- 24	388	- 88(B)	641	- 70(A)
157	- 66	389	- 88(A)	642	- 70(B)
158	- 114	390	- 88(C)	643	- 70(C)
159	- 06	391	- 88(D)	644	- 70(D)
160	- 122(A)	392	- 88(E)	645	- 69(E)
161	- 122(B)	393	- 89(A)	646	- 70(F)
162	- 122(C)	394	- 89(B)	647	- 71
163	- 122(D)	395	- 90(C)	648	- 73(A)
164	- 122(E)	396	- 90(D)	649	- 73(B)
165	- 37	397	- 90(E)	650	- 73(C)
166	- 21	398	- 90(F)	651	- 73(D)
167	- 121(A)	399	- 90(G)	652	- 73(E)
168	- 121(B)	400	- 90(H)	653	- 75
169	- 121(C)	403	- 92	654	- 79(A)
170	- 132	404	- 86	655	- 79(B)
172	- 109(A)	405	- 87(A)	656	- 79(C)

657	- 79(D)	976	- 49(A)	238	- 80(A)
658	- 79(E)	977	- 49(B)	239	- 80(B)
659	- 79(F)	981	- 48	240	- 80(C)
660	- 79(G)				
662	- 13	RECAM 1 (Ankara)		StPont 1	
663	- 97(A)				
664	- 97(B)	20	- 132	3 and n.1	- 34
665	- 97(C)			19	- 50(B)
666	- 72	RECAM 2 (Ankara region)		20	- 57(A)-(B)
669	- 85			21	- 59(A)
670	- 98	403	- 132		
970	- 45(A)				
971	- 45(C)	RECAM 4 (Konya)			
973	- 50(A)				
974	- 50(B)	237	- 70(A)		

2. Annual Bulletins

AE		811 - 51(B)	1448	- 80(C)
		812 - 53(A)	2003.	1708 - 47
1899.	183 - 111(A)	813 - 57	1708	- 63(A)
	185 - 122(A)	814 - 43	1710	- 53(A)
1902.	169 - 98	1986. 683 - 16(A)	1711	- 46
1903.	261 - 40	684 - 83	1712	- 48
	(p.) 48 - 41	1987. 938a-c - 16(A)	1713	- 45(C)
1906.	21 - 77	939a-b - 16(B)	1714	- 64
1907.	58 - 84(A)	940 - 16(C)	1715	- 50(B)
1922.	5 - 90(B)	1989. 730 - 58(A)-(B)	1716	- 50(A)
1932.	49 - 118(A)	1991. 1498 - 28	2005.	1476 - 09
1937.	90 - 122(A)	1994. 1724a-d - 115	2006.	1483 - 35
	91 - 117(J)	1723 - 116	1484	- 117(K)
1946.	178 - 30	1996. 1493 - 10	1485	- 117(H)
1961.	127 - 54(A), (B)	2001. 1915 - 117(I)	2007.	1457 - 49(C)
1985.	808 - 52(B)			
	809 - 52(A)	- 83	1458	- 44
	810 - 51(A)	2002. 1446 - 80(A)	1459	- 45(B)
		1447 - 80(B)		

SEG

44. 1029 16(A)

3. Journals

4. Authors

Anderson	1897-98	66	- 105	74	- 122(A)
		66	- 110	74	- 122(B)
65	- 111(A)	72	- 05	74	- 122(C)

74	- 132	230 no. 20 - 82(A)	22-23 - 59(B)
74	- 126(A)	230 no. 21 - 74(A)	24 and n.7 - 50(B)
74	- 126(B)	230 no. 23 - 82(B)	24 - 58(A)
		230 no. 24 - 74(B)	24 n.7 - 45(A)
Anderson 1899		230 no. 25 - 84(D)	24 n.7 - 45(C)
		230 no. 28 - 84(C)	119-120 - 45(C)
59 no.5	- 111(A)	230 no. 29 - 11	
60 no.8	- 110	230 no. 30 - 73(C)	Bittel 1957
63 no. 10	- 105	230 no. 31 - 73(A)	
93 no. 73	- 05	230 no. 32 - 79(B)	90 no. 1a - 54(A)
93 no. 74	- 02	230 no. 33 - 79(F)	92 no. 1b - 41
101 no. 86	- 120	230 no. 34 - 79(G)	92 no. 2 - 54(B)
102 no. 87	- 122(A)	230 no. 35 - 73(D)	
103 no. 88	- 122(B)	230 no. 36 - 73(C)	Bittel 1985
103 no. 89	- 122(C)	230 no. 37 - 71	
104 no. 90	- 126(A)	230 no. 38 - 79(G)	10-11 - 52(B)
104 no. 91	- 126(B)	230 no. 39 - 79(G)-(H)	11-12 - 52(A)
106 no. 93	- 131(A)	323 n.16 - 16(A), 90(B)	13 - 51(A)
106 no. 94	- 132(2)		14 - 51(B)
107 no. 95	- 132(1)	Ballance 1960	15-16 - 53(A)
Anderson 1910			24 - 57
164 n.4	- 40	138 no. 137 - 90(B)	26-27 - 43
Anlağan 1968		184 no. 165 - 78	
6	- 22	Ballance in MAMA 8	Bosch 1967
Ballance 1958			
230 no. 1	- 79(C)	62 no. 66 - 08	
230 no. 2	- 76(A)	67 no. 68 - 117(B)	
230 no. 3	- 76(B)	67 no. 69 - 122(A)	
230 no. 4	- 79(B)	91 no. 93 - 31	
230 no. 5	- 79(D)	91 no. 94 - 32(A)	
230 no. 6	- 75	91 no. 95 - 32(B)	
230 no. 7	- 70(D)	91 no. 96 - 33(A)	
230 no. 8	- 85	147 no. 118 - 30	
230 no. 9	- 79(A)	148 no. 120 - 117(C)	
230 no. 10	- 70(A)	148 no. 121 - 33(B)	
230 no. 11	- 70(B)	148 no. 122 - 29(A)	
230 no. 12	- 70(C)	148 no. 123 - 111(A)	
230 no. 13	- 78	148 no. 124 - 02	
230 no. 14	- 77	148 no. 125 - 05	
230 no. 15	- 84(A)	151 no. 126 - 122(B)	
230 no. 16	- 73(A)	299 no. 237 - 118(A)	
230 no. 17	- 79(E)	333 no. 273 - 117(I)	
230 no. 18	- 72	335 no. 274 - 37	
230 no. 19	- 73(B)	335 no. 275 - 118(B)	
		341 no. 278 - 131(A)	
		358 no. 295 - 122(C)	
		363 no. 299 - 126(B)	
		364 no. 300 - 110	
		364 no. 301 - 105	
		365 no. 302 - 117(E)	

365 no. 303	- 117(F)	22 no. 3	- 16(B)	Devreker and Waelkens
366 no. 304	- 04	24 no. 4	- 16(C)	1984, I, A
345 no. 381	- 117(A)	37 n.87	- 86	
Buckler, Calder and Cox		Christol, Drew Bear and		23 - 09
	1924	Özsait 1993		224 no. 36 - 10
77 no. 111 - 129(B)		168 n.54	- 90(C)	Donati 1765-75, 1
Cagnat 1903a		Christol and Loriot 1993		147 no. 1 - 117(A)
193 - 40		214 - 58(A)		Ehrenberg and Jones 1949
Cagnat 1903b		217 - 57		129 no. 294 - 98
169-170 - 41		217-218 - 41		Eyice 1970-71
Calder 1911		219 - 58(B)		
no. 2 - 36		Christol and Loriot 2001		271 - 70(E)
no. 5 - 39(A)		100 no. 7 - 58(A)		von Flottwell 1895
no. 6 - 39(B)		106 no. 1a) - 117(A)		
no. 7 - 39(C)		106 no. 1b) - 83		42 - (27), 29(A)
no. 9 - 66		Conti 2004		French 1976a
no. 12 - 65(B)		74 no. 21 - 115		52 - 02, 05, 06,
no. 13 - 129(A)		75 no. 22 - 65(A)		25, 70(A),
Callander 1906		89 no. 43 - 11		(C), (E), (F),
160 no. 10 - 82(B)		92 no. 48 - 16(B)		103
160 no. 11 - 82(A)		189 no. 4 - 28		53 - 08, (27), 40,
172 no. 56 - 77		Cousin 1904		58(A), 90
173 - 16(A)		401-2 - 77		(B), (C)
173 no. 58 - 84(A)		408 - 98		French 1978b
173 no. 59 - 84(B)		Cronin 1902		294 - 07
173 no. 60 - 84(C)		102 no. 7 - 98		French 1980
173 no. 61 - 84(D)		105 no. 11 - 97(A)		716 no. 9 - 08
Christol and Drew Bear		105 no. 12 - 97(B)		717 no. 10 - 117(B)
1986		108 - 95(A)-(C)		717 no. 11 - 34
45 - 88(B)		109, 110 - 96		718 no. 14 - 38(A)
47 n.30 - 90(D)		119 no. 46 - 70(A)		719 no. 15 - 22
52 - 90(C)		121 no. 48 - 70(B)		722 no. 22 - 118(A)
Christol and Drew Bear		121 no. 49 - 70(C)		727 Map 2 no. 5 - 88(D)
1987		Devreker and Strubbe 1996		727 Map 2 no. 6 - 90(B)
19 no. 2 - 16(A)		61 no. 10 - 10		727 Map 2 no. 7 - 95(D)
20 n.31 - 88(B), 90(A)				727 Map 2 no. 8 - 97(A)
				727 Map 2 no. 9 - 97(B)
				727 Map 2 no. 10 - 98

728 Map 3 no. 15	- 117(G)	63 no (3)	- 95(E)	337 no. 1385 <i>ter</i>	- 90(A)
728 Map 3 no. 16	- 07			425 no. 1784	- 08
728 Map 3 no. 20	- 67	French 2003		425 no. 1784a	- 117(B)
728 Map 3 no. 23	- 103			426 no. 1787	- 117(A)
French 1981		185 no. 72	- 117(G)	428 no. 1805a	- 33(A)
		186 no. 73	- 35	428 no. 1806	- 33(B)
167 no. 13	- 16(A)	187 no. 74	- 117(K)		
168	- 16(B), (C)	188 no. 75	- 116	Levick 1985	
	- 49(B),	188 no. 76	- 115		
	51(A),	192 no. 77	- 118(A)	103 no. 94	- 98
	52(A)	193 no. 78	- 117(H)		
168-169	- 50(B)	194 no. 79	- 112	Loriot 1978	
170 no. 14	- 83	Garstang 1908			
French 1984d		9	- 54(A)	72 n.6	- 54(A)
				81 no. 5	- 41
123	- 41	Habicht 1971		81 no. 6	- 54(A)
French 1987a		96	- 22	Macpherson 1954	
191	- 53(B)	Hamilton 1842, 2		113 no. 1	- 111(B)
194	- 49(C)	416 no. 99	- 33(B)	113 no. 2	- 105
French 1988a		428 no. 139	- 08	113 n.3	- 30
		489 no. 448	- 90(A)	114 no. 3	- 114
274	- 51(C), 60	Henzen 1862		114 no. 4	- 121(A)
275	- 28	66	- 08	114 no. 5	- 66
French 1989a		66	- 117(B)	115 no. 6	- 65(B)
		66, 67	- 33(A)	115 no. 7	- 129(A)
38	- 58(A)	67	- 33(B)	115 no. 8	- 38(A)
38, 39	- 58(B)	68	- 117(C)	116 no. 9	- 38(B)
39	- 57	de Jerphanion 1928		116 no. 10	- 38(C)
French 1990a		277 no. 52	- 117(D)	116 no. 11	- 38(D)
		277 no. 53	- 117(E)	117 no. 12	- 45(B)
French 1990b		Laminger-Pascher 1992		117 no. 13	- 36
13	- 116	125 no. 163	101(A)	118 no. 14	- 39(A)
15	- 115	155 no. 225	102(A)	118 no. 15	- 39(B)
French 1991b		156 no. 226	102(B)	118 no. 16	- 39(C)
		188 no. 299	103	118 no. 17	- 29(A)
81	- 28	Le Bas and Waddington		119 no. 18	- 17(A)
French 1997			1870, 2	119 no. 19	- 17(B)
				120	- 30
				120 no. 7a	- 124(A)
				120 no. 7b	- 125(A)
				Map Fig. 1	- 128(A)
				Macpherson 1958	
				162 no. 208	- 105
				162 no. 207	- 111(B)
				166 no. 215	- 112
				177 no. 245	- 38(A)

177 no. 246	- 38(B)	39 no. 81 - 34	Ramsay (W.M.) 1906a
178 no. 247	- 38(C)		
178 no. 248	- 38(D)	Mommsen 1884b	234 - 16(A)-(C)
179 no. 249	- 114		
179 no. 250	- 121(A)	584 no. 1368 - 92	Ramsay (W.M.) 1907
180 no. 251	- 29(A)		
180 no. 252	- 17(A)	Orelli and Henzen 1828-56, 3	449 n.19 - 72
181 no. 253	- 17(B)		
184	- 36		
185	- 39(A)-(C)	389 no. 6913 - 08	Ramsay (W.M.) 1909a
186	- 65(A), (B), 66		277 - 103
187	- 129(A)	Pace 1916-20	
192 no. 275	- 124(A)		Ramsay (W.M.) 1909b
193 no. 276	- 125(A)	51 no. 29 - 89(B)	
194 no. 277	- 45(C)		8 - 79(A)
McCrum and Woodhead 1961		Perrot 1867	8-9 - 79(B)
136 no. 417	- 38(A)	102 - 117(B)	Ramsay (W.M.) 1916
		111 - 33(A)	
		113 - 117(C)	132 - 103
Magie 1950, 2		Perrot et al. 1872, 1	Ramsay (W.M.) 1926
1082 n.32	- (27)	227 no. 111 - 117(B)	105 - 16(A)
Miltner (Fr. & H.) 1937		228 no. 112 - 117(C)	
19 no. 15	- 118(A)	228 no. 113 - 118(B)	Ramsay (W.M.) 1930b
19 no. 16	- 122(A)	286 no. 148 - 33(A)	
20 no. 18	- 117(B)	286 n.1 - 33(B)	252 - 96
21 no. 21	- 117(J)		
27 no. 28	- 117(F)	Ramsay (A.M.) 1909	Ramsay (W.M.) 1941
Mitchell in French 1973		5 - 71	
26	- 117(G)	20 no. 1 - 70(A)	94 no. 61 - 45(A)
Mitchell 1973		21 no. 2 - 70(C)	95 no. 64 - 50(A)
73	- 22	21 no. 3 - 71	288 n.1 - 96
Mitchell 1993		21 no. 4 - 73(B)	Robert 1965
122	- 22	21 no. 5 - 73(C)	
Mommsen 1884a		22 no. 6 - 73(A)	73 - 77
		24 no. 7 - 72	
		26 no. 8 - 85	Rohde 1943/44
		27 no. 9 - 84(A)	
		28 no. 10 - 84(B)	807 - 38(B)
		28 no. 11 - 84(C)	- 38(C)
		28 - 103	- 38 (D)
		29 no. 12 - 84(D)	
			Sandys 1919
		Ramsay (W.M.) 1905	
35 no. 71	- 33(A)		136 - 117(B)
35 no. 72	- 117(I)	415 no. 7 - 77	
38 no. 80	- 03	416 - 84(A)	

Sarre 1896a	164 no. A1a	- 45(A)	Süel 1989
39 - 97(A)	165	- 63(B)	
	165-166 no. A2	- 63(A)	344 - 62
	166	- 53(A)	
Sarre 1896b	167-168 no. A3	- 46	Texier 1839-49, 1
	168-169 no. A4	- 48	
122, 175 no. 24a - 97(A)	169-171 no. B1	- 45(C)	190 - 33(B)
	171-172 no. B2	- 64	
Sterrett 1883-84	173-174 no. B3	- 50(B)	Tournefort 1717a, 2
	175-176 no. B4	- 50(A)	
178 nos 178-181 - 94(A)	176 no. B5	- 49(B)	453 - 117(A)
309 no. 356 - 45(A)	177 no. B6	- 49(A)	
320 no. 377 - 50(A)			Tournefort 1717b, 3
321 no. 378 - 37			
Sterrett 1884-85	Strobel and Gerber 2007		324 - 117(A)
	617 no. 1	- 49(C)	
153-4 nos 261-263 - 102(B)	618 no. 2	- 44	Tournefort 1718, 2
155 no. 265 - 102(A)	619 no. 3	- 45(B)	
155 - 102(C), (D)	Strobel 2007		181 - 117(A)
196 - 95(A), (B)			
387 nos 560, 561 - 87(A)	1409 no. A1	- 47	Waldmann 1981
400 no. 587 - 88(A)	1411 no. A1	- 45(A)	99 no. 7 - 90(C)
401 no. 588 - 88(B)	1411 no. A2	- 63(A)	100 no. 8 - 90(D)
Sterrett 1885	1412 no. A2a	- 63(B)	
	1413 no. A3	- 46	Winter 1996
	1414 no. A4	- 48	
12 nos 8, 9 - 94(A)	1415 no. B1	- 45(C)	317 no. 25 - 103
43 no. 60 - 45(A)	1416 no. B2	- 64	
Strobel and Gerber 2003	1417 no. B3	- 50(B)	
	1418 no. B4	- 50(A)	
162-164 no. A1 - 47	1419 no. B5	- 49(B)	
	1419 no. B6	- 49(A)	

4.6 INDICES

4.6.1 Imperial Milestones

Note: The dates, cited here, for the Imperial tribunician power (and also consulship and imperial acclamation) are taken from the tables published by Kienast (1996)

Augustus

6 BC, 26.vi-31.xii

(TR·P·XIX·COS·XI·DES·XII·IMP·XV)

- 088(D). Esendere 4
- 090(C). Gençali 3
- 094(B). Dedeçam 2 (1)
- 095(D). Kıyakdede 4
- 095(E). Kıyakdede 5 (1)
- 097(A). Selki 1
- 097(B). Selki 2
- 098. Yunuslar

- H.1 *Via Sebaste*
- H.1 *Via Sebaste*
- H.1 *Via Sebaste*
- H.1 *Via Sebaste*
- H.1 *Via Sebaste*
- H.1 *Via Sebaste*
- H.1 *Via Sebaste*
- H.1 *Via Sebaste*

Titus with Domitianus

AD 80, 01.vii-81, before mid iii

(TR·P·X·IMP·XV·COS·VI[II])

- 008. Mulk

- A.1 Ancyra - Pessinus (- Amorium)

AD 81, from mid iii-30.vi

(TR·P·X·IMP·XVII·COS·VIII·DES·IX)

- 103. Apa

- J.3 Col. Lystra (- [?] Dalisandus - Laranda)

Domitianus

AD 81, 30.ix-13.ix

(TR·P·COS·VII)

- 007. Bacı

- A.1 Ancyra - Pessinus (- Amorium)

AD 82, from mid iii-13.ix

(TR·P·COS·VIII·DES·IX)

- 067. Abazlı 1
- 117(B). Ankara 2
- 117(G). Ankara 7
- 122(A). Oğulbey 1 (1)
- 128(C). Bağıçı 3

- F.8 Ancyra (- Caesaria per Aquas Saruvenas)
- P.1 Pilgrim's Road (?)
- P.1 Pilgrim's Road (?)
- P.1 Pilgrim's Road
- P.1 Pilgrim's Road

AD 89/90, 14.ix-13.ix

(TR·P·IX·COS·XIV)

- 074(D). Eğribayat 4 (2)

- F.9 Col. Iconium (- Col. Archelaüs - Caesaria)
or G.1 Ancyra - Col. Iconium

(?) **Domitianus**

- 076(B). Kızılçakuyu 2 (1)
- 076(C). Kızılçakuyu 3 (1)

- F.9 Col. Iconium (- Col. Archelaüs - Caesaria)
- F.9 Col. Iconium (- Col. Archelaüs - Caesaria)

079(C). Obruk 3 (1)

F.9 Col. Iconium (- Col. Archelaïs - Caesaria)

(?) Titus or Domitianus

038(A). Hasanoğlan 1 (1)

F.2 Ancyra (- Amasia)

or F.3 Ancyra - Tavium (- Zela)

Nerva**AD 97, 01.i-17.ix**

(TR·P·COS·III)

034. İskilip
 040. Sungurlu
 042. Demirşeyh
 051 (C). Karakeçili 3
 054(B). Kaymaz 2
 056. Ekmekçi (2)
 059(B). Alaca 2
 060. Akören (1) (rest.)
 069(A). Çağırkan 1
 076(A). Kızılçakuyu 1 (1)
 076(B). Kızılçakuyu 2 (2)
 076(C). Kızılçakuyu 3 (2)
 079(B). Obruk 2 (1)
 079(C). Obruk 3 (2)
 079(D). Obruk 4
 079(F). Obruk 6 (2) (rest.)
 079(G). Obruk 7 (1)
 099. Değirmen

D.1 Ancyra (- Amisus)
 F.2 Ancyra (- Amasia)
 F.2 Ancyra (- Amasia)
 F.2 Ancyra (- Amasia)
 F.2 Ancyra (- Amasia)
 F.2 Ancyra (- Amasia)
 F.2 Ancyra (- Amasia)
 F.2 Ancyra (- Amasia)
 F.2 Ancyra (- Amasia)
 F.8 Ancyra (- Caesaria per Aquas Saruvenas)
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 H.1 *Via Sebaste*

AD 97, 01.i-17.ix(?)

([TR·P·].COS·III)

049(A). Haydarbeyli 1

F.3 Ancyra - Tavium (- Zela)

AD 97, 18.ix-09.xii

(TR·P·II·COS·III)

045(A). Büyük Nefes 1
 047. Eski Karaağıl (rest.)

F.3 Ancyra - Tavium (- Zela)
 F.3 Ancyra - Tavium (- Zela)

Traianus**AD 98 (?)**

(TR·P·COS·II)

017(B). Balıkhisar 2 (rest.)
 017(C). Balıkhisar 3 (rest.)
 019. Taşpınar (2)
 020. Cükük
 023(B). Akkuzulu 3 (rest.)
 032(A). Çiftlik 1
 032(B). Çiftlik 2
 033(A). Kalecik 1
 035. Ankara, Siteler
 038(A). Hasanoğlan 1 (2)

C.2 Ancyra - Gangra (- Hadrianopolis)
 C.2 Ancyra - Gangra (- Hadrianopolis)
 C.2 Ancyra - Gangra (- Hadrianopolis)
 C.2 Ancyra - Gangra (- Hadrianopolis)
 C.2 Ancyra - Gangra (- Hadrianopolis)
 D.1 Ancyra (- Amisus)
 D.1 Ancyra (- Amisus)
 D.1 Ancyra (- Amisus)
 F.2 Ancyra (- Amasia)
 or F.3 Ancyra - Tavium (- Zela)
 F.2 Ancyra (- Amasia)

038(B). Hasanoğlu 2	or F.3 Ancyra - Tavium (- Zela) F.2 Ancyra (- Amasia)
060. Akören (3)	or F.3 Ancyra - Tavium (- Zela) F.3 Ancyra - Tavium (- Zela)

AD 97 or 98 Nerva or Traianus

031. Elecik D.1 Ancyra (- Amisus)

Hadrianus

AD 118/119, 10.xii-09.xii

(TR·P·III)

045(C). Büyük Nefes 3 F.6 Tavium (- Melitene) or F.7 Tavium (- Caesaria)
064. Musabeyli F.6 Tavium (- Melitene) or F.7 Tavium (- Caesaria)

AD 119/120, 10.xii-09.xii

(TR·P·III)

025. Şemseddin
030. Kalabağ
075. Muşki Yayla

C.2 Ancyra - Gangra (- Hadrianopolis)
D.1 Ancyra (- Amisus)
F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
or G.1 Ancyra - Col. Iconium

AD 121/122, 10.xii-09.xii

(TR·P·VI)

002. Alacaatlı (2)
005. Balıkuyumcu
006. Mali (2) (rest.)
017(A). Balıkhisar 1 (2)
022(A). Akkuzulu 1
028. Yukarı Yanlar (2)
029(A). Akyurt 1 (rest.)
033(B). Kalecik 2
038(C). Hasanoğlan 3

038(D). Hasanoğlan 4
039(A). Elmadağ 1
039(B). Elmadağ 2 (rest.)
039(C). Elmadağ 3
050(A). Dambasan 1 (rest.)

065(B). Tol 2 (2)
088(A). Esendere 1
111(A). Eryaman 1
114. Macun
116. Ankara, Akköprü
117(C). Ankara 3
117(J). Ankara 10

A.1 Ancyra - Pessinus (- Amorium)
A.1 Ancyra - Pessinus (- Amorium)
A.1 Ancyra - Pessinus (- Amorium)
C.2 Ancyra - Gangra (- Hadrianopolis)
C.2 Ancyra - Gangra (- Hadrianopolis)
C.2 Ancyra - Gangra (- Hadrianopolis)
D.1 Ancyra (- Amisus)
D.1 Ancyra (- Amisus)
F.2 Ancyra (- Amasia)
or F.3 Ancyra - Tavium (- Zela)
F.2 Ancyra (- Amasia)
or F.3 Ancyra - Tavium (- Zela)
F.2 Ancyra (- Amasia)
or F.3 Ancyra - Tavium (- Zela)
F.2 Ancyra (- Amasia)
or F.3 Ancyra - Tavium (- Zela)
F.2 Ancyra (- Amasia)
or F.3 Ancyra - Tavium (- Zela)
F.2 Ancyra (- Amasia)
or F.3 Ancyra - Tavium (- Zela)
F.8 Ancyra (- Caesaria per Aquas Saruvenas)
H.1 *Via Sebaste*
P.1 Pilgrim's Road
P.1 Pilgrim's Road
P.1 Pilgrim's Road
P.1 Pilgrim's Road (?)
P.1 Pilgrim's Road (?)

117(K). Ankara 11 (2)	P.1 Pilgrim's Road (?)
117(L). Ankara 12	P.1 Pilgrim's Road (?)
122(B). Oğulbey 2	P.1 Pilgrim's Road
128(A). Bağıçı 1	P.1 Pilgrim's Road

(?) AD 121/122

125(B). Günalan 2 (1) (rest.)	P.1 Pilgrim's Road
127(B). Abazlı 2 (rest.)	P.1 Pilgrim's Road

AD 127/128, 10.xii-09.xii

(TR·P·XII)

090(A). Gençali 1 (1)	H.1 <i>Via Sebaste</i>
-----------------------	------------------------

AD 128/129, 10.xii-09.xii

(TR·P·XIII)

012. Meydan	A.5 Col. Iconium - Laodicia (Philomelium) (?) or G.3 Savatra - Laodicia
070(A). Konya 1	(?) F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium or H.1 <i>Via Sebaste</i>
079(A). Obruk 1	(?) F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
085. Yazibelen	G.1 Ancyra - Col. Iconium
094(A). Dedeçam 1 (1)	H.1 <i>Via Sebaste</i>

(?) YEAR

(? TR·P·XIII = AD 128/129)

070(D). Konya 4	(?)F.9 Col. Iconium (- Col. Archelais - Caesaria) or G.1 Ancyra - Col. Iconium or H.1 <i>Via Sebaste</i>
070(E). Konya 5 (1)	(?)F.9 Col. Iconium (- Col. Archelais - Caesaria) or G.1 Ancyra - Col. Iconium or H.1 <i>Via Sebaste</i>
107(B). Çoğlu 2	P.1 Pilgrim's Road

(?) Hadrianus

073(B). Kulak Murat Hanı 2 (1)	F.9 Col. Iconium (- Col. Archelais - Caesaria) or G.1 Ancyra - Col. Iconium
073(C). Kulak Murat Hanı 3 (1)	F.9 Col. Iconium (- Col. Archelais - Caesaria) or G.1 Ancyra - Col. Iconium

Hadrianus or Antoninus Pius

087(A). Yassören 1 (1) (rest.)	H.1 <i>Via Sebaste</i>
102(A). Kavak 1	J.3 Col. Lystra (- [?] Dalisandus - Laranda) or H.1 <i>Via Sebaste</i>

Antoninus Pius**AD 140/141, 10.xii-09.xii**

(TR·P·IV)

070(B). Konya 2

(?) F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 or G.1 Ancyra - Col. Iconium
 or H.1 *Via Sebaste*

AD 141/142, 10.xii-09.xii

(TR·P·V)

070(C). Konya 3 (1)

(?) F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 or G.1 Ancyra - Col. Iconium
 or H.1 *Via Sebaste*

Sept. Severus and Caracalla with Geta**AD 197/198, 10.xii-09.xii**

(TR·P·VI·IMP·XI·COS·(II) or COS·II)

016(A). Çapalı 1 (1)

A.9 *Via Sebaste* (Apollonia) (- Apamea)

029(B). Akyurt 2 (rest.)

D.1 Ancyra (- Amisus)

049(B). Haydarbeyli 2 (2)

F.3 Ancyra - Tavium (- Zela)

050(B). Dambasan 2 (2)

F.3 Ancyra - Tavium (- Zela)

053(A). Yekbaş 1 (2)

F.3 Ancyra - Tavium (- Zela)

055. Gökçam

F.3 Ancyra - Tavium (- Zela)

063(A). Küçük Nefes 1

F.6 Tavium (- Melitene) or F.7 Tavium (- Caesaria)

077. Akbaş Yayla

F.9 Col. Iconium (- Col. Archelaïs - Caesaria)

078. Divanlar

F.9 Col. Iconium (- Col. Archelaïs - Caesaria)

086. Uluborlu (1)

H.1 *Via Sebaste*

090(B). Gençali 2 (1)

H.1 *Via Sebaste***(?) AD 197/198**

(TR·P·VI)

051(A). Karakeçili 1 (rest.)

F.3 Ancyra - Tavium (- Zela)

052(A). Yazır 1 (rest.)

F.3 Ancyra - Tavium (- Zela)

073(A). Kulak Murat Hanı 1 (2)

(?) F.9 Col. Iconium (- Col. Archelaïs - Caesaria)

or G.1 Ancyra - Col. Iconium

045(B) Büyük Nefes 2

F.3 Ancyra - Tavium (- Zela)

082(A). Ennek 1

F.9 Col. Iconium (- Col. Archelaïs - Caesaria)

084(A). Altınekin 1

G.1 Ancyra - Col. Iconium

090(F). Gençali 6 (1)

H.1 *Via Sebaste***AD 198/199, 10.xii-09.xii**

(TR·P·VII)

072. Tilki Han

F.9 Col. Iconium (- Col. Archelaïs - Caesaria)

or G.1 Ancyra - Col. Iconium

074(A). Eğribayat 1 (1)

F.9 Col. Iconium (- Col. Archelaïs - Caesaria)

or G.1 Ancyra - Col. Iconium

AD 207/208, 10.xii-09.xii

(TR·P·XVI)

115. Ankara, Batıkent

P.1 Pilgrim's Road

117(M). Ankara 13

P.1 Pilgrim's Road (?)

AD 198 or 208 (TR·P·VI or (X)VI·COS·III with Caracalla COS·III])

126(A). Karaali 1 (rest.)	P.1 Pilgrim's Road
129(B). Yöreli 2	P.1 Pilgrim's Road
131(G). Afşar 7 (1)	P.1 Pilgrim's Road

(?) YEAR

074(C). Eğribayat 3 (1)	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium
079(E). Obruk 5	F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
101(D). Hatunsaray 4	J.3 Col. Lystra (- [?] Dalisandus - Laranda) or H.1 <i>Via Sebaste</i>

Caracalla (M. Aurelius Antoninus) **AD 211/212, 10.xii-09.xii** (TR·P·XV·COS·IV)

118(A). Ankara, Çankaya 1	P.1 Pilgrim's Road
121(B). Örencik 2 (2)	P.1 Pilgrim's Road
129(A). Yöreli 1	P.1 Pilgrim's Road

Elagabalus (M. Aurelius Antoninus) **AD 218, 16.v-09.xii**

052(B). Yazır 2 (2)	F.3 Ancyra - Tavium (- Zela)
083. Ağsaaklı	F.11 Savatra - Cana (- Sidamaria)
090(H). Gençali 8 (2)	H.1 <i>Via Sebaste</i>
117(H). Ankara 8	P.1 Pilgrim's Road
117(I). Ankara 9	P.1 Pilgrim's Road
119(B). Ankara, Ahlatlıbel 2 (2)	P.1 Pilgrim's Road

Severus Alexander**AD 222**

060(A). Eskiyyapar 1	F.2 Ancyra (- Amasia)
062. Bolatcık (2)	or F.3 Ancyra - Tavium (- Zela) F.3 Ancyra - Tavium (- Zela)

AD 222/223, 10.xii-09.xii

(TR·P·II·COS·I)

036. Kayaş	F.2 Ancyra (- Amasia) or F.3 Ancyra - Tavium (- Zela)
037. Ortaköy	F.2 Ancyra (- Amasia) or F.3 Ancyra - Tavium (- Zela)
049(C). Haydarbeyli 3	F.3 Ancyra - Tavium (- Zela)
118(B). Ankara, Çankaya 2	P.1 Pilgrim's Road
119(A). Ankara, Ahlatlıbel 1	P.1 Pilgrim's Road

Maximinus**AD 235, ii/iii(?)-236, 07.i/16.v**

101(A). Hatunsaray 1 (2)	J.3 Col. Lystra (- [?] Dalisandus - Laranda)
(?) 101(C). Hatunsaray 3 (1)	H.1 <i>Via Sebaste</i>
(?) 106(A). İlyagut 1 (1)	P.1 Pilgrim's Road
(?) 106(B). İlyagut 2 (1)	P.1 Pilgrim's Road

112. Ankara, Etimesgut (1)	P.1 Pilgrim's Road
with Maximinus	AD 236, 07.i/16.v-238, mid April
018. Sünlü	C.2 Ancyra - Gangra (- Hadrianopolis)
057. Çomar	F.3 Ancyra - Tavium (- Zela)
Gordianus I and Gordianus II	AD 238
041. Cevheri	F.2 Ancyra (- Amasia)
054(A). Kaymaz 1	F.3 Ancyra - Tavium (- Zela)
Gordianus III	AD 238-244
101(B). Hatunsaray 2 (2)	H.1 <i>Via Sebaste</i>
101(C). Hatunsaray 3 (2)	H.1 <i>Via Sebaste</i>
131(A). Afşar 1	P.1 Pilgrim's Road
Philippus with Philippus	AD 244-247
046. Bicikler	F.3 Ancyra - Tavium (- Zela)
082(B). Ennek 2	F.11 Savatra - Cana (- Sidamaria)
Philippus (Iunior) (Aug.)	(?) YEAR
090(G). Gençali 7 (2)	H.1 <i>Via Sebaste</i>
Traianus Decius	AD 249-251
054(B). Karakeçili 2	F.3 Ancyra - Tavium (- Zela)
Trebonianus Gallus	AD 251-253
043. Hacılarhanı	F.2 Ancyra (- Amasia)
and Volusianus	AD 251-253
058(B). Eskiyyapar 2 (2)	F.3 Ancyra - Tavium (- Zela)
122(D). Oğulbey 4	P.1 Pilgrim's Road
131(E). Afşar 3	P.1 Pilgrim's Road
Valerianus and Gallienus	AD 253, before 23.x-255
089. "Sarıyar"	H.1 <i>Via Sebaste</i>
111(B). Eryaman 2	P.1 Pilgrim's Road
117(A). Ankara 1	P.1 Pilgrim's Road (?)
124(A). Ahiboz 1	P.1 Pilgrim's Road
with Valerianus	AD 255-257/258

009. Ertuğrul	A.1 Ancyra - Pessinus (- Amorium)
with Valerianus and Saloninus	(?) AD 257/258
102(B). Kavak 2 (2)	J.3 Col. Lystra (- [?] Dalisandus - Laranda) or H.1 <i>Via Sebaste</i>
with (?) Saloninus and Salonica	(?) AD 255
069(B). Çağırgan 2	F.8 Ancyra (- Caesaria per Aquas Saruvenas)
with [Saloninus] Valerianus	AD 257/258-260, Spring
074(B). Eğribyat 2	F.9 Col. Iconium - Col. Archelaïs (- Caesaria) or G.1 Ancyra - Col. Iconium
and Valerianus (Saloninus)	AD 260, Spring-Autumn
094(B). Dedeçam 2 (2)	H.1 <i>Via Sebaste</i>
Aurelian	AD 270-275
003. Dodurga 1	A.1 Ancyra - Pessinus (- Amorium)
048. Körpeli	F.3 Ancyra - Tavium (- Zela)
122(C). Oğulbey 3 (2)	P.1 Pilgrim's Road
Carus with Carinus and Numerianus	AD 282-283
084(D). Altinekin 4 (2)	G.1 Ancyra - Col. Iconium
088(E). Esendere 5 (2)	H.1 <i>Via Sebaste</i>
Diocletian	AD 284, 20.xi-286, 01.iv
013. Sarayönü	A.5 Col. Iconium - Laodicia (-Philomelium)
Diocletian and Maximianus	AD 286, 01.iv-293, 21.v(?)
094(A). Dedeçam 1 (2)	H.1 <i>Via Sebaste</i>
125(A). Günalan 1	P.1 Pilgrim's Road
126(B). Karaali 2	P.1 Pilgrim's Road
Diocletian and Maximianus with Constantius and Galerius	AD 293, 21.v(?)-305, 01.v
003(?). Dodurga 2	A.1 Ancyra - Pessinus (- Amorium)
028. Yukarı Yanlar (4)	C.2 Ancyra - Gangra (- Hadrianopolis)
094(A). Dedeçam 1 (3)	H.1 <i>Via Sebaste</i>
105. Bayram (2)	P.1 Pilgrim's Road
106(B). İlyagut 2 (2)	P.1 Pilgrim's Road
106(C). İlyagut 3 (1) (incomplete)	P.1 Pilgrim's Road
110. Erkeksu Çiftlik (2)	P.1 Pilgrim's Road

112. Ankara, Etimesgut (2)	P.1 Pilgrim's Road
113. Yuva (1)	P.1 Pilgrim's Road
115. Ankara, Batıkent (2)	P.1 Pilgrim's Road
117(E). Ankara 5	P.1 Pilgrim's Road (?)
122(E). Oğulbey 5 (1)	P.1 Pilgrim's Road
131(B). Afşar 2	P.1 Pilgrim's Road

Severus and Maximinus *Caesares* **AD 305, 01.v-306, 25.vii**

015. Bakırpınar	A.5 Col. Iconium - Laodicia (- Philomelium)
095(E). Kıyakdede 5 (2)	H.1 <i>Via Sebaste</i>

Galerius and Constantinus **AD 307-308**

(?) 010. Ballıhisar	A.1 Ancyra - Pessinus (- Amorium)
106(B). İlyagut 2 (3)	P.1 Pilgrim's Road

Maximinus, Constantinus and Licinius **AD 311-313**

(?) 010. Ballıhisar	A.1 Ancyra - Pessinus (- Amorium)
---------------------	-----------------------------------

Constantinus and Licinius **AD 313, viii/ix-317, 28.ii**

113. Yuva (2)	P.1 Pilgrim's Road
115. Ankara, Batıkent (3)	P.1 Pilgrim's Road
132. Sarıhüyük	P.1 Pilgrim's Road

with **Crispus, Licinius and Constantinus** **AD 317, 01.iii-318**

016(A). Çapalı 1 (3)	A.9 <i>Via Sebaste</i> (Apollonia) (- Apamea)
016(B). Çapalı 2 (2)	A.9 <i>Via Sebaste</i> (Apollonia) (- Apamea)
016(C). Çapalı 3 (1)	A.9 <i>Via Sebaste</i> (Apollonia) (- Apamea)
065(A). Tol 1 (2)	F.8 Ancyra (- Caesaria per Aquas Saruvenas)
088(B). Esendere 2 (1)	H.1 <i>Via Sebaste</i>
(?) 090(A). Gençali 1 (2)	H.1 <i>Via Sebaste</i>
090(D). Gençali 4 (1)	H.1 <i>Via Sebaste</i>
(?) 090(F). Gençali 6 (2)	H.1 <i>Via Sebaste</i>

Constantinus with Crispus and Constantinus **AD 324, 19.ix-326, iii(?)**

088(B). Esendere 2 (2)	H.1 <i>Via Sebaste</i>
090(A). Gençali 1 (3)	H.1 <i>Via Sebaste</i>

Constantinus with Constantinus, Constantius and Constans **AD 333, 25.xii-335, 18.ix**

014. Ladik (1)	A.5 Col. Iconium - Laodicia (-Philomelium)
070(E). Konya 5 (2)	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium or H.1 <i>Via Sebaste</i>
074(A). Eğribayat 1 (2)	F.9 Col. Iconium (- Col. Archelais - Caesaria)

(?) 074(C). Eğribayat 3 (2)	or G.1 Ancyra - Col. Iconium F.9 Col. Iconium (- Col. Archelais - Caesaria) or G.1 Ancyra - Col. Iconium
080(A). Abditolu 1 (1)	F.10 Col. Iconium (- Sidamaria - Tyana - Caesaria)
080(B). Abditolu 2	F.10 Col. Iconium (- Sidamaria - Tyana - Caesaria)
080(C). (?)Abditolu (1)	F.10 Col. Iconium (- Sidamaria - Tyana - Caesaria)
081. Karkin	F.10 Col. Iconium (- Sidamaria - Tyana - Caesaria)
084(C). Altinekin 3 (2)	G.1 Ancyra - Col. Iconium
(?) 086. Uluborlu (2)	H.1 <i>Via Sebaste</i>
087(A)(?). Yassiören 1 (2)	H.1 <i>Via Sebaste</i>
088(C). Esendere 3 (2)	H.1 <i>Via Sebaste</i>
094(A). Dedeçam 1 (6)	H.1 <i>Via Sebaste</i>
113. Yuva (3)	P.1 Pilgrim's Road
117(F). Ankara 6 (2)	P.1 Pilgrim's Road (?)
122(E). Oğulbey 5 (2)	P.1 Pilgrim's Road
124(B). Ahiboz 2	P.1 Pilgrim's Road
128(B). Bağıçi 2 (3)	P.1 Pilgrim's Road

Constantinus with Constantius, Constantius, Constans and Dalmatius (name earsed)**AD 335, 18.ix-337, 22.v**

090(E). Gençali 5 (3)	H.1 <i>Via Sebaste</i>
090(F). Gençali 6 (3)	H.1 <i>Via Sebaste</i>

Constantinus, Constantius and Constans**AD 337, 09.ix-340, beg. April**

087(A). Yassiören 1 (2)	H.1 <i>Via Sebaste</i>
093(A). Süküllü 1	H.1 <i>Via Sebaste</i>
094(A). Dedeçam 1 (6)	H.1 <i>Via Sebaste</i>

Iulianus**AD 361, 03.xi-363, 26/27.vi**

011. Bahçesaray (2)	A.5 Col. Iconium - Laodicia (- Philomelium)
016(B). Çapalı 2 (3)	A.9 <i>Via Sebaste</i> (Apollonia) (- Apamea)
(?) 028. Yukarı Yanlar (5)	C.2 Ancyra - Gangra (- Hadrianopolis)
065(A). Tol 1 (3)	F.8 Ancyra (- Caesaria per Aquas Saruvenas)
113. Ankara, Batıkent (3)	P.1 Pilgrim's Road

Iovianus**AD 363, 27.vi-364, 17.ii**

090(B). Gençalı 2 (2)	H.1 <i>Via Sebaste</i>
-----------------------	------------------------

Valentinianus I and Valens**AD 364, 28.iii-367, 24.viii**

014. Ladik (2)	A.5 Col. Iconium - Laodicia (- Philomelium)
028. Yukarı Yanlar (6)	C.2 Ancyra - Gangra (- Hadrianopolis)
080(A). Abditolu 1 (2)	F.10 Col. Iconium (- Sidamaria - Tyana - Caesaria)
122(A). Oğulbey 1 (2)	P.1 Pilgrim's Road
125(B). Günalan 2 (2)	P.1 Pilgrim's Road

Valentinianus I, Valens and Gratianus

014. Ladik (2)
 028. Yukarı Yanlar (6)
 070(C). Konya 3 (2)

080(A). Abditolu 1 (2)
 090(E). Gençali 5 (4)

Valens, Gratianus and Valentinianus II

073(A). Kulak Murat Hanı 1 (3)
 (?) 073(B). Kulak Murat Hanı 2 (2)
 073(C). Kulak Murat Hanı 3 (2)
 (?) 073(D). Kulak Murat Hanı 4
 (?) 076(A). Kızılçakuyu 1 (2)
 076(C). Kızılçakuyu 3 (3)
 079(B). Obruk 2 (2)
 079(F). Obruk 6 (3)
 079(G). Obruk 7 (2)
 (?) 079(H). Obruk 8 (2)
 080(C). (?)Abditolu (2)

AD 367, 24.viii-375, 17.xi

A.5 Col. Iconium - Laodicia (- Philomelium)
 C.2 Ancyra - Gangra (- Hadrianopolis)
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 or G.1 Ancyra - Col. Iconium
 or H.1 *Via Sebaste*
 F.10 Col. Iconium (- Sidamaria - Tyana - Caesaria)
 H.1 *Via Sebaste*

AD 375, 17.xi-378, 09.viii

F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 or G.1 Ancyra - Col. Iconium
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 or G.1 Ancyra - Col. Iconium
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 or G.1 Ancyra - Col. Iconium
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 or G.1 Ancyra - Col. Iconium
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 or G.1 Ancyra - Col. Iconium
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 or G.1 Ancyra - Col. Iconium
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 or G.1 Ancyra - Col. Iconium
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 or G.1 Ancyra - Col. Iconium
 F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
 or G.1 Ancyra - Col. Iconium
 F.10 Col. Iconium (- Sidamaria - Tyana - Caesaria)

Gratianus, Valentinianus II and Theodosius I

016(A). Çapalı 1 (5)
 093(B). Süküllü 2

AD 379, 19.i-383, 19.i

A.9 *Via Sebaste* (Apollonia) (- Apamea)
 H.I *Via Sebaste*

4.6.2 Incomplete or partly legible Inscriptions

001. Çayyolu (1) & (2)	A.1 Ancyra - Pessinus (- Amorium)
016(A). Çapalı 1 (4)	A.9 <i>Via Sebaste</i> (Apollonia) (- Apamea)
016(C). Çapalı 3 (2)	A.9 <i>Via Sebaste</i> (Apollonia) (- Apamea)
044. Zincir	F.3 Ancyra - Tavium (- Zela)
053(B). Yekbaş 2	F.3 Ancyra - Tavium (- Zela)
058 (B). Eskiyyapar 2 (1)	F.3 Ancyra - Tavium (- Zela)
061. Çoprasık	F.3 Ancyra - Tavium (- Zela)
066. Köseli	F.8 Ancyra (- Caesaria)
070(F). Konya 6	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium or H.1 <i>Via Sebaste</i>
073(B). Kulak Murat Hanı 2	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium
073(E). Kulak Murat Hanı 5	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium
074(A). Eğribyat 1 (3)	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium
074(A). Eğribyat 4 (3)	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium
079(C). Obruk 3 (1)	F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
079(H). Obruk 8 (1) & (2)	F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
084(B). Altinekin 2	G.1 Ancyra - Col. Iconium
084(D). Altinekin 4 (1)	G.1 Ancyra - Col. Iconium
087(B). Yassióren 2	H.1 <i>Via Sebaste</i>
088(C). Esendere 3 (1)	H.1 <i>Via Sebaste</i>
090(D). Gençali 4 (2)	H.1 <i>Via Sebaste</i>
090(E). Gençali 5 (1), (5)	H.1 <i>Via Sebaste</i>
090(A). Aş. Kaşıkara 1	H.1 <i>Via Sebaste</i>
091(B). Aş. Kaşıkara 2	H.1 <i>Via Sebaste</i>
092. Kumdanlı	H.1 <i>Via Sebaste</i>
094(A). Dedeçam 1 (4)	H.1 <i>Via Sebaste</i>
095(B). Kıyakdede 2	H.1 <i>Via Sebaste</i>
101(C). Hatunsaray 3 (1)	H.1 <i>Via Sebaste</i>
102(B). Kavak 2 (3)-(4)	J.3 Col. Lystra (- [?] Dalisandus - Laranda) or H.1 <i>Via Sebaste</i>
105. Bayram (2)	P.1 Pilgrim's Road
106(A). İlyagut 1 (2)	P.1 Pilgrim's Road
106(B). İlyagut 2 (4)	P.1 Pilgrim's Road
106(C). İlyagut 3 (1)-(3)	P.1 Pilgrim's Road
110. Erkeksu Çiftlik (1)	P.1 Pilgrim's Road
117(D). Ankara 4	P.1 Pilgrim's Road (?)
120. Emircöl	P.1 Pilgrim's Road
121(A). Örencik 1	P.1 Pilgrim's Road
122(C). Oğulbey 3 (1)	P.1 Pilgrim's Road
128(B). Bağıçı 2 (1)	P.1 Pilgrim's Road
131(F). Afşar 6	P.1 Pilgrim's Road
131(G). Afşar 7 (2)	P.1 Pilgrim's Road

4.6.3 Illegible, incomplete, non-restorable

002. Alacaatlı (1)	A.1 Ancyra - Pessinus (- Amorium)
006. Malı (1)	A.1 Ancyra - Pessinus (- Amorium)
011. Bahçesaray (1)	A.5 Col. Iconium - Laodicia Combusta (- Philomel.)
015. Bakırpinar (1)	A.5 Col. Iconium - Laodicia Combusta (- Philomel.)
016(A). Çapalı 1 (2)	A.9 <i>Via Sebaste</i> (Apollonia) (- Apamea)
016(B). Çapalı 2 (1)	A.9 <i>Via Sebaste</i> (Apollonia) (- Apamea)
017(A). Balıkhisar	C.2 Ancyra - Gangra (- Hadrianopolis)
019. Taşpinar (1)	C.2 Ancyra - Gangra (- Hadrianopolis)
021. Ömercik	C.2 Ancyra - Gangra (- Hadrianopolis)
023(A). Akkuzulu 2	C.2 Ancyra - Gangra (- Hadrianopolis)
024. Koyunbaba	C.2 Ancyra - Gangra (- Hadrianopolis)
026. Kınık	C.2 Ancyra - Gangra (- Hadrianopolis)
028. Yu. Yanlar (1) and (3)	C.2 Ancyra - Gangra (- Hadrianopolis)
049(B). Haydarbeyli 2 (1)	F.3 Ancyra - Tavium (- Zela)
050(B). Dambasan 2 (1)	F.3 Ancyra - Tavium (- Zela)
052(B). Yazır 2 (1)	F.3 Ancyra - Tavium (- Zela)
053(A). Yekbaş 1 (1)	F.3 Ancyra - Tavium (- Zela)
056. Ekmekci (1)	F.3 Ancyra - Tavium (- Zela)
059(A). Alaca 1	F.3 Ancyra - Tavium (- Zela)
060. Akören	F.3 Ancyra - Tavium (- Zela)
062. Bolatçık (1)	F.3 Ancyra - Tavium (- Zela)
063(B). Küçük Nefes 2	F.6 Tavium (- Melitene)/F.7 Tavium (- Caesaria)
065(A). Tol 1 (1)	F.8 Ancyra (- Caesaria)
065(B). Tol 2 (1)	F.8 Ancyra (- Caesaria)
071. Konya, Dikilitaş	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium
073(A). Kulak Murat Hanı 1 (1)	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium
073(C). Kulak Murat Hanı 3 (1)	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium
073(D). Kulak Murat Hanı 4	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium
074(D). Eğribyat 4 (1)	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium
074(E). Eğribyat 5	F.9 Col. Iconium (- Col. Archelaïs - Caesaria) or G.1 Ancyra - Col. Iconium
076(B). Kızılçakuyu 2	F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
076(C). Kızılçakuyu 3 (1)	F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
079(F). Obruk 6 (1)	F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
084(C). Altınekin 3 (1)	G.1 Ancyra - Col. Iconium
088(E). Esendere 5 (1)	H.1 <i>Via Sebaste</i>
090(E). Gençali 5 (2)	H.1 <i>Via Sebaste</i>
090(G). Gençali 7 (1)	H.1 <i>Via Sebaste</i>
090(H). Gençali 8 (1)	H.1 <i>Via Sebaste</i>
094(A). Dedeçam 1 (5)	H.1 <i>Via Sebaste</i>
095(A). Kıyakdede 1	H.1 <i>Via Sebaste</i>
095(C). Kıyakdede 3	H.1 <i>Via Sebaste</i>
096. Kireli	H.1 <i>Via Sebaste</i>

097(C). Selki 3	H.1 <i>Via Sebaste</i>
100(A-B). Bayat 1-2	H.1 <i>Via Sebaste</i>
101(A). Hatunsaray 1 (1)	J.3 Col. Lystra (- [?] -Dalisandus - Laranda)
101(B). Hatunsaray 2 (1)	J.3 Col. Lystra (- [?] -Dalisandus - Laranda) or H.1 <i>Via Sebaste</i>
102(B). Kavak 2 (1)	C.10 Col. Lystra (- Laranda - Sidamaria) or H.1 <i>Via Sebaste</i>
102(C-D). Kavak 3, 4	C.10 Col. Lystra (- Laranda - Sidamaria) or H.1 <i>Via Sebaste</i>
107(A). Çoğlu 1	P.1 Pilgrim's Road
108. Tatlar (2)	P.1.Pilgrim's Road
109(A), (B). Susuz 1, 2	P.1 Pilgrim's Road
117(F). Ankara 6 (1)	P.1 Pilgrim's Road (?)
117(K). Ankara 11 (1)	P.1 Pilgrim's Road (?)
119(B). Ankara, Ahlatlıbel 2 (1)	P.1 Pilgrim's Road
121(B). Örencik 2 (1)	P.1 Pilgrim's Road
121(C). Örencik 3	P.1 Pilgrim's Road
123. Beynam Çiftlik	P.1 Pilgrim's Road
127(C). Abazlı 3	P.1 Pilgrim's Road
128(B). Bağıçı 2 (2)	P.1 Pilgrim's Road
128(D). Bağıçı 4	P.1 Pilgrim's Road
130. Bezirhane	P.1 Pilgrim's Road
131(D), (E). Afşar 4, 5	P.1 Pilgrim's Road

4.6.4 Ancient Geography

Ancyra

- | | |
|--------------------------|--|
| 038(A). Hasanoğlan 1 (2) | F.2 Ancyra - (Amasia)
or F.3 Ancyra - Tavium (- Zela) |
| 038(B). Hasanoğlan 2 | F.2 Ancyra - (Amasia)
or F.3 Ancyra - Tavium (- Zela) |
| 125(A). Günalan 1 | P.1 Pilgrim's Road |
| 126(B). Karaali 2 | P.1 Pilgrim's Road |

Apollo(nia)

- | | |
|-----------------------|------------------------|
| 090(D). Gençali 4 (1) | H.1 <i>Via Sebaste</i> |
|-----------------------|------------------------|

Civita(s) Pess(inuntium)

- | | |
|---------------|-----------------------------------|
| 009. Ertuğrul | A.1 Ancyra - Pessinus (- Amorium) |
|---------------|-----------------------------------|

(Colonia) Antiochia

- | | |
|-----------------------|------------------------|
| 094(A). Dedeçam 1 (6) | H.1 <i>Via Sebaste</i> |
|-----------------------|------------------------|

Col(onia) Lustrenium

- | | |
|---------------------|---|
| 102(B). Kavak 2 (2) | J.3 Col. Lystra (- [?] Dalisandus - Laranda)
or H.1 <i>Via Sebaste</i> |
|---------------------|---|

4.6.5 Roman Officials

Asinnius Lepidus

(Severus Alexander) AD 222 (early)

- | | |
|-------------------|------------------------------|
| 062. Bolatcık (2) | F.3 Ancyra - Tavium (- Zela) |
|-------------------|------------------------------|

Atticius Norbanus Strabo, T. (see Map 4)

(Sept. Severus) AD 197/198

- | | |
|--------------------------------|--|
| 016(A). Çapalı 1 (1) | A.9 <i>Via Sebaste</i> (Apollonia) (- Apamea) |
| 045(B). Büyük Nefes 2 | F.3 Ancyra - Tavium (- Zela) |
| 049(B). Haydarbeyli 2 (2) | F.3 Ancyra - Tavium (- Zela) |
| 050(B). Dambasan 2 (2) | F.3 Ancyra - Tavium (- Zela) |
| 051(A). Karakeçili 1 | F.3 Ancyra - Tavium (- Zela) |
| 052(A). Yazır 1 | F.3 Ancyra - Tavium (- Zela) |
| 053(A). Yekbaş 1 (2) | F.3 Ancyra - Tavium (- Zela) |
| 055. Gökçam | F.3 Ancyra - Tavium (- Zela) |
| 063(A). Küçük Nefes 1 | F.6 Tavium (- Melitene)/F.7 Tavium (-Caesaria) |
| 073(A). Kulak Murat Hanı 1 (2) | F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
or G.1 Ancyra - Col. Iconium |
| 077. Akbaş Yayla | F.9 Col. Iconium (- Col. Archelaïs - Caesaria) |
| 078. Divanlar | F.9 Col. Iconium (- Col. Archelaïs - Caesaria) |

082(A). Ennek 1	F.11 Savatra - Cana (- Sidamaria)
084(A). Altınekin 1	G.1 Ancyra - Col. Iconium
090(B). Gençali 2 (1)	H.1 <i>Via Sebaste</i>
090(F). Gençali 6 (1)	H.1 <i>Via Sebaste</i>

Aurelius Basileus (Severus Alexander) AD 221-222 (early)

058(A). Eskiypar 1 F.3 Ancyra - Tavium (- Zela)

Aurelius Priscianus (Tetrarchy) AD 293-305

028. Yukarı Yanlar (4) C.2 Ancyra - Gangra (- Hadrianopolis)

Caecilius Urbicus Aemilianus, P. (Sept. Severus) AD 208/209

115. Ankara, Batıkent (1) P.1 Pilgrim's Road
117(M). Ankara 13 P.1 Pilgrim's Road (?)

Caesennius Gallus, A. (see Map 1) (Titus) AD 81

008. Mülk A.1 Ancyra - Pessinus (- Amorium)
103. Apa J.3 Col. Lystra (- [?] Dalisandus - Laranda)

(Domitianus) AD 81

007. Bacı A.1 Ancyra - Pessinus (- Amorium)

(Domitianus) AD 82

067. Abazlı 1 F.8 Ancyra (- Caesaria)
117(B). Ankara 2 P.1 Pilgrim's Road (?)
117(G). Ankara 7 P.1 Pilgrim's Road (?)
122(A). Oğulbey 1 (1) P.1 Pilgrim's Road
128(C). Bağıçı 3 P.1 Pilgrim's Road

(Titus or Domitianus) AD 81 or 82

038(A). Hasanoğlan 1 (1) F.2 Ancyra (- Amasia)
or F.3 Ancyra - Tavium (- Zela)

Cornutus Aquila (Augustus) 6 BC

088(D). Esendere 4 H.1 *Via Sebaste*
090(C). Gençali 3 H.1 *Via Sebaste*
094(B). Dedeçam 2 (1) H.1 *Via Sebaste*
095(D). Kıyakdede 4 H.1 *Via Sebaste*
095(E). Kıyakdede 5 (1) H.1 *Via Sebaste*
097(A). Selki 1 H.1 *Via Sebaste*
097(B). Selki 2 H.1 *Via Sebaste*

098. Yunuslar

H.1 *Via Sebaste***Egnatius Victor Lollianus, L.**

(Elagabalus) AD 218

083. Ağsaklı

F.11 Savatra - Cana (- Sidamaria)

117(I). Ankara 9

P.1 Pilgrim's Road (?)

Larcius Macedo, A.

(see Map 3)

(Hadrianus) AD 118/119 (TR·P·III·COS·III)

045(C). Bü. Nefes 3

F.6 Tavium (- Melitene)/F.7 Tavium (-Caesaria)

064. Musabeyli

F.6 Tavium (- Melitene)/F.7 Tavium (-Caesaria)

(Hadrianus) AD 119/120 (TR·P·III·COS·III)

025. Şemseddin

C.2 Ancyra - Gangra (- Hadrianopolis)

030. Kalabağ

C.2 Ancyra - Gangra (- Hadrianopolis)

075. Muşki Yayla

F.9 Col. Iconium (- Col. Archelaüs - Caesaria)

or G.1 Ancyra - Col. Iconium

(Hadrianus) AD 121/122 (TR·P·VI·COS·III)

002. Alacaatlı

A.1 Ancyra - Pessinus (- Amorium)

005. Balıkuyumcu

A.1 Ancyra - Pessinus (- Amorium)

006. Malı (rest.)

A.1 Ancyra - Pessinus (- Amorium)

017(A). Balıkhisar 1 (2)

C.2 Ancyra - Gangra (- Hadrianopolis)

022. Akkuzulu 1

C.2 Ancyra - Gangra (- Hadrianopolis)

028. Yukarı Yanlar (2)

C.2 Ancyra - Gangra (- Hadrianopolis)

029(A). Akyurt 1 (rest.)

D.1 Ancyra (- Amisus)

033(B). Kalecik 2

D.1 Ancyra (- Amisus)

038(C). Hasanoğlan 3

F.2 Ancyra (- Amasia)

or F.3 Ancyra - Tavium (- Zela)

038(D). Hasanoğlan 4

F.2 Ancyra (- Amasia)

or F.3 Ancyra - Tavium (- Zela)

039(A). Elmadağ 1

F.2 Ancyra (- Amasia)

or F.3 Ancyra - Tavium (- Zela)

039(B). Elmadağ 2

F.2 Ancyra (- Amasia)

or F.3 Ancyra - Tavium (- Zela)

039(C). Elmadağ 3

F.2 Ancyra (- Amasia)

or F.3 Ancyra - Tavium (- Zela)

050(A). Dambasan 1 (rest.)

F.2 Ancyra (- Amasia)

065(B). Tol 2 (2)

F.8 Ancyra (- Caesaria)

107(B). Çoğlu 2

P.1 Pilgrim's Road

111(A). Eryaman 1

P.1 Pilgrim's Road

114. Macun

P.1 Pilgrim's Road

116. Ankara, Akköprü

P.1 Pilgrim's Road

117(C). Ankara 3

P.1 Pilgrim's Road (?)

117(J). Ankara 10

P.1 Pilgrim's Road (?)

117(K). Ankara 11 (2)	P.1 Pilgrim's Road (?)
117(L). Ankara 12	P.1 Pilgrim's Road (?)
122(B). Oğulbey 2	P.1 Pilgrim's Road
127(B). Abazlı 2	P.1 Pilgrim's Road
128(A). Bağıçi 1	P.1 Pilgrim's Road

Licinnius Serenianus (Maximinus) AD 235-236

057. Çomar	F.3 Ancyra - Tavium (- Zela)
------------	------------------------------

Pomponius Bassus, T.
(see Map 2)

(Nerva) AD 96, 18.ix-31.xii (TR·P·COS·II)

cp. RRMAM 3.3 Cappadocia. 066. Sakaltutan (2)

(Nerva) AD 97, 01.i-17.ix (TR·P·COS·III)

034. İskilip	D.1 Ancyra (- Amisus)
040. Sungurlu	F.2 Ancyra (- Amasia)
042. Demirşeyh	F.2 Ancyra (- Amasia)
051(C). Karakeçili 3	F.2 Ancyra (- Amasia)
054(B). Kaymaz 2	F.2 Ancyra (- Amasia)
056. Ekmekçi (2)	F.2 Ancyra (- Amasia)
059(B). Alaca 2	F.2 Ancyra (- Amasia)
069(A). Çağırkan 1	F.8 Ancyra (- Caesaria)
079(C). Obruk 3 (2)	F.9 Col. Iconium (- Col. Archelaïs - Caesaria)
099. Değirmen	H.1 <i>Via Sebaste</i>

(Nerva) AD 97, 18.ix-09.xii (TR·P·II·COS·III)

45(A). Bü. Nefes 1	F.3 Ancyra - Tavium (- Zela)
47. Eski Karaağıl	F.3 Ancyra - Tavium (- Zela)

(Nerva) (?) YEAR

049(A). Haydarbeyli 1	F.3 Ancyra - Tavium (- Zela)
-----------------------	------------------------------

(Nervan, then Traianic)

060. Akören (rest.)	F.3 Ancyra - Tavium (- Zela)
---------------------	------------------------------

(Traianus) AD 98 (TR·P·COS·II)

17(B). Balıkhisar 2	C.2 Ancyra - Gangra (- Hadrianopolis)
17(C). Balıkhisar 3	C.2 Ancyra - Gangra (- Hadrianopolis)
19. Taşpınar (2)	C.2 Ancyra - Gangra (- Hadrianopolis)
20. Cüçük	C.2 Ancyra - Gangra (- Hadrianopolis)
23(B). Akkuzulu 3	C.2 Ancyra - Gangra (- Hadrianopolis)

32(A). Çiftlik 1	C.2 Ancyra - Gangra (- Hadrianopolis)
32(B). Çiftlik 2	C.2 Ancyra - Gangra (- Hadrianopolis)
33(A). Kalecik 1	C.2 Ancyra - Gangra (- Hadrianopolis)
35. Ankara, Siteler	F.2 Ancyra (- Amasia) or F.3 Ancyra - Tavium (- Zela)
38(A). Hasanoğlan 1 (2)	F.2 Ancyra (- Amasia) or F.3 Ancyra - Tavium (- Zela)
38(B). Hasanoğlan 2	F.2 Ancyra (- Amasia) or F.3 Ancyra - Tavium (- Zela)

(Traianus) AD 100 (TR·P·IV·COS·III)

cp. RRMAM 3.3 Cappadocia. 003.Yavaşhan

(? Traianus) AD 98

031. Elecik	D.1 Ancyra (- Amisus)
-------------	-----------------------

EUMAAM, M. (Trebonianus Gallus) AD 251-253

058(B). Eskiyapar 2 (2)	F.3 Ancyra - Tavium (- Zela)
-------------------------	------------------------------

[-]ian[us] (Sept. Severus) AD 198-209

101(D). Hatunsaray 4 J.3 Col. Lystra (- [?] Dalisandus - Laranda)

5. ILLUSTRATIONS: MAPS

5.1 Conspectus Maps	16
5.1.1 Galatia West	
5.1.2 Galatia East	
5.2 Distribution Maps: Milestones and Governors	254
1. A. Caesennius Gallus	
2. T. Pomponius Bassus	
3. A. Larcius Macedo	
4. T. Atticius Norbanus Strabo	

5.2.1 Distribution Map of Milestones: A. Caesennius Gallus**AD 80-81**

- | | |
|---------------------|---|
| 1. 007. Bacı | A.1 Ancyra - Pessinus (- Amorium) |
| 2. 008. Mülk | A.1 Ancyra - Pessinus (- Amorium) |
| 3. 103. Apa | J.3 Col. Lystra (- [?]Dalisandus - Laranda)
or J.2 Col. Lystra (- Isaura Nova) |
| 4. - Sakaltutan (1) | RRMAM 3.3 Cappadocia. 066 |


AD 82

- | | |
|-------------------------|---|
| 5. 117(B). Ankara 2 | P.1 Pilgrim's Road (?) |
| 6. 117(G). Ankara 7 | P.1 Pilgrim's Road (?) |
| 7. 122(A). Oğulbey 1(1) | P.1 Pilgrim's Road |
| 8. 128(C). Bağıçi 3 | P.1 Pilgrim's Road |
| 9. 067. Abazlı 1 | F.8 Ancyra (- Caesaria per Aquas Saruvenas) |
| 10. - Sinop 1 | RRMAM 3.4 (Pontus et Bithynia) |

AD 81 or 82

- | | |
|-----------------------------|-----------------------|
| 11. 038(A). Hasanoğlan 1(1) | F.2 Ancyra (- Amasia) |
|-----------------------------|-----------------------|

5.2 Distribution Maps: Milestones and Governors



5.2.1 Distribution Map of Milestones: A. Caesennius Gallus

5.2.2 Distribution Map of Milestones: T. Pomponius Bassus

AD 96

1. - Sakaltutan (2) RRMAM 3.3 Cappadocia. 066

AD 97, 01.i - 17.ix

- | | | |
|-----|---------------------|--|
| 2. | 34. İskilip | D.1 Ancyra (per territorium Amasiae)(- Amisus) |
| 3. | 40. Sungurlu | F.2 Ancyra (- Amasia) |
| 4. | 42. Demirşeyh | F.2 Ancyra (- Amasia) |
| 5. | 51(C). Karakeçili 3 | F.3 Ancyra -Tavium (- Zela - Neocaesaria) |
| 6. | 54(B). Kaymaz 2 | F.3 Ancyra -Tavium (- Zela - Neocaesaria) |
| 7. | 56. Ekmekçi (2) | F.3 Ancyra -Tavium (- Zela - Neocaesaria) |
| 8. | 59(B). Alaca 2 | F.3 Ancyra -Tavium (- Zela - Neocaesaria) |
| 9. | 69(A). Çağırkan 1 | F.8 Ancyra (- Caesaria per Aquas Saruvenas) |
| 10. | 79(C). Obruk 3 (2) | F.9 Col. Iconium (- Col. Archelaïs - Caesaria) |
| 11. | 99. Değirmen | H.1 <i>Via Sebaste</i> |
| 12. | - Amasya | RRMAM 3.3 Cappadocia. 019 |

AD 97, 18.ix - 09.xii

- | | | |
|-----|--------------------|--|
| 13. | 45(A). Bü. Nefes 1 | F.3 Ancyra - Tavium (- Zela - Neocaesaria) |
| 14. | 47. Eski Karaağıl | F.3 Ancyra - Tavium (- Zela - Neocaesaria) |

Nervan, (?) year

- | | | |
|-----|----------------------|--|
| 15. | 49(A). Haydarbeyli 1 | F.3 Ancyra - Tavium (- Zela - Neocaesaria) |
| 16. | 60. Akören (rest.) | F.3 Ancyra - Tavium (- Zela - Neocaesaria) |
| 17. | - Tokat 6 | RRMAM 3.3 Cappadocia. 054(F) |
| 18. | - Uluköy 2 | RRMAM 3.3 Cappadocia. 149(B) |

AD 98

- | | | |
|-----|-------------------------|---|
| 19. | 17(B). Balıkhisar 2 | C.2 Ancyra - Gangra (- Hadrianopolis) |
| 20. | 17(C). Balıkhisar 3 | C.2 Ancyra - Gangra (- Hadrianopolis) |
| 21. | 19. Taşpınar (2) | C.2 Ancyra - Gangra (- Hadrianopolis) |
| 22. | 20. Cüçük | C.2 Ancyra - Gangra (- Hadrianopolis) |
| 23. | 23(B). Akkuzulu 3 | C.2 Ancyra - Gangra (- Hadrianopolis) |
| 24. | 32(A). Çiftlik 1 | D.1 Ancyra (per territorium Amasiae) (- Amisus) |
| 25. | 32(B). Çiftlik 2 | D.1 Ancyra (per territorium Amasiae) (- Amisus) |
| 26. | 33(A). Kalecik 1 | D.1 Ancyra (per territorium Amasiae) (- Amisus) |
| 27. | 35. Ankara, Siteler | F.2 Ancyra (per territorium Amasiae) (- Amasia) |
| 28. | 38(A). Hasanoğlan 1 (2) | F.2 Ancyra (- Amasia) |
| 29. | 38(B). Hasanoğlan 2 | F.2 Ancyra (- Amasia) |

AD 100

- | | | |
|-----|------------|---------------------------|
| 30. | - Yavaşhan | RRMAM 3.3 Cappadocia. 003 |
|-----|------------|---------------------------|


(?) AD 98

- | | | |
|-----|-------------------|---|
| 31. | 31. Elecik | D.1 Ancyra (per territorium Amasiae) (- Amisus) |
| 32. | - Çaltılı | RRMAM 3.3 (Cappadocia) |
| 33. | - Elvançelebi (1) | RRMAM 3.3 (Cappadocia) |
| 34. | - Abdalata, Tekke | RRMAM 3.3 (Cappadocia) |
| 35. | - Çeşmeören | RRMAM 3.3 (Cappadocia) |

(?) Date

- | | | |
|-----|-------------------|------------------------|
| 36. | - Yalak 3 (rest.) | RRMAM 3.3 (Cappadocia) |
|-----|-------------------|------------------------|

5.2 Distribution Maps: Milestones and Governors



5.2.2 Distribution Map of Milestones: T. Pomponius Bassus

5.2.3 Distribution Map of Milestones: A. Larcius Macedo

AD 118/119

- | | |
|-----------------------|---|
| 1. 45(C). Bü. Nefes 3 | F.7 Tavium per Therma (- Caesaria)
or F.4 Tavium (- Sebastopolis - Sebastia)
or F.5 Tavium (- Sebastia)
or F.6 Tavium (- Melitene) |
| 2. 64. Musabeyli | F.7 Tavium per Therma (- Caesaria)
or F.4 Tavium (- Sebastopolis - Sebastia)
or F.5 Tavium (- Sebastia)
or F.6 Tavium (- Melitene) |


AD 119/120

- | | |
|--------------------|--|
| 3. 25. Şemseddin | C.2 Ancyra - Gangra (- Hadrianopolis) |
| 4. 30. Kalabağ | C.2 Ancyra - Gangra (- Hadrianopolis) |
| 5. 75. Muşki Yayla | F.9 Col. Iconium (- Col. Archelaüs - Caesaria) |

AD 121/122

- | | |
|-------------------------------|--|
| 6. 02. Alacaatlı | A.1 Ancyra - Pessinus (- Amorium) |
| 7. 05. Balıkuyumcu | A.1 Ancyra - Pessinus (- Amorium) |
| 8. 06. Malı (rest.) | A.1 Ancyra - Pessinus (- Amorium) |
| 9. 17(A). Balıkhisar 1 (2) | C.2 Ancyra - Gangra (- Hadrianopolis) |
| 10. 22. Akkuzulu 1 | C.2 Ancyra - Gangra (- Hadrianopolis) |
| 11. 28. Yukarı Yanlar (2) | C.2 Ancyra - Gangra (- Hadrianopolis) |
| 12. 29(A). Akyurt 1 (rest.) | D.1 Ancyra (- Amisus) |
| 13. 33(B). Kalecik 2 | D.1 Ancyra (- Amisus) |
| 14. 38(C). Hasanoğlan 3 | F.2 Ancyra (- Amasia) |
| 15. 38(D). Hasanoğlan 4 | F.2 Ancyra (- Amasia) |
| 16. 39(A). Elmadağ 1 | F.2 Ancyra (- Amasia) |
| 17. 39(B). Elmadağ 2 | F.2 Ancyra (- Amasia) |
| 18. 39(C). Elmadağ 3 | F.2 Ancyra (- Amasia) |
| 19. 50(A). Dambasan 1 (rest.) | F.3 Ancyra - Tavium (- Zela - Neocaesaria) |
| 20. 65(B). Tol 2 (2) | F.8 Ancyra (- Caesaria) |
| 21. 107(B). Çoğlu 2 | P.1 Pilgrim's Road |
| 22. 111(A). Eryaman 1 | P.1 Pilgrim's Road |
| 23. 114. Macun | P.1 Pilgrim's Road |
| 24. 116. Ankara, Akköprü | P.1 Pilgrim's Road |
| 25. 117(C). Ankara 3 | P.1 Pilgrim's Road (?) |
| 26. 117(J). Ankara 10 | P.1 Pilgrim's Road (?) |
| 27. 117(K). Ankara 11 (2) | P.1 Pilgrim's Road (?) |
| 28. 117(L). Ankara 12 | P.1 Pilgrim's Road (?) |
| 29. 122(B). Oğulbey 2 | P.1 Pilgrim's Road |
| 30. 127(A). Abazlı 2 | P.1 Pilgrim's Road |
| 31. 128(A). Bağıçı 1 | P.1 Pilgrim's Road |

5.2 Distribution Maps: Milestones and Governors




5.2.3 Distribution Map of Milestones: A. Larcius Macedo

5.2.4 Distribution Map of Milestones: T. Atticius Norbanus Strabo**AD 198**

- | | | |
|-----|-------------------------------|--|
| 1. | 16(A). Çapalı 1(1) | A.8 <i>Via Sebaste</i> (Apollonia) (- Apamea) |
| 2. | 45(B). Büyük Nefes 2 | F.3 Ancyra - Tavium (- Zela - Neocaesaria) |
| 3. | 49(B). Haydarbeyli 2 (2) | F.3 Ancyra - Tavium (- Zela - Neocaesaria) |
| 4. | 50(B). Dambasan 2 (2) | F.3 Ancyra - Tavium (- Zela - Neocaesaria) |
| 5. | 51(A). Karakeçili 1 | F.3 Ancyra - Tavium (- Zela - Neocaesaria) |
| 6. | 52(A). Yazır 1 | F.3 Ancyra - Tavium (- Zela - Neocaesaria) |
| 7. | 53(A). Yekbaş 1 (2) | F.3 Ancyra - Tavium (- Zela - Neocaesaria) |
| 8. | 55. Gökçam | F.3 Ancyra - Tavium (- Zela - Neocaesaria) |
| 9. | 63(A). Küçük Nefes 1 | F.6 Tavium (- Melitene) or F.7 Tavium (- Caesaria) |
| 10. | 73(A). Kulak Murat Hanı 1 (2) | F.9 Col. Iconium (- Col. Archelaïs - Caesaria) |
| 11. | 77. Akbaş Yayla | F.9 Col. Iconium (- Col. Archelaïs - Caesaria) |
| 12. | 78. Divanlar | F.9 Col. Iconium (- Col. Archelaïs - Caesaria) |
| 13. | 82(A). Ennek 1 | F.11 Savatra - Cana (- Sidamaria) |
| 14. | 84(A). Altınkekin 1 | G.1 Ancyra - Col. Iconium |
| 15. | 90(B). Gençali 2 (1) | H.1 <i>Via Sebaste</i> |
| 16. | 90(F). Gençali 6 (1) | H.1 <i>Via Sebaste</i> |

5.2 Distribution Maps: Milestones and Governors



5.2.4 Distribution Map of Milestones: T. Atticius Norbanus Strabo

6. ILLUSTRATIONS: FIGURES

6.1 Facsimiles of Published Texts

1. 08. Mulk Hamilton 1842, 2, 428 no. 139
Titus with Domitianus AD 81
2. 11. Bahçesaray MAMA 7. 9
Iulianus
3. 13. Sarayönü BIAA Archive
Diocletianus
4. 16(A). Çapalı 1 (3) Christol and Drew Bear 1987, 20
(3) Constantinus I and Licinius I with 3 sons
5. 16(A). Çapalı 1 (4)-(5) Christol and Drew Bear 1987, 21 Fig. 3
(4) ?
(5) Gratianus, Valentinianus II and Theodosius I
6. 25. Şemseddin CIL 3. 14184⁵⁸
Hadrianus AD 119/120
7. 29(A). Akyurt 1 von Flottwell 1895, 42 and Fig.
Hadrianus (?)AD 121/122
8. 31. Elecik CIL 3. 14184⁵⁶
(?) Traianus
9. 32(A). Çiftlik 1 CIL 3. 14184⁵⁷
Traianus AD 98
10. 33(B). Kalecik 2 Hamilton 1842, 2, 416 no. 99
Hadrianus AD 121/122
11. 37. Ortaköy Sterrett 1883-84, 321 no. 378
Severus Alexander AD 223
12. 45(A). Bü. Nefes 1 Sterrett 1883-84, 309 no. 306
Nerva AD 97
13. 50(A). Dambasan 1 (rest.) Sterrett 1883-84, 320 no. 377
Hadrianus (?)AD 121/122
14. 70(D). Konya 4 MHB(alliance) Notes from Calder's 1908 notebook
Hadrianus (?)AD 128/129
15. 73(A). Kulak Murat Hanı 1 Ramsay (A.M.) 1909, 22 no. 6 and Fig. 6
(3) [Valens, Gratianus] and Valentinianus II
16. 73(C). Kulak Murat Hanı 3 Ramsay (A.M.) 1909, 21 no. 5
(2) Valens, Gratianus and Valentinianus II
17. 73(A). Kulak Murat Hanı 1 Ramsay (A.M.) 1909, 22 no. 6 and Fig. 7
(2) Sept. Severus and Caracalla with Geta
18. 74(A). Eğribayat 1 MHB(alliance) Notes from Calder's 1908 notebook
(1) Sept. Severus and Caracalla with Geta
(2) Constantinus with 3 sons
19. 74(B). Eğribayat 2 ibid.
Valerianus and Gallienus with Saloninus
20. 75. Muşki Yayla ibid.
Hadrianus AD 119/120
21. 77. Akbaş Yayla ibid.
Sept. Severus and Caracalla with Geta
22. 79(D). Obruk 4 ibid.
Nerva

6.1 Facsimiles of Published Texts

MPICA . . . APDIVIVES
 PASIANI . FAVGPONTMAX
 TRIBPOTESTXIMPXVCOS
 VICENSORPP . . . XX
 CAES
 COSVIIPRINCIVVENT_{TIS}
 ACAESENNIVMGALLIVM
 LEGPROPRVIASPROVNCI
 ARV. G . . . TIAECAPPAD.
 CIAEPONTIPISIDIAEPA
 PHLAGONIAELYCAONIAE
 ARMENIAEMINORIS
 STRAVERVNT
 LXXI

6.1.1 08. Mülk
Hamilton 1842, 2, 428 no. 139

Serai (R 1906; R.C. 1910)

Imp. C[æ]sari
 Gaio V[al]terio
 D[icitu]r c[on]fletiāno
 Pro Felici in-
 victo Augusto
 M. [P].

6.1.3 13. Sarayönü BIAA Archive

F[ac]CILU[AN]O[R]IET
 VICTORSAC
 TRIUMFATORI
 ERPETCAUC
 IMCSSS
 ΜΘΙΙΙΙ

6.1.2 11. Bahçesaray MAMA 7. 9

	D N
	L VAL CONSTANTINO
	INIA O
4	PP FF IN
	VICT AVGG ET F
	VAL CRISPO ET VA
	CONSTANTINI LICINI
8	ET CL VAL CONSTANTINO
	AB
	CAESSS
	M

6.1.4 16(C). Çapalı 1
Christol and Drew Bear 1987, 21 Fig. 3


UAL
 ET
 UALEN INIĀNO E T
 PPFFQFQFOSIO
 FFF
 NUIC[IT] ANS + F

6.1.5 16(D)-(E). Çapalı 1
Christol and Drew Bear 1987, 21 Fig. 3

6.1 Facsimilies of Published Texts

IMP CAESARI
 DIVI TRAIANI PAR.
 HIC F DIVI NERVAE
 NEPOTI TRAIANO
 5 HADRIANO AVG PONT
 MAX TRI POT IV COS III
 per A LARCIUM MA
 cEDONEM LEGAVG
 PR PR M
 10 //XXXXX
 //M

6.1.6 25. Şemseddin CIL 3. 14184.58



6.1.7 29(A). Akyurt 1 von Flottwell 1895, 42 and Fig.

BASSVM LEG
 RO P//AETORE
 XXVI

6.1.8 31. Elecik CIL 3. 14184.56

IMP CAESARI
 ONIFTRAIANIPARTHI
 CIFDIVINERYAENEPOTI
 TRAIANO HADRIANO
 AVG PONT MAX TRIB POT
 COS II IPPIAARCIVM
 MACEDON MLEGAVG
 PP PR MI
 XXXV

IMP NERVA TRA
 IANVS CAESAR AVG
 GERMANICVS PON
 TIF MAX TRIB POT //
 5 P P COS II RESTITV //
 IT PER T POMPO //
 NIVM BASSVM
 LEG PRO PR //
 //XXVI

6.1.9 32(A). Çiftlik 1 CIL 3. 14184.57

IMP CAESVAI
 SEVERO
 PROPIO FEL IN
 VICTO AVG TRIB
 5 POT II COS I
 M P

6.1.11 37. Ortaköy
Sterrett 1883-84, 321 no. 378

IMP
 NERVA CAESAR AV
 PONT MAX TRIB POTES VII
 COS III IP PRESTITVIT
 PER POM PON // M
 BASSVM LEG PRO PR
 PMTA

6.1.12 45(A). Bü. Nefes 1
Sterrett 1883-84, 309 no. 306

6.1 Facsimiles of Published Texts

*Tamba Hassan. The stone is partly embedded in the ground
in the cemetery. Copied by J. H. Haynes.*

I S S I
R
I A
E N E O
O
C P O T
O

6.1.13 50(A). Dambasan 1
Sterrett 1883-84, 320 no. 377

P	
C//	VITRAIA
N//	VI
N:	OSTRA
IA	RIANVs
I%	EXMA:
C	XCMEE-
A	A.COSSE
C%	11 111
	111111
	111111
	2 iii

6.1.14 70(D). Konya 4
MHB(allance) Notes from Calder's 1908 notebook

6.1 Facsimiles of Published Texts


tribus D(ominis) N(ostris)
Fl. V]alente

et] Fl. Gratia[no
et F]l. Valen[tiniano
[perpetuis ac vic-]
[toriosissimis semper]
Au]ggg

ETFLV
QEP E UIRHIC
PI~~E~~ CI CCFN
CC

6.1.15 73(A). Kulak Murat Hanı 1
Ramsay (A.M.) 1909, 22 no. 6 and Fig. 6

6.1.16 73(C). Kulak Murat Hanı 3
Ramsay (A.M.) 1909, 21 no. 5



6.1.17 73(A). Kulak Murat Hanı 1
Ramsay (A.M.) 1909, 22 no. 6 and Fig. 7

6.1 Facsimiles of Published Texts

AVCA		IMP CAI
NICV	IC SM	P·S L·VALERIAN
AXIMV	TITI	ETR ^S LICINS
XII. PG	VII	GALLIENVM
IM		ET P CORNE
COS: I		LIVM "This N doubtful wmc"
MARCVS AVRE		VINCENNIVM
NTONINVS A		NOBILISSIMV
ONS PART		CAESAREM
AXIMVS L·S:		AVCVSTOS
TVERVNT MILPA		

6.1.18 74(A). Eğribyat 1

MHB(alliance) Notes from Calder's 1908 notebook

6.1.19 74(B). Eğribyat 2

MHB(alliance) Notes from Calder's 1908 notebook

IMPCAESAREDI
VI TRAIANI PAR
TICIP DIVINER
VAE NEPOTTI TRA
AIANO HADRIAN

III C PHILLIT MAX (ang point max)

contd.
||||! V COS III
JM
MACEDONEM
PPOPR

6.1.20 75. Muşki Yayla MHB(alliance) Notes from Calder's 1908 notebook

6.1 Facsimiles of Published Texts

EUEPIUSPATIA
 VAGARABAJMOPAR
 THICUS MXXI PONT
 IFEX MAXIMVSTRIBU
 (sic) NICIA POTESTATIS UT IMP
 IICOS PRPR PROCOS ET
 IMPCAPA\AP\URANTO
 A\IAOCCONS PARTHIC
 MAXO\STITUEBUMPER
 STRABONEMLE
 TRMILEMPASS

6.1.21 77. Akbaş Yayla
 MHB(alliance) Notes from Calder's 1908 notebook

EAN ECAESAREAVG
 AXIMOBV
 ESTAT PA
 ?) TRIB.P

6.1.22 79(D). Obruk 4
 MHB(alliance) Notes from Calder's 1908 notebook

IMP	DD
AVGT	1122
TRIB	1121
PATRIA	LVALENTE
	LGRATIA O
	ET FLVALE T

etc as in R's copy

6.1.23 79(G). Obruk 7
 MHB(alliance) Notes from Calder's 1908 notebook

V...PERAVCC
 MC
 IIII

PF,
 CIVCIVM
 ^BIAUM
 UM
 , , P.

6.1.24 79(H). Obruk 8
 MHB(alliance) Notes from Calder's 1908 notebook

6.1.25 82(A). Ennek 1
 MHB(alliance) Notes from Calder's 1908 notebook

6.1 Facsimiles of Published Texts

IM CAER
 M. IULIVS
 FILIPPVS
 PF AVG
 CTMAUL
 FILIPPVS
 CACRAA
 FILIOPERUR
CYTIC

6.1.26 82(B). Ennek 2
MHB(allance) Notes from Calder's 1908 notebook

IMP CAESAR
 DIVITRAIAN
 IPARTHICIEIL
 DIVINERVAEN
 EPOSTRAIANV
 SHADRIANVS AV
 GPIONTIEE XM
 AXIMVSTRIB V
 NICIAEPOTES
 TATIS XI COS III
 HIP

6.1.27 85. Yazibelen
Ramsay (A.M.) 1909, 26 no. 8 and Fig. 8

OP! CAESARE DIVI
 TRAIANI · F · DIVINERVAE
 NEPOTITRAIANO
 ADRIANO AVG · PONT
 TRIB · P · VII COS III

XII

6.1.28 88(A). Esendere 1
Sterrett 1884-85, 400 no. 587

[erased]
 [erased]
 [erased] TRIPFINVICTVS
 VGSETFVNERSPO
 ETUASCONSTANTINO
 LICINNIO ETI^hUAS
 CONSTANTINO NOB^b
 C LONIA

6.1.29 88(B). Esendere 2
Sterrett 1884-85, 401 no. 588

IMP C P
 VALERIANO
 FAUC
 ETIMP CAESAR
 PL GALLIENO
 PF AVG FILIO
 EIUS MP


6.1.30 89. "Sariyar" IK 67. 158

6.1 Facsimiles of Published Texts


IMP · CAES · SEPT ·
 SEVER S P
 AVG ARABICVS
 NICVSPA T
 XI VSPONT
 TRIB · POT · VIII
 P · P · PROCOSE
 CAES · M · AVR · ANTONI
 NVS AVG · COS PART
 MAXIMVS RESTITVE
 RVNT PER · PE T · ATTICIV
 MNOR · M PRAO NEM
 LEG AVG PR · R · MIL PASS

XXIX

6.1.31 90(B). Gençalı 2 Pace 1916-20, 51 no. 29



6.1.32 93(A). SÜCÜLLÜ 1 IK 67. 159



6.1.33 SÜCÜLLÜ 2 IK 67. 160

Side A, Nos. 1 and 2.

DDNN
 FL CL CONSTANTINOMAX
 IMO
 ET FL IVL CONSTANTIO ET FL
 CL CONSTANTI RIIIP
 VICTORIB / SEMPAVG
 ABANTIOCHIA
 PONTIF · MAX · TRIB ·
 POT XIII COS III
 P · P
 MP U

Side B, No. 3.

IMP C M A V R V A L
 MAXIMIANO
 FIN VICT AVG
 S O N N E P A A P
 R
 B CAESARIB

Side B, No. 4.

IMP C A S
 MARCAPO
 ET IMP CAES
 M A V R V A L
 MAXIMIANO
 P F A V G

6.1.34 94(A). Dedeçam 1
Sterrett 1883-84, 178 nos 178-181

6.1 Facsimiles of Published Texts

INV
MAX///
INVAVGETFL
CONSTANTIO
GALVAL
MAXIMIAN
SSR

6.1.35 105. Bayram
Anderson 1899, 63 no. 10

IMP CAESARIDI
VITRAIANI PARTICI
FIL DIVINERVAE NEPO
TITRAIANO HADRINO
AVG PO:/: M: / TRPOT
VI COS III PER ALARCI
VM MACDONEM LEG AVG
PR PR

M // / / / /

IV // / / / /

6.1.37 111(A). Eryaman 1
Anderson 1899, 59 no. 5

IMP CAESAR DIV VESPASIA
NI // / / / BONALFO / / / / AVG PONT
MAX / / / / VALENTINI / / / / / / / / / / / /
IX IMPERATOR / / / / / / / / / / / / / / / / / /
A CAESEN NI VM QALLVM / / / / / / / / / / / /
COS X V /
VIAS T /
CAPPADOCIAE PONTIPI SL DIAE
PAPHLAGONIAE LYCAONIAE
ARMENIAE MINO / / / / S STAYIT
MIL XV /

6.1.38 122(A). Oğulbey 1
Anderson 1899, 102 no. 97

B > F,
IMP CAES,
/ / / / / / / / / / / /
IMP CAES C
VAL DIOCLETIANO
INV AVG ET IMP CAES
M AVR VAL MAXIMIANO
P F INV AVG ET
FLA VAL CONSTANTI / / / / /
ET G VAL MAXIMIANO
NOBILISSIMIS
CAESARIBVS
25 MV

6.1.36 110. Erkeksu Çiftlik
Anderson 1899, 60 no. 8

I / / / P / C / / / / / / / / / / / / / / / /
DIVITRAIAN / / AR
TICIFDIVINERVAE
NEPOTITRAIANO
HADRIANO AVG PONT
MAXTRPOTVICOS
IIIPERALARCIVM
MACEDONEMLEG
AVGPRPR
XXV ke

6.1.39 122(B). Oğulbey 2
Anderson 1899, 103 no. 88

6.1 Facsimiles of Published Texts

BFDN
IMPCAESLDON//
AVRELIANO
PF INVICTO
AVG
///V

MAVRANTON//SAV6C@III
R E S T I T U E R V N T
M
XXXIII Δ

6.1.40 122(C). Oğulbey 3
Anderson 1899, 103 no. 89

6.1.41 126(A). Karaali 1
Anderson 1899, 104 no. 90

D //V
IMPCAESCAVRVAL
DIOCLETIANVSPFINV
AVGETIMPCAESM
erased
PFINVAVGABANCYRA
MXXXVIII

6.1.42 126(B). Karaali 2 Anderson 1899, 104 no. 91

B E
IMP CAES
MANTONIO
GORDIANO
FELICI
INVICTOAY
SOS///OCOP (?)

6.1.43 131(A). Afşar 1
Anderson 1899, 106 no. 93

IMP////LVALERIO
CONSTANTINOPFINNG TE
IMPCAESVAL *erased* NO
erased PFIN//VG
MLXV
MZE


6.1.44 132. Sarıhüyük
Anderson 1899, 106 no. 94

6.2 Drawings of Squeezes

- | | | |
|-----|----------------------|--|
| 1. | 02. Alacaatlı | Hadrianus AD 121/122 |
| 2. | 05. Balıkuyumcu | Hadrianus AD 121/122 |
| 3. | 06. Malı | (2) Hadrianus |
| 4. | 07. Bacı | Domitianus AD 81 |
| 5. | 16(A). Çapalı 1 | (1) Sept. Severus and Caracalla with Geta AD 198 |
| 6. | 16(A). Çapalı 1 | (3) Constantinus and Licinius with sons |
| 7. | 16(A). Çapalı 1 | (5) Gratianus, Valentinianus II and Theodosius I |
| 8. | 16(B). Çapalı 2 | (2) Constantinus and Licinius with sons |
| 9. | 16(B). Çapalı 2 | (3) Iulianus |
| 10. | 16(C). Çapalı 3 | (1) Constantinus and Licinius with sons |
| 11. | 17(C). Balıkhisar 3 | Traianus |
| 12. | 19. Taşpınar | (2) Traianus AD 98 |
| 13. | 23(B). Akkuzulu 3 | Traianus |
| 14. | 29(A). Akyurt 1 | Traianus |
| 15. | 32(A). Çiftlik 1 | Traianus AD 98 |
| 16. | 35. Ankara, Siteler | Traianus AD 98 |
| 17. | 38(B). Hasanoğlan 2 | Traianus AD 98 |
| 18. | 38(D). Hasanoğlan 4 | Hadrianus AD 121/122 |
| 19. | 40. Sungurlu | Nerva AD 97 |
| 20. | 41. Cevheri | Gordianus I and II AD 238 |
| 21. | 42. Demirşeyh | Nerva AD 97 |
| 22. | 43. Hacılarhanı | Trebonianus Gallus |
| 23. | 49(A). Haydarbeyli 1 | Nerva AD 97 |
| 24. | 50(A). Dambasan 1 | Hadrianus AD 121/122 |
| 25. | 50(B). Dambasan 2 | Sept. Severus and Caracalla with Geta AD 198 |
| 26. | 51(A). Karakeçili 1 | Sept. Severus and Caracalla with Geta |
| 27. | 51(B). Karakeçili 2 | Traianus Decius |
| 28. | 51(C). Karakeçili 3 | Nerva AD 97 |
| 29. | 52(A). Yazır 1 | Sept. Severus and Caracalla with Geta |
| 30. | 52(B). Yazır 2 | Elagabalus |
| 31. | 53(A). Yekbaş 1 | (2) Sept. Severus and Caracalla with Geta AD 198 |
| 32. | 53(B). Yekbaş 2 | (?) |
| 33. | 54(B). Kaymaz 2 | Nerva AD 97 |
| 34. | 57. Çomar | Maximinus with Maximus |
| 35. | 58(A). Eskiypar 1 | Severus Alexander |
| 36. | 58(B). Eskiypar 2 | Trebonianus Gallus |
| 37. | 61. Çopraşık | (?) |
| 38. | 45(C). Bü. Nefes 3 | Hadrianus AD 121/122 |
| 39. | 65(A). Tol 1 | (1) Constantinus and Licinius with sons |
| 40. | 69(A). Çağırgan 1 | (2) Iulianus |
| 41. | 69(B). Çağırgan 2 | Nerva AD 97 |
| 42. | 70(A). Konya 1 | Valerianus and Gallienus with Saloninus and
Salonina |
| 43. | 70(C). Konya 3 | Hadrianus AD 128/129 |
| 44. | 70(E). Konya 5 | (1) Antoninus Pius AD 142 |
| 45. | 70(F). Konya 6 | (1) Hadrianus
(2) Constantinus with 3 sons
(?) Hadrianus |

46. 72. Tilki Han
 47. 73(C). Kulak Murat Hanı 3
 48. 73(E). Kulak Murat Hanı 5
 49. 74(A). Eğribayat 1
 50. 74(D). Eğribayat 4
 51. 74(D). Eğribayat 4
 52. 76(B). Kızılçakuyu 2
 53. 79(A). Obruk 1
 54. 79(C). Obruk 3
 55. 79(E). Obruk 5
 56. 79(F). Obruk 6
 57. 79(G). Obruk 7
 58. 84(C). Altınkekin 3
 59. 88(C). Esendere 3
 60. 88(E). Esendere 5
 61. 90(C). Gençali 3
 62. 90(E). Gençali 5
 63. 90(F). Gençali 6
 64. 90(G). Gençali 7
 65. 90(H). Gençali 8
 66. 94(A). Dedeçam 1
 67. 94(A). Dedeçam 1
 68. 94(B). Dedeçam 2
 69. 95(D). Kiyakdede 4
 70. 97(A). Selki 1
 71. 97(B). Selki 2
 72. 98. Yunuslar
 73. 99. Değirmen
 74. 101(C). Hatunsaray 3
 75. 101(A). Hatunsaray 1
 76. 101(B). Hatunsaray 2
 77. 101(D). Hatunsaray 4
 78. 102(B). Kavak 2
 79. 102(B). Kavak 2
 80. 115. Ankara, Batıkent
 81. 117(M). Ankara 13
 82. 122 (D). Oğulbey 4
- Sept. Severus and Caracalla with Geta AD 199
 (2) Valens, Gratianus and Valentinianus II
 (?)
 (1) Sept. Severus and Caracalla with Geta AD 199
 (2) Constantinus with 3 sons
 (2) (?)Domitianus AD 89/90
 (3) (?)
 (2) Nerva AD 97
 Hadrianus AD 128/129
 (1) Nerva AD 97
 Sept. Severus and Caracalla with Geta
 (2) Nerva
 (3) Valens, Gratianus and Valentinianus II
 (1) Nerva
 (2) Valens, Gratianus and Valentinianus II
 Constantinus with 3 sons
 (2) Constantinus with 3 sons
 Carus with sons
 Augustus 6 BC
 (3) Constantinus with 3 sons
 (4) Valentinianus I, Valens and Gratianus
 (1) Sept. Severus and Caracalla with Geta
 (2) Constantinus and Licinius with sons
 (3) Constantinus with 3 sons
 (2) Philippus II
 (2) Elagabalus
 (1) Hadrianus AD 128/129
 (6) Constantinus with 3 sons
 (2) Diocletianus et coll.
 (3) Maximinus
 (6) Constantinus with 3 sons
 (1) Augustus 6 BC
 (2) Valerianus, Gallienus and Valerianus Saloninus
 Augustus 6 BC
 Augustus 6 BC
 Augustus 6 BC
 Augustus 6 BC
 Nerva AD 97
 (2) Gordianus III
 (2) Maximinus AD 235
 (2) Gordianus III
 Sept. Severus and Caracalla with Geta
 (2) Valerianus and Gallienus with Saloninus
 (3)-(4) (?)
 (1) Sept. Severus and Caracalla with Geta
 (2) Diocletianus et coll.
 (3) Constantinus and Licinius
 (4) Iulianus
 Sept. Severus and Caracalla with Geta
 Trebonianus Gallus and Veldumnianus Volusianus

6.2 Drawings of Squeezes



6.2.1 02. Alacaathı

IMP CAESARIDI
VITRAIANI PARTHICIE DI
VINERVAENE POTITRA
IANO HADRIANO AVC
PONT MAX TR POT VI
COS III PERAI ARCI
VMM MACEDONEM
LEG AVG - PR PR.
M XXIV

10 cm

6.2.2 05. Balıkuyumcu

6.2 Drawings of Squeezes

IMP AE SA RI
 D VITRAI A I I
 PARTHIC FDI
 VIN E VENE
 P C ITRAI NO
 HACR I O AVC
 P DI ITM X T PPO^T
 COSI I P
 ISS

— 10 cm —


6.2.3 06. Malı

XIN • TRI
 S. COS. VII. PER.
 NNIVM. CALLVM.
 ACA LECATVM. PRO. PR. VINS. PRO
 VINC. IR. M. GALATIAE.
 CAPPA. NE. ONTI. PISI
 DIAF CONAE. LUCA
 ONIAL. MENIAE. MINO
 RIS. STRAVIT.


— 25 cm —

6.2.4 07. Bacı

6.2 Drawings of Squeezes



6.2.5 16(A). Çapalı 1




6.2.6 16(A). Çapalı 1

6.2 Drawings of Squeezes

δδδι
 FIGRATI
 FLOALEN
 (LTPLFFQdO / 10
 ΣΑΡΡ, FF
 ΤΗΝΙΤΕΑΕΣ ΗΓΑΥ

— 25 cm —

6.2.7 16(A). Çapalı 1



EΞΤΩΝΝ
 ΚΙΣΤΑΝΤΙΝΟΕΤ

ΒΙΤΛΥΓΓΕΤΗ
 ΙΚΡΙΣΠΟΤΥΛΑΝΤΑΝΤΙΝΙ
 ΕΤΛΥΛΑΝΤΑΝΤΙΝΟ
 ΛΒΑΕΣΣ

ΔΔ
 ΙΝ
 ΕΞΤΩΝΝ
 ΦΙΛΑΥΔΙ
 ΠΡΙΛΑΝΟ
 ΠΡΟΦΕΛΙΚΙΛΙΤ
 ΜΠΑΞΕΜΠΑΥ
 Ν
 Η

— 50 cm —

6.2.8 16(B). Çapalı 2

— 50 cm —

6.2.9 16(B). Çapalı 2

6.2 Drawings of Squeezes



DDNN
FLAV(US)CONSTANTINO



6.2.10 16(C). Çapalı 3

I RAI ANI
SA V G C E
N I V S
T P I B P S T P I
R E S T I T V I T F
P O M P O N
S V M L E C P R
E T O P



6.2.11 17(C). Balıkhisar 3


IMP·NERVA
TRAIAN VS·CAE
SAR AVG CERMA
NICVS·PONT·MAX·
TRIB·POT·P.P·COS·
II RESTITVIT·PER
T·POMPONIVMBAS
SVMLEC·PRO
PRAETORE
V XXII



6.2.12 19. Taşpinar

6.2 Drawings of Squeezes

IMP N
 I RAIANV
 SARAVC F.M.
 NICVS PO
 TRIE POTP.
 RESTITV
 T·POM1PO
 BASSVM
 PRAETO



6.2.13 23(B). Akkuzulu 3

-SAR
 VPAR
 RVA
 JAN
 AV
 RI.F
 ERA
 GET
 G.P
 X



6.2.14 29(A). Akyurt 1

IMP·NERVA·TRA
 IANVS·CAESAR·AVG
 GERMANICVS·POA
 T·IFMAX·TRIB·POT
 P·PCOSII·R·STITV
 IT PER·T·POMPU
 NIVM BASSVM
 RO·PR



6.2.15 32(A). Çiftlik 1

P NERVA
 I RAIANVS·CAE
 SAR·AVG·CRMA
 NICVS·PONT·MAX
 TRIB·POT·P·PCOSI
 RESTITVIT·PER
 T·POMPO·N VNI
 BASSVM·LGI RO
 PRAETORE
 III



6.2.16 35. Ankara, Siteler

6.2 Drawings of Squeezes

AVG·GERMANICVS PONTI
 MAX·TRIB·POT·P·P CoSTT
 RESTITVIT PER PoMPO
 NIVM BASSVM LEC·PRO
 PRAETORE ABANCYRA
 XXVI KΞ

6.2.17 38(B). Hasanoğlan 2

IMP CAESAR P
 DIVITRAIPARTH I
 CIVCIVINERVAENE POTI
 TRAIANO HADRIANO —
 AVGPONTMAXTRPOTVI
 COSIII PERALARCIVM
 MACEDONEM LEC AVG
 P R - P R - H I

'NP
 CESAR AVG
 PONTMAXTRIB·POTEST
 COSIII·P·P· RESTITVIT·PER
 PoM PONIVM·BASSVM
 LEG · PRO · PR

6.2.18 38(D). Hasanoğlan 4

M · JH

6.2.19 40. Sungurlu

6.2 Drawings of Squeezes

IMP CAES MAINTONIO
 CORDIANO SEMPRONI
 ANOROMANO AFRI
 CANO SENIOR PIUFE
 LICI INUICIOAV G
 ET IMP CAES MANTO
 NIO CORDIANO SE
 MPRONIANORO
 MANOFN CANOI
 UNIORIP' OFELICII
 NUICTCAVC DOMI
 NISINDULCENTISS
 IMIS
 M P
 IE

 25 cm

6.2.20 41. Cevheri

NEVA CAES
 AVG PONTIF MAX
 TRIB POTES
 CO III P P RES
 TITVITPER
 OM PONIVM
 ISSVM LEG
 PRO PR

M

 25 cm

6.2.21 42. Demirşeyh

IMP CAE SVIBIC T
 EBONI O CALLO
 NUICTO AVG TRI
 BPOTPP CONS PRON S
 EST

 25 cm

6.2.22 43. Hacılarhani

6.2 Drawings of Squeezes

IMP
NERVA·CAESAR·AVG
PONT·MAX·TRIB·P
COS·III·P·P·RESTITVIT·PER
POM PONIUM·BASSV^{II}
LEG·PRO·PR

P·M X I

— 25 cm —

6.2.23 49(A). Haydarbeyli 1

IMP
CAISARIDIVI
IANI F DIVI
NERVAE NEPOTE
TIAIANI M O ADRIAI
AVSPOAT·MA

— 10 cm —

6.2.24 50(A). Dambasan 1

ERT!! IVS
JUSPERTI, IAN
AVC.RI DIABENIC
PARTHIC MAX PONTI
FEX MA/II TRIB POT
VIIMPY, COS II P 'P
PROCOSET IM PCAE
SARMARCUSAURAN
TONINVS AULUSTVS COS
PARTH·MAXIM

ER SU
PEPATTICIVM STRA
BV' ..LEG AVG PR PR
V

— 25 cm —

6.2.25 50(B). Dambasan 2

6.2 Drawings of Squeezes

N T PER ATTIC STRA
BONEMTEGATVM
AVS SPAP
MXIII
IΓ

6.2.26 51(A). Karakeçili 1

BF
IMPCAES
MESSIO
QUINTO
TRAIAN
DECII
PFEIA

NI

II

IΓ

25 cm

6.2.27 51(B). Karakeçili 2


IMP
NERVA CAESAR AVG
PONT MAX TRIB POTEST
COS III PP RESTITUIT PER
POMPONIUM BASSVM
LEG PPO PR

P M X[—]III IΓ

25 cm

6.2.28 51(C). Karakeçili 3

6.2 Drawings of Squeezes



6.2.29 52(A). Yazır 1

IMPCAE SA
IRUEPINEPO
SANTONI
FILIUS MAUR
ANTONINUS PIU
SFEC AUG TRIB
POTES T COS PR
OCOSPPRES
ITUIT

IA

— 25 cm —

6.2.30 52(B). Yazır 2

6.2 Drawings of Squeezes


IMP CAES L SEPT' VI
 VSS EVERVSPIU CREF K III
 A VQARAB ADIABENIC
 PARTHIC MAX PON TI
 EEX MAXI M TRIB POT
 VIIMP XIC OS II PP

PROC O SET IMP CAE
 SARMARCV SAVRAN
 TONINVS ET SEPTI
 VS CONODVR
 CAESAR RESTITUR CVI
 PER ATTICIVN
 STRARONELEGATUM




6.2.31 53(A). Yekbaş 1

6.2 Drawings of Squeezes



6.2.32 53(B). Yekbaş 2



6.2.33 54(B). Kaymaz 2

IMI^{CAES}
AXIGIVERO
MAXIMI
NOPIOFEII
CIAUGET,
IWEROMA
XIMONOBILIS
IMOCAESARIRE
SSTITV
ITPERIICINNIV
MSEKENIANUMIE
EΛVGPRR.

6.2.34 57. Çomar

6.2 Drawings of Squeezes

BILLSSLU
ESARVIA
USTATE
LIAISAM
STITUTPER
URBASILEUM
EGAVGPRPR

K Γ

— 10 cm

6.2.35 58(A). Eskiyapar 1

IMPERAT
ONCSARTREK
ONORGALLOET
VPE
CONSLAND
STITUSPERM
ELMAAN
ESAN
PRPR

— 10 cm

6.2.36 58(B). Eskiyapar 2

LO
XIANOPHE
ICI
P
A PROCOS

— 10 cm

6.2.37 61. Çopraşık

6.2 Drawings of Squeezes

IMP
 CAESAR I
 IANΟΛΔΡΙΑ I
 ΛΥΓΡΟΛΙΜΑ
 XIMO·TRIBV
 NICO·PIT·Cos
 ΜΙCΥRΩ·ΛΑΜΛ
 CIOMACEDDAIE
 SEG·ΛΥΓΡ
 MILIAP·Π

25 cm

6.2.38 45(C). Bü. Nefes 3

JULIANO
 ARUST
 CTRIYM

IMP·NERVA·CAES
 AR·AV·C·PONI·
 MAX·IRIB·POIES·CO
 S·III·PPRESIIIVIPE
 RPOM PONIUM·BASS
 VM·IEG·PRO·PR·P·M·

IXXXIII

IM.
 A2 CRIS PC
 CONSTANTI
 SETN C2
 STANTINO
 CAUS

9Δ

25 cm

6.2.40 69(A). Çağırgan 1

6.2.39 65(A). Tol 1

6.2 Drawings of Squeezes

IMP CAES P A E
 LICIN' NIO VA
 LERIANOPFAVC
 ETIMP CAES P LI
 CINNIO ECNA
 TIO CALLENO
 PFAYC ET P II
 CINNIO ECNATI
 OVALERIANOSA
 LONIANO INDVL CEN
 TISSIMO CAES AV C
 ET SALONINA Matri
 AVCS ET CAST ROR
 UXAPFAVC

— 25 cm —

6.2.41 69(B). Çağırkın 2

IMP·CAESAR·P·I·V·I
 TRAIAN·NI·P·ARTI·IIG
 F·D·I·V·I·N·E·R·V·A·T·N·E
 'OSTRAIANVS·I·V·I
 ORIANVS·AVCPN
 MAX·TRIB·POI·III
 COSIII P·P
 III.

MIL P X

— 10 cm —

6.2.42 70(A). Konya 1

6.2 Drawings of Squeezes

IMP
 CAESARI DIVI H,
 DRIANIFILIO·DI
 TRAIANIPARTHIC
 NEPOTI·DIVINEF
 AEPRONEPOTIT·E
 LIOHADIANO·I.T
 NINOAVGVSTCFK
 FONT·MAX·I
 TRIET F·III·CO S·III
 MIL·PASSVM·
 X> VIII



6.2.43 70(C). Konya 3


FL CON T/
 POS TUL C N
 ISAV C C D
 JSTRIPPC!
 COS III PFB

MIL V



6.2.44 70(E). Konya 5

6.2 Drawings of Squeezes



6.2.45 70(F). Konya 6

IMP CAES SEPTI
 SEVERUS PIVS PER. T.
 NAXA VGVSTVS A RABI
 CUS DIABENIC VS PAR
 THICVS MAXIMVS PONTI
 FEX MAXIMVS TRIB POT VII
 IMP XI COS II PP PRO COS
 ET IMP CAESAR MARCVS
 REI SVNTOR JV
 VGC CONS PR
 I C MAXI
 AVREST ERVN
 MILP SS

D D D N
 ELLALEN
 T ECCRATII
 ETELV EITII
 ANOP ERECI

SS 5

I II C X V II

6.2.47 73(C). Kulak Murat Hani 3

10 cm

IMP
S

M
AV

I IV

T


I

E R


10 cm

6.2.48 73(E). Kulak Murat Hani 5

6.2 Drawings of Squeezes



6.2.49 74(A). Eğribayat 1



6.2.50 74(D). Eğribayat 4

ΛΧ ΛC
ΡΛΛC

ΕΛΛΑΤ - ΝΕΡΒΑΕΓΑ -
ΛΥCΡΩΝΤΙΦΙΔΛΙΧΙΔΤΡΙ
ΒΥΝΙΑ ΠΩΣ ΣΤΑΤΕ ΠΑΤΡΙ
ΡΑΤΡΙΑ ΕΓΟΣ III

Λ

10 cm

6.2.51 74(D). Eğribayat 4

6.2.52 76(B). Kızılçakuyu 2

6.2 Drawings of Squeezes

NEPC STRAVANVS
 HADRIANVS AVS
 PON MAXTRIBOT
 XIII CC...
 M PP
 MIL VII

6.2.53 79(A). Obruk 1

KJ
 JC
 C
 AN
 CT MO

? PT·PT:PTO
 CT·ET·IMR·CΛE
 Τ·ΜΛΡCU/Λ
 ΕΙΙU·ΛΝΓC
 Τ·ΛΛGVR
 Λ PT

6.2.55 79(E). Obruk 5

ΙΑΡΝΕΡΒΑ
 CAESAR AVG PONTI
 MAXTRIB POTPPRE^T
 TITVIT COS III PER POM
 PONIVMBASSVM
 L[EG] PR PR
 PSS

ΙΠΣ
 ΤΟΝΤΥΙΓ ΣF
 ΙΓΛΛVCP C PR
 ΣΠΙΙ

N 2 N 900

6.2.54 79(C). Obruk 3

25 cm

6.2 Drawings of Squeezes


IMPN ER L CAESARE
 AVFC MAXIMO
 TRIBVIDDUNI N
 PATR' F LVALE ANTE
 ET FL GRATIANO
 ET FL VALENTINIANO
 PERPETVIRAC VICTO
 RIORISIMISREM RIK
 AVSSS
 MA

6.2.56 79(F). Obruk 6

IMPN ER DE NN
 AVCPONTM FL VALENTE
 . . . IPPO, FS - ETE GRATIANO
 ETE VALENTINIANO
 PERPETVIRAC VICTO
 RIORISIMISREM RIK
 AVSSS
 MA

6.2.57 79(G). Obruk 7

6.2 Drawings of Squeezes



6.2.58 84(C), Altınekin 3

DORRN CAE
CONSTANTINOS
MAX AUG

ET FLIUL CONSTANTIO
ET FLIUL CONSTANTI

6.2.59 88(C), Esendere 3

IMP.CAE S.
M·AURC·ARO
AVG·FT

MAURCNIRIUS
IQVCLAES RUS
ETM AUR NUMERI NO
NOBILIS SIMOCAES API

6.2.60 88(E), Esendere 5

IMP·CAESAR·DIVIF
WCVTV·PONT·A^{AA}XI
ISX·FSIC·XII·I·
TEST·XII^AVIA
JLI CVRANT
CURNVTO / CMLALEC
SVO PRO·PR·ECIT
XXIII

6.2.61 90(C), Gencali 3

6.2 Drawings of Squeezes

UD NN
 FLUALENTINIAN
 ET FLALEN TE
 EG - IANANO
 FA - CONSTANTINO
 MAXI AYC
 ET /
 ET FLIV CONSTANTIO
 ET FLIV CONSTANTE
 N YI HI T
 XXIIIX

25 cm

6.2.62 90(E). Gençali 5

FLCONSTANTINO
 MAXI AYC
 ET FLIV CONSTANTIO
 ET FLIV CONSTANTE
 ET ST'
 RVNI PERT
 VMINOR, 111
 LE SAVSPR PRMILIA
 XXVII

25 cm

6.2.63 90(F). Gençali 6

6.2 Drawings of Squeezes

IMP·CAES
MI VELPHILIPP
NOBISSSI
MOIMPFILIOAVS
Q Q

 10 cm

6.2.64 90(G). Gençali 7

IMP C ΔΙ ΥΙ ΣΕΡΤΙ
S EU RI IC PUSΔΙ U
M. KE LM ON
UPP JUS, E LAX, UGPONTI
Γ X MAX I MUSTRIB POT C
SPP Y R O EON RESTITUIT

 10 cm

6.2.65 90(H). Gençali 8

DDN N

IAK


ETFLIVL CONSTANTIO ETFL
CLCONSTANTE
VICTORI TEMP
ABANTIOCHIA AVCC
IACIN AVCC
PONTIF MAX TRIB
POTXIII COSIII
P. P.

MP NY

 25 cm

6.2.66 94(A). Dedeçam 1

6.2 Drawings of Squeezes



6.2.67 94(A). Dedeçam 1

VIPC EBAE[N] NIF
IMPC AES MA XIM
PPLIC NN IMPXV
VALERIANO VIAM
EST GALLENO NTE
ACERIANO QVILA
. AUG~~XQG~~
MP

10 cm


6.2.68 94(B). Dedeçam 2

LIVI FZ
MA CONS XI DL
XV TRIB I OT XII
VIAM SEGA TEN CVRAI
TE CC RNV. 'AQV'
SVO PROFI A O
XXXII


25 cm

6.2.69 95(D). Kiyakdede 4

6.2 Drawings of Squeezes



6.2.70 97(A). Selki 1



6.2.71 97(B). Selki 2

IMP·CAES·AI LIVI·AVGV·
TVS·PON·T·VIV· '·CO·XI·PESI
XII·IMP·XV·TRID·POTES·YIIX.
VIAM·SEB·ASTEN·CVRA 'TE
CORNU·TU·AQV L·LEG·VO
PRO·PRAETORE ECIT

6.2.72 98. Yunuslar

6.2 Drawings of Squeezes

IMP NERVA ECAESARI
AV' CNTIF MAX
T^D P^L C P
COS III

PER T I OM PONIVM
BASSI V^I LEG
AVG PRO PR
M P XVIII

6.2.73 99. Değirmen

IMP CAES M ANT
GORDIANO P AVG
<MI^EP^REST<
I

6.2.74 101(C). Hatunsaray 3

IMP CAES GIV
LIVS VERVS
MAXIMINVS
PIUS F EL AVG
RESTI TVIT
MI^EI

6.2.75 101(A). Hatunsaray 1

GUKUNI AY
AV C MI^EP^REST
II

6.2.76 101(B). Hatunsaray 2

6.2 Drawings of Squeezes

PΛTC RΛGΣ
 TIMIVSSEU
 PΛTINXΛ
 ICV ΛBE
 I USMΛXI
 ΛΛXI
 EΙ

EΛT
 EL
 VG

ERVN
 IAN
 CPT

 25 cm

6.2.77 101(D). Hatunsaray 4

IMP CAESARIP
 LICINN. OVALERI bN
 VLE PR LICINNI φ
 ALERIANO
 VPIORVM
 GETCOR
 SALONINO
 VNOIVNIORI
 VLAELAUC
 CLVIS TREN SIVM

 25 cm

6.2.78 102(B). Kavak 2 (2)

D D b NTIN
 eBD HΛHN
 HΛEED
 IIO T
 EΛK O
 N

 25 cm

6.2.79 102(B). Kavak 2 (3) and (4)

6.2 Drawings of Squeezes

FLI Q̄II ANOΛΑΑΧΙ
 IMP CAESAR IN PROXIMA ḠCLOVIA ET RI
 MIVS SEVERUS P
 EERTINAX AV C A T T O R F T H A P E R
 RICVS ADIA
 PARTHICVS MAXIMVS FELTRIB
 FELTRIB POTEST
 IMP XII COS I VAL CONSTANTINO PF INV AVG
 COS P
 ET IMP CAESAR ET FLA RIC & ESNA
 LIVSANTONI
 AVG FELIX TIG AL ALN AXI C VIANO NOBILI
 TATIS XHM
 PROCOSE P A
 CVS MAX
 COS II VIAM
 STRATA MANOVO
 FECEPUNT PER P
 ICAECILIVMURBICVM
 A MILIANUM LEG AVG GGG
 PRO PRCOS DESIGNAT
 M VIII Θ

MP XVIII


 50 cm

6.2.80 115. Ankara, Batikent

IMP CAES
 QVIBIOTREB
 OΛΠΟCAΛLÓPIÓ
 FELL CI AVG EI
 IMP CAES Q A
 FINI OCA LÓVEI
 DVVNIA NÓV
 OLVSIAN NÓΛVG

 10 cm

6.2.82 122 (D). Oğulbey 4

IMP. CAES. L. SEPTI
 MIVS SEVERUS P
 VSPERTINAX AVG
 A RABICVSADI BENICVS
 PARTHICVS MAXIMVS FELTRIB
 POTEST XU IMP. XII COS III
 COS P P
 ET IMP. CAES. MAURELINS
 TONINUS PIUS AVG. FELTRIB POTEST
 XI IMP. II COS III PRO COS

I VIAM ST RATA MANO NOFE
 CERUNT PER P CAECILIVM
 URBICUM AEMILIANUM LEG AVG E S
 PRO PRCOS DESIGNATUM

MP VI
 25 cm

6.2.81 117(M). Ankara 13


7. ILLUSTRATIONS: PLATES

7.1 Milestones


- | | | |
|-----|--------------------------|---|
| 01. | 06. Malı | Hadrianus, (?)AD 121/122 |
| 02. | 07. Bacı | Domitianus AD 81 |
| 03. | 16(A). Çapalı 1 | (1) Sept. Severus and Caracalla with Geta AD 197/198 |
| 04. | 16(B). Çapalı 2 | (1) Constantinus and Licinius AD 317 or 318
(2) Iulianus |
| 05. | 16(C). Çapalı 3 | Constantinus and Licinius AD 317 or 318 |
| 06. | 21. Ömercik | — |
| 07. | 22. Akkuzulu 1 | Hadrianus AD 121/122 |
| 08. | 23(B). Akkuzulu 3 | Traianus, (?) AD 98 |
| 09. | 34. İskilip | Nerva AD 97 |
| 10. | 40. Sungurlu | Nerva AD 97 |
| 11. | 41. Çevheri | Gordianus I & Gordianus II AD 238 |
| 12. | 49(B). Haydarbeyli 1 | (2) Sept. Severus and Caracalla with Geta AD 197/198 |
| 13. | 49(B). Haydarbeyli 2 | (2) Sept. Severus and Caracalla with Geta AD 197/198 |
| 13. | 49(A). Haydarbeyli 2 | Nerva AD 97 |
| 15. | 50(A). Dambasan 1 | Hadrianus, AD 121/122 |
| 16. | 50(B). Dambasan 2 | Sept. Severus and Caracalla with Geta AD 197/198 |
| 17. | 51(A). Karakeçili 1 | Sept. Severus and Caracalla with Geta |
| 18. | 51(C). Karakeçili 3 | Nerva AD 97 |
| 19. | 52(A). Yazır 1 | Sept. Severus and Caracalla with Geta, (?)AD 197/198 |
| 20. | 54(A). Kaymaz 1 | Gordianus I (& Gordianus II ?) AD 238 |
| 21. | 55. Gökçam | Sept. Severus and Caracalla with Geta AD 197/198 |
| 22. | 56. Ekmekci | Nerva AD 97 |
| 23. | 56. Ekmekci | Nerva AD 97 |
| 24. | 56. Ekmekci | Nerva AD 97 |
| 25. | 58(A). Eskiyapar 1 | Severus Alexander AD 222 |
| 26. | 60. Akören | (1) Nerva, (?)AD 97
(2) Traianus |
| 27. | 62. Bolatcık | Severus Alexander AD 222 or 223(?) |
| 28. | 45(C). Bü. Nefes 3 | Hadrianus AD 118/119 |
| 29. | 64. Musabeyli | Hadrianus AD 119 |
| 30. | 65(A). Tol 1 | (1) [Constantinus and Licinius]
(2) Iulianus |
| 31. | 65(B). Tol 2 | Hadrianus AD 121/122 |
| 32. | 67. Abazlı 1 | Domitianus AD 82 |
| 33. | 69(A). Çağırkan 1 | Nerva AD 97 |
| 34. | 69(A). Çağırkan 1 | Nerva AD 97 |
| 35. | 69(B). Çağırkan 2 | Valerianus and Gallienus |
| 36. | 69(B). Çağırkan 2 | Valerianus and Gallienus |
| 37. | 70(A). Konya 1 | Hadrianus AD 128/129 |
| 38. | 70(C). Konya 3 | Antoninus Pius AD 142 |
| 39. | 70(E). Konya 5 | (1) ? Hadrianus, AD 128/129
(2) Constantinus I and 3 sons AD 333-335 |
| 40. | 72. Tilki Han | Sept. Severus and Caracalla with Geta AD 198/199 |
| 41. | 73(B). Kulak Murat Han 2 | (?) Hadrianus |
| 42. | 73(C). Kulak Murat Han 3 | (1) ? Hadrianus |

- (2) Valens, Gratianus and Valentinianus II
 (?)
 (1) Sept. Severus and Caracalla with Geta AD 198/199
 (2) Constantinus I
 (?) Domitianus
 (1) Nerva AD 97
 (2) (?)Valens, Gratianus and Valentinianus II
 (1) (?)
 (2) Nerva AD 97
 (1) (?)
 (2) Nerva AD 97,
 (3) Valens, Gratianus and Valentinianus II
 Hadrianus AD 128/129
 Sept. Severus and Caracalla with Geta
 Elagabalus
 Constantinus I
 Hadrianus AD 129
 Constantinus I
 Augustus 6 BC
 Carus with Carinus and Numerianus
 (2) Carus
 (?)
 (?)
 Augustus 6 BC
 Augustus 6 BC
 Augustus 6 BC
 Augustus 6 BC
 (2) Gordianus III
 (2) Gordianus III
 Sept. Severus and Caracalla with Geta
 (1) Sept. Severus and Caracalla with Geta AD 197/198
 (2) Diocletianus and colleagues
 (3) Constantinus I and Licinius I
 (4) Iulianus
 Hadrianus AD 121/122
 Domitianus AD 82
 Caracalla AD 212
 Valerianus and Gallienus
 (1) Hadrianus AD 122-123(?)
 (2) Valentinianus I and Valens
 Hadrianus, (?) AD 121/122
 Hadrianus, (?) AD 121/122
 Hadrianus AD 121/122
 (3) Constantinus I
 Domitianus AD 82
 Sept. Severus and Caracalla with Geta, (?)AD 211/212
 (?)
 (1) Sept. Severus and Caracalla with Geta, (?) 197/198
 (2) (?)

7.1 Photographs of Milestones



7.1.1 06. Malı



7.1.2 07. Bacı



7.1.3 16(A). Çapaklı 1

7.1 Photographs of Milestones



7.1.4 16(B). Çapalı 2



7.1.5 16(C). Çapalı 3




7.1.6 21. Ömercik

7.1 Photographs of Milestones



7.1.7 22. Akkuzulu 1



7.1.8 23(B). Akkuzulu 3



7.1.9 34. İskilip



7.1.10 40. Sungurlu

7.1 Photographs of Milestones




7.1.11 41. Çevheri



7.1.12 49(A). Haydarbeyli 1



7.1.13 49(B). Haydarbeyli 2



7.1.14 49(B). Haydarbeyli 2

7.1 Photographs of Milestones




7.1.15 50(A). Dambasan 1




7.1.16 50(B). Dambasan 2


7.1 Photographs of Milestones




7.1.17 51(A). Karakeçili 1



7.1.18 51(C). Karakeçili 3




7.1.19 52(A). Yazır 1




7.1.20 54(A). Kaymaz 1

7.1 Photographs of Milestones



7.1.21 55. Gökçam




7.1.22 56. Ekmekci

7.1 Photographs of Milestones



7.1.23 56. Ekmekci



7.1.24 56. Ekmekci



7.1.25 58(A). Eskiypar 1



7.1.26 60. Akören

7.1 Photographs of Milestones



7.1.27 62. Bolatçık




7.1.28 45(C). Büyük Nefes 3

7.1 Photographs of Milestones



7.1.29 64. Musabeyli



7.1.30 65(A). Tol 1



7.1.31 65(B). Tol 2




7.1.32 67. Abazlı 1

7.1 Photographs of Milestones



7.1.33 69(A). Çağırkan 1



7.1.34 69(A). Çağırkan 1




7.1.35 69(B). Çağırkan 2



7.1.36 69(B). Çağırkan 2

7.1 Photographs of Milestones



7.1.37 70(A). Konya 1



7.1.38 70(C). Konya 3

7.1 Photographs of Milestones



7.1.39 70(E). Konya 5



7.1.40 72. Tilki Han



7.1.41 73(B). Kulak Murat Han 2



7.1.42 73(C). Kulak Murat Han 3

7.1 Photographs of Milestones



7.1.43 73(E). Kulakmurat 5



7.1.44 74(A). Eğribayat 1



7.1.45 74(D). Eğribayat 4




7.1.46 76(A). Kızılcakuyu 1

7.1 Photographs of Milestones




7.1.47 76(B). Kızılcakuyu 2



7.1.48 76(C). Kızılcakuyu 3


7.1 Photographs of Milestones



7.1.49 79(A). Obruk 1



7.1.50 79(E). Obruk 5



7.1.51 83. Ağsaklı



7.1.52 84(C). Altınekin 3

7.1 Photographs of Milestones



7.1.53 85. Yazıbelen



7.1.54 88(C). Esendere 3


7.1 Photographs of Milestones



7.1.55 88(D). Esendere 4



7.1.56 88(E). Esendere 5



7.1.57 90(E). Gençalı 5

7.1 Photographs of Milestones



7.1.58 91(A). Aş. Kaşıkara 1



7.1.59 95(B). Kiyakdede 2




7.1.60 95(D). Kiyakdede 4



7.1.61 95(D). Kiyakdede 4

7.1 Photographs of Milestones



7.1.62 97(A). Selki 1




7.1.63 97(B). Selki 2




7.1.64 101(C). Hatunsaray 3

7.1 Photographs of Milestones




7.1.65 101(B). Hatunsaray 2



7.1.66 101(D). Hatunsaray 4




7.1.67 115. Ankara, Batıkent



7.1.68 116. Ankara, Akköprü

7.1 Photographs of Milestones



7.1.69 117(G). Ankara 7



7.1.70 121(B). Örencik 2




7.1.71 124. Ahiboz 1 & 2

7.1 Photographs of Milestones



7.1.72 124(A). Ahiboz 1



7.1.73 125(B). Günalan 2




7.1.74 127(A). Abazlı 2


7.1 Photographs of Milestones



7.1.75 127(A). Abazlı 2




7.1.76 128(A). Bağıçı 1




7.1.77 128(B). Bağıçı 2

7.1 Photographs of Milestones




7.1.78 128(C). Bağıçi 3



7.1.79 129(A). Yöreli 1



7.1.80 131(F). Afşar 6



7.1.81 131(G). Afşar 7

7.2 Squeezes


- | | | |
|-----|----------------------|---|
| 1. | 07. Bacı | Domitianus AD 81 |
| 2. | 09. Ertuğrul | Valerianus and Gallienus with Valerianus |
| 3. | 16(A). Çapalı 1 | (1) Sept. Severus and Caracalla with Geta AD 198
(5) Gratianus, Valentinianus II and Theodosius I
(3) Constantinus and Licinius |
| 4. | 16(A). Çapalı 1 | (5) Gratianus, Valentinianus II and Theodosius I |
| 5. | 17(A). Balıkhisar 1 | Hadrianus AD 121/122 |
| 6. | 18. Sünlü | Maximinus |
| 7. | 20. Cüciük | Traianus AD 98 |
| 8. | 22. Akkuzulu 1 | Hadrianus AD 121/122 |
| 9. | 28. Yu. Yanlar | (2) Traianus
(5) (?) Iulianus
(4) Diocletianus et coll.
(5) (?) Iulianus |
| 10. | 28. Yu. Yanlar | (6) Valentinianus I, Valens and Gratianus |
| 11. | 29(B). Akyurt 2 | Sept. Severus and Caracalla with Geta AD 198 |
| 12. | 32(B). Çiftlik 2 | Traianus AD 98 |
| 13. | 34. İskilip | Nerva AD 97 |
| 14. | 35. Ankara, Siteler | Traianus AD 98 |
| 15. | 38(A). Hasanoğlan 1 | (1) (?) Domitianus
(2) Traianus AD 98 |
| 16. | 38(C). Hasanoğlan 3 | Hadrianus AD 121/122 |
| 17. | 39(A). Elmadağ 1 | Hadrianus AD 121/122 |
| 18. | 49(B). Haydarbeyli 2 | Sept. Severus and Caracalla with Geta AD 198 |
| 19. | 49(C). Haydarbeyli 3 | Severus Alexander AD 223 |
| 20. | 50(B). Dambasan 2 | Sept. Severus and Caracalla with Geta AD 198 |
| 21. | 54(A). Kaymaz 1 | Gordianus I AD 238 |
| 22. | 60. Akören | (1) (?) Nerva
(2) Traianus |
| 23. | 62. Bolatçık | Severus Alexander AD 222 |
| 24. | 64. Musabeyli | Hadrianus AD 118/119 |
| 25. | 65(B). Tol 2 | Hadrianus AD 121/122 |
| 26. | 67. Abazlı 1 | Domitianus AD 82 |
| 27. | 70(C). Konya 3 | (1) Antoninus Pius AD 142 |
| 28. | 70(C). Konya 3 | (2) Valentinianus I, Valens and Gratianus |
| 29. | 72. Tilki Han | Sept. Severus and Caracalla with Geta AD 198 |
| 30. | 76(A). Kızılçakuyu 1 | (1) Nerva AD 97
(2) (?) |
| 31. | 76(C). Kızılçakuyu 3 | (2) Nerva AD 97 |
| 32. | 76(C). Kızılçakuyu 3 | (3) Valentinianus I, Valens and Gratianus |
| 33. | 79(B). Obruk 2 | (1) Nerva AD 97 |
| 34. | 79(B). Obruk 2 | (2) Valentinianus I, Valens and Gratianus |
| 35. | 83. Ağsaaklı | Elagabalus |
| 36. | 88(D). Esendere 4 | Augustus 6 BC |
| 37. | 90(B). Gençalı 2 | (1) Sept. Severus and Caracalla with Geta AD 198
(2) Iovianus (?) |
| 38. | 90(D). Gençalı 4 | (1) Constantinus and Licinius |
| 39. | 94(A). Dedeçam 1 | (1) Hadrianus AD 128/129 |

- (6) Constantinus with 3 sons
40. 95(D). Kiyakdede 4 Augustus 6 BC
41. 95(E). Kiyakdede 5 Augustus 6 BC
42. 115. Ankara, Batıkent (1) Sept. Severus and Caracalla with Geta AD 208
43. 115. Ankara, Batıkent (2) Diocletianus and Maximianus with Constantius I and Galerius
(2) Diocletianus and Maximianus with Constantius I and Galerius
(3) Constantinus I and Licinius I
(4) Flavius Iulianus
44. 116. Ankara, Akköprü Hadrianus

7.2 Photographs of Squeezes



7.2.1 07. Baci




7.2.2 09. Ertuğrul

7.2 Photographs of Squeezes




7.2.3 16(A). Çapalı 1



7.2.4 16(A). Çapalı 1

7.2 Photographs of Squeezes




7.2.5 17(A). Balıkhisar 1




7.2.6 18. Sünlü

7.2 Photographs of Squeezes



7.2.7 20. Cucük



7.2.8 22. Akkuzulu 1

7.2 Photographs of Squeezes




7.2.9 28. Yu. Yanlar

7.2 Photographs of Squeezes




7.2.10 28. Yu. Yanlar



7.2.11 29(B). Akyurt 2

7.2 Photographs of Squeezes




7.2.12 32(B). Çiftlik 2



7.2.13 34. İskilip

7.2 Photographs of Squeezes



7.2.14 35. Ankara, Siteler



7.2.15 38(A). Hasanoğlan 1

7.2 Photographs of Squeezes



7.2.16 38(C). Hasanoğlan 3




7.2.17 39(A). Elmadağ 1

7.2 Photographs of Squeezes




7.2.18 49(B). Haydarbeyli 2




7.2.19 49(C). Haydarbeyli 3

7.2 Photographs of Squeezes



7.2.20 50(B). Dambasan 2

7.2 Photographs of Squeezes



7.2.21 54(A). Kaymaz 1



7.2.22 60. Akören

7.2 Photographs of Squeezes



7.2.23 62. Bolatcık




7.2.24 64. Musabeyli

7.2 Photographs of Squeezes




7.2.25 65(B). Tol 2



7.2.26 67. Abazli 1

7.2 Photographs of Squeezes



7.2.27 70(C). Konya 3




7.2.28 70(C). Konya 3

7.2 Photographs of Squeezes




7.2.29 72. Tilki Han




7.2.30 76(A). Kızılcakuyu 1

7.2 Photographs of Squeezes




7.2.31 76(C). Kızılcakuyu 3



7.2.32 76(C). Kızılcakuyu 3

7.2 Photographs of Squeezes



7.2.33 79(B). Obruk 2




7.2.34 79(B). Obruk 2

7.2 Photographs of Squeezes



7.2.35 83. Ağsaklı




7.2.36 88(D). Esendere 4

7.2 Photographs of Squeezes



7.2.37 90(B). Gençalı 2



7.2.38 90(D). Gençalı 4

7.2 Photographs of Squeezes



7.2.39 94(A). Dedeçam 1

7.2 Photographs of Squeezes




7.2.40 95(D). Kıyakdede 4

7.2 Photographs of Squeezes




7.2.41 95(E). Kiyakdede 5

7.2 Photographs of Squeezes




7.2.42 115. Ankara, Batikent

7.2 Photographs of Squeezes



7.2.43 115. Ankara, Batikent

7.2 Photographs of Squeezes



7.2.44 116. Ankara, Akköprü