

# ROMAN ROADS & MILESTONES OF ASIA MINOR

AVG·P·M·TRIB·POT·VII  
I ////////////// III COS·VII·P·P·  
IMP·TITO·CAESARE·AVG·F·COS·V  
!!!!!!!!!!!! O!!!! ARE!! G·F·COS·II  
CN·POMPEIVS·COLLEGA·LEG·AVG  
PRO·PR· //////////////////

DAVID H. FRENCH

VOL. 3 MILESTONES  
FASC. 3.3 CAPPADOCIA

British Institute at Ankara

Electronic Monograph 3  
2012

© British Institute at Ankara 2012

ISBN 978 1 898249 26 9

All rights reserved. No parts of this publication may be reproduced, stored in a retrieval system, or transmitted, in any form or by any means, electronic, mechanical, photocopying, recording, or otherwise, without the prior permission of the British Institute of Archaeology at Ankara.

*Cover illustration: 004. Yurtbaşı, Cumont 1905b, 201*



## CONTENTS

[illegible]

## 1. ACKNOWLEDGEMENTS

For more than two decades the Ministry of Culture and Tourism generously supported my researches and unfailingly granted the necessary permission.

For my work in Cappadocia I was accompanied in the field by Ministry representatives who were, as ever, indispensable: they aided and assisted my efforts with the greatest patience and good humour, and contributed greatly to the success of my researches.

1976	Mahmut Aslan
1977	Sedat Heper; İbrahim Atalay
1978	İbrahim Atalay
1981	Byn Pınar Türkan
1982	İsmet Ediz
1983	İsmet Ediz
1984	İsmet Ediz
1985	Muhsin Erdoğan
1986	Yaşar Ünlü
1987	Enver Sağır
1989	Mehmet Akalkan
1990	Byn Sena Mutlu
1994	Byn Nursel Uçkan
1995	Şaban Kök
1998	Byn Şerife Yılmaz

My heartfelt, *candan* gratitude to them all.

Dr Melih Aslan conveyed to me a copy of the milestone at Keklikoluk (no. 098[D]) and Prof. Dr. Hasan Malay a copy of the milestone at Pozantı (no. 166). To both my appreciative thanks.

Brigitte Le Guen very kindly sent information (together with a photograph) on the Özükevâk milestone (no. 139).

The maps in this fascicule were drawn by Brian Williams. Michele Massa, Research Scholar at the BIA, scanned negatives and prints for use in the photographic illustrations.

The final version of this fascicule was prepared for electronic publication by Abby Robinson, Research Scholar of the British Institute at Ankara.

To Stephen Mitchell, Secretary of the Institute, and to Lutgarde Vanderput, Director, I am grateful for their continuing support.

## 2. BIBLIOGRAPHY

### 2.1 Abbreviations

The following abbreviations, for journals and serials and for books and series, are not generally found in the current lists.

AdI Annali dell'Istituto di Corrispondenza Archeologica

AST Araştırma Sonuçları Toplantısı

BdI Bullettino dell'Istituto di Corrispondenza Archeologica

Bull Robert (J. and L.) Bulletin Épigraphique

KST Kazı Sonuçları Toplantısı

RECAM Regional Epigraphic Catalogues of Asia Minor (BIA Monographs)

RRMAM Roman Roads and Milestones of Asia Minor (BIA Monographs)

StPont Studia Pontica 1-3,1. Brussels

### 2.2 Bibliography

Note: The abbreviations primarily employed here are listed in *L'Année Philologique*, "Index of Articles"; they are supplemented, where necessary, by *AJA* 90 (1986), 384-394 "Abbreviations for Periodicals and (2) for Individual Works" and *AJA* 104 (2000), 10-24, and by *Zeitschriftenverzeichnis nach Abkürzungen*, *JdI Archäologische Bibliographie*

Anderson, J.G.C.

– 1897-98 Exploration in Asia Minor during 1898: First Report. *BSA* 4, 49-78

– 1899 Exploration in Galatia cis Halym. Part 2. *JHS* 19, 52-134 and 280-318

Babinger, Fr.

– 1923 *Hans Dernschwams Tagebuch einer Reise nach Konstantinopel und Kleinasien 1553/1555*.

Munich and Leipzig

Ballance, M.H.

– 1958 Roman Roads in Lycaonia. *AnatSt* 8, 223-234

– 1964 Derbe and Faustropolis. *AnatSt* 14, 139-145

Baz, F.

– 2007 *Die Inschriften von Komana (Hierapolis) in Kappadokien*. Istanbul

Bittel, K.

– 1955 Funde in östlichen Galatien. *IstMitt* 6, 22-41

Boré, E.

– 1840 *Correspondence et Mémoires d'un Voyageur en Orient* 1-2. Paris

Boybeyi, S. and Probst, P.

– 2008 Ein neuer Meilenstein aus Keklikoluk (Kappadokien). *EpigrAnat* 41, 135-138

Brant, J.

– 1836 Journey through a Part of Armenia and Asia Minor in the Year 1835. *JRoyGeogrSoc* 6, 204

Cagnat, R.

– 1894 Report in "Travaux". *BAntFr*: 132-134

Carolides, P.

– 1882 Τὰ Κόμανα καὶ τὰ ἐρεῖπια αὐτῶν. Athens

Christol, M. and Drew Bear, T.

– 1986 Documents latins de Phrygie. *Tyche* 1, 41-87

– 1987 *Un Castellum Romain près d'Apamée de Phrygie*. Vienna (DenkschrWien 189)

– 2009 L'aménagement de la *Via Tauri* sous les Sévères. *Anatolia Antiqua* 17, 239-254

Christol, M., Drew Bear, T. and Özsait, M.

- 1993 Trois milliaires d'Asie Mineure. *Anatolia Antiqua* 2, 159-169

Christol, M. and Lorient, X.

- 1986 Le Pontus et ses gouverneurs dans le second tiers du 3<sup>e</sup> siècle. In Rémy, B., *Mémoires 7. Recherches épigraphiques: documents relatifs à l'histoire des institutions et de l'administration de l'Empire romain*, 13-40. Saint-Étienne
- 1993 Aurelius Basileus, gouverneur de Cappadoce, problèmes de géographie administrative dans la première moitié du III<sup>e</sup> siècle après J.-C. *Cahiers du Centre G. Glotz*, 209-221
- 2001 P. Alfius Avitus et P. Plotius Romanus, gouverneurs de Galatie. *AC* 70, 97-121

Cousin, G.

- 1904 *Kyros le Jeune en Asie Mineure*. Nancy (Lyons; repr. Paris 1905)

Cumont, Fr.

- 1902 Nouvelles inscriptions du Pont. *REG* 15, 311-335
- 1904 Nouvelles Inscriptions du Pont. *REG* 17, 329-334
- 1905a Deux pierres milliaires du Pont. *CRAI*, 347-351
- 1905b Le Gouvernement de Cappadoce sous les Flaviens. *Bulletins de la Classe des Lettres* (Académie Royale de Belgique), 197-224

Demougin, S.

- 2005 Romans prosopographiques. In Desmulliez and Hoët van Cauwenberghe 2005, 171-187
- Desmulliez, J. and Hoët van Cauwenberghe, C.
- 2005 (eds) *Le monde romain à travers l'épigraphie: méthodes et pratiques. Actes du XXIV<sup>e</sup> Colloque internationale de Lille, 8-10 novembre 2001*. Lille

Dodgeon, M. H. and Lieu, S. N. C.

- 1991 *The Roman Frontier and the Persian Wars* (AD 226-363). London and New York

Drew Bear, T.

- 1991 Inscriptions de Cappadoce. In des Courtis, J. et al. (eds), *De Anatolia Antiqua (Eski Anadolu)* 1, 130-149. Paris (B. Inst. Fr. Et. Anat. Ist. 32)

Equini, H. S.

- 1970 *Malatya* 2. Roma (Orientis Ant. Coll. 10)

French, D. H.

- 1976 Researches on Roman Roads and Milestones in 1974. *TürkAD* 22, 1, 51-54 (in Turkish)
- 1980 The Roman Road System of Asia Minor. In Temporini, H. and Haase, W. eds, *ANRW* 2.7, 2, 698-729. Berlin
- 1981 Milestones of Pontus, Galatia Phrygia and Lycia. *ZPE* 43, 149-174
- 1984 Roma Yolları ve Miltaşları. *AST* 2 (*İzmir* 1984), 123-129
- 1985a Milestones of Cappadocia. *EpigrAnat* 5, 147-154
- 1985b Roma Yolları ve Miltaşları. *AST* 3 (*Ankara* 1984), 143-154
- 1986a Recent Archeological Research in Pontus. *EpigrAnat* 8, 71- 83
- 1986b Küçük Asya, Roma Yolları ve Miltaşları 1985. *4 AST* (*Ankara* 1986), 109-112
- 1987 Küçük Asya, Roma Yolları ve Miltaşları 1986. *5 AST* (*Ankara* 1987), 191-204
- 1989 Aurelius Basileus, Governor of Cappadocia. In Herzog, H.E. and Frei-Stolba, R. eds, *Labor omnibus unus. Gerold Walser zum 70. Geburtstag*, 38-44. Wiesbaden (Historia Einzelschr. 60)
- 1990 1989 Roma Yolları, Miltaşları ve Yazıtları Araştırması. *8 AST* (*Ankara* 1990), 229-240
- 1991a 1990 Yılı Roma Yolları, Miltaşları Araştırması. *9 AST* (*Çanakkale* 1991), 149-163
- 1991b New Milestones from Pontus and Galatia. In Rémy, B. (ed.), *Pontica 1. Recherches sur l'histoire du Pont dans l'Antiquité*, 77-96. Istanbul (Varia Anatolica 5)
- 1992 1991 Yılı Roma Yolları, Miltaşları ve Yazıtları Araştırmaları. *10 AST* (*Ankara* 1992), 199-206
- 1995 1994 Döneminde Roma Yolları, Miltaşları ve Yazıtları. *13 AST* (*Ankara*), 1-4 and Figs 1-4

- 2008 Notes on Cappadocian Milestones. The Caesaria-Melitene Road. *EpigrAnat* 41, 125-134
- Garstang, J.
- 1908 Notes on a Journey through Asia Minor. *LivAnnArchAnthr* 1, 1-12
- Grégoire, H.
- 1909 Rapport sur un voyage d'exploration dans le Pont et en Cappadoce. *BCH* 33, 1-169
- Grothe, H.
- 1911 *Meine Vorderasienexpedition 1906 und 1907*, 1-2. Leipzig
- Harper, R. P.
- 1964 Roman senators in Cappadocia. *AnatSt* 14, 163-168
- 1970 Podandus and the Via Tauri. *AnatSt* 20, 149-153 and Pls 21-22
- 1972 Some Inscriptions of Roman Cappadocia. In *7 Türk Tarih Kongresi, Ankara 1970*, 160-165. Ankara (TTK Publ. Ser. VII, no. 7)
- Hild, F.
- 1977 *Das byzantinische Strassensystem in Kappadokien*. Wien (DenkschrWien 131)
- Hogarth, D. G. and Munro, J. A. R.
- 1893 *Modern and Ancient Roads in Eastern Asia Minor*. London (RGS Suppl. 3, 5)
- Jacopi, G.
- 1937 Missione archeologica italiana in Anatolia. Relazione sulla prima campagna esplorativa (settembre-novembre 1935). *Boll. Reale Ist.Arch. Storia dell'Arte* 7, 3-26 and Figs 1-90
- 1938 Esplorazioni e studi in Paflagonia e Cappadocia. Relazione sulla secunda campagna esplorativa (Agosto-October 1936). *Boll. Reale Ist.Arch. Storia dell'Arte* 8, 3-43 and Figs 1-162
- 1939 *Esplorazione e Studi in Paflagonia alla Commagene*. Roma (reprint of Jacopi 1938)
- Jerphanion, G. de
- 1914-21 Inscriptions de Cappadoce et du Pont. *MelBeyrouth* 7, 1-22
- 1928 Mélanges d'archéologie anatolienne. Monuments préhelléniques, gréco-romains, byzantins et musulmans de Pont, de Cappadoce et de Galatie. *MelBeyrouth* 13, 1-332 and Pls 1-120
- Jerphanion, G. de and Jalabert, L. de
- 1908 Inscriptions d'Asie Mineure (Pont, Cappadoce, Cilicie). *MelBeyrouth* 3, 437-478
- Keppie, L. J. F.
- 1991 *Understanding Roman Inscriptions*. London
- Kienast, D.
- 1996 *Römische Kaisertabelle. Grundzüge einer römischen Kaiserchronologie*. Darmstadt (2nd ed.; reprinted 2004)
- Le Bas, Ph. and Waddington, W. H.
- 1870 *Voyage archéologique en Grèce et en Asie Mineure* 3. *Inscriptions grecques et latines recueillies en Asie Mineure*. Part 5. *Asia Minor*. 1. *Inscriptions grecques et latines*. 2. *Explication des inscriptions*. Paris (repr. Hildesheim 1972)
- Le Guen-Pollet, Br.
- 1989 Sebastopolis du Pont (Sulusaray). *EpigrAnat* 13, 51-86 and Pls 8-10
- 1991a Liste des errata et corrigenda (*EpigrAnat* 13, 51ff). *EpigrAnat* 17, 101-102
- Lehmann, C. F.
- 1903 Zwei griechische Inschriften römischer Zeit aus Klein-Arménien und Kommagene. In *Festschrift zu Otto Hirschfelds sechzigstem Geburtstage*, 391-407. Berlin
- Loriot, X.
- 1976 Le Pont au III<sup>e</sup> siècle de notre ère. *BullSocNatAntFrance*, 44-61
- 1981 Les acclamations impériales dans la titulature de Sévère Alexandre et de Gordian III. *ZPE* 43, 225-235
- 1996 Sur la datation du proconsulat d'Asie de L. Egnatius Victor Lollianus. In Chastagnol, A. et al. (eds), *Splendidissimus Civitas. Études d'histoire romaine en hommage à François*

- Jacques*, 221-229. Paris
- 2006 Les gouverneurs du Pont de Gallien à Julien (260-363). In Demougin, S. et al. (eds) 2006, 399-445
  - McCrum, M. and Woodhead, A.G.
  - 1961 *Select documents of the principates of the Flavian Emperors AD 69-96*. Cambridge
  - Magioncalda, A.
  - 1984-85 La carriera di Cl. Aurelius Tiberius. *AnnGiurisprGenova* 20, 127-141
  - Mitford, T. B.
  - 1972 *The Roman Frontier on the Upper Euphrates*. Oxford DPhil
  - 1974 Some Inscriptions from the Cappadocian Limes. *JRS* 64, 160-175
  - 1980 Cappadocia and Armenia Minor: Historical Setting of the Limes. In Temporini, H. and Haase, H. eds, *ANRW* 2.7, 2, 1169-1228
  - 1988 Further Inscriptions from the Cappadocian Limes. *ZPE* 71, 167-178
  - Mommsen, Th.
  - 1884a Additamenta tertia ad Corporis vol. III. *EphEp* 5, 1-104
  - 1884b Accutarium additamentorum ad Corporis vol. III. *EphEp* 5, 569-624
  - Munro, J. A. R.
  - 1900 Some Pontic milestones. *JHS* 20, 159-166
  - Olshausen, E. and Biller, J.
  - 1984 *Historisch-geographische Aspekte der Geschichte des Pontischen und Armenischen Reiches. Teil 1. Untersuchungen zur historischen Geographie von Pontos unter den Mithratiden*. Wiesbaden (TAVO Beih. B 29/1)
  - Pekary, Th.
  - 1968 *Untersuchungen zu den römischen Reichstrassen*. Bonn (Antiquitas 1.17)
  - Petolescu, C. C.
  - 1991 Nots prosopographiques 4. *Dacia* 35, 201-203
  - Pflaum, H. G.
  - 1948 *Le marbre de Thorigny*. Paris
  - Polacco, L.
  - 1970 (1972) Topaklı. The 1970 campaign of excavation. *TürkAD* 19-1, 187-200
  - 1971 Topaklı. Campagna di scavo 1970. Relazione preliminare. *SMEA* 14, 27-38
  - 1972/73 Topaklı. Campagna di scavo 1970. Relazione preliminare. *AttiVenezia* 131, 85-100
  - Ramsay, W. M.
  - 1882a Inscriptions of Cilicia, Cappadocia and Pontus. *JPhil* 9, 142-160
  - 1883 Unedited inscriptions of Asia Minor. *BCH* 7, 258-278 and 297-398
  - 1903 Cilicia, Tarsus and the great Taurus pass. *GeogJ* 22, 357-413
  - 1904 Lycaonia. *ÖJhBeibl* 7, 57-132
  - 1916 Colonia Caesarea (Pisidian Antioch) in the Augustan Age. *JRS* 6, 83-134
  - 1941 *The social basis of Roman power in Asia Minor*. Aberdeen
  - Rémy, B.
  - 1989 *Les carrières sénatoriales dans les provinces romaines d'Anatolie au Haut-Empire*. Istanbul-Paris (Varia Anatolica 2)
  - von Ritter, C.
  - 1843 *Die Erdkunde . . . oder allgemeine vergleichende Geographie* 10. *Das Stufenland des Euphrat- und Tigrissystems*. Berlin
  - Sarre, F.
  - 1896a Reise in Phrygien, Lykien und Pisidia. *AEMÖ* 19, 26-57
  - 1896b *Reise in Kleinasien. Sommer 1895*. Berlin
  - Stein, A.
  - 1957 rev. Pflaum, *Le Marbre de Thorigny*, in *Eunomia* 1, 67, quoted Lorient 1976, 60

Sterrett, J.R.S.

- 1883-84 *An epigraphical journey in Asia Minor*. Boston (Pap. Amer. School Class. St. 2)
- 1885 *Preliminary report of an archaeological journey made in Asia Minor during the summer of 1884*. Boston

Taylor, J. G.

- 1868 Journal of a tour through Armenia, Kurdistan and Upper Mesopotamia. *JRGS* 38, 281-361

Thomasson, B.

- 1984 *Laterculi Praesidum* 1. Göteborg (1st ed.)
- 2009 *Laterculi Praesidum* 1. Göteborg (2nd ed.) (electronic publication)

Thompson, R. C.

- 1910 A Journey by some unmapped Routes in the Western Hittite Country between Angora and Eregli. *Proc. Soc. Bibl. Arch.* 32, 181-191, 237-242, 289-295

Tibiletti, G.

- 1971 Nota al miliario di Çalış. *OA* 10: 67-74
- 1977 Un miliario romano dell' Cappadocia recentemente scoperto. *Epigraphica* 39, 168-171

Townsend, P. W.

- 1955 Sextus Catus Clementinus Priscillianus, Governor of Cappadocia in A.D. 238. *ClPhil* 50, 41-42

Waddington, W. H.

- 1883 Inscriptions grecques et latines de Cataonie. *BCH* 7, 125-148

Wagner, J.

- 1985 (ed.) *Die Römer am Euphrat und Tigris*. Feldmeilen (Antike Welt 16. Sondernummer)

Wilson, D. R.

- 1958 *Exploration in Pontus 1958*. (Typescript notes in BIA Library)
- 1960 Two milestones from Pontus. *AnatSt* 10, 133-140

Yavi, E.

- 1986 *Tokat*. İstanbul

Yorke, V. W.

- 1898 Inscriptions from Eastern Asia Minor. *JHS* 18, 306-327

Yüce, A.

- 1992 Uygur'da Bulunan Mil Taşları. *TürkAD* 30, 209-215 and Figs 1-2

### 3. NOTES AND COMMENTS

#### 3.1 The Imperial Titulature on Nervan and Trajanic Milestones of Cappadocia

If Anderson's text of the Abdalata, Tekke milestone (below, no. 041) was correctly recorded, the position of the numeral II at the end of the imperial titulature probably indicates the Traianic sequence **TR·P·P·P·COS II**. This sequence in Traianus' titulature is certainly invariable on milestones of Galatia (in the territory of Ancyra) and, with one exception, of Cappadocia. This exception is the Trajanic milestone, 003. Yavaşhan (in the territory of Caesaria) on which the imperial titulature follows a different sequence, namely, **TR·P·COS·P·P**. There is, however, one other variation in this text: the omission of a numeral after TR·P, namely **TR·P·(III)·COS·III·P·P**.

Interestingly, this sequence, **TR·P·COS·P·P**, is found on Nervan milestones both of Galatia (territories of Ancyra and Tavium) and of Cappadocia (territories certainly of Amasia and Caesaria, probably of Comana Pontica). Again, however, there is an exception. On a discrete group of Nervan milestones - discovered on the territory of Neoclaudiopolis and of Colonia Iconium - the imperial titulature follows the sequence, **TR·P·P·P·COS**, employed, as indicated above, on all the known Trajanic milestones of Galatia and of Cappadocia (with the one exception).

On coins of Nerva the obverse titulature invariably adopts the sequence **TR·P·COS·P·P**, e.g. RIC 2: 223 (AD 96), 224-225 (AD 97). The coins of Traianus continued to employ this same sequence, **TR·P·COS·P·P** - which had been used (1) for coins of Nerva and (2) for the Nervan titulature on the above-mentioned group of milestones found on the territories of Neoclaudiopolis and Colonia Iconium - in stark contrast with the imperial titulature employed on all but one Trajanic milestone (003. Yavaşhan).

#### 3.2 The *praenomen* of Septimius Geta

On the *praenomen*, see Kienast (Kienast 1996, 166): "P. Septimius Geta, von 195–205 (?) vorübergehend auch L. Septimius Geta".

On the 149(A). Uluköy 1 milestone, the L of L. Septimius Geta is unequivocally preserved. Other instances occur in Cappadocia, all on the Caesaria - Melitena road:

- 105(A). Göksun 8
- 107(C). Yağmurlu 3
- 108(I). Kanlıkavak 9(1)
- 118(B). Izgın, Çatburun 2
- 147(D). Izgın 1(2)

An example of the *praenomen* P(ublius) for Septimius Geta has not yet been recorded on Cappadocian milestones.

#### 3.3 The Date of 108(C). Kanlıkavak 3 and the Governor, Cat(ius) Clement[ - ]

On the date of the milestone, 108(C). Kanlıkavak 3, see the recent discussion (French 2008, 125-130) where it is suggested that the name inscribed on this milestone was not Gordianus *Caesar* with Pupienus and Balbinus *Augusti*, as previously thought, but Diadumenianus *Caesar* with Macrinus *Augustus*. On the basis of the Demirci milestone (below, no. 161) the name [Opellio] Antonino fits the recorded letter-losses and the available spaces better, in my view, than the name Ant. Gordiano;



*contra* Thomasson (2009, 110 no. **29:37a**) who notes the acknowledged uncertainties (French l.c.).

Cuspidius Flaminus Severus is well attested as governor of Cappadocia under Gordianus *Caesar*; he thereafter continued his governorship under Gordianus *Augustus* (see below, **3.4**). It is possible that Catus Clemens – it is not clear whether the cognomen of the governor was Clemens or Clementinus – was governor of Cappadocia first under Maximinus with Maximus *Caesar* (i.e. AD 237-238) after Licinnius Serenianus (also governor under Maximinus with Maximus *Caesar*; see below, **3.3**) and then – for a very brief span in the 99 days during which Pupienus and Balbinus were *Augusti* and Gordianus was *Caesar* – remained governor before Cuspidius Flaminus Severus became governor while Gordianus was still *Caesar*. Hence the uncertainties.

In the light of the Kirkgeçit stone (below, no. 165), I here make an adjustment to my earlier proposal for the sequence of governors (French 2008, 130) and to the chronology both of the other Macrinus texts on the Pilgrim's Road (nos 159, 161) and of Kanlıkavak 3 (no. 108[C]). A coherent group, the three milestones (nos 159, 165, 169), record major road work – on the *Via Tauri* – datable to AD 217, 11 April – mid-June; the similarity in the phraseology of the two texts (nos 165, 166) I suggest that (1) the Macrinus text (no. 165) can be interpreted as a continuation of similar road-work (of Caracalla [no. 166]) dated to the early months of the same year, AD 217, and further (2) that the work, both under Caracalla and under Macrinus, was supervised by the same governor, Sulla Cerialis, who was then replaced by Catus Clemens [ - ] for the second half of AD 217 to mid-218. On this chronology, therefore, the Kanlıkavak milestone records road-work carried out later, in AD 217-218 (?), by Catus Clemens [ - ].

### **3.4 Licinnius Serenianus, on Milestones of Severus Alexander and Maximinus**

It is possible to argue that the two-line space between lines 4 and 7 of 079(B). Çakırlar, Barcın Geçidi 2 constitutes evidence for an earlier inscription (of Severus Alexander) which was erased and replaced by the text of Maximinus. If this argument (French 2008, 130-131) is correct, it can be concluded that Licinnius Serenianus was appointed governor of Cappadocia in the last year (AD 235) of Severus Alexander and continued his office under Maximinus. A similar, vacant space showing traces of erasure of an earlier inscription occurs on two other stones, 083 and 085(B).

In general the name of Licinnius Serenianus was erased, more often than not, on milestones of Cappadocia. The governor's name, however, was not universally excised: on the Caesaria-Melitene road it survives intact on two stones: 098(B). Keklikoluk 2 and 107(D). Yağmurlu 4 (and, if the restorations are correct, on 086(A). Kemer 13 and 100(A). Keklikoluk 4), and on the Tavium-Zela road at Çomar (RRMAM 3.1.57). The erasure is clearly visible on 083, 085(B) and (D), 092(A), 097(B) and 126(B). On these erasures, however, note the comment made by Christol and Lorient (1993, 217 and n. 38): “Il n'y a pas de raison déterminante de les attribuer systématiquement à Licinnius Serenianus”.

On Licinnius Serenianus, governor of Cappadocia, Hogarth and Munro noted (1893, 709): “Prof. Ramsay refers to Cyprian, ‘Epp.’ 75. 10, where Serenianus, ‘acerbus et dirus persecutor’, is said to have been governor of Cappadocia in AD 235”. The same comment and reference is made by Thomasson (1984, 272 no. **44**; 2009, 111 no. **29:044**). Can the erasure of Serenianus' name be safely attributed to the work of later (post-Constantinian?) Christians? cf. the comments of Baz (2007, 89 and n.152): “Die Grund für die Rasur bleibt im Dunkeln”.

It is of interest to observe that of all the governors of Cappadocia only the name of Licinnius Serenianus was the target of erasure. On two (ex 15) milestones the full text is intact, the imperial

names and titles neither lost nor damaged and the governor's name clearly preserved. The presence of an erasure then becomes significant for those texts, e.g. 079(B). Çakırlar, Barcın Geçidi 2 (no. 2 below), and 094(A). Doğankonak 1 (no. 7 below), on which the governor's name has been erased: on the basis of the Çomar and the Yağmurlu 4 texts (which are intact), all can be attributed, with some certainty, to Maximinus. On three (nos 079[B], 083 and 085[B]) there is a double erasure of Licinnius Serenianus' name, one on a text of Severus Alexander, the other on a text of Maximinus.

1. – Çomar (- RRMAM 3.2.057, on the territory of Tavium)	intact text
2. 079(B). Çakırlar, Barcın Geçit 2(1),(2)	[erased]
3. 083. Şar 2(1),(2)	[erased]
4. 085(B). Mollahüseyin 2(1),(2)	[erased]
5. 085(D). Mollahüseyin 5	[erased]
6. 086(A). Kemer 13	restored text
7. 094(A). Doğankonak 1	[erased]
8. 097(B). Doğankonak, Şabanağa Mevkii 2	[erased]
9. 098(B). Keklikoluk 2	[erased]
10. 100(A). Keklikoluk 4	[erased]
11. 104(C). Göksun 3	[erased]
12. 107(D). Yağmurlu 4	intact text
13. 118(D). Izgın, Çatburun 4	[erased?]
14. 127. Sevdilli, Büyükköy Mezrası	[erased]
15. 128(B). Yaztopallı 2	[erased]

Licinnius Serenianus was, on this evidence, governor of Cappadocia in the final year or years of Severus Alexander and for the first year or years of Maximinus.

### 3.5 Pupienus and Balbinus, and Gordianus III: a Sequence of Text-forms

The recent publication (Boybeyi and Probst 2008, 135) of the text on a milestone found at Keklikoluk (here 098(D). Keklikoluk 7) raises the possibility that the sequence of text-forms independently advanced (French 2008, 131-132) for milestones (of Gordianus III) found on the Caesaria - Melitene road should now be revised in one particular. Text-form (4) was proposed as follows: "Erasure of the Augusti on text-form (1); the names and titles of Gordianus inscribed in the area of the erasure; '-erunt' not re-cut to '-it'". This proposal requires revision.

Boybeyi and Probst (2008, 137 and n.9) observed that there is no evidence of erasure on the Keklikoluk 7 stone. They point out also that the verb *restituerunt* was retained (ungrammatically) from an earlier exemplar which named Pupienus and Balbinus with or without Gordianus. On one milestone (098[H]. Yalak 12) the plural *-erunt* has evidently been re-cut to *-it*. They argued for all texts similar to Keklikoluk 7 (Gordianus in the dative case and *restituerunt* unchanged) to be *quasi als eine Loyaltätsbekundung des Statthalters Cuspidius Flaminius Severus*; for milestones as honorific dedications, see Pekary (1968, 16-22 "Zur Dedikationscharakter der Meilensteine").

After further examination of the squeezes taken on the other milestones in question, it can now be accepted that the observation made by Boybeyi and Probst is entirely correct. There are no evident traces of an erased, earlier text (of Pupienus and Balbinus, with or without Gordianus) which was replaced after Gordianus became Augustus. Accordingly, the text-form (4) in the proposed schema (French 2008, 131-132) must be now interpreted not as a re-cutting over an earlier version but as a unique, if somewhat ungrammatical, text of Gordianus *Augustus*. The published schema should, therefore, be revised as follows:

(1) A new inscription

**Imp Caes - - - - Pupienus et - - - - Balbinus, . . . . Augusti . . . . , restituerunt  
per Cuspidium Flaminium Severum**

No example survives.

(2) A second, new inscription

**Imp Caes - - - - Pupienus et - - - - Balbinus, . . . . Augusti . . . . et  
M Antonius Gordianus nobilissimus Caesar restituerunt  
per Cuspidium Flaminium Severum**

No example survives.

(3) Adaptation of text-form (2); the names of the two Augusti on text-form (2) erased; the area of the erasure not re-inscribed; ‘-erunt’ re-cut to ‘-it’. The initial title ‘Imp Caesar’ of text-form (2) were retained for, and applied to, Gordianus; however, the words describing his former status ‘nobilissimus Caesar’ were not removed.

**Imp Caes - - - - Pupienus et - - - - Balbinus, . . . . Augusti . . . . et  
M Antonius Gordianus nobilissimus Caesar restituit  
per Cuspidium Flaminium Severum**

3 examples, e.g. 087(B). Kemer 2 (CIL 3. 6953; RRMAM 2. 546)

(4) A new inscription (on a new stone); ‘restituerunt’ retained from the earlier rubric.

**Imp (or Imper) Caesar M Antonio Gordiano . . . . Augusto restituerunt  
per Cuspidium Flaminium Severum legatum pro praetore**

14 examples, e.g. 089(B) Kemer 8 (CIL 3. 12198; RRMAM 2. 552)

(5) A new inscription (on a new stone)

**Imp Caes M Antonius Gordianus . . . . Augustus . . . . restituit  
per Cuspidium Flaminium Severum**

1 example, 120(B). Izgın 2 (CIL 3. 6905, 12168; RRMAM 2. 776)

The relevant milestones (on the Caesaria – Melitene road) naming Gordianus are as follows:

#### **Gordianus III Caesar**

Gordianus in nominative

087(B). Kemer 2

[6 lines erased above Gordianus]

restituit; re-cut ?

093(H). Yalak 12

[4 lines erased above Gordianus]

restituit; re-cut

104(B). Göksun 2(1)

[(? no. of) lines above Gordianus]

restituit; re-cut ?

#### **Gordianus III Augustus**

Gordianus in dative

068(C). Aslanbeyli Yaylası, Hanboğaz 3

restituerunt

072(C). Değirmentaş, Arkaçlar Mvk. 2.3	restituerunt
074(C). İmirzağa, Eski Harabe Mvk. 3	restituerunt
075(C). İmirzağa, Barçin Mvk. 3	restituerunt
079(D). Çakırlar, Barçin Gç. 4	restituerunt
080(B). Çakırlar, Meşelik 2	restituerunt (restored)
084. Mollahüseyin 4	restituerunt
089(B). Kemer 8	restituerunt
095. Doğankonak, Kumocağı (1)	restituerunt
097(C). Doğankonak, Şabanağa Mvk. 3	restituerunt
098(D). Keklikoluk 7	restituerunt
105(D). Göksun 11(1)	restituerunt
108(F). Kanlıkavak 6	restituerunt
108(M). Kanlıkavak 13	restituerunt (restored)

**Gordianus III Augustus**

Gordianus in nominative

120(B). Izgın 2

rest[itu]it

### 3.6 Truncated Texts of the Tetrarchy

The spread of the full text of the Tetrarchs over more than two stones can now be seen (French 2008, 133) as an acceptable explanation for the occurrence of seemingly incomplete texts of Diocletianus and his colleagues.

### 3.7 The formula ‘- - orum’

On three milestones found within the territory of Amasia the word *Amasenorum* occurs without qualification:

040. Saray II. 9-11 ‘viam re[st]ituit m p l Amasenorum’ (no distance figure)	[?]
Gordianus III]	
044. Sapa II. 9-11 ‘viam restituit l m p Amasenorum’ (no distance figure)	[Gordianus III]
046. Ertuğrul II. 2-5 ‘(viam?) restituit l m p Amasenorum mil p LXXV l oe’	[? Gordianus III]

The emperor is cited in the nominative case, i.e. the subject of ‘restituit’. A straightforward restoration for *Amasenorum*, namely ‘(civitas) Amasenorum (dedicavit)’, would, therefore, be ungrammatical.

At the neighbouring city of Zela, modern Zile, there are four examples of an abbreviated formula which is relevant here:

1. 056(A). Zelit + the emperor’s name in the nominative case
2. 056(B). Civ Zel + the emperor’s name in the dative case
3. 056(C). Zelit + the emperor’s name in the dative case
4. 056(D). Zelit + the emperor’s name in the dative case

In the third example, it is possible to restore CIV as civ(itas), i.e. civ(itas) Zelit(anorum dedicavit). Similarly, Zelit – in examples 3 and 4 – may be completed as an abbreviation for (civitas) Zelit(anorum dedicavit). The first example, on the other hand, follows the uncertainty of the texts at Sapa and Ertuğrul on the territory of Amasia.

The formula ‘civita(s) or civitat(e) + genitive plural -orum’ is found on milestones of Cappadocia and of other provinces; for Cappadocia, cp. Civitas Nicopolitanor(um), 048. Akşar. On the territory of Amasia a possible interpretation would then be ‘(civitate) Amasenorum’, “from the city of Amasia” or, at Zile, ‘civ(itate) Zelit(anorum)’. A genitive, ‘civitat(is) Amasenorum’, would depend an (uninscribed) noun.

Noteworthy, in this context, is the formula ‘ad fines -orum’, known elsewhere in Asia Minor. It should also be noted that on this same road the phrase ‘ad fines Galatorum’ was used at least twice (023(A). Bağlıca 1 and 036. Güngörmez), though in both cases perhaps somewhat derogatively. No doubt at Saray, Sapa and Ertuğrul the words ‘ad fines’ could be readily understood, even if not inscribed on the stone: (ad fines) Amasenorum. If, then, ‘Amasenorum’ is not linked to ‘m p’, what is the meaning of ‘m p’ on the Sapa and Ertuğrul milestones?

### 3.8 Provincial Boundary (Maps 5.1.1-2)

The boundary of the province has been drawn in broad terms, as it is indicated, largely, by the location of milestones – dated to the sixth year of Septimius Severus, AD 197/198 – bearing the name of the governor, C. Iulius Flaccus Aelianus; cp. RRMAM 3.2 Galatia Notes and Comments. In the south Severan milestones (of AD 197/198) are found on the territory of Melitene and in the north on the city-territories of Amasia and Neocaesaria. East of these two cities lie the city of Nicopolis and eastwards beyond Nicopolis the territory of Satala in Armenia Minor. *The Itinerarium Antonini* (217,2) locates the *fines* of Pontus at Sedisca (? in the mountains c. 15 km SW of Gümüşhane). On the east the Euphrates river is taken to be the boundary and, on the south, the Taurus mountains (specifically at the Cilician Gates) (*Itinerarium Burdigalense* 579,1). On the west the province is defined by eastern border of Galatia (RRMAM 3.2 Galatia Maps 5.1.2). The *Itinerarium Burdigalense* (576,3) locates the *fines* of Galatia and Cappadocia between *mutatio Andrapa* and *mansio Parnasso*, probably at a point [now flooded by the waters of the Hırfanlı dam] on the Acı Dere stream, c. 13.5 km NW of Değirmenyolu [formerly Parlasan], ancient Parnassus.

The boundary of the province Cappadocia, in the sixth year of Septimius Severus’ rule, is illustrated here on Maps 5.1.1-2 Conspectus Maps. A description of the relevant terrain and physical features in addition to a detailed account of roads, both observed and reported, is given in the parallel volume, RRMAM 4. Roads. Fasc. 3. Cappadocia.

### 3.9 Imperial Dates

The imperial dates, cited here, are taken from the tables published by Kienast (1996).

### NOTE on Photographs and Squeezes

The photographic illustrations in the fascicules of RRMAM are not intended to give more than a visual indication of the location and condition of the milestone: in publishing photographs in this and in all the fascicules of RRMAM I have been attempting to illustrate their state as recorded. My photographs do not, indeed mostly cannot, stand as an ultimate authority on the text. I decided at the outset of my work that when a milestone is extant, accessible and recordable, the primary source for the text would be, if at all possible, a paper squeeze made with one or multiple (overlapping but not bonding) sheets of a standard size; but cf. the method introduced by Walser (1971). My squeezes are stored in the BIA. Photographs of the collection are available on the BIA website: [www.biaatr.org/squeeze/index.php](http://www.biaatr.org/squeeze/index.php).

## **4. MILESTONES**

#### 4.1 Numbered Milestones

- |                                    |  |
|------------------------------------|--|
| 001. Sarılar                       | 049. Aşağı Ekecik 1-3                        |
| 002. Çalış                         | 050. Boğazbaşı, formerly Dönekse 1-2         |
| 003. Yavaşhan                      | 051. Yağmurlu, formerly Ohtap                |
| 004. Yurtbaşı, formerly Melikşerif | 052. Gözova, formerly Omala 1-2              |
| 005. Olgunlar, formerly Sipdiğin   | 053. Kılıçlı, formerly Gömenek               |
| 006. Gölova, formerly Ağvanis      | 054. Tokat 1-6 & Museum 1-2                  |
| 007. Sevindik                      | 055. Turhal 1-2                              |
| 008. Küçük Güzel                   | 056. Zile 1-4                                |
| 009. Hatipli                       | 057. Kurupınar                               |
| 010. Niksar                        | 058. Kargın                                  |
| 011. Çaltılı, formerly Zilhor      | 059. Çamlıbel                                |
| 012. Akça, formerly Fidi           | 060. Kervansaray                             |
| 013. Çalkara                       | 061. Sulusaray                               |
| 014. Karaağaç                      | 062. Dutluca, formerly Malumseyit            |
| 015. Çakırsu, formerly Yornus      | 063. Uylubağı                                |
| 016. Yerkozlu                      | 064. Elmalı                                  |
| 017. Aşağı Baraklı 1-2             | 065. Kayseri                                 |
| 018. Çiğdemlik, formerly Zana      | 066. Sakaltutan                              |
| 019. Amasya                        | 067. Özlüce, formerly Taf 1-4                |
| 020. Bulduklu                      | 068. Aslanbeyli Yaylası, Hanboğaz 1-5        |
| 021. Aydoğdu                       | 069. Aslanbeyli Yaylası, Hanyeri             |
| 022. Boğa                          | 070. Değirmentaş 1-4                         |
| 023. Bağlıca 1-2                   | 071. Değirmentaş, Arkaçlar Mevkii 1.1-2      |
| 024. Doğanstepe, formerly Zara     | 072. Değirmentaş, Arkaçlar Mevkii 2.1-7      |
| 025. Toklucak, formerly Oluz       | 073. İmirzağa                                |
| 026. Karayakup                     | 074. İmirzağa, Eski Harabe Mevkii 1-4        |
| 027. Çavuş                         | 075. İmirzağa, Barçın Mevkii 1-9             |
| 028. Beke                          | 076. Çakırlar form. Elemanlı, Barçın Yaylası |
| 029. Boğazkaya, formerly Bebük 1-4 | 077. Çakırlar form. Elemanlı, Karapınar 1-3  |
| 030. Figani 1-3                    | 078. Çakırlar form. Elemanlı, Beşiktaş 1-3   |
| 031. Köseeyüp                      | 079. Çakırlar form. Elemanlı, Barçın Geçidi  |
| 032. Kozören 1-3                   | 1-7  |
| 033. Çitli 1-2                     | 080. Çakırlar form. Elemanlı, Meşelik 1-5    |
| 034. Mecitözü 1-2                  | 081. Çakırlar formerly Elemanlı              |
| 035. Elvançelebi                   | 082. Şar 1                                   |
| 036. Güngörmez                     | 083. Şar 2                                   |
| 037. Çorum 1-2 & Museum            | 084. Mollahüseyin 4                          |
| 038. Tolahmet                      | 085. Mollahüseyin 1-3, 5-6                   |
| 039. Karapınar                     | 086. Kemer 13-14                             |
| 040. Saray                         | 087. Kemer 1-2                               |
| 041. Abdalata, Tekke               | 088. Kemer 3-6                               |
| 042. Çeşmeören, formerly Harzadin  | 089. Kemer 7-12                              |
| 043. Hamdi                         | 090. Dayıoluk 1-4                            |
| 044. Sapa                          | 091. Dayıoluk 5                              |
| 045. Seyfe                         | 092. Yalak 5-8                               |
| 046. Ertuğrul                      | 093. Yalak 1-4, 9-12                         |
| 047. Deniz                         | 094. Doğankonak, formerly Haydan 1-4         |
| 048. Akşar                         | 095. Doğankonak, form. Haydan, Kumocağı      |

096. Doğankonak, form. Haydan, Sakaltutan Boğazı  
 097. Doğankonak, form. Haydan, Şabanağa Mevkii 1-6  
 098. Keklikoluk 1-2, 6-7  
 099. Keklikoluk 3  
 100. Keklikoluk 4-5  
 101. Keklikoluk, Kayapınar Mevkii 1-5  
 102. Mürsel 1-3, 4-6  
 103. Mehmetbey 1-2  
 104. Göksun 1-7, 13-14, 17-19  
 105. Göksun 8-12  
 106. Göksun 15-16  
 107. Yağmurlu, formerly Aziz 1-7  
 108. Kanlıkavak 1-19  
 109. Yeniyapan 1-6  
 110. Karaömer 1  
 111. Karaömer 2-3  
 112. Düğünyardu  
 113. Karaömer, Kızılcaşuyu Mahallesi 1-3  
 114. Ördek  
 115. Alımpınar  
 116. Afşin 1-3  
 117. Emirli 1-2  
 118. İzgın, Çatburun 1-4  
 119. Çağılhan 1-2  
 120. İzgın 1-2  
 121. Yapraklı, formerly Burtu  
 122. Hasankendi  
 123. Elbistan 1-14  
 124. Demircilik 1-2  
 125. Güçük 1-2  
 126. Sevdilli, Büyükköy Mezraası  
 127. Sevdilli, Gölpınar Mezraası  
 128. Yaztopallı 1-3  
 129. Gözecik 1-3  
 130. Darıca  
 131. Şekerpınar  
 132. Fethiye, formerly Hasanbadri  
 133. Porsuk 1-3  
 134. Akbenliçiftlik  
 135. İzibüyük  
 136. Kabalı  
 137. Kadışehri  
 138. Çamsaray, formerly Dabana  
 139. Özükevak  
 140. Güzelbeyli, formerly Silis 1-2  
 141. Yıldıztepe  
 142. Alayurt, form. Araplar  
 143. Akyazı  
 144. Mahmatlar  
 145. Uygur 1-2  
 146. Ezinepınar  
 147. Kapıkaya 1-4  
 148. Suluova  
 149. Uluköy, formerly Sonusa 1-3  
 150. Ilıca 1-2  
 151. Şebinkarahisar  
 152. Elmelik  
 153. Sadak  
 154. Tütenli  
 155. Eskimalatya  
 156. Bahçebaşı, formerly Orduzu  
 157. Gülhüyük, formerly Muhlisoba  
 158. Değirmenyolu, formerly Parlasan  
 159. Topakkaya, formerly Çimenliyolu  
 160. Aksaray  
 161. Demirci  
 162. Kemerhisar, Salmanlı Çiftlik 1-3  
 163. Kavuklu 1-3  
 164. Eminlik 1-2  
 165. Kırkgeçit Deresi  
 166. Pozantı 1  
 167. Pozantı 2  
 168. Pozantı, Soğukpınar



## 4.2 Designated Roads and Numbered Milestones

### A. IN GALATIAM

1. Tyana - Nysa (- Ancyra) . . . . . (2.F.12)  
 2. Caesaria (per Aquas Saruvenas) (- Ancyra) . . . . . (2.F.8) . . . 001-002

001. Sarılar

002. Çalış


3. Caesaria (per Therma) (- Tavium) . . . . . (2.F.7)  
 4. Melitene (per Basilika Therma) (- Tavium) . . . . . (2.F.6)  
 5. Amasia (- Gangra) . . . . . (2.F.1)  
 6. Caesaria - Colonia Archelaïs (- Colonia Iconium) . . . . . (2.F.9)  
 7. Caesaria - Tyana - Sidamaria (- Barata) (- Colonia Iconium) . . . . . (2.F.10) . . . 003

003. Yavaşhan

8. Sidamaria (- Cana - Savatra) . . . . . (2.F.11)  
 9. Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra) . . . . . (2.F.2) . . . 004-047


004. Yurtbaşı, form. Melikşerif  
 005. Olgunlar, form. Sipdiğin  
 006. Gölova, form. Ağvanis  
 007. Sevindik  
 008. Küçük Güzel  
 009. Hatipli  
 010. Niksar  
 011. Çaltılı, form. Zilhor  
 012. Akça, form. Fidi  
 013. Çalkara  
 014. Karaağaç  
 015. Çakırsu, form. Yornus  
 016. Yerkozlu  
 017. Aşağı Baraklı 1-2  
 018. Çiğdemlik, form. Zana  
 019. Amasya  
 020. Bulduklu  
 021. Aydoğdu  
 022. Boğa  
 023. Bağlıca 1-2  
 024. Doğanentepe, form. Zara  
 025. Toklucak, form. Oluz  
 026. Karayakup  
 027. Çavuş  
 028. Beke  
 029. Boğazkaya, form. Bebüke 1-4  
 030. Figani 1-3  
 031. Köseeyüp  
 032. Kozören 1-3

## 5.1 Conspectus Maps



### 5.1.1 Cappadocia West

## 5.1 Conspectus Maps



### 5.1.2 Cappadocia East

- 033. Çitli 1-2
- 034. Mecitözü 1-2
- 035. Elvançelebi
- 036. Güngörmez
- 037. Çorum 1-2 & Museum
- 038. Tolahmet
- 039. Karapınar
- 040. Saray
- 041. Abdalata, Tekke
- 042. Çeşmeören, form. Harzadin
- 043. Hamdi
- 044. Sapa
- 045. Seyfe
- 046. Ertuğrul
- 047. Deniz

10. Nicopolis - Sebastia (- Tavium). . . . . (2.F.5) . . . 048-049

- 048. Akşar
- 049. Aşağı Ekecik 1-3

11. Neocaesaria - Zela (- Tavium - Ancyra) . . . . . (2.F.3) . . . 050-057

- 050. Boğazbaşı, form. Dönekse 1-2
- 051. Yağmurlu, form. Ohtap
- 052. Gözova, form. Omala 1-2
- 053. Kılıçlı, form. Gömenek
- 054. Tokat 1-6 & Museum 1-2
- 055. Turhal 1-2
- 056. Zile 1-4
- 057. Kurupınar

12. Sebastia - Sebastopolis (- Tavium) . . . . . (2.F.4) . . . 058-064

- 058. Kargın
- 059. Çamlıbel
- 060. Kervansaray
- 061. Sulusaray
- 062. Dutluca, form. Malumseyit
- 063. Uylubağı
- 064. Elmalı

## **B. PER GALATIAM IN ASIAM**

1. Salaberina (- Comitanassus - Amorium) (*compendium* ?) (2.B.1)(5.B.1)

## **C. CAPPADOCIA**

- 1. Colonia Archelaïs - Tyana
- 2. Caesaria - Sebastia . . . . . 065

## 065. Kayseri

## 3. Caesaria - Melitena . . . . . 066-130

- 066. Sakaltutan
- 067. Özlüce, form. Taf 1-4
- 068. Aslanbeyli Yaylası, Hanboğaz 1-5
- 069. Aslanbeyli Yaylası, Hanyeri
- 070. Değirmentaş 1-4
- 071. Değirmentaş, Arkaçlar Mevkii 1.1-2
- 072. Değirmentaş, Arkaçlar Mevkii 2.1-7
- 073. İmirzağa
- 074. İmirzağa, Eski Harabe Mevkii 1-4
- 075. İmirzağa, Barçin Mevkii 1-9
- 076. Çakırlar form. Elemanlı, Barçin Yaylası
- 077. Çakırlar form. Elemanlı, Karapınar 1-3
- 078. Çakırlar form. Elemanlı, Beşiktaş 1-3
- 079. Çakırlar form. Elemanlı, Barçin Geçidi 1-7
- 080. Çakırlar form. Elemanlı, Meşelik 1-5
- 081. Çakırlar form. Elemanlı
- 082. Şar 1
- 083. Şar 2
- 084. Mollahüseyin 4
- 085. Mollahüseyin 1-3, 5-6
- 086. Kemer 13-14
- 087. Kemer 1-2
- 088. Kemer 3-6
- 089. Kemer 7-12
- 090. Dayıoluk 1-4
- 091. Dayıoluk 5
- 092. Yalak 5-8
- 093. Yalak 1-4, 9-12
- 094. Doğankonak, form. Haydan 1-4
- 095. Doğankonak, form. Haydan, Kumocağı
- 096. Doğankonak, form. Haydan, Sakaltutan Boğazı
- 097. Doğankonak, form. Haydan, Şabanağa Mevkii 1-6
- 098. Keklikoluk 1-2, 6-7
- 099. Keklikoluk 3
- 100. Keklikoluk 4-5
- 101. Keklikoluk, Kayapınar Mevkii 1-5
- 102. Mürsel 1-3, 4-6
- 103. Mehmetbey 1-2
- 104. Göksun 1-7, 13-14, 17-19
- 105. Göksun 8-12
- 106. Göksun 15-16
- 107. Yağmurlu, form. Aziz 1-7
- 108. Kanlıkavak 1-19
- 109. Yenyapan 1-6
- 110. Karaömer 1
- 111. Karaömer 2-3

112. Düğün yurdu
113. Karaömer, Kızılcasuyu Mahallesi 1-3
114. Ördek
115. Alımpınar
116. Afşin 1-3
117. Emirli 1-2
118. İzgın, Çatburun 1-4
119. Çağılhan 1-2
120. İzgın 1-2
121. Yapraklı, form. Burtu
122. Hasankendi
123. Elbistan 1-14
124. Demircilik 1-2
125. Gücük 1-2
126. Sevdilli, Büyükköy Mezraası
127. Sevdilli, Gölpınar Mezraası
128. Yaztopallı 1-3
129. Gözecik 1-3
130. Darıca

4. Sebastia - Melitene . . . . . 131-132

131. Şekerpınar
132. Fethiye, form. Hasanbadrik

5. Sebastia - Comana Pontica
6. Sebastia - Neocaesaria
7. Satala - Arabissus (*compendium?*)
8. Sebastia - Cocusus (*compendium?*)
9. Nicopolis - (*via per ripam*) [Arauracos]
10. Nicopolis - (*via per ripam*) [Analiba]
11. Nicopolis - (*via per ripam*) [Zimara]
12. Nicopolis - Comana Pontica
13. Cybistra - Pylae . . . . . 133(A),(C)

133(A)(C). Porsuk 1, 3

14. Tyana - Pylae . . . . . 133(B)

133(B) Porsuk 2

15. Amasia - therma
16. Zama - therma

#### **D. DE GALATIA PER CAPPADOCIAM IN PONTUM ET BITHYNIAM**

1. (Ancyra -) per territorium Amasiae (- Amisus) . . . . . (2.D.1)(4.D.1)

**E. PER GALATIAM IN PONTUM ET BITHYNIAM**

1. Amasia (- Antoniopolis) (- Claudopolis) . . . . . (2.E.1)(4.E.1)

**F. IN PONTUM ET BITHYNIAM**

1. Caesaria - Zela - Amasia (- Amisus) . . . . . (4.F.1) . . . 134-148

134. Akbenliçiftlik  
135. İzibüyük  
136. Kabalı  
137. Kadışehri  
138. Çamsaray, form. Dabana  
139. Özükkavak  
140. Güzelbeyli, form. Silis 1-2  
141. Yıldıztepe  
142. Alayurt, form. Araplar  
143. Akyazı  
144. Mahmatlar  
145. Uygur 1-2  
146. Ezinepınar  
147. Kapıkaya 1-4  
148. Suluova

2. Neocaesaria ([ - Pompeiopolis] - Nicomedia) . . . . . (4.F.2) . . . 149-150

149. Uluköy, form. Sonusa 1-3  
150. Ilıca 1-2

3. Neocaesaria (- Polemonium) . . . . . (4.F.3)  
4. Nicopolis (- Polemonium) . . . . . (4.F.4)  
5. Nicopolis - Colonia (- Cerasus) . . . . . (4.F.5) . . . 151

151. Şebinkarahisar

**G. IN CILICIAM, ISAURIAM ET LYCAONIAM**

1. Sidamaria (- Derbe - Laranda) . . . . . (7.D.1)  
2. Cocusus (- Flaviopolis - Anazarbus - Mopsuestia) . . . . . (7.D.2)

**H. IN COMMAGENAM SYRIAE**

1. [Caesaria - Melitena road] - Cocusus (- Germanicia) . . . . . (8.B.2)  
2. Melitena - Sozopetra (- Doliche). . . . . (8.B.3)  
3. Melitena per ripam ad Samosata . . . . . (8.B.1)

**L. DE PONTO ET BITHYNIA PER CAPPADOCIAM AD SYRIAM USQUE**

1. (Trapezus) - Satala per ripam ad Melitenam (- Samosata) . . . . . (4.L.1)(8.L.1) . . . 152-156

- 152. Elmelik
- 153. Sadak
- 154. Tütenli
- 155. Eskimalatya
- 156. Bahçebaşı, form. Orduzu

**P. PER PONTUM ET BITHYNIAM, GALATIAM, CAPPADOCIAM  
ET CILICIAM, ISAURIAM ET LYCAONIAM AD SYRIAM USQUE**

1. (The Pilgrim's Road) (Chalcedon - Nicaea - Iuliopolis - Ancyra) - Colonia Archelaïs  
- Tyana - *Via Tauri* (- Tarsus - Antiochia) (4.P.1)(2.P.1)(7.P.1)(8.P.1) . . 157-167

- 157. Gülhüyük, form. Muhlisoba
- 158. Değirmenyolu, form. Parlasan
- 159. Topakkaya, form. Çimenliyolu
- 160. Aksaray
- 161. Demirci
- 162. Kemerhisar, Salmanlı Çiftlik 1-3
- 163. Kavuklu 1-3
- 164. Eminlik 1-2
- 165. Kırkgeçit Deresi
- 166. Pozantı 1
- 167. Pozantı 2
- 168. Pozantı, Soğukpınar



### 4.3 Epigraphic Conventions

MAJUSCULE	Letters read on the stone (or preserved in an earlier copy) but not understood by the editor
[α β γ] [a b c]	Letters, lost through breakage or no longer visible, restored by the editor
{α β γ} {a b c}	Letters cut in antiquity but thought by the editor to be superfluous
⟨α β γ⟩ ⟨a b c⟩	Letters thought by the editor to have been accidentally omitted in antiquity and, therefore, supplied by the editor
(α β γ) (a b c)	Letters supplied by the editor in order to complete or to amplify an ancient abbreviation
⌈α β γ⌋ ⌈a b c⌋	Letters erased in antiquity but still wholly visible
⌈α β γ⌋ ⌈a ḅ c̣⌋	Letters erased in antiquity and only partly preserved
⌈[α β γ]⌋ ⌈[a b c]⌋	Letters erased in antiquity, no longer visible, restored by the editor
α̣ β̣ γ̣ ạ ḅ c̣	Letters, damaged and/or only partly preserved, the interpretation of which is open to doubt; consult the drawing (where available)
(sic)	Words or letters correctly cut but thought to be grammatically or orthographically remarkable or unusual; where possible, given by the editor as preserved on the stone
α̣ β̣ γ̣ ạ ḅ c̣	(A modern error) Letters or words emended from an earlier copy of an inscription which is not now available to the editor; a note is given in the apparatus or in the commentary
/α β γ/ /a b c/	(An ancient error) Letters or words incorrectly cut, or malformed, or for which, in error, different letters or words have been inscribed on the stone; suggested corrections are supplied by the editor; consult the drawing (where available) and the commentary
α̣ β̣ γ̣ ạ ḅ c̣	Letters seen by an earlier copyist but no longer visible or preserved
(vac) or (v)	vacat, i.e. an empty space
[ . . 4 . . ] [ . . . . ]	The figure, or the number of dots, within the square brackets indicates the precise number of letters required to fill a known space or to complete the inscription
[ - - - - ] - - - -	The dashes within the square brackets indicate an indefinite number of letters to be restored in the text in order to fill a known space or to complete the inscription; if the square bracket is not present, the number of missing letters (and hence of missing lines) is not known
ligatures	The presence of ligatured letters is indicated in the commentary
αβ γ ab c αβ   γ ab   c	The vertical line indicates the original line-divisions, whether falling in a single word or between two words, in an inscription which is printed as continuous text or as verse
αβ  γ ab  c αβ    γ ab    c	The double vertical line indicates the end of every fifth line (the fifth, tenth, fifteenth and so on), whether falling in a single word or between two words, in an inscription printed as continuous text or as verse

## **4.4 Texts**

## A. IN GALATIAM

### A.2 CAESARIA (per Aquas Saruvenas) (- Ancyra)

#### 001. Sarılar

<i>Province, Sub-Province + Admin. Code</i>	Nevşehir, Avanos 50-01-1
<i>Map</i>	Avanos 76-If
<i>Location</i>	“In the graveyard” (Thompson)
<i>Copy</i>	Thompson and Weissberger 1909. Text here of Thompson
<i>Publication</i>	Thompson 1910, 291
	RRMAM 2, 1. 859 (notice only)
<i>Description</i>	“A milestone” (Thompson)
<i>Dimensions</i>	Not given

<i>Text</i>	[Imp Caesari]
2	[C Messio Quin]- <b>to</b> [Tr]aia[no]
4	<b>Decio pio</b> [f]elici Au-
6	<b>gusto</b> - ? -

<i>Caput Viae</i>	[Caesaria]
<i>Date</i>	Traianus Decius <i>Augustus</i> , (?)AD 249

#### 002. Çalış

<i>Province, Sub-Province + Admin. Code</i>	Nevşehir, Avanos 50-01-2
<i>Map</i>	Avanos 76-If
<i>Location</i>	“Il monumento, prima conservato a Çalış «presso la casa del sig. Katip Bekir, vicemuhtar di Çalış» (almeno fino al luglio 1970) quindi portato al Museo di Nevehir, proviene «da Belkug, una località situata circa 10 km a nord» non da Çalış” (Tibiletti 1977: 169). According to the Museum authorities in Nevşehir, the stone was recovered (?date) when foundations for electricity pylons were dug in the village. Now in the Nevşehir Museum [Inv. no. 1708]
<i>Copy</i>	Meriggi 1967; DHF 28.viii.1974. DHF squeeze in BIA. No DHF photo. Text here from DHF squeeze (drawing, Fig. 6.2.1 [p. 354])
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i>
	Squeeze: 50. Nevşehir 01, Çalış
<i>Publication</i>	Polacco 1970 (1972), 188 and Fig. 2 Tibiletti 1971, 67 (text and photos of Meriggi) Polacco 1971, 29 and Pl. 6 no. 6 Polacco 1972/3, 88 and n.9 (note on text) French 1976, 52 (notice only) Tibiletti 1977, 168-171 AE 1977. 814 (texts of Polacco 1971, Tibiletti 1971 and 1977) French 1980, 724 no. 28 (text of Polacco 72/3) RRMAM 2, 1. 858 (notice only)
<i>Description</i>	A simple cylinder. Small break at top rear; broken below. Grey limestone. The

shaft is oval in section. Letters: slightly worn.  
*Dimensions* Ht (ex.) 0.97; wi. (front) 0.395; depth (side) 0.305. Letters: **E** of **IMPER** 0.04

*Text*

**Imperator**  
**Caesar Gaius**  
**Iulius Verus**  
4 **Maximinus**  
**pius felix invi-**  
**ctus Aug et Ga-**  
**ius Iulius Ver-**  
8 **us Maximus no-**  
**bilissimus Cae-**  
**sar vias e<t> pontes**  
**vetustate cun-**  
12 **lapsas {asas} reş-**  
**[ti]ṭụeṛuṇṭ p̣e[r]**  
- - - -

(sic)

lines 14 et seqq.: [Licinnium Serlenianum leg | Aug pro pr | mp - - ], cp.  
RRMAM 3.2 (Galatia). 57. Çomar

*Caput Viae*

[Caesaria]

*Date*

AD 236, c. Jan-May–238, mid-April(?), Maximinus *Augustus* with Maximus  
*Caesar*

**A.7 CAESARIA -TYANA (- Col. Iconium)****003. Yavaşhan**

<i>Province, Sub-Province + Admin. Code</i>	Kayseri, Yeşilhisar 38-10-0
<i>Map</i>	Niğde 79-İ
<i>Location</i>	“ . . . . , alongside a well on E side of the Khan in the yard” (Garstang). Present whereabouts not established (DHF visit 17.ix.1973)
<i>Copy</i>	Garstang 1907. The stone has not been examined by DHF. Text here of Garstang
<i>Publication</i>	Garstang 1908, 8-9 and Pl. 12 French 1976, 52 (notice only) RRMAM 2, 1. 578 (notice only)
<i>Description</i>	“Large, cylindrical stone hollowed as a trough for animals to drink, . . . . Grit stone” (Garstang)
<i>Dimensions</i>	“Ht. 2. 20; diam. 0.80” (Garstang)
<i>Text</i>	<div style="display: flex; justify-content: space-between;"> <div style="width: 10%;">[Imp Caesari Nervae]</div> <div style="width: 10%;">2</div> <div style="width: 80%;">[T]raiano Aug[usto]</div> </div> <div style="display: flex; justify-content: space-between;"> <div></div> <div>4</div> <div>Germanico pont max trib potest cos III p p restituit per Pom- ponium Bassum leg Aug pro pr XXXX</div> </div> <div style="display: flex; justify-content: space-between;"> <div></div> <div>6</div> <div></div> </div> <div style="display: flex; justify-content: space-between;"> <div></div> <div>8</div> <div></div> </div> <div style="margin-top: 10px;"> line 4: (?) trib potest &lt;IIII&gt; cos III  line 2: <b>AVG</b> (Garstang) </div>
<i>Caput Viae</i>	(Caesaria)
<i>Date</i>	AD 100(?) Traianus <i>Augustus</i>
<i>Commentary</i>	According to Kienast (1996, 123) Traianus' TR·P (I) = AD 97, 28.x-09.xii but his COS·III began on AD 100, 01.i

**A.9 SATALA - NICOPOLIS - NEOCAESARIA - AMASIA (- Ancyra)****004. Yurtbaşı, form. Melikşerif**

<i>Province, Sub-Province + Admin. Code</i>	Erzincan, Refahiye 24-05-0
<i>Map</i>	Şebinkarahisar 110-s
<i>Location</i>	“Fr. d’une colonne de granit, sous l’escalier du Quonack, à Meliki-Cheriff . . . .” (Boré apud CIL); “ . . . . , découverte à quelque distance en amont de Mélik-Shérif, à ce qu’on nous affirma, . . . . ” (St. Pont. 2). Present whereabouts not established (DHF visit 26.vii.1981)
<i>Copy</i>	Boré 1837; Cumont (Fr. and E.) 01 June, 1900. The stone has not been examined by DHF. Text here of Cumont 1905b (facsimile of the printed text, Fig. 6.1.2 [p. 325]) with readings from Boré’s text as printed by Le Bas and Waddington (facsimile of the printed text, Fig. 6.1.1 [p. 325])
<i>Publication</i>	Boré 1840, 1, 370 Le Bas and Waddington 1870, 2, 430 no. 1814b (text of Boré) CIL 3. 306 (text of Boré); [p.] 975 Add. (notice); [p.] 1251 Add. (notice) St. Pont. 1 (Anderson), 87 (no. 477) and n.4 (notice) St. Pont. 2 (Cumont [Fr. and E.]), 328 (no. 477) (notice) Cumont 1905b, 201 ILS 3. 8904 (text of CIL [Boré] and Cumont) McCrum and Woodhead 1961, 46 no. 86 (text of ILS) Mitford 1972, 3, no. 205 (text of Cumont 1905b) French 1980, 716 no. 7 (text of CIL [Boré] and Cumont) RRMAM 2, 1. 365 (notice only)
<i>Description</i>	(L’inscription) “est gravée sur une belle colonne milliaire de calcaire noir aujourd’hui brisée en deux fragments” (Cumont 1905b)
<i>Dimensions</i>	Not given
<i>Text</i>	<p>(? vac) <b>Imp Vespasiano</b> (? vac)</p> <p>2 <b>Caesare Aug·p·m·trib·pot·VII</b></p> <p><b>imp·XIII·cos·VII·p·p·</b></p> <p>4 <b>Imp·Tito·Caesare·Aug·f·cos·V</b></p> <p>[[Domitian]]o [[Caes]]are [[Au]]g·f·cos·II</p> <p>6 <b>Cn·Pompeius·Collega·leg·Aug</b></p> <p>(vac) <b>pro·pr·</b>[ - - - ]</p> <p>8 (vac) <b>III</b></p> <p>(vac) <b>γ’</b></p> <p>lines 1-2: <b>Imp·Vespasiano</b>   <b>Caesare</b> . . . . . (Boré)</p> <p>line 2: <b>Aug·p·m·trib·pot·VII</b> om. Boré</p> <p>line 3: <b>imp XIII cos . . OIVII</b> [horizontal bar over XIII and VII] (Boré); after <b>PP</b> Boré inserted <b>OIVII</b> [POTVII (Cumont)] here from line 2</p> <p>line 3: (?) <b>p·p·</b>[censore]</p> <p>line 4: <b>Aug f</b> om. Boré</p> <p>line 5: om. Boré</p> <p>line 5: <b>cos II</b> (Cumont) [Boré placed COS II after POMPEIUS]; <b>cos II</b>[II] (ILS)</p> <p>line 6: <b>Cn·Pompeius cos II</b> [horizontal bar over II] (Boré)</p> <p>line 7: (?) <b>pro·pr·</b>[viam stravit]; Cumont, in his printed copy, indicates a</p>

lacuna at the end of the line  
 lines 7-8: **pro·pr . . . III** | <sup>(vac)</sup> **T** (Boré); Boré inserted **III** | **T** here from  
 lines 8-9  
 lines 8-9: “sur le second morceau” (Cumont 1905b)

Cumont indicates *two* fragments. Is it possible that Cumont (? unlike Boré) did not see the top (perhaps concealed) of the stone or that Boré saw *three* fragments, on one of which were inscribed the words not recorded by Cumont: **Imp·Vespasiano** | **Caesare** (line 1 and the beginning of line 2)?

*Caput Viae* (Satala ?)  
*Date* AD 76, 01.i-Feb. Vespasianus and Titus *Augusti* with Domitianus (name erased)  
*Caesar*  
*Commentary* For the date, see Kienast (1996, 109). In AD 76, according to Kienast (l.c.), Vespasianus would have been IMP XVIII and Domitianus COS IIII (as indicated in ILS). From which road is this milestone? cp. Dessau (ILS 3. 8904): “incertum a quo loco”; the mile-figure, III MP, could perhaps have been measured from Satala or, alternatively from Nicopolis. In either case the stone would have been transported to Melikşerif from a distant location; cp. Cumont (loc. cit.) “en amont de M.”. Cumont (loc. cit.) describes the second fragment as a “morceau”. Perhaps numerals were lost in front of **III** and γ', e.g. [XXXX]**III** and [μ]γ' (cp. the mile-figure on the milestone from 005. Olgunlar: **XXXXV**) and, therefore, the stone had been carried from the Satala-Nicopolis road?

### 005. Olgunlar, form. Sipdiğın

*Province, Sub-Province + Admin. Code* Erzincan, Refahiye 24-05-0  
*Map* Şebinkarahisar 110-ş  
*Location* “Dans l’église de Kondilia, près de Guerdjanis” [= modern Refahiye] (Cumont);  
 “. . . . au village musulman de Zipti, [= Sipdiğın, now Olgunlar] . . . . l’on nous apprit qu’on avait emporté récemment de là une “pierre écrite” pour construire l’église grecque de Kondilia à une lieue dans la montagne. En effet, dans la chappelle de cette pauvre paroisse, une belle colonne milliaire supportait la table d’autel” (St. Pont.). Present whereabouts not established (DHF visit 26.vii.1981). I do not know the modern location of Kondilia.  
*Copy* Cumont (Fr. and E.) 01 June, 1900. The stone has not been examined by DHF. Text here of Cumont 1905b (facsimile of the printed text, Fig. 6.1.3 [p. 325])  
*Publication* Cumont 1905b, 221 n.3  
 St. Pont. 2 (Cumont [Fr. and E.]), 324 (no. 476) (notice)  
 Mitford 1972, 3, no. 204 (text of Cumont)  
 RRMAM 2, 1. 364 (notice only)  
*Description* (Le texte) “gravé sur une colonne de calcaire gris” (Cumont 1905b)  
*Dimensions* “H. 0 m 90” (Cumont 1905b)  
*Text*

(1)	[Imp Caesar divi Ve]sp[as]iani f
2	[Domitianus Aug Germanicus p m] [tr p XI imp XXI]I cos XVI [ce]nso[r]
4	[ - - - - - ]I[ - - - - - ] (? vac)
6	(vac) mil p (vac) XXXXV

line 4: (?) [perpetuus p p v]i[am restituit]  
 line 5: (?) [per - - ]

(2) [Imp Caes divi Trai]-  
 2 [ani Parthici f] **divi**  
**Nervae nepoti Traia-**  
 4 **no Hadriano Aug**  
**p m tr p XIII cos III**  
 6 (vac) **p p**  
 (vac) **mil p**  
 8 (vac) **XXXXV**

line 4: (?) **Aug**[usto]

lines 7-8: “le nombre de milles subsiste de l’inscription primitive” (Cumont 1905b), i.e. lines 7-8 of text (1) were retained when it was replaced by text (2).

*Commentary on text* I have subjected text (1) to drastic surgery. The inscription makes no sense as it was published by Cumont. In line 7 of Cumont’s text, MP III cannot stand for m(ilia) p(assuum) III (*pace* Mitford) in the middle of the Imperial titulature - an unparalleled procedure. The text is here restored, on the basis of Cumont’s suggestions (1905b, 221 n.3) as a milestone of Domitianus. I have used the formulae known on other Domitianic milestones (list in RRMAM 2, [p.] 431) of AD 91-92 and have allowed c. 24-25 letters per line.

*Caput Viae* (Nicopolis ?)

*Date* (1) (?) AD 92 Domitianus *Augustus*

(2) AD 128/129, 10.xii-09.xii Hadrianus *Augustus*

*Commentary* The milestone was probably brought from the Satala - Nicopolis highway. The distance-figure is inconclusive. By coincidence, the possible location of this stone, at or near Çukuryazı (formerly Mahmer), 4 km E of Çatalçam (formerly Zevker) on the line of the Roman road between Satala and Nicopolis, is almost equidistant from both: 66.34 km (- XXXXV MP). Since Çukuryazı lies W of the Çimenlidağ watershed, it is possible that the stone was erected on the territory of Nicopolis. Olgunlar lies 10 km SSW of Çatalçam.

## 006. Gölova, form. Ağvanis

*Province, Sub-Province + Admin. Code* Sivas, Suşehri 58-08-3

*Map* Şebinkarahisar 108-r

*Location* “Dans le cimetière” (St. Pont.); “In 1900 in the cemetery” (Mitford). Present whereabouts not established (DHF visit 06.ix.1981)

*Copy* Cumont (Fr. and E.) (?) 31 May, 1900. The stone has not been examined by DHF. Text here of Cumont from Mitford (1972, 3)

*Publication* St. Pont. 2 (Cumont [Fr. and E.]), 319-320 (no. 475) (notice)

Mitford 1972, 3, no. 203-1 (“text of Cumont in 1900”)

RRMAM 2, 1. 933 (notice only)

*Description & Dimensions* Not given

*Text* **DDD nnn**  
 2 **Valentinia-**



4        **no et Valen-**  
           **te et Gr̃atiano**  
           **perpetuis**  
 6        **Augustis**

post line 6: “no indication of distance” (Mitford)

*Caput Viae*        [Nicompolis]  
*Date*                AD 367, 24.viii-375, 17.xi Valentinianus I, Valens and Gratianus *Augusti*

### 007. Sevindik

*Province, Sub-Province + Admin. Code*        Sivas, Suşehri 58-08-1  
*Map*                Şebinkarahisar 106-r  
*Location*        “A quarante minutes d’Orta-Keui, le cimetière arménien de Sevindouk contenait une pierre milliaire” (St. Pont.); “In 1900 in the Armenian cemetery near the Church” (Mitford 1972, 3). Present whereabouts not established (DHF visit 06.ix.1981)  
*Copy*                Cumont (Fr. and E.) (?)31 May, 1900; Grégoire September 1907. The stone has not been examined by DHF. Text here of Cumont from Mitford (1972, 3) (facsimile, Fig. 6.1.4 [p. 325])  
*Publication*        St. Pont. 2 (Cumont [Fr. and E.]), 319 (no. 372) (notice)  
                           Grégoire 1909, 33, 36 (notice)  
                           Mitford 1972, 3, no. 202 (“text of Cumont in 1900”)  
                           Mitford 1980, 1201 n.93 (notice)  
                           RRMAM 2, 1. 935 (notice only)  
*Description*        “Column of grey limestone, broken above, and re-used in antiquity as a tombstone. The epitaph is above” (Mitford 1972, 3)  
*Dimensions*        “Ht. 1.25; diam. 0.40” (Mitford 1972, 3)  
*Text*                Consult the facsimile (Fig. 6.1.4 [p. 325])  
*Caput Viae*        [Nicompolis]  
*Date*                (?)Constantinian  
*Commentary*        Cumont’s text is clearly defective. The letters as illustrated are perhaps the remains of a Constantinian text: CONS in line 4, and (?) CONSTANTIO in line 3. Mitford, on the other hand, interprets the lower lines as Greek, from a later re-use of the column as a tombstone

### 008. Küçük Güzel

*Province, Sub-Province + Admin. Code*        Sivas, Suşehri 58-08-0  
*Map*                Şebinkarahisar 104-p  
*Location*        “In 1907 in a village house” (Mitford). Present whereabouts not established (DHF visit 04.ix.1981). The village has now been flooded by the dam on the Kelkit river  
*Copy*                Grégoire 1907. The stone has not been examined by DHF. Text here of Grégoire from Mitford (1972, 3) (facsimile, Fig. 6.1.5 [p. 325])  
*Publication*        Grégoire 1909, 37  
                           Mitford 1972, 3, no. 200-1 (“text of Grégoire in 1907”)  
                           RRMAM 2, 1. 934 (notice only)

<i>Description</i>	“Fragment of a column, considered by Grégoire to be a milestone. The text has been effaced, so that only a few letters can be read” (Mitford)
<i>Dimensions</i>	“Ht. 0.27; diam. 0.37. Very fine, small and regular letters 2cm.” (Mitford)
<i>Text</i>	Consult the facsimile (Fig. 6.1.5 [p. 325])
<i>Date</i>	(?)

### 009. Hatipli

<i>Province, Sub-Province + Admin. Code</i>	Tokat, Reşadiye 60-05-1
<i>Map</i>	Reşadiye 95-n
<i>Location</i>	In the village; at the house of muhtar, Nuri Tanverdi. Brought from Akköprü mevkii c. 1974 by the YSE workmen, from a quarry, c. 0.30 km E of the bridge, called Hanyeri, c. 1.00 km SE of the village
<i>Copy</i>	DHF 25.vii.1986. DHF squeeze and photos (Pl. 7.1.1 [p. 373]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 60. Tokat 05, Hatipli Stone: (1) B/W Neg.: DHF M/86/22.10 (2) Col. Slide: DHF 263.04-05
<i>Publication</i>	French 1987, 193 (notice only)
<i>Description</i>	A simple cylinder. Broken below. Hard, grey andesite. Shaft tapers slightly towards top. Top flat; in centre: a small round hole. Letters: slightly worn
<i>Dimensions</i>	Ht 1.13; diam. (base) 0.39, (top) 0.31. Letters: (text 2) 0.040-48
<i>Text</i>	(1) (underneath lines 3-4 of text [2])

- - - -  
 [ - - - - ] **et Imp**  
 [Caes M Aur Val Maxi]**miano**  
 - - - -

(2) (on the top of text [1])

**Impera**[to]r<i> C[aes]  
**Fl Val Constan**[ti]**no**  
**maximo victo**[r<i>]  
 4 **ac triumphator**<i>  
**semper Aug**  
**et Fl Cl Constantino**  
**et Fl Iul Constantio**  
 8 **et Fl Iul Constantae** (sic)  
 [ - - - - ]  
 [ - - - - ]  
 (vac)  
 [ ? ]C[ ? ]

lines 9-10: (?) [[et Fl Delmatio]] | [[nnnnbbbb Caessss]], cp. 13. Çalkara  
 line 11: (?) [a Neo]c[aesaria]

*Caput Viae* (Neocaesaria ?)

- Date* (1) (?)AD 293-305 [Diocletianus] and Maximianus [*Augusti* with Constantius and Galerius *Caesares*]  
 (2) AD 335, 18.ix-337, 22.v Constantinus *maximus victor Augustus* with four sons, Constantinus, Constantius, Constans and Delmatius (name erased) *Caesares*

### 010. Niksar

- Province, Sub-Province + Admin. Code* Tokat, Niksar 60-04-0  
*Map* Ünye 93-m / Reşadiye 93-n  
*Location* “Now used as a base to support a pillar in the verandah of the house of M. Gulgulian” (St. Pont.). Present whereabouts not established (DHF visit 08.vii.1977, 26.vii.1986)  
*Copy* Anderson, Munro and Welch 27 July, 1899. The stone has not been examined by DHF. Text here of CIL (Anderson and Munro)  
*Publication* CIL 3. 14184<sup>19</sup> (text from Anderson and Munro)  
 St. Pont. 1 (Anderson), 58 (no. 456) (notice)  
 RRMAM 2, 1. 950 (notice only)  
*Description & Dimensions* Not given

*Text*

	[I]mperato<i>i> [C]aes	
	Fl Val Constantino	
	maximo victor<i>i>	
4	ac triumphatori	
	semper Aug	
	et Fl Cl Constantino	
	[e]t Fl Iul Co[ns]tantio	
8	[e]t Fl Iul [Const]antae	(sic)
	(vac) nobb [Caes]s	
	- - - -	

line 10: the governor's name and a distance figure is lost here

- Caput Viae* [Neocaesaria]  
*Date* AD 333, 25.xii-335, 18.ix Constantinus *maximus victor Augustus* with three sons, Constantinus, Constantius and Constans *Caesares*; it is also possible that the name of the fourth son, Delmatius, was added (in line 10) later (AD 335-337)

### 011. Çaltılı, form. Zilhor

- Province, Sub-Province + Admin. Code* Tokat, Erbaa 60-03-0  
*Map* Samsun 90-1  
*Location* “In old cemetery, outside and to W of village” (Munro); “in an deserted cemetery” (St. Pont.). Now in the garden of the cami, on the right of the gate  
*Copy* Anderson, Munro and Welch 06 August, 1899; DHF 08.vii.1977. DHF squeeze in BIA. No DHF photo. Text here from DHF squeeze (drawing, Fig. 6.2.2 [p. 354])  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 60. Tokat 03, Çaltılı

<i>Publication</i>	Munro 1900, 159 no. 1 AE 1900. 148 (text of Munro) CIL 3. 14184 <sup>23</sup> (text from Anderson and Munro) St. Pont. 1 (Anderson), 74 (no. 420) (notice) RRMAM 2, 1. 939 (notice only)
<i>Description</i>	A simple cylinder. Broken above. Hard, pale limestone. Letters: clear and sharp
<i>Dimensions</i>	Ht 1.06; diam. (top) 0.45. Letters: 0.050-60, (line 7) X 0.060 (line 8) K 0.085
<i>Text</i>	(1) (underneath text [2]) traces

(2) (on top of text [1])

-----  
 2 [- - - restitu]-  
**it per Pōmpo[ni]-**  
 4 **um·Bassum·lēg**  
**Aug·pro·pr·**  
 6 (vac) **mil·p**  
 (vac) **XXIII**  
 8 (vac) **κγ'**

line 8: horizontal bar over the numeral KI

<i>Caput Viae</i>	(Neocaesaria)
<i>Date</i>	(2) Nerva or Traianus, on the basis of the governor's name

## 012. Akça, form. Fidi

<i>Province, Sub-Province + Admin. Code</i>	Tokat, Erbaa 60-03-0
<i>Map</i>	Samsun 89-m
<i>Location</i>	"In a dere in the hillside" (St. Pont.). Now in front of the cami
<i>Copy</i>	Anderson, Munro and Welch 26 July, 1899; DHF 08.vii.1977. DHF squeeze in BIA. No DHF photo. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i>
	Squeeze: 60. Tokat 01, Akça
<i>Publication</i>	CIL 3. 14184 <sup>21</sup> (text from Anderson and Munro) St. Pont. 1 (Anderson), 55 (no. 455) (notice only) RRMAM 2, 1. 936 (notice only)
<i>Description</i>	A simple cylinder. Broken above. Hard, pale limestone. Letters: worn
<i>Dimensions</i>	Ht (vis.) 0.75; diam. (top) 0.43. Letters: (text 2) 0.025-35, (text 3) 0.050-60
<i>Text</i>	(1) (underneath text [2] and text [3]) traces

(2) (below line of text [3] and on top of text [1])

-----  
 2 (vac) **mil p XXX**  
**μίλ·λ'**  
 4 **Aur Priscianus v p praes**  
**pr P d n m q eorum**

lines 4-5: **v**(ir) **p**(erfectissimus) **praes**(es) | **pr**(ovinciae) **P**(onti) **d**(evotus)  
**n**(umini) **m**(aiestati)**q**(ue) **eorum**, cp. below, 18. Çiğdemlik

(3) (above text [2])

- - - -

**nnnnbbbb Caessss**

For the use of ‘nnnnbbbb Caessss’ for the four sons of Constantinus, see below, 015 Çakırsu

*Caput Viae* (Neocaesaria)  
*Date* (1) (?)  
 (2) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with  
 Constantius and Galerius *Caesares*, on the basis of the governor’s name  
 (3) [AD 335–337 Constantinus *maximus victor Augustus* with four sons,  
 Constantinus, Constantius, Constans and Delmatius *Caesares*] ?

### 013. Çalkara

*Province, Sub-Province + Admin. Code* Tokat, Erbaa 60-03-0  
*Map* Samsun 89-1  
*Location* “Iacet prope moscheam” (CIL); “at Çalkara” (St. Pont.). Present whereabouts not  
 established (DHF visit 08.vii.1977, 24.vii.1986)  
*Copy* Anderson, Munro and Welch 26 July, 1899. The stone has not been examined by  
 DHF. Text here of CIL (Anderson and Munro)  
*Publication* CIL 3. 14184<sup>20</sup> (text from Anderson and Munro)  
 St. Pont. 1 (Anderson), 55 (no. 454) (notice)  
 RRMAM 2, 1. 938 (notice only)  
*Description & Dimensions* Not given  
*Text* (1) (below text [2])

- - - -  
 2 **mil p XXV**  
**μῖλ κε’**  
 4 (vac)  
**Aur Priscianus** [v p pr]  
 6 **pr P d n m** [q eorum]

lines 5-6: for the abbreviations, see below, 018. Çiğdemlik

(2) (above text [1])

**Impe[r]ator<i> Caes**  
**Fl Val Constantino**  
**maximo victor<i>**  
 4 **ac triumphator<i>**  
**semper Aug**  
**et Fl Cl Constan[t]ino**  
**et Fl Iul Constantio**  
 8 **et Fl Iul Const[a]ntae** (sic)

et [[F]l Delmatio]]  
 \*  
 nnn[n]bb[b]b [Caess]ss  
 \*

*Caput Viae* (Neocaesaria)  
*Date* (1) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*, on the basis of the governor's name  
 (2) AD 335, 18.ix–337, 22.v Constantinus *maximus victor Augustus* with four sons, Constantinus, Constantius, Constans and (names erased) Delmatius *Caesares*

#### 014. Karaağaç

*Province, Sub-Province + Admin. Code* Tokat, Erbaa 60-03-0  
*Map* Samsun 88-m  
*Location* In the village; at the house of Ali Alkan, in the *ahır* (byre). Brought from a nearby area called Tonu or Tanoba arası, on the S side of the village  
*Copy* DHF 24.vii.1986. DHF squeeze (drawing, Fig. 6.2.3 [p. 355]) and photos (Pl. 7.1.2 [p. 373]) in BIA. Text here from DHF squeeze  
*BIA Collections:* *Squeeze and Stone Photographs*  
 Squeeze: 60. Tokat 06, Karaağaç  
 Stone: (1) B/W Neg.: DHF M/86/22.09  
 (2) Col. Slide: DHF 263.01-03  
*Description* A simple cylinder. Broken below. Hard, grey limestone. Top flat  
 Letters: clear; diagonal-bar A  
*Dimensions* Ht 0.61; diam. (below) 0.45. Letters: 0.030 (letter O)–0.045 (line 6 letter T)

*Text*

	<b>İmperator</b> <i>	Caes
	<b>Fl Val Cō</b> /nstantino/	
	<b>maximo victor</b> <i>	
4	<b>ac triumphator</b> <i>	
	<b>semper Aug</b>	
	<b>et</b> <F> <b>l Cl Constantino</b>	
	<b>et Fl Iul Constantio</b>	
8	<b>et Fl Iul Constantae</b>	(sic)
	[[et Fl Delmatio]]	
	[n]nnn[bbbb Caesss]	
	----	

line 2: **FLVALCOVICTOR** (lapis)

*Caput Viae* [Neocaesaria]  
*Date* AD 335, 18.ix–337, 22.v Constantinus *maximus victor Augustus* with four sons, Constantinus, Constantius, Constans and (names erased) Delmatius *Caesares*

#### 015. Çakırsu, form. Yornus

*Province, Sub-Province + Admin. Code* Amasya, Taşova 05-05-2  
*Map* Samsun 87-m

<i>Location</i>	“Built into the wall of a Byz(antine) house, about c. 10 mins. walk E of village, in the valley of a tributary of the Taneli Dere” (Wilson 1960); seen there by DHF (09.vii.1977) (Pl. 7.1.3 [p. 374]). Now in Amasya Museum [Inv. no. 80.5.2]
<i>Copy</i>	Wilson Summer 1958; DHF 09.vii.1977 at Çakırsu, 27.viii.1984 and 20.xi.1984 in museum. A facsimile of Wilson’s printed copy is given here (Fig. 6.1.6 [p. 326]). DHF squeeze and photos in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 05. Amasya 08, Çakırsu Stone: (1) B/W Neg.: DHF R/77/10.04, M/86/13.14-15 and M/89/12.11 (2) Col. Slide: DHF 303.0-08
<i>Publication</i>	Wilson 1958, Notes 58/11 Wilson 1960, 137 no. 2 AE 1961. 26b (comments on text of Wilson) AE 1975. 785 (text of Wilson) Christol and Drew Bear 1986, 47 n.31 (notice of text [2] in Wilson 1960) Christol and Drew Bear 1987, 21 n.32 (notice of text [2] in Wilson 1960) RRMAM 2, 1. 063 (notice only)
<i>Description</i>	A simple cylinder. Chipped above, otherwise complete. Hard, pale limestone. The shaft tapers very slightly towards top. Top flat; under base, a square tenon. Surface and letters: some wear. Letters: (text 1) broken-bar A, U for V, (text 6) very irregular in shape and size, diagonal-bar A, U for V, (text 7) letters irregular in size, broken-bar A
<i>Dimensions</i>	Ht 1.94; diam. (base) 0.48; (tenon) ht 0.17; wi. 0.265. Letters: (text 1) 0.040-50 but line 2 DIOCLETIANO and lines 7-8 CONSTANTIO and MAXIMIANO 0.065-75, (text 2) 0.025-40, (line 1) d 0.040, (text 3) 0.040-55, (line 7) O in CON 0.035, (text 6) 0.035-70, (text 7) c. 0.55 but (line 2) O in ORIO 0.045 and (line 3) P 0.080
<i>Text</i>	(1) (below text [5] and on the r. of text [3]) <div style="text-align: center;"> <b>Imp·Caes·C·Aur·Val·</b>  <b>[D]iocletiano</b>  <b>p f inv Aug e[t]</b>  4    <b>_[Imp Caes M Aur Val]´</b>        <b>_[Maximiano]´</b>  <b>p f inv Aug et Fl Val</b>  <b>Constantio et</b>  8    <b>Gal Val Maximiano</b>        <b>nobiliss Caess</b>            (vac)        <b>mil·p·XXXV</b>        <b>μῑλ·λϵ´</b>  12   <b>_[A]ur Priscianus v p pr p[r]´</b>        <b>_[Po]nt d n m q eorum´</b> </div> <p style="text-align: center;">lines 12-13: for the abbreviations, see below, 18. Çiğdemlik</p> (2) (below text [1]) <div style="text-align: center;"> <b>ddd NNN Fl Va&lt; &gt; Crispo et</b>  2    <b>Val Constantino _[Licinnio]´ [et]</b> </div>

**Fl Constantino nobbbb**  
**4 Caesss**

line 1: **ddd NNN**, dominis nostris, added by a different hand

(3) (on the l. of text [5])

**Imp Ç[aes]**  
**Fl Val Ç[onst]antino**  
**maximo victor<i>**  
**4 ac triumphator<i>**  
**semper Aug**  
**et Fl Cl Ço[n]stantino**  
**et Fl Iul Constantio**  
**8 et Fl Iul Constantae** (sic)  
**et Fl Delmatio**  
**nnnnbbbb Caessss**

line 10: **nnnnbbbb Caessss**, nobilissimis Caesaribus

(4) (underneath text [2])  
 (?)

(5) (underneath text [6])  
 possible traces

(6) (on the top of, and below, text [3] and on the r. of text [1])

**Impp Caess ΔΔNN**  
**2 Fl Valentiniano**  
**[e]t Fl Valente**  
**4 et Gratiano**  
**perpetuis [Augg]g**

line 1: **ΔΔNN**, **D**(ominis) **n**(ostris)

(7) (on the r. of text [3])

**D n Fl H-**  
**2 onorio**  
**p Aug**

line 1: **D**(omino) **n**(ostro)

line 3: **p**(erpetuo)

*Caput Viae*  
*Date*

(Amasia)

(1) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus (names erased)  
*Augusti* with Constantius and Galerius *Caesares*

(2) AD 317 or 318 Crispus, Licinius and Constantinus, *Caesares* (under  
 Constantinus and Licinius *Augusti*)

(3) AD 335, 18.ix–337, 22.v Constantinus *maximus victor Augustus* with four  
 sons, Constantinus, Constantius, Constans and Delmatius *Caesares*



(4) (?)

(5) (?)

(6) AD 367, 24.viii-375, 17.xi Valentinianus I, Valens and Gratianus *Augusti*(7) AD 393, 28.i-423, 15.viii(?) Honorius *Augustus***016. Yerkozlu***Province, Sub-Province + Admin. Code* Amasya, Taşova 05-05-3*Map* Samsun 86-m*Location* Brought from the village; found between the village and Aşağı Baraklı. Now in Amasya Museum [Inv. no. 79.7.1]*Copy* DHF 25.viii.1984 and 31.x.1998. DHF squeeze and photos (Pl. 7.1.4 [p. 374]) in BIA. Text here from DHF squeeze. The stone is illustrated in the brochure *Guide to the Amasya Museum* published by the Museum.*BIA Collections:* *Squeeze and Stone Photographs*

Squeeze: 05. Amasya 21, Yerkozlu

Stone: (1) B/W Neg.: DHF M/84/09.03 and M/98/08.02

*Publication* French 1985b, 145 and Fig. 8

RRMAM 2, 1. 075 (notice only)

*Description* A simple cylinder. Broken below. Hard, pale limestone.

Letters: (text 1) worn and damaged, (text 2) mostly clear and sharp; (text 1) diagonal lower bar, (text 2) broken-bar A

*Dimensions* Ht (vis.) 0.97; diam. (top) 0.36. Letters: (text 1) 0.035-45, (line 10) M 0.10, (text 2) (lines 1 and 3) 0.040-45 but (lines 2 and 7) 0.055-70*Text* (1) (partly underneath, and on the l. of, text [2])

[Imp Caes]

**M Aṽr Car**[o p f]**invicto Aṽ**[g]4 (vac) [e]**t M Aṽ**[rr][Ca]**rino et** [Nume]-**riano nobi**[lissi]-**mis Caesar**i[bus]8 **Claud Longin**[us]**v p praes p P**(vac) **μ γι**

lines 4-6: restored after the text of 025. Toklucak

line 9: **v**(ir) **p**(erfectissimus) **praes**(es) **p**(rovinciae) **P**(onti)line 10: **μ** for **μ**(ίλια)

(2) (partly on the top, and on the r., of text [1])

**Imp Caes C Aur Val****Diocletiano****p f inv Aug et**4 **[[Imp Caes M Aur Val]]****[[Maximiano]]****p f inv Aug et Fl** [Val]**Constant**[io et]

8      **Gal Val Maximiano**  
**nobiliss Caess**  
(vac)  
(vac) [mil] **p XI[II]**  
- - ? - -

lines 2, 7 and 8: note the increased and, therefore, emphatic letter-size  
post line 10: (?) inscription lost; for an identical text, see 015. Çakırsu (1)

*Caput Viae*      (Amasia)  
*Date*      (1) AD 282, end-283, early Carus *Augustus* with Carinus and Numerianus  
*Caesares*  
(2) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus (names erased)  
*Augusti* with Constantius and Galerius *Caesares*

### 017(A). Aşağı Baraklı 1

*Province, Sub-Province + Admin. Code*      Amasya, Taşova 05-05-3  
*Map*      Samsun 86-m  
*Location*      Not given by de Jerphanion. Seen by DHF at the gate to the village cami  
(09.vii.1977). Now concealed by cement plaster  
*Copy*      de Jerphanion July–September, 1907; DHF 09.vii.1977. No DHF squeeze. No  
DHF photo. Text here of de Jerphanion and Jalabert  
*Publication*      de Jerphanion and Jalabert 1908, 441 no. 1  
RRMAM 2, 1. 057 (notice only)  
*Description*      “Colonne quadrangulaire dont la face gravée est légèrement bombée; . . . .” (de  
Jerphanion and Jalabert)  
*Dimensions*      “. . . . ; haut. environ 1 m. large 0m, 30, lettres régulières de 5 cent.” (de  
Jerphanion and Jalabert)

*Text*      **Imp Caes F<1>Val**  
**Constantio**  
**p f invic Aug et**  
4      **Imp Caes Gal Val**  
**Maximiano**  
**p f invic Aug et**  
**Flavio Valer<io>**  
8      [Severo et Gal Val]  
[Maximino]  
[nobb Caess]  
- - ? - -

line 2: ligature **TI**

*Caput Viae*      [Amasia]  
*Date*      AD 305, 01.v–306, 25.vii Constantius and Galerius *Augusti* with [Severus and  
Maximinus *Caesares*]

### 017(B). Aşağı Baraklı 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 017(A)
<i>Location</i>	“A 40 min. au N-E de Baraklé” (de Jerphanion and Jalabert). Present whereabouts not established (DHF visits 09.vii.1977 and 02.viii.1987)
<i>Copy</i>	de Jerphanion July-September, 1907. The stone has not been examined by DHF. Text here of de Jerphanion and Jalabert (facsimile of the printed text, Fig. 6.1.7 [p. 326])
<i>Publication</i>	de Jerphanion and Jalabert 1908, 441-442 no. 2 RRMAM 2, 1. 058 (notice only)
<i>Description</i>	“La pierre a été retaillée; ... et la colonne, auparavant cylindrique et régulière, affecte maintenant la forme d’une moitié de colonne en saillie sur un prisme de section triangulaire. Le commencement des lignes a été entamé” (de Jerphanion and Jalabert)
<i>Dimensions</i>	“Hauteur totale 1m,80, de la partie inscrite 0m,80; caractères réguliers et très lisibles de 6 à 7 cent.” (de Jerphanion)

<i>Text</i>	[I]m̄perator<i> Caes [Fl V]al Constantino [max]imo victor<i> 4 [ac] triumphator<i> [s]emper Aug [et Fl] Cl Constantino [et Fl I]ul Constantio 8 [et Fl I]ul Constanti{ae} [[et Fl Delmatio]] [nnnn]bbbb Caessss . LAE
-------------	---

line 3: “le second M est certain” (de Jerphanion)

line 6: “la copie porte E ou C” (de Jerphanion)

lines 7-8: “les premiers caractères douteux” (de Jerphanion)

line 11: [MIA.N]E (de Jerphanion), μί [u]ε´ (DHF). “La copie de la dernière ligne n’est malheureusement pas très sûre” (de Jerphanion)

<i>Caput Viae</i>	(Amasia)
<i>Date</i>	AD 335, 18.ix-337, 22.v Constantinus <i>maximus victor Augustus</i> with four sons Constantinus, Constantius, Constans and (name erased) Delmatius <i>Caesares</i>

### 018. Çiğdemlik, form. Zana

<i>Province, Sub-Province + Admin. Code</i>	Amasya 05-00-1
<i>Map</i>	Samsun 85-m
<i>Location</i>	In the village; at the house of Bilal Ayvalı, where it is built into the garden wall
<i>Copy</i>	DHF 26.xi.1985. DHF squeeze in BIA. No photo. Text here from DHF squeeze (drawing, Fig. 6.2.4 [p. 355])
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 05. Amasya 09, Çiğdemlik
<i>Publication</i>	French 1986b, 110 (notice only) RRMAM 2, 1. 065 (notice only)

<i>Description</i>	A simple cylinder. Broken above. Hard, pale limestone. Inscribed area smoothed, remainder of shaft roughly dressed.
<i>Dimensions</i>	Letters: some wear; (text 2) broken-bar A, diagonal lower-bar L Ht (vis.) 1.17; diam. (top) c. 0.50. Letters: (text 2) 0.050-70
<i>Text</i>	(1) (underneath text [2]) obliterated  (2) (on the top of text [1]) [Imp Caes] [C Aur Val] [Diocletiano] 4 [p f inv Aug et] [Imp Caes] [M Aur Val] [[Maximiano]] 8 [p f i] <b>n·v·Aug·et</b> <b>F[la]vio·Val·</b> <b>Constantio</b> <b>et Gal·Val</b> 12 <b>Maximiano</b> <b>nobil·Caess</b> <b>mil·p·iβ</b> <b>Aur·Priscianus</b> 16 <b>v p·praes·p·Pont</b> <b>d·n m q eorum</b>  line 7: traces of an erasure visible below the remaining traces of line 6 lines 10 and 12: note the increased letter-size lines 16-17: see above, 018. Çiğdemlik
<i>Caput Viae</i>	(Amasia)
<i>Date</i>	(1) (?) (2) AD 293, 21.v(?)–305, 01.v [Diocletianus and Maximianus <i>Augusti</i> ] with Constantius and Galerius <i>Caesares</i>

**019. Amasya**

<i>Province, Sub-Province + Admin. Code</i>	Amasya 05-00-0
<i>Map</i>	Amasya 83-n
<i>Location</i>	“Amasiae iacet iuxta pontem fractam fluvii Iris; mox periit” (CIL); “On a stone beside a ruined bridge over the Iris” (Ramsay). Re-found (1985) on N bank of the Yeşilırmak, near the N arches of the Roman bridge (Taş or Alçak Köprü) in the middle of the town. Seen by DHF at the Hazeran Konak (27.xi.1985). Now in the Amasya Museum
<i>Copy</i>	Sir Charles Wilson c. 1880; DHF 27.xi.1985. DHF squeeze (drawing, Fig. 6.2.5 [p. 356]) and photos (Pl. 7.1.5 [p. 374]) in BIA. Text here from Wilson <i>apud</i> Ramsay and from DHF squeeze
<i>BIA Collections</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 05. Amasya 03, Amasya

	Stone: (1) B/W Neg.: DHF M/85/07.03-04 (2) Col. Slide: DHF 252.17-18
<i>Publication</i>	Ramsay 1882a, 155 no. 16 (text from Wilson) Mommsen 1884a, 39 no. 82 (text of Wilson <i>apud</i> Ramsay) CIL 3. 6896 (text of Wilson <i>apud</i> Ramsay) French 1986b, 110 and Fig. 1 RRMAM 2, 1. 056 (notice only)
<i>Description</i>	A simple cylinder. Broken above and below (and now on r.). Hard, pale limestone. Inscribed area smoothed; remainder of shaft roughly dressed. Letters: well cut, regular, sharp and clear
<i>Dimensions</i>	Ht c. 0.50; diam. 0.43. Letters: 0.052-60
<i>Text</i>	<p style="text-align: center;"><b>Imp Nerva Caes Aug</b></p> <p style="text-align: center;">2    <b>pontif·max trib po-</b></p> <p style="text-align: center;">4    <b>test·cos·III p p resti-</b></p> <p style="text-align: center;">6    <b>tuit per Pomponi-</b></p> <p style="text-align: center;">         <b>um Bassum leg</b></p> <p style="text-align: center;">         <b>Aug·pro·pr</b></p> <p style="text-align: center;">         [mil] p [ - ]</p>
<i>Caput Viae</i>	(Amasia)
<i>Date</i>	AD 97, 01.i-17.ix Nerva <i>Augustus</i>
<i>Commentary</i>	According to Kienast (1996, 120), Nerva began his COS III on AD 01 January 97 and ended his TR P (I) on 17 September 97.

**020. Bulduklu**

<i>Province, Sub-Province + Admin. Code</i>	Amasya 05-00-0
<i>Map</i>	Amasya 83-n
<i>Location</i>	Brought from the village to the Amasya Museum [Inv. no. 99.12.1]
<i>Copy</i>	DHF 27.x.1998. DHF squeeze (29.x.1998) in BIA. No DHF photo. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i>
	Squeeze: 05. Amasya 07, Bulduklu
<i>Description</i>	A simple cylinder. Broken below. Hard, pale limestone. The top is rounded. The shaft tapers slightly towards the top. Letters: some wear
<i>Dimensions</i>	Ht (ex.) 0.50; wi. c. 0.40. Letters: 0.040-55
<i>Text</i>	<p style="text-align: center;"><b>Imp Caes G M-</b></p> <p style="text-align: center;">2    <b>essius Q Traia-</b></p> <p style="text-align: center;">4    <b>nus Daecius pius f-</b> (sic)</p> <p style="text-align: center;">6    <b>elix invictus Aug</b></p> <p style="text-align: center;">         <b>trib potest p p cos</b></p> <p style="text-align: center;">8    <b>procos viam resti-</b></p> <p style="text-align: center;">         [tuit per - - - - ]</p> <p style="text-align: center;">         - - - -</p> <p style="text-align: center;">line 3: Daecius for Decius</p>
<i>Caput Viae</i>	[Amasia]

*Date* AD 249, Sept/Oct - (?) (before COS II DES) Traianus Decius *Augustus*

## 021. Aydoğdu

*Province, Sub-Province + Admin. Code* Amasya 05-00-0  
*Map* Amasya 83-n  
*Location* In the village; beside the *musalla taşı* (coffin table) in front of the cemetery  
*Copy* DHF 27.xi.1985. DHF squeeze (drawing, Fig. 6.2.6 [p. 356]) and photos (Pl. 7.1.6-7 [p. 375]) in BIA. Texts here from DHF squeeze  
*BIA Collections:* *Squeeze and Stone Photographs*  
 Squeeze: 05. Amasya 01, Aydoğdu  
 Stone: (1) B/W Neg.: DHF M/85/07.01-02  
*Publication* French 1985b, 144 (notice only)  
 French 1986b, 110 and Fig. 2  
 RRMAM 2, 1. 059 (notice only)  
*Description* A simple cylinder. Broken below and chipped at front. Hard, pale limestone. The top is flat. The shaft tapers slightly towards the top.  
 Letters: worn; (text 3) irregular in size and shape, broken-bar A, U for V  
*Dimensions* Ht 1.06; diam. (top) 0.38. Letters: (text 2) 0.040-45, (text 3) (line 1) 0.040-70  
*Text* (1) (underneath text [2])  
 obliterated; some letters survive under texts (2) and (3)

(2) (on the top of text [1])

**Imp Caes' C**  
**Aurel' Val**  
**Diocletiano**  
 4 **p f inv' Aug et**  
**Imp Caes' M**  
**Aurelio Val**  
**[[Maxim]ianō]**  
 8 **p f inv Aug et**  
**Flay[io Val]er**  
**Co[nstanti]o et**  
**G[alerio Val]**  
 12 **M[aximiano]**  
**[nobb Caess]**  
 - - - -

(3) (partly above, partly on top of, text [2] lines 1-5)

**DD nn**  
 2 **Valentinianu[s]**  
**Valens**  
 4 **et Gratianus**  
**Augg**

*Caput Viae* [Amasia]

*Date* (1) (?)  
 (2) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus (names erased)  
*Augusti* with Constantius and Galerius *Caesares*

(3) AD 367, 24.viii-375, 17.xi Valentinianus I, Valens and Gratianus *Augusti***022. Boğa**

<i>Province, Sub-Province + Admin. Code</i>	Amasya 05-00-1
<i>Map</i>	Amasya 82-u
<i>Location</i>	Formerly built into the steps of the village cami. Now in the Amasya Museum
<i>Copy</i>	DHF 26.xi.1985. DHF squeeze (drawing, Fig. 6.2.7 [p. 356]) in BIA. No photo. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 05. Amasya 06, Boğa
<i>Publication</i>	French 1986b, 110 (notice only) RRMAM 2, 1. 062 (notice only)
<i>Description</i>	A simple cylinder. Broken below; damaged on left. Hard, pale limestone. Inscribed area smoothed; remainder of shaft roughly dressed. Top flat. The shaft tapers towards top. Letters: worn
<i>Dimensions</i>	Ht (ex.) 1.00; diam. (top) 0.40, (base) 0.51. Letters: 0.030-35, (line 12) O 0.028
<i>Text</i>	[[7 lines erased]] 8 <b>VIII</b> <b>θ'</b> 10 <b>Aur Priscianus</b> <b>v p praes p p P</b> (sic) 12 <b>d n m q eorum</b>  lines 11-12: see above, 12. Akça
<i>Caput Viae</i>	(Amasia)
<i>Date</i>	AD 293, 21.v(?) - 305, 01.v Diocletianus and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i> , on the basis of the governor's name

**023(A). Bağlıca 1**

<i>Province, Sub-Province + Admin. Code</i>	Amasya 05-00-3
<i>Map</i>	Amasya 82-n
<i>Location</i>	In the village; at the cami (Pl. 7.1.8 [p. 375])
<i>Copy</i>	DHF 28.xi.1984 and 07.vii.1986. DHF squeeze and photos (Pl. 7.1.8-10 [p. 376]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 05. Amasya 04, Bağlıca 1 Stone: (1) B/W Neg.: DHF M/86/14.04-06 (2) Col. Slide: DHF 260.32-37
<i>Publication</i>	French 1985b, 144 (notice only) French 1986b, 110 Fig. 2 (notice only) RRMAM 2, 1. 060 (notice only)
<i>Description</i>	A simple cylinder. Broken above. Hard, pale limestone. The shaft tapers slightly towards top. Base flat. Inscribed area smoothed (text 1), remainder of shaft roughly dressed (texts 2 and 3) Letters: (text 1) sharp and clear, (text 2) lines worn and indistinct, broken-bar A
<i>Dimensions</i>	Ht 1.45; diam. (base) 0.48. Letters: (text 1) 0.040-60, (line 8) O 0.035, (line 9)

lines 0.060, (text 2) 0.035-40, (lines 2 and 8) 0.050

*Text*

- (1) (on the front of the shaft)
- [Imp Caes divi]  
[Nervae nepos Tr]-  
[aianus Hadria]-  
4 [nus Aug pont]-  
[if max trib pot]-  
**est**[at XIII i]**mp**  
**[[X]]III**<sup>(vac)</sup> **p p·mil·ab**  
**Amasia·ad fi**<sup>(nes)</sup>  
8 **Galatorum**  
(c. 0.205 gap)  
**mil p**  
**[[XX]]**

lines 1-5: restored after the text of 036. Güngörmez  
line 10: line over numeral

- (2) and (3) (upside down to text [1])
- Imp [Caes] Val**  
**Maximiano**  
**p f invict Aug et**  
4 **Imp·Caes Flav**  
**Val Seve**<sup>ro</sup>  
**p f invict Aug et**  
**G·Val [[Maximino]] et**  
8 **Fl·Val·Constantino**  
(vac) **nobb Caess**

lines 1-2: recut from Imp Caes C Aur Val I Diocletiano  
lines 4-5: recut from Imp·Caes Gal Val I Maximiano; fragments of the letters **GALVAL** are clearly visible  
line 7: recut from G·Val Maximiano et; fragments of the letters **MAXIMIANO** are clearly visible; the name MAXIMINO was subsequently name erased  
line 8: recut from Fl·Val·Constantio

*Caput Viae*  
*Date*

- (Amasia)  
(1) (?)AD 128/129 Hadrianus *Augustus*  
(2) AD 293-305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*  
(3) AD 306, ca. Aug.-307, iii/iv or 16.ix Galerius and Severus *Augusti* with Maximinus (name erased) and Constantinus *Caesares*

*Commentary*

For *fi*<sup>(nes)</sup> *Galatorum*, see also 36. Güngörmez

For the date of text (3), see Kienast (1996, 284, 290). Severus was raised to Emperor in c. August 306; he abdicated in March/April 307 and died on 16 September, AD 307

**023(B). Bağlıca 2**



*Province, Sub-Province + Admin. Code and Map* As 023(A)

*Location* In the village; at the house of Mehmet Bülbul. Brought from his *bahçe* (orchard) below and E of Bekçi Tepe, on the S edge of the village; the area is called Eski Bağ. Now in the Amasya Museum

*Copy* DHF 05.vii.1986. DHF squeeze (drawing, Fig. 6.2.8 [p. 356]) and photos (Pl. 7.1.11 [p. 376]) in BIA. Text here from DHF squeeze

*BIA Collections: Squeeze and Stone Photographs*  
Squeeze: 05. Amasya 05, Bağlıca 2  
Stone: (1) B/W Neg.: DHF M/86/14.01  
(2) Col. Slide: DHF 260.30-31

*Publication* French 1987, 192 (notice only)

*Description* A simple cylinder. Broken below. Hard, pale limestone. The shaft tapers slightly towards the top; the top is flat. Letters: A without bar, Δ for lines D, U for V  
Surface and letters: slightly worn

*Dimensions* Ht (ex.) 0.42; diam. (top) 0.29. Letters: 0.030-50

<i>Text</i>	<p style="text-align: center;"><b>Imp·Caes Ma An-</b> 2 <b>tonius Gordian-</b> <b>us divi Gordian-</b> 4 <b>i nepos pius fel[i]-</b> <b>x invictus Augu-</b> 6 <b>stus [p p] tribun[i]ç</b> -----</p>	(sic)
-------------	---	-------

line 1: **Ma** for **Ma**(rco)

lines 2 and 3: **Δ** for **D**

*Caput Viae* [Amasia]

*Date* AD 238 (?), Gordianus III *Augustus*, cp. below, 044. Sapa

## 024. Doğantepe, form. Zara

*Province, Sub-Province + Admin. Code* Amasya 05-00-0

*Map* Amasya 82-n

*Location* In the village; at the house (no. 21) of Şevket Tiryaki

*Copy* DHF 22.xi.1984. DHF photo. in BIA. Text here from DHF notes

*BIA Collections: Squeeze and Stone Photographs*  
Stone: (1) B/W Neg.: DHF M/86/14.01

*Publication* French 1985b, 144 (notice only)

RRMAM 2, 1. 066 (notice only)

*Description* A simple cylinder. Broken above. Hard, pale limestone

*Dimensions* Ht (vis.) 0.78; diam. c. 0.45

<i>Text</i>	<p style="text-align: center;">----- <b>mil</b> [p] <b>XI</b> <b>ια'</b></p>
-------------	--

*Caput Viae* (Amasia)

*Date* (?)

**025. Toklucak, form. Oluz**

<i>Province, Sub-Province + Admin. Code</i>	Amasya 05-00-2
<i>Map</i>	Amasya 81-o
<i>Location</i>	In the village; in front of the mosque
<i>Copy</i>	DHF 06.vii.1986. DHF squeeze and photos (Pl. 7.1.12-13 [p. 377]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 05. Amasya 16, Toklucak Stone: (1) B/W Neg.: DHF M/86/14.02-03
<i>Publication</i>	French 1987, 192 (notice only)
<i>Description</i>	A re-used column. Broken above and below; part of moulding survives. Hard, grey limestone. Surface rough. Letters: worn and indistinct; (texts 1 and 2) irregular
<i>Dimensions</i>	Ht (max.) 0.95; diam. 0.49. Letters: (text 1) 0.030-40, (text 2) 0.020-50

*Text* (1) (on r. of text 2 and partly overlapping)

[Imperator]  
[Caes M Aur Caro]  
[p f inv] **Aug et MM**  
4 **Αυρ Carino et**  
[Num] **eriano nob**  
[ilis] **simis Caesaribus**  
[Cl L] **ong**[inus v p]  
8 **pr**[aes prov Pont]

- - - -

line 3: **MM** for **M**(arci)

line 4: **Aurr** for **Aur**(elii)

lines 7-8: see above, 16. Yerkozlu

(2) (on l. of text 1 and partly overlapping)

[Fl Constantino]  
[p f m victori]  
[semper Aug]  
4 [et Fl Cl Constantino]  
[et Fl] **Iul Constantio**  
[et] **Fl Iul Consta**[nti]  
[nob] **iliss Caes**  
8 **Fl Iul Leontius**  
[v] **p praes prov**  
**Helenopo**[nti]

line 10: [v(ir)] **p**(erfectissimus) **praes**(es) **prov**(inciae) | **Helenopo**[nti]

For a more complete text of Constantinus, see below 029(B). Boğazkaya 2, text (2)

<i>Caput Viae</i>	[Amasia]
<i>Date</i>	(1) ) AD 282, end-283, early Carus <i>Augustus</i> with Carinus and Numerianus <i>Caesares</i>

- (2) AD 333, 25.xii-335, 18.ix [Constantinus *maximus victor Augustus* with three sons, Constantinus], Constantius and Constans *Caesares*

## 026. Karayakup

<i>Province, Sub-Province + Admin. Code</i>	Amasya, Göynücek 05-01-0
<i>Map</i>	Amasya 81-p
<i>Location</i>	In the village; at the house of Hüseyin Genç. Brought from Kilise Mevkii, c. 8 km N of the village
<i>Copy</i>	DHF 26.x.1995. DHF squeeze and photo. (Pl. 7.1.14 [p. 378]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 05. Amasya 14, Karayakup Stone: (1) B/W Neg.: DHF M/95/07.05
<i>Description</i>	A re-used column. Complete at the top; broken below. Hard, pale limestone. Surface: smoothly finished.
<i>Dimensions</i>	Letters: sharp and clear, regular in shape, pronounced apices; broken-bar A Ht 0.70; diam. (top) 0.32. Letters: 0.040-48
<i>Text</i>	<p><b>Imp·Caes·G·Val</b>  <b>Maximiano</b>  <b>p f invict·Aug·et</b>  4 <b>Imp Caes·Flav·</b>  <b>Val·[[Şev̄ero]]</b>  <b>p f invict·Aug·et</b>  <b>G Val·[[M̄aximino]] et</b>  8 <b>Fl Val Constantino</b>  (vac) <b>nobb Caess</b>  [ - ]</p>

<i>Caput Viae</i>	[Amasia]
<i>Date</i>	AD 306, c. Aug.-307, March/April or 16. September Galerius and Severus (name erased) <i>Augusti</i> with Maximinus (name erased) and Constantinus <i>Caesares</i>
<i>Commentary</i>	It is assumed here that this milestone was originally erected on the Amasia-Ancyra road. For the date of the text, see Kienast (1996, 284, 290). Severus was raised to Emperor in c. August 306; he abdicated in March/April 307 and died on 16 September, AD 307.

## 027. Çavuş

<i>Province, Sub-Province + Admin. Code</i>	Amasya 05-00-3
<i>Map</i>	Amasya 81-n
<i>Location</i>	Beside and N of the old şose from Çorum to Amasya, c. 350 m E of the old turning for the village; lying in a field
<i>Copy</i>	DHF 13.vii.1975 and 10.vii.1977. DHF photo. in BIA
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i> Stone: (1) B/W Neg.: DHF R/75/07.10
<i>Publication</i>	RRMAM 2, 1. 064 (notice only)
<i>Description</i>	A simple cylinder. Complete. Hard, grey limestone
<i>Dimensions</i>	Not recorded

*Text* No visible inscription

## 028. Beke

*Province, Sub-Province + Admin. Code* Amasya 05-00-3  
*Map* Amasya 81-n  
*Location* “Dans le [même] village” (St. Pont.). Present whereabouts not established (DHF visit 23.vii.1983)  
*Copy* Proestakis (“dragoman du vilayet de Sivas”) (? date); conveyed to Grégoire by Mordtmann  
*Publication* St. Pont. 3, 1 (Anderson et al.), 221 (no. 446a) (notice)  
 RRMAM 2, 1. 061 (notice only)  
*Description & Dimensions* Not given  
*Text* None given

## 029(A). Boğazkaya 1, form. Bebük

*Province, Sub-Province + Admin. Code* Çorum, Mecitözü 19-05-0  
*Map* Çorum 80-o  
*Location* Location not given. Present whereabouts not established (DHF visit 15.vii.1977)  
*Copy* Dernschwam with Busbecq 05 April, 1555. The stone has not been examined by DHF. Text here of CIL (Dernschwam)  
*Publication* Dernschwam text: Babinger 1923, 206  
 CIL 3. 308 (text of Dernschwam)  
 St. Pont. 1 (Anderson), 16 (no. 452) (notice)  
 Pflaum 1948, 66-68 (comments)  
 Stein 1957, 6-7 (comments)  
 Lorient 1976, 57 (text of CIL 3. 308, and comments)  
 RRMAM 2, 1. 322 (notice only)  
 Lorient 2006, 402 (citation of Dernschwam text)  
*Description & Dimensions* Not known

*Text*

-----  
 2 **C·Iul·Vero·Maxim{in}o** (sic)  
**nobilissimo Caesar<i>**  
 4 **per·P·Aelium·Vibia-**  
**num pr provinc·Pont(i)**  
 6 **m [ - ]**

line 2: **MAXIMINO** (lapis)

line 5: **PVINC·RO**

*Caput Viae* (Amasia)  
*Date* AD 236, 07.i/16.v-238, mid-April [Maximinus *Augustus* with] Maximus *Caesar*

## 029(B). Boğazkaya 2, form. Bebük

*Province, Sub-Province + Admin. Code and Map* As 029(A)  
*Location* “In coemeterio” (CIL); “In a cemetery below the village Bebük” (Anderson)

1903). Now in the village, at the entrance to the Lower Cami

<i>Copy</i>	Anderson (?) 16 July, 1899; DHF 15.vii.1977. DHF squeeze in BIA. No DHF photo. Texts here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i>
	Squeeze: 19. Çorum 20, Boğazkaya 2
<i>Publication</i>	CIL 3. 14184 <sup>37</sup> (text from Anderson) St. Pont. 1 (Anderson), 8, 16 (no. 451) (notice) French 1981, 156 (notice only) RRMAM 2, 1. 323 (notice only)
<i>Description</i>	A simple cylinder. (?) Complete. Hard, pale limestone. Letters: irregular in shape and size, worn and indistinct; (texts 1 and 2) broken-bar A
<i>Dimensions</i>	Ht 1.26; diam. 0.38. Letters: (text 3) 0.035-55
<i>Text</i>	(1a) and (1b) (underneath and obliterated by text [2]; ll. 1-3 here are located below and r. of text 2 line 14 which partly covers the first letters of line 1; the letters MQ of text 2 line 13 cut through the distance-numeral of text [1])

(1a) (larger, irregularly cut letters, c.0.050)

-- ? --  
[Dioc]letiano  
2 [ - - - - - ] et  
- - - -

(1b) (smaller, neatly cut letters, c. 0.030-35) (one line visible underneath [Dioc]letiano and numerous lines visible underneath text [2])

- - - -  
[et Gal] Val  
[Maximiano]  
2 [Aur Prisc]ianus  
[v p] praes-pro(v) Ponti  
4 d n m q eorum  
(vac) κς'

lines 3-4: for the abbreviations, see above, 18. Çiğdemlik

(2) (on the top of texts [1] and [2])

BF  
DD nn  
Imp Caes Fl  
4 Constantino  
p f m vic sem-  
per Aug et  
[Fl] Cl Constantino  
8 et Fl Iul Constantio  
et Fl Iul Constante (sic)  
nobiliss Caess  
Fl Iul Leontius  
12 v p praes provinc

**Helenop d n m q  
eorum**  
(vac) [κς']

lines 12-14: **v**(ir) **p**(erfectissimus) **praes**(es) **provinc**(iae) | **Helenop**(onti)  
**d**(evotus) **n**(umini) **m**(aiestate)**q**(ue) | **eorum**; for the abbreviations,  
see above, 18. Çiğdemlik

*Caput Viae* (Amasia)  
*Date* (1a, 1b) (?) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with  
Constantius and Galerius *Caesares*  
(2) AD 333, 25.xii–335, 18.ix Constantinus *maximus victor Augustus* with three  
sons, Constantinus, Constantius and Constans *Caesares*

**029(C). Boğazkaya 3, form. Bebük**

*Province, Sub-Province + Admin. Code and Map* As 029(A)  
*Location* In the village; at the house (no. 12) of Mahmut Özkolukısa. Brought by the owner  
from his fields which are located below the village and opposite the road-junction  
on the Çorum - Amasya highway; dug out from 4 m depth  
*Copy* DHF 15.vii.1977. DHF squeeze in BIA. No DHF photo. Texts here from DHF  
squeeze  
*BIA Collections:* *Squeeze and Stone Photographs*  
Squeeze: 19. Çorum 19, Boğazkaya 3  
*Publication* French 1981, 151 no. 4  
AE 1986. 656 (text of French)  
RRMAM 2, 1. 324 (notice only)  
Loriot 2006, 412 (citation of text and governor's name)  
*Description* A simple cylinder. (?)Complete. Very hard, blue limestone  
Letters: (text 1) some wear and loss, unevenly shaped and spaced, (text 2) neatly  
cut, sharp and clear, broken-bar A  
*Dimensions* Ht 1.36; diam. (top) 0.41. Letters: (text 1) 0.030–45, (text 2) c. 0.030 but (line 9)  
E 0.020  
*Text* (1) (underneath ll. 1–10 + 11, and below line 10, of text (2))  
[Imp Caesar]  
[Gaius] **Iu/l/ius**  
**Ve[rus Ma]ximinus**  
4 **p f** [inv Augustu]s **trib-**  
**uni[c]i[a po]test**  
**p p ços p[ro]cos et**  
[G] **Iu[l]i[us] Verus**  
8 **Ma[x]im{in}us no-** (sic)  
**lilissibus Caes-** (sic)  
**sar Aug per A/e/-**  
**I/i/um Vibianu-**  
12 **m v p praesid**  
**provinc**  
**m p**  
**κς'**

line 2: **IVIIVS** (lapis)  
 line 8: **MAXIMINUS** (lapis)  
 lines 10-11: **AFILLVM** (lapis)  
 lines 12-13: **v(ir) p(erfectissimus) praesid(em) provinc(iae) Ponti**

(2) (on top of ll. 1-8 of text [1])  
 [Impp Caess]  
 [Gal Val Maximiano]  
**p f i n v A u g** [[et]]  
 4 [[Val Licin Licinnio]]  
**p f i n v A u g et**  
**Gal** [[Val Maximino]]  
**et Flav Constantino**  
 8 **fill·Aug**  
 (vac)  
**Fl' Severus v p p p**  
**Diosp**  
 (gap, c. 0.16)  
 11 **κς'**

line 8: **fill Aug - fil(ii) Aug(ustorum)**  
 lines 9-10: **v(ir) p(erfectissimus) p(raeses) | p(rovinciae) | Diosp(onti)**

*Caput Viae* (Amasia)  
*Date* (1) AD 236, 07.i/16.v-238, mid-April Maximinus *Augustus* with Maximus *Caesar*  
 (2) AD 308, 11.xi-311, beg. May Galerius and Licinnius (names erased) *Augusti*,  
 with Maximinus (name erased) and Constantinus, *fili Augustorum*  
*Commentary* The erasure of Licinnius and Maximinus (and also, perhaps, of Galerius) were no doubt effected under Constantinus.

### 029(D). Boğazkaya 4, form. Bebük

*Province, Sub-Province + Admin. Code and Map* As 029(A)  
*Location* In the village; at the Lower Cami. Brought from a *çeşme* (fountain) at the old village in the valley to W of the new village  
*Copy* DHF 24.vii.1983. DHF squeeze in BIA. No DHF photo. Texts here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 19. Çorum 18, Boğazkaya 4  
*Publication* RRMAM 2, 1. 325 (notice only)  
*Description* A simple cylinder. Broken above, otherwise complete. Hard, pale limestone. Shaft tapers slightly towards top.  
 Letters: (text 1) irregular shape and size, unevenly spaced, worn and faint, lunate E, (text 2) sharp and clear but unevenly cut  
*Dimensions* Ht (ex.) 1.73; diam. (at middle) 0.44. Letters: (text 1) 0.025-60, (text 2) 0.025-35, (line 2) O 0.020  
*Text* (1) (on the lower half of the shaft; lines 1-4 underneath lines 3-8 of text [2])  
 - - - -

2     [ - ]T[ - - ]  
       **M**[ - - - - ]  
 4     [ - - - - ]  
       [ - - - - ]  
 6     [ - - - - ]  
       [ - - - - ]  
 8     [ - - - - ]  
       [ - - - - ]  
 10    [ - - - - ]  
       (vac)  
 11            **κς'**

line 8: faint traces of letters, possibly **Αυρ Βαλentinian[us]**

(2) (on the upper half of the shaft, on top of ll. 1-4 of text [1])

[Impp Caes]§ **F!**  
**Val Constantio et**  
**Gal Val Maximiano**  
 4    **pp ff invict Augg**  
      **et Fl Val** [[[Severo]]]  
      **et Gale Val** (sic)  
      [[[Maximino]]]  
 8    **nobill Caess**  
      (c. 0.14 gap)  
      **κς'**

line 4: **p(iis) f(elicibus) invict(is) Aug(ustis)**

line 9: the distance numeral is cut in between lines 6 and 7 of text [1]

<i>Caput Viae</i>	(Amasia)
<i>Date</i>	(1) (?) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i> (2) AD 305, 01.v–306, 25.vii Constantius and Galerius <i>Augusti</i> with Severus (name erased) and Maximinus (name erased) <i>Caesares</i>
<i>Commentary</i>	If the restoration of line 8 is correct, the date of text (1) can be established from a complete inscription which names Aur(elius) Valentinianus as <i>praeses</i> of Pontus under the Tetrarchy (French 1981, 158 no. 9 = RRMAM 3.4 [Pontus et Bithynia] 49(D). Vezirköprü 4).

### 030(A). Figani 1

<i>Province, Sub-Province + Admin. Code</i>	Çorum, Mecitözü 19-05-0
<i>Map</i>	Çorum 80-o
<i>Location</i>	In the village; at the cami. Used as a support for a wooden column in the <i>şadırvan</i> (water-tank with wash-basins for <i>abdest</i> [pre-prayer ablutions]). The stone has been buried since c. 1980 when the <i>şadırvan</i> was re-built
<i>Copy</i>	DHF 24.vii.1983. No squeeze. No DHF photo. Text here from DHF notes
<i>Publication</i>	RRMAM 2, 1. 336 (notice only)
<i>Description</i>	A simple cylinder. Very hard, blue limestone
<i>Dimensions</i>	Ht (est.) 1.50



*Text*

**Imperator**  
 2 **Caes M Aur**  
**Caro p f invict**  
 4 **Aug et [ - ]**  
 - - - -  
 (remainder of text is not visible)

*Caput Viae* [Amasia]  
*Date* AD 282 Carus *Augustus* [with Carinus and Numerianus?], cp. the text of 025.  
 Toklucak

### 030(B)-(C). Figani 2-3

*Province, Sub-Province + Admin. Code and Map* As 030(A)  
*Location* As 030(A)  
*Publication* RRMAM 2, 1. 337-338 (notice only)  
*Copy* Not recordable (24.vii.1983); buried since c. 1980.

### 031. Köseeyüp

*Province, Sub-Province + Admin. Code* Çorum, Mecitözü 19-05-0  
*Map* Çorum 80-o  
*Location* In the village; in the cemetery  
*Copy* Anderson (?) 16 July, 1899; DHF 15.vii.1977. DHF squeeze and photo. (Pl. 7.1.15 [p. 378]) in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 19. Çorum 123, Köseeyüp  
 Stone: (1) B/W Neg.: DHF R/77/11.03  
*Publication* CIL 3. 14184<sup>38</sup> (text from Anderson)  
 St. Pont. 1 (Anderson), 8, 16 (no. 450) (notice)  
 RRMAM 2, 1. 347 (notice only)  
*Description* A simple cylinder. Complete. Hard, pale limestone. Top flat. Letters: very worn and faint  
*Dimensions* Ht (vis.) 1.25; diam. (top) 0.43. Letters: (text 2) c. 0.050, (text 3) 0.045-55

*Text*

(1) (underneath text [2] and text [3])  
 perhaps traces  
  
 (2) (underneath, on the r. of, and largely obliterated by, text [3])  
 [Imp Nerva Ca]eş  
 2 [Aug pontif ma]x  
 [trib potest] çoş·III  
 4 [p p - - -]  
 (c. 0.57 gap)  
 mp XXXI·  
  
 lines 3 and 5: horizontal line over numerals  
  
 (3) (on the top, and on the l., of [2])  
 (Maltese cross on the l. of inscription)

**BF**  
**Imp Caes Fl**  
**Constantino**  
4 [p f m] **vic sem**[per]  
(vac) **Aug et**  
[Fl Cl] **Constantino**  
[et Fl Iul] **Constantio**  
8 [et Fl] **Iul Constanti**  
**nobiliss Caess**  
**Fl Iul Leontius**  
[v] **p praes provinc**  
12 [H]elenop d n m q  
(vac) **eorum**  
(vac)  
**mil p**  
**XXXI**  
16 **N**

lines 11-12: [v(ir)] **p**(erfectissimus) **praes**(es) **provinc**(iae) | [H]elenop(onti),  
cp. 29(B). Boğazkaya 2(2)

line 6: the presence of the letter N is obscure; ? intended for ΛΑ, i.e. λα´

*Caput Viae* (Amasia)

*Date* (1) (?)

(2) (?)AD 97, 01.0i-17.ix Nerva *Augustus*

(3) AD 333, 25.xii-335, 18.ix Constantinus *maximus victor Augustus* with three sons, Constantinus, Constantius and Constans *Caesares*

*Commentary* According to Kienast (1996, 120), Nerva began his COS III on AD 01 January 97 and ended his TR P (I) on 17 September 97.

### 032(A). Kozören 1

*Province, Sub-Province + Admin. Code* Çorum, Mecitözü 19-05-0

*Map* Çorum 79-o

*Location* In the village; at the house of Mehmet Toraner, at SW (= outside) corner

*Copy* DHF 01.vii.1986. DHF squeeze and photos (Pl. 7.1.16 [p. 378]) in BIA. Text here from DHF squeeze

*BIA Collections: Squeeze and Stone Photographs*

Squeeze: 19. Çorum 113, Kozören 1

Stone: (1) B/W Neg.: DHF M/86/13.03

(2) Col. Slide: DHF 260.09

*Publication* French 1987, 191 (notice only)

*Description* A simple cylinder. Broken below. Hard, pale limestone. The top is roughly cut in the shape of a round cap. Inscribed face smoothed.  
Letters: regular in shape and size, well cut but very worn and (in places) faint; U for V

*Dimensions* Ht c. 0.80; diam. (at break) c. 0.46. Letters: 0.030 but (line 1) I of IMP 0.045

*Text* **Imp Caesa[r M Iu]-**  
**lius Fel[i]ppus [pi]-**

(sic)

4            **us fel[ix] Aug trib**  
               **{e} potest p p et M**  
               **Iulius [F]eli[p]pus** (sic)  
               **nobilissimus Cae-**  
               **sar viam restitu-**  
 8            **it mil X[L]**

lines 2 and 5: Felippus for Philippus, cp. RRMAM 3.2. 73(B) Filippus for Philippus

*Caput Viae*        (Amasia)  
*Date*                AD 244, vii/viii-247, vii/viii Philippus *Augustus* with Philippus *Caesar*

### 032(B). Kozören 2

*Province, Sub-Province + Admin. Code and Map*    As 032(A)  
*Location*        In the village; now built, upside down, into the courtyard gate of the cami, on the left of the entrance  
*Copy*              DHF 14.x.1995. DHF squeeze and photos (15.x.1995) (Pl. 7.1.17 [p. 379]) in BIA. Text here from DHF squeeze  
*BIA Collections:* *Squeeze and Stone Photographs*  
                       Squeeze: 19. Çorum 114, Kozören 2  
                       Stone: (1) B/W Neg.: DHF M/95/04.13  
                       (2) Col. Slide: DHF 412.28  
*Description*      A simple cylinder. Hard, pale limestone. The top is not visible. Base flat; chipped around the edges. The inscription is cut on a prepared surface. Surface and letters: worn, especially at the top.  
*Dimensions*      Ht (vis.) 1.51; diam. (base) c. 0.51. Letters: c. 0.055-65

*Text*                        - - - -  
                               [et Imp Caes]  
                               [Marcus Aur]-  
                               **el(ius) Antonin-**  
 5                        **us·Aug \_et [L S]´-**  
                               \_[ept Geta nob]´  
                               \_[Caes]´ **resti-**  
                               **tuerunt·per**  
                               **C·Iulium·Flaccum**  
 10                        **Aelianum·**  
                               **leg·pr·pr**  
                               **mil·pas<s>**  
                               **XXXXI·**  
                               ·μᾶ·

*Caput Viae*        (Amasia)  
*Date*                AD 197/198(?) [L. Septimius Severus] and M. Aurelius Antoninus (Caracalla)  
                       *Augusti* [with L. Septimius Geta (names erased) *Caesar*]; for an intact text of Septimius Severus, see below, 050(B). Boğazbaşı 2  
*Commentary*      Here we have unequivocal testimony that, under Septimius Severus, ancient Amasia and its territory lay within the province of Cappadocia. The imperial *legatus*, C. Iulius

Flaccus Aelianus, is prolifically attested along the Caesaria - Melitene road, that is to say, in the heartland of Cappadocia (see the distribution-map, 5.2.1 [p. 317]).

### 032(C). Kozören 3

*Province, Sub-Province + Admin. Code and Map* As 032(A)

*Location* In the village; brought from the old cami. Now in the courtyard of the new cami

*Copy* DHF 14.x.1995. DHF squeeze in BIA. No DHF photo. Text here from DHF squeeze

*BIA Collections:* *Squeeze and Stone Photographs*

Squeeze: 19. Çorum 115, Kozören 3

*Description* A simple cylinder. Hard, grey limestone. Roughly shaped shaft which flares outwards at the bottom, thus forming a base or plinth. Surface and letters: worn. Letters: diagonal-bar F

*Dimensions* Ht (ex.) 0.85; wi. (top) 0.42, (base) 0.57. Letters: c. 0.035

*Text*

-----  
[et Imp Caes]  
[G Viviu]s  
4 **Veld[um]nianus**  
**Volussia-** (sic)  
**nus p f inv**  
**Aug**  
(vac) **μί**  
(vac)  
8 (vac) **λγ'**

*Caput Viae* (Amasia)

*Date* AD 251, (?)Aug-253, (?)Aug [Trebonianus Gallus and] Volusianus *Augusti*

### 033(A). Çitli 1

*Province, Sub-Province + Admin. Code* Çorum, Mecitözü 19-05-0

*Map* Çorum 79-n

*Location* “La borne ‘sert de colonne devant la chambre de la mosquée de Tchiftli’, village situé dans la haute vallée du Lycus, non loin de sa source” (Cagnat); “Dans le (même) village” (Cumont). Present whereabouts not established (DHF visits 15.vii.1977, 26.vi.1986 and 14.vi.1990)

*Copy* Girard (?date). The stone has not been examined by DHF. Text here of CIL (Girard) with emendations of French 1981

*Publication* Cagnat 1894, 132 and n.1 (text from Girard)  
Cumont 1902, 329 (notice)  
CIL 3. 13643 (text of Girard apud Cagnat)  
St. Pont. 3, 1 (Anderson et al.), 221 (no. 248) (notice)  
Mitford 1972, 3, no. 206-2 (notice)  
Loriot 1976, 53 n.4 (notice)  
French 1981, 157 and 162 (revision of text)  
RRMAM 2, 1. 993 (notice only)  
AE 1986. 662 (text of French 1981)  
French 1991b, 84 (note on location)

*Description & Dimensions* Not given

*Text* (1) (below, and underneath, text [2])

-----  
 2     **m p XXXIII**  
       **N PB Aur Priscianu[s]**  
 4     **v p praes pro(v) Po[n]ti**  
       **d n m q eorum**  
       \* n m q eorum \*

For an intact tetrachic text, see below, 056(D). Zile 4

(2) (above, and on the top of, text [1])

**DD nn O(?)**  
**\*Imp Caes F<l> Val**  
**Constantino**  
 4     **p f m vic[t]o[ri] sēm-**  
       **[pe]r A[ug]**  
       **[et Fl Cl Con]stanti[no]**  
       **[et Fl Iul C]onstant[io]**  
 8     **[et Fl] Iul C[on]stant[i]**  
       **[n]obis Cae[s]s**  
       **[Fl Iul] Leontius**  
       \* \* \*  
       **[v p p]rae[s] pr Helenop]**  
 12    **[d] n m q**  
       **[eorum]**

line 4: **p(io) f(elici) m(aximo)**

For an intact text, see above, 29(B). Boğazkaya 2(2)

*Caput Viae* (Amasia)

*Date* (1) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with  
 Constantius and Galerius *Caesares*, on the basis of the governor's name  
 (2) AD 333, 25.xii–335, 18.ix Constantinus *maximus victor Augustus* with three  
 sons, Constantinus, Constantius and Constans *Caesares*

### 033(B). Çitli 2

*Province, Sub-Province + Admin. Code and Map* As 033(A)

*Location* In the village; lying in the street beside the cami. Found, lying near-horizontally  
 c. 1 m below surface, in November 1989 by the *muhtar*, Mustafa Balat, in Derler  
 Mevkii, c. 3 km W of village; the area was an old(?) village and Islamic *mezarlık*  
 (cemetery)

*Copy* DHF 14.vi.1990. DHF squeeze in BIA. No DHF photo. Text here from DHF  
 squeeze

*BIA Collections:* *Squeeze and Stone Photographs*

Squeeze: 19. Çorum 31, Çitli 2

*Publication* French 1992, 150 (notice only)

*Description* A simple cylinder. Broken above and below. Hard, pink-and-white limestone.  
 Perhaps a re-used column; the shaft is finely smoothed and straight.

Letters: worn; note the variants of A, (texts 1 and 3) straight-bar A, (text 2) broken-bar A

*Dimensions* Ht (max.) 1.64; diam. (top) 0.35. Letters: (text 1) (line 3) **O** of **ONG** 0.034, (text 2) (line 4) **N** of **ANO** 0.048, (line 10) **O** of **PONT** 0.013, (text 3) (line 5) **O** of **LEO** 0.037

*Text* (1) (at the front of the shaft)

-----  
 2 [Numerian]o no-  
 [bill C]aēsari  
 (vac)  
 4 buş Cl /L/onginuş  
 praes  
 (vac)  
 6 λθ'

line 4: **B V Ş C L I O N G I N V Ş** (lapis)

(2) (on the r., and partly on the top, of text [1])

-----  
 [et Fl] Val  
 [C]onstantio  
 [et G]alerio Val  
 4 [Max]imiano  
 [nob]ill Caess  
 [[mil pass]]  
 XXXVIII  
 (vac)  
 8 λθ'  
 Aur Priscianus  
 v p praes pr Ponti  
 d n m q eorum

(3) (on the r., and partly on the top, of text [1]; above, and partly on the top of, text [2])

-----  
 2 [et] Fl Cl Con (sic)  
 et Fl Iul Const(a)n (sic)  
 4 et Fl Iul Const (sic)  
 nobiliss Caess  
 6 [F]l Iul Leontius  
 v p praes prov  
 8 Helenop d n m q  
 eorum

lines 7-9: for an undamaged replicate, consult the text of 29(B). Boğazkaya 2(2)

*Caput Viae* (Amasia)

*Date* (1) AD 282 end-early 283 [Carus Augustus with Carinus] and Numerianus

*Caesares*

(2) AD 293, 21.v(?)–305, 01.v [Diocletianus and Maximianus *Augusti*] with Constantius and Galerius as *Caesares*

(3) AD 333, 25.xii–335, 18.ix [Constantinus *maximus victor Augustus*] with three sons, Constantinus, Constantius and Constans *Caesares*

**034(A). Mecitözü 1**

*Province, Sub-Province + Admin. Code* Çorum, Mecitözü 19-05-0  
*Map* Çorum 79-o  
*Location* “At Avghat Hadji Keui, in the Medjid-euzu” (Anderson). Present whereabouts not established (DHF visits 15.vii.1977 and 02.vii.1986)  
*Copy* Cumont to Anderson 02 June, 1899. The stone has not been examined by DHF. Text here of St. Pont. (Anderson)  
*Publication* St. Pont. 1 (Anderson), 23 (no. 446) (notice)  
 RRMAM 2, 1. 348 (notice only)  
*Description & Dimensions* Not given

*Text*

-----  
**CXXXVI**  
 perhaps - [m] p XXXVI

*Caput Viae* (Amasia)

*Date* (?)

**034(B). Mecitözü 2**

*Province, Sub-Province + Admin. Code and Map* As 034(A)  
*Location* In the town; at the house of Mustafa Yılmaz (Mine Sokak 30, Sarıdede Mahalle)  
*Copy* DHF 14.x.1995. DHF squeeze in BIA. No DHF photo. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 19. Çorum 125, Mecitözü 2  
*Description* A simple cylinder. Broken above; rough below. Hard, pale limestone. The inscription is cut on a smoothed surface. Letters and surface: worn and chipped.  
*Dimensions* Ht c. 0.95; diam. (min.) 0.40. Letters: c. 0.035

*Text*

[Imp Caes]-  
 [ar M Iulius Ph]-  
 [lippus pius]  
 4 [feli]x A[ug trib]  
 {e} **potest p** [p et]  
**M Iulius** [Philip]-  
**pus nob**[ilissimus ?]  
 8 **Caesar viam**  
**restituit**  
 (vac) **mil XX**[XIV]  
 λδ´

*Caput Viae* (Amasia)

*Date* AD 244, vii/viii-247, vii/viii [Philippus] *Augustus* with Philippus as *Caesar*  
*Commentary* The text here has been modelled, in part, on the parallel example found at Kozören (032[A]. Kozören 1), c. 4 km E of Mecitözü.

### 035. Elvançelebi

*Province, Sub-Province + Admin. Code* Çorum, Mecitözü 19-05-0  
*Map* Çorum 78-o  
*Location* “Twenty mins. below the village at a fountain beside the chaussée” (St. Pont.). Present whereabouts not established (DHF visits 15.vii.1977, 19.ix.1985, 02.vii.1986)  
*Copy* Anderson (?) 06 June, 1899. The stone has not been examined by DHF. Texts here of CIL (Anderson)  
*Publication* CIL 3. 14184<sup>39</sup> (text from Anderson)  
 St. Pont. 1 (Anderson), 11 (no. 449) (notice)  
 RRMAM 2, 1. 332 (notice only)  
*Description & Dimensions* Not given

*Text* (1) (underneath text [2])

2     **restituit pe[r]**  
       [T Po]mponium  
 4     [Bas]sum leg  
       [Aug pro pr]

(2) (on the top of text [1])

[I]mper Caes [C Aur Val]  
 [Di]ocletiano p f invic  
 [Au]g et Imp Caes M Aur [Val]  
 4     [Ma]ximiano p f invic A[ug]  
       [et F]l Constantio et G[al]  
       [Val] Maximiano nobill  
       [Ca]ess m[i]l p [X]XXVIII  
           (vac)  
 8     [Aur P]riscian[u]s v p [pr]  
       [pro]p Pont d n m q e[orum]

line 7: recut from/over line 2 of text (1)

*Caput Viae* (Amasia)  
*Date* (1) Nerva or Traianus, on the basis of the governor's name  
 (2) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*

### 036. Güngörmez

*Province, Sub-Province + Admin. Code* Çorum, Mecitözü 19-05-0  
*Map* Çorum 78-o  
*Location* In the village; at the house of Mustafa Dinç. Now in the Çorum Museum [Inv. no.



	30.1.86]
<i>Copy</i>	DHF 27.vi.1986. DHF squeeze (drawing, Fig. 6.2.9 [p. 358]) and photo. (Pl. 7.1.18 [p. 379]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 19. Çorum 90, Güngörmez Stone: (1) B/W Neg.: DHF M/83/02.04
<i>Publication</i>	French 1985a, 123 and Fig. 2 RRMAM 2, 1. 339 (notice only)
<i>Description</i>	A simple cylinder and plinth. Broken into two pieces. Hard, blue limestone. Top flat. Plinth rough, very simply shaped. Letters: irregularly cut and spaced but sharp and clear; U for V
<i>Dimensions</i>	Ht 1.14 + 0.75; diam. 0.40; (plinth) ht 0.15; diam. 0.46. Letters: 0.035-70, (line 7) P 0.080

<i>Text</i>	<b>Imp C[ae]- sar di[vi] Nervae 4 nepos·T[rai]- anus H[adri]- anus Au[g] pontif m[ax] 8 trib·pot[es]- t XIII im[p] XII[I] p p v[i]- am a[b Ama]- 12 sia at fine[s] (sic) Galatorum milia mi·p·XXXXII</b>
-------------	--

line 12: **at** for **ad**

<i>Caput Viae</i>	Amasia
<i>Date</i>	AD 128/129, 10.xii-09.xii Hadrianus <i>Augustus</i>
<i>Commentary</i>	For the phrase <i>at fines Galatorum</i> , see the near-replicate, 23(A). Bağlıca 1

### 037(A). Çorum 1

<i>Province, Sub-Province + Admin. Code</i>	Çorum 19-00-0
<i>Map</i>	Çorum 76-o
<i>Location</i>	“In oppido Tschorum ad moscheam parvam” (CIL). Present whereabouts not established (DHF visit 25.vii.1983)
<i>Copy</i>	Anderson (?)04 June, 1899. The stone has not been examined by DHF. Text here from CIL (Anderson)
<i>Publication</i>	CIL 3. 14184 <sup>40</sup> (text from Anderson) St. Pont. 1 (Anderson), 7 (no. 448) (notice) French 1980, 725 no. 31 (text of CIL [Anderson]) RRMAM 2, 1. 329 (notice only)
<i>Description &amp; Dimensions</i>	Not given

*Text*

**Imp Caesa[r]**  
**G Mēss<i>us**  
**Quintus** [Traia]-  
4 **nus Decius** [pius]  
**fēlix invictu[s]**  
**Aug tribuni**[c po]-  
**test p p cos II**  
8 [vi] **am restit**[uit]  
[per] **VM**[...c.8..]  
[...c.13.....]  
- - - -

line 7: <pontifex maximus> omitted by lapicide, cp. the titulatur omissions,

RRMAM 3.4 Pontus et Bithynia. 48(B). Arica 2

line 9: [per] Val[erium Nepotianum] ?

*Caput Viae* [Amasia]

*Date* AD 250, 01.i-v/vi Traianus Decius *Augustus*

*Commentary* For Valerius Nepotianus, governor under Traianus Decius, see the texts, RRMAM 3.4 Pontus et Bithynia. 48(B). Arica 2 and 56. Ortaklar  
For the date of Decius' COS II, see Kienast (1996, 204)

### 037(B). Çorum 2

*Province, Sub-Province + Admin. Code and Map* As 37(A)

*Location* In the town; at Dutdede Türbe, Üçtutlar Mah.. The stone is now in the Çorum Museum

*Copy* DHF 07.viii.1989. DHF squeeze in BIA. No DHF photo. Texts here from DHF squeeze

*BIA Collections:* *Squeeze and Stone Photographs*  
Squeeze: 19. Çorum 36, Çorum 2

*Publication* French 1991a, 231 (notice only)

*Description* A simple cylinder. Complete. Hard, pale limestone. Top flat; the shaft tapers slightly at top; bottom flat.

Letters: worn; (2) cursive A, tilted L, curvilinear M, and N with a short, almost horizontal

*Dimensions* Ht 1.92; diam. (base) 0.39, (top) c. 0.35. Letters: (text 1) c. 0.040, (text 2) (line 3) D 0.033 and O 0.039 in DIOC, E in CAESS 0.042

*Text* (1) (lines 1-6 underneath text [2], lines 7-8 partly underneath, lines 9-18 on rt of lines 7-8 of text [2])

[ - - - - ]  
[ - - - - ]  
**M**[ - - - ]  
4 **A**[ - - - ]  
[ - - - - ]  
[ - - - - ]  
[trib pot VI i] **mp** [XI]  
8 [cos] **II·p·p** [pro] -

**cos·et·Imp·Caes**  
**Marcus·Aurelius**  
**Antoninus**  
 12 **Aug** \_ \_ \_ \_ '  
 \_ \_ \_ \_ \_ '  
 [re]stitu[erunt] **per**  
**C·Iulium**·[Flaccum]  
 16 **Aelianum**  
**leg pr pr**  
**m·p[as]s·LV**  
 (vac)

For an undamaged replicate, consult the text of 050(B). Boğazbaşı 2

(2) (above, and on the top of, text [1])

**DD nn**  
**Imper [C]aes Caio Aurel Val**  
**Diocletiano p f invicto**  
 4 **Aug et Imp Caes M Aur Val**  
**Maximiano p f inv Aug et**  
**Fl Val Constantio et Gal**  
**Val Ma[x]imiano nobill**  
 8 (vac) **Caess mil [p]**  
 (vac) **LV**

*Caput Viae* (Amasia)  
*Date* (1) AD 197/198(?) [L. Septimius Severus] and M. Aurelius Antoninus (Caracalla)  
*Augusti* with L. Septimius Geta (names erased) *Caesar*  
 (2) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with  
 Constantius and Galerius *Caesares*

### 037(C). Çorum Museum

*Location* The provenance is lost. The stone is now in the Çorum Museum [Inv. no. 6.505.68]  
*Copy* DHF 10.x.1974. DHF squeeze (drawing, Fig. 6.2.10 [p. 358]) and photos (Pl. 7.1.19 [p. 379]) in BIA. Text here from DHF squeeze  
*BIA Collections:* *Squeeze and Stone Photographs*  
 Squeeze: 19. Çorum 35, Çorum Museum (photo. Col. Slide: DHF 294.37–38)  
 Stone: (1) B/W Neg.: DHF R/74/17.06–07  
*Publication* French 1976, 53 (notice only)  
 French 1981, 153 no. 6  
 AE 1986. 655 (text of French 1981)  
 RRMAM 2, 1. 991 (notice only)  
 Lorient 2006, 407 (citation of text)  
*Description* A re-used column. Broken below. Pale limestone. Letters: sharp and clear  
*Dimensions* Ht (ex.) 0.97; diam. (top) 0.30. Letters: (line 1) A 0.085  
*Text* **Imperator**

**Caesari M**  
**Aurelio Pro/b/o**  
4 **p f invict**  
**Aug·pont max**  
**trib pot IIII p·p**  
**proc ab Amasia**  
8 **mil p ς' tran/si/ta a solo**  
**conposita**  
10 **curante**  
**Ael Quintiano**  
**v p pr p P**

line 3: **PRORO** (lapis), cp. below, 115. Alımpınar

line 8: consult drawing

line 12: v(iro) p(erfectissimo) pr(aeside) p(rovinciae) P(onti)

*Caput Viae* Amasia  
*Date* AD 279, Summer-280, Summer Probus *Augustus*  
*Commentary* The cutter's error, PRORO (line 3) for PROBO, is known on at least one other milestone (to be published as RRMAM 3.4 [Pontus et Bithynia] 43. Boyabat 2).  
 The phrase *transita a solo conposita* is unique in Asia Minor.

### 038. Tolahmet

*Province, Sub-Province + Admin. Code* Çorum 19-00-0  
*Map* Çorum 77-ö  
*Location* Brought from the village. Now in the Çorum Museum [Inv. no. 2.1.96]  
*Copy* DHF 12.x.2000. DHF squeeze (drawing, Fig. 6.2.11 [p. 357]) in BIA. No DHF photo. Text here from DHF squeeze  
*BIA Collections:* *Squeeze and Stone Photographs*  
 Squeeze: 19. Çorum 139, Tolahmet  
*Description* A simple cylinder. Broken above and below. Hard, pale limestone. The horizontal section of the shaft is oval  
 Letters: irregular in size and spacing but sharp and clear; pronounced apices;  
 U for V  
*Dimensions* Ht (ex.) 0.66; diam. (l.-r. axis) 0.40. Letters: 0.020-35

*Text*

**Imp C[a]ę̣ G·V̇i̇v̇i̇us**  
**Trebon<ia>nus Gallus**  
**pius·fel·Aug·et**  
4 **Imp Caes·C·Tre-**  
**boni<an>us·Beldu-**  
**nmianus Volu-**  
**sianus·piu[s]**  
8 **fel Aug [trib]**  
**pot·cō[s pp]**  
**viam [restituerunt]**  
**per [ - - - - ]**  
 - - - -

*Caput Viae* [Amasia]  
*Date* AD 252 Trebonianus Gallus and Volusianus *Augusti*  
*Commentary* For the date of Volusianus' COS, see Kienast (1996, 210)

### 039. Karapınar

*Province, Sub-Province + Admin. Code* Çorum 19-00-0  
*Map* Çorum 76-ö  
*Location* In the village; in the cemetery on N side of the village  
*Copy* DHF 27.vii.1983. DHF squeeze (drawing, Fig. 6.2.12 [p. 358]) in BIA.  
 No DHF photo.  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 19. Çorum 127, Ovakarapınar  
*Publication* RRMAM 2, 1. 349 ("Ovakarapınar") (notice only)  
*Description* A simple cylinder. Broken at top. Hard, blue limestone. Surface: worn.  
*Dimensions* Ht (visible) 0.84; wi. 0.49

#### Text

2      - - - -  
          **mi p** [LII]  
          **vß'**

There is a horizontal bar above the numeral **NB**  
 There are traces of letters (Greek ?) underneath lines 2-3

*Caput Viae* (Amasia)  
*Date* (?)

### 040. Saray

*Province, Sub-Province + Admin. Code* Çorum, Çorum 19-00-0  
*Map* Çorum 76-p  
*Location* In the village; lying in the street at the corner of the house owned by Mehmet Ertuğrul  
*Copy* DHF 16.vii.1987. DHF squeeze (drawing, Fig. 6.2.13 [p. 358]) and photo. in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 19. Çorum 131, Saray  
 Stone: (1) B/W Neg.: DHF R/77/11.06  
 (2) DHF Col. Slide: 275.35  
*Description* A simple cylinder. Broken into two pieces (upper part used as a column base in house). Hard, grey limestone. The shaft tapers towards the top; base flat.  
 Letters: irregularly cut and spaced, slightly worn but clear; A with short diagonal bar, U for V  
*Dimensions* Ht (front) 1.23; diam. (base) c. 0.50. Letters: 0.030-45  
*Text* (1) (underneath text [2])  
          obliterated  
 (2) (on the top of text [1])

[Imp Caes M Ant]-  
 [onius Gordia]-  
 [nus divi Gordi]-  
 4 [ani nepos pius]  
 [felix invic]tus  
 [Aug]ustus  
 p p tribunici-  
 8 aē potestatis  
 viam res[ti]tu-  
 it m p  
 Amasenorum

line 11: (?) (civitas) **Amasenorum**

*Caput Viae* Amasia

*Date* (1) (?)

(2) AD 238, 09.v(?)–09.xii [Gordianus III] *Augustus*, cp. below, 044. Sapa

*Commentary* The text has been restored on the basis of 044. Sapa (see below). For the use of a genitive plural with or without *civitas*, see below, 044. Sapa and 046. Ertuğrul; the subject is discussed above, **Notes and Comments 3.7**.

#### 041. Abdalata, Tekke

*Province, Sub-Province + Admin. Code* Çorum 19-00-0

*Map* Çorum 76-ö

*Location* Location not given. Present whereabouts not established (DHF visits 14.vii.1977 and 16.vii.1987)

*Copy* Anderson 08 June, 1899. The stone has not been examined by DHF. Text here of CIL (Anderson)

*Publication* CIL 3. 14184<sup>45</sup> (text from Anderson)  
 CIL 3, (p.) 2328<sup>82</sup> (correction: Harsadin for Harsadan)  
 St. Pont. 1 (Anderson), 22 (no. 445) (notice)  
 Bittel 1955, 24 (notice)  
 RRMAM 2, 1. 319 (notice only)

*Description & Dimensions* Not given

*Text* [Imp Nerva Trai]-  
 [anus Caesar Aug]  
 [Germanicus pont]  
 4 [max trib pot p p cos]  
**II restituit per T**  
**Pomponium**  
**Bassum leg**  
 8 **Aug pro pr**  
 (vac)  
**mil·p·LVII**  
 vζ'

*Caput Viae* (Amasia)

*Date* (?)AD 98 Traianus *Augustus*, on the basis of the governor's name

*Commentary* The name of Pomponius Bassus, governor of Galatia and Cappadocia between AD 96-100, restricts the date of this milestone either to Nerva's principate (AD 96-98) or to the early years (AD 98-100) of Traianus; see above, **Notes and Comments 3.1**.

#### 042. Çeşmeören, form. Harzadin

<i>Province, Sub-Province + Admin. Code</i>	Çorum 19-00-0
<i>Map</i>	Çorum 76-p
<i>Location</i>	"In coemeterio" (CIL). Now in the Çorum Museum [Inv. no. 28.1.87]
<i>Copy</i>	Anderson 08 June, 1899; DHF 14 and 16.vii.1977, 27.vi.1986. DHF squeeze (drawing, Fig. 6.2.14 [p. 358]) and photo. (Pl. 7.1.20 [p. 379]) in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 19. Çorum 29, Çeşmeören Stone: (1) B/W Neg.: DHF R/77/11.06
<i>Publication</i>	CIL 3. 14184 <sup>44</sup> (text from Anderson) St. Pont. 1 (Anderson), 18 (no. 444) (notice) Bittel 1955, 24 (notice only) RRMAM 2, 1. 327 (notice only)
<i>Description</i>	A simple cylinder and plinth. Hard, pale limestone. Top flat; the shaft tapers slightly towards the top; simple, round plinth. Inscribed area smoothed; remainder of shaft roughly dressed. Letters: worn but clear; regular
<i>Dimensions</i>	Ht (total) 1.87; diam. (top) 0.44; (plinth) ht 0.18. Letters: c. 0.050

<i>Text</i>	<b>Imp·Nerva·[Caes]</b>
	2 <b>Aug·pont</b> [if max]
	<b>trib·potes</b> [t cos III]
	4 <b>p·p·resti</b> [tuit per]
	<b>Pompon</b> [ium]
	6 <b>Ba</b> [ss]u <b>m</b> [leg]
	<b>Aug·p</b> [ro pr]
	(c. 0.21 gap)
	8 <b>m/il/p·L</b>
	<b>v'</b>

line 8: MBPL (lapis)

<i>Caput Viae</i>	(Amasia)
<i>Date</i>	Nerva <i>Augustus</i> , (?) AD 97, 01.i-17.ix

#### 043. Hamdi

<i>Province, Sub-Province + Admin. Code</i>	Çorum 19-00-0
<i>Map</i>	Çorum 74-p
<i>Location</i>	In the lower village; lying in front of the house owned by Serbest Erol. Now in the Çorum Museum [Inv. no. 31.1.87]
<i>Copy</i>	DHF 16.xi.1985. DHF squeeze (photo. Pl. 7.2.1 [p. 409]) in BIA. No DHF photo. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Stone Photographs</i>	

<i>Publication</i>	Squeeze: 19. Çorum 92, Hamdi (photo. B/W Neg.: DHF M/85/10.11, 14) French 1985b, 143 (notice only) French 1986a, 80 no. 4 and Fig. 6 Christol and Lorient 1986, 20-21 (text of French 1986a) AE 1986. 652 (text of French from Christol and Lorient) French 1986b, 109 (notice only) RRMAM 2, 1. 341 (notice only)
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. The shaft tapers towards the top. Inscribed surface smoothed and recessed; remainder of shaft roughly worked.
<i>Dimensions</i>	Letters: worn but clear; U for V Ht 1.90. Letters: 0.040-55, (line 6) O and (line 9) V 0.030

<i>Text</i>	(vac) <b>B F</b> <b>Imp Caesar C I-</b> <b>ulius Verus</b> 4 <b>[[Maximinus pi]]us</b> <b>felix Aug tri-</b> <b>buniciae potest</b> <b>p p cos procos</b> 8 <b>per Claudianum</b> <b>v e praes provinc</b> (vac) <b>m p</b>
-------------	---

line 9: **v**(irum) **e**(minentissimum) **praes**(idem) **provinc**(iae Ponti)

<i>Caput Viae</i>	(Amasia)
<i>Date</i>	AD 235 or 236 Maximinus <i>Augustus</i>
<i>Commentary</i>	For the name of the <i>praeses</i> , Claudianus, see below, 144(B). Uyğur 2, where the name is written per·Cl·l[a]udianum. He was governor of Pontus; his contemporary in Cappadocia was Licinnius Serenianus, for whom see above, <b>Notes and Comments 3.4</b> . For the date AD 236, see Christol and Lorient (1986, 21). The datation is not clear. Maximinus became COS (I) in AD 236 but in this year he also took TRP II, according to Kienast (1996, 183). In the text here the tribunician year is not indicated. The name of the son, Maximus, raised to <i>Caesar</i> between 07.i and 16.v, AD 236, is absent.

#### 044. Sapa

<i>Province, Sub-Province + Admin. Code</i>	Çorum 19-00-0
<i>Map</i>	Çorum 74-p
<i>Location</i>	In the village; at the school. Brought from Ziyaret mevkii. Now in the Çorum Museum [Inv. no. 30.1.87]
<i>Copy</i>	DHF 22.vii.1983. DHF squeeze (drawing, Fig. 6.2.15 [p. 359]) and photos (Pl. 7.1.21 [p. 380]) in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 19. Çorum 130, Sapa Stone: (1) B/W Neg.: DHF M/83/02.01-02 (2) Col. Slide: DHF 236.03
<i>Publication</i>	French 1984, 123 and Fig. 3



	Christol and Lorient 1986, 23 (citation of DHF text)
	RRMAM 2, 1. 350 (notice only)
<i>Description</i>	A simple cylinder. Broken below. Hard, pale limestone. Top flat. Letters: neat and regular, sharp and clear; A with short diagonal-bar or with broken-bar
<i>Dimensions</i>	Ht (ex.) 1.14; diam. (top) 0.47. Letters: 0.035-40, (line 2) O 0.030

<i>Text</i>	<b>Imp·Caes</b>
	<b>M·Antonius</b>
	<b>Gordianus divi</b>
	<b>Gordiani nepos·</b>
5	<b>pius·felix·invictus</b>
	<b>Augustus·</b>
	<b>p p·tribuniciae·</b>
	<b>potestatis</b>
	<b>viam·restituit</b>
10	<b>m p·Amasen-</b>
	<b>orum</b>

lines 10-11: (?) (Civitas) **Amasenorum**, cp. the text of 046. Ertuğrul, below; the subject is discussed above, **Notes and Comments 3.6**.

<i>Caput Viae</i>	Amasia
<i>Date</i>	AD 238, 09(?)·v-(?) 09.xii Gordianus III <i>Augustus</i>
<i>Comment</i>	Christol and Lorient (1986, 23) note the absence of COS in line 6. Gordianus was designated COS in AD 238 “seit Mai (?)” before his COS I in AD 239; his TRP II began AD 238, 09.xii (Kienast 1996, 195).

#### 045. Seyfe

<i>Province, Sub-Province + Admin. Code</i>	Çorum 19-00-0
<i>Map</i>	Çorum 74-p
<i>Location</i>	In the village
<i>Copy</i>	DHF 20.viii.1984. DHF squeeze (drawing, Fig. 6.2.16 [p. 359]) in BIA. No DHF photo. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i>
	Squeeze: 19. Çorum 134, Seyfe
<i>Publication</i>	RRMAM 2, 1. 351 (notice only)
<i>Description</i>	A simple cylinder. Broken above. Hard, pale limestone. Base flat. Letters: somewhat worn but legible
<i>Dimensions</i>	Ht (ex.) 0.91; diam. (base) 0.47. Letters: (Latin) 0.045-50, (Greek) 0.070

<i>Text</i>	- - - - (vac) <b>mil p LXXVI</b> <b>ος'</b>
-------------	--

There is a horizontal line over both numerals

<i>Caput Viae</i>	(Amasia)
-------------------	----------

Date (?)

#### 046. Ertuğrul

*Province, Sub-Province + Admin. Code* Çorum 19-00-0  
*Map* Çorum 74-p  
*Location* In the village; at the house of Hüseyin Anıt  
*Copy* DHF 20.viii.1984. DHF squeeze (drawing, Fig. 6.2.17 [p. 359]) and photos (Pl. 7.1.22 [p. 380]) in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 19. Çorum 80, Ertuğrul  
 Stone: (1) B/W Neg.: DHF M/84/06.01  
 (2) Col. Slide: DHF 244.19-20  
*Publication* French 1985b, 143 (notice only)  
 RRMAM 2, 1. 333 (notice only)  
*Description* A simple cylinder. Broken above. Hard, pale limestone. Base flat. Letters: worn and indistinct, irregular in shape and size  
*Dimensions* Ht (ex.) 1.04; diam. (base) 0.46. Letters: 0.035-50, (line 5) O 0.060

*Text*

- - - -  
 - - - -  
 [po]testat[i]s]  
 2     restituit  
       m p·Amaseno-  
 4     rum mil p LXXV  
       (vac) oe'

line 1: (?) [po]testate or [po]testati[s] as above, cp. 044. Sapa  
 lines 5-6: **Amasenorum**, cp. 044. Sapa, above; the subject is discussed  
 above, **Notes and Comments 3.6**.

*Caput Viae* (Amasia)  
*Date* (?) Gordianus III, as 044. Sapa, above

#### 047. Deniz

*Province, Sub-Province + Admin. Code* Çorum 19-00-0  
*Map* Çorum 74-r  
*Location* In the village; at the house of İdris Özgüden  
*Copy* DHF 25.vii.1983. DHF squeeze (drawing, Fig. 6.2.18 [p. 360]) in BIA. No DHF photo. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 19. Çorum 73, Deniz  
*Publication* RRMAM 2, 1. 331 (notice only)  
*Description* A simple cylinder. Broken below. Hard, pale limestone. Top flat. Letters: worn and indistinct, irregular and poorly inscribed; (line 2) Δ for D, (line 3) H for E, S in shape of Γ  
*Dimensions* Ht (ex.) 0.68; diam. (below) 0.40. Letters: 0.030-40  
*Text* (1) (underneath text [2])

obliterated

(2) (on the top of text [1])

**In Ces(?) A' Valerio Δ[io]-**

(sic)

**cḥtiano pi f̣e[l invic]-**

(sic)

**to Au⟨g⟩ et In Ce[s M]**

(sic)

4 **Aur Maximian[o p fel]****in Aug et Fḷaỵio [Max]-****imiano et Gaḷ [Val Con]-****stantio ṇọḅ[b]**8 **Ç⟨a⟩ẹsṣ mi**line 1: **Ces** for **C⟨a⟩es**; **A'** for **A(urelius)**lines 1 and 3: **In** for **Im(p)**lines 5-7: the names of the *Caesares* have been mistakenly arranged, Flavius *Maximianus* and Gal. [Val.] *Constantius* for Flavius *Constantius* and Gal. Val. *Maximianus*.*Caput Viae*

[Amasia]

*Date*

(1) (?)

(2) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*

**A.10 NICOPOLIS - SEBASTIA (- Tavium)****048. Akşar**

<i>Province, Sub-Province + Admin. Code</i>	Sivas, Suşehri 58-08-1
<i>Map</i>	Şebinkarahisar 104-r
<i>Location</i>	“In a garden hedge” (Hogarth and Munro); “At a corner of a house” (Cumont). In the village, at a corner of the house owned by Temel Yıldırım
<i>Copy</i>	Taylor 1866; de Courtois 1866; Hogarth and Munro 1891; Cumont (Fr. and E.) 29 May, 1900; DHF 04.ix.1982. DHF squeeze in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 58. Sivas 01, Akşar
<i>Publication</i>	Taylor 1868, 302 and Fig. Le Bas and Waddington 1870, 2, 431 no. 1814d (text of de Courtois to Waddington) CIL 3. 6057 (text of de Courtois <i>apud</i> Le Bas and Waddington) Hogarth and Munro 1893, 727 CIL 3. 12154 (copy sent by Hogarth) CIL 3. 14184 <sup>12</sup> (reference to Taylor 1868) St. Pont. 2 (Cumont [Fr. and E.]), 314 (no. 473) and photo. (Fig.) (notice) Mitford 1972, 3, no. 201-1 (text of Cumont) RRMAM 2, 1. 929 (notice only; ll. 7-11 cited)
<i>Description</i>	A simple cylinder. Complete. Hard, red andesite. Shaft tapers slightly towards the top; round tenon under base. Surface: slightly worn Letters of inscription enhanced with red paint
<i>Dimensions</i>	Ht 1.72; diam. (base) 0.47; (tenon) ht 0.09; diam. 0.26. Letters: (line 1) 0.055, (line 4) E in AE 0.045, E in NE 0.042, O in POT 0.040, (line 10) I 0.065
<i>Text</i>	(1) (underneath text [2]) lost  (2) (on the top of text [1]) (vac) [I]mp <b>Caesari divi Traia-</b> <b>ni Parthici f divi Ner-</b> 4 <b>vae nepoti Traiano</b> <b>Hadriano Aug p m</b> <b>trib pot XIII cos III p p</b> <b>Civitas Nicopolita-</b> 8 <b>nor</b> (vac) (vac) <b>m p</b> (vac) (vac) <b>VII</b> (vac) ζ´
<i>Caput Viae</i>	Nicopolis
<i>Date</i>	AD 128, 10.xii/129, 09.xii Hadrianus <i>Augustus</i>
<i>Commentary</i>	For phrases similar to <i>Civitas Nicopolitanor(um)</i> , see above [p. 14], <b>Notes and</b>
<b>Comments 3.7.</b>	

**049(A)-(C). Aşağı Ekecik 1-3**

<i>Province, Sub-Province + Admin. Code</i>	Sivas, Yıldızeli 58-10-3
<i>Map</i>	Akdağmadeni 87-ü
<i>Location</i>	“Un cimetière qui occupe une éminence voisine, . . . .”
<i>Publication</i>	St. Pont. 2 (Cumont, Fr.and E.), 213 RRMAM 2, 1. 930-332 (notice only)
<i>Copy</i>	Cumont 05 May, 1900
<i>Description</i>	“ . . . . trois colonnes de calcaire, rongées par la pluie, et qui sont probablement d’anciennes bornes milliaires, . . . . ”
<i>Dimensions</i>	Not given
<i>Text</i>	No visible inscription

**A.11 NEOCAEASARIA - ZELA (- Tavium)****050(A). Boğazbaşı 1, form. Dönekçe**

*Province, Sub-Province + Admin. Code* Tokat, Niksar 60-04-0  
*Map* Reşadiye 93-n  
*Location* “A Deunéxé” (Cumont). Present whereabouts not established (DHF visit 08.vii.1977)  
*Copy* Cumont from Girard (date?). The stone has not been examined by DHF. Text here of Cumont  
*Publication* Cumont 1902, 333 no. 53  
 St. Pont. 1 (Anderson), 60 n.2 (no. 466) (notice)  
 RRMAM 2, 1. 937 (notice only)  
*Description & Dimensions* Not given

*Text*

	<b>Imp·Caes·M·Ante</b>	(sic)
	<b>Gord·filius divi</b>	
	<b>Gordiani nepos</b>	
4	<b>pius·felix·invi-</b>	
	<b>ctus·Aug [p] p</b>	
	<b>tribunic pot</b>	
	<b>viam restituit</b>	
8	(vac) <b>mil</b>	
	(vac)	

line 2: **Gord(iani)·**

*Caput Viae* (Neocaesaria)  
*Date* AD 238, 09.v(?)–09.xii Gordianus III *Augustus*; for the date, cp. 044. Sapa

**050(B). Boğazbaşı 2, form. Dönekçe**

*Province, Sub-Province + Admin. Code and Map* As 050(A)  
*Location* “ . . . , maintenant dans le jardin d’Asur Karaaslan appuyé contre le mur de sa maison, y fut transporté par son propriétaire il y a une quarantaine d’années depuis le lieu-dit Göcek, qui se trouve ca. 1 km au Sud-Ouest du village; . . . ” (Christol et al. 1993, 159). The stone is now built into the SE corner of the house (Pl. 7.1.23 [p. 380]) (owned by the son, Muharrem Karaaslan); brought, according to the son, from a locality called Tolas or Tolis mevkii or Dere mevkii, c. 2 km S of the village. The Roman road passes below (“in front of”) Tolas mevkii. The stone was brought to the village c. 1944 and built into the house c. 1974.  
*Copy* Mehmet Özsait (?date); DHF 20.x.1994. DHF squeeze and photos (Pl. 7.1.23 [p. 380]) in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Photograph*  
 Squeeze: 60. Tokat 11, Boğazbaşı 2  
 Stone: (1) B/W Neg.: DHF M/94/18.06  
 (2) Col. Slide: DHF 403.08  
*Publication* Christol, Drew Bear and Özsait 1993, 159 and Figs 1-3  
 AE 1993. 1563 (notice of Christol et al. 1993)  
 French 1995, 1 (notice only)

<i>Description</i>	A simple cylinder. Complete. Hard, dark grey basalt. The top is flat; the shaft simple and straight. Surface: smoothed. The inscription begins c. 0.06 from the top.
<i>Dimensions</i>	Surface and letters: well preserved; A, E, G, U “h. 1.90; diam. 0.50 h.l. 0.04” (Christol et al.); ht 1.93; diam. 0.37. Letters: (line 1) I of IMP 0.062, E of CAES 0.056, (line 10) T of ANT 0.042, (line 17) I of MIL 0.05
<i>Text</i>	<p><b>Imp·Caesar</b>  <b>L Septimius</b>  <b>Severus Pius</b>  4 <b>Pertinax Aug</b>  <b>Arab·Adiab Parth</b>  <b>max·pontif max</b>  <b>trib pot VI imp XI</b>  8 <b>cos II p p procos</b>  <b>et Imp Caes M' Aur</b>  <b>Antoninus</b>  <b>Aug et Septimi]</b>-  12 <b>us Geta] Caesar</b>  <b>res{s}tituerunt</b>  <b>per C·Iul·Flac-</b>  <b>cum Aelianum</b>  16 <b>leg pr pr</b>  (vac) <b>mil·p·</b>  (vac) <b>VIII</b>  (vac) <b>η'</b></p> <p>lines 1-4: “Les V ont aux ll. 1-4 la forme de U” (Christol et al.)  lines 11-12: <b>Aug [et &lt;L&gt; Septimi]</b> (DHF), <b>Aug [[et P Sept ]]   [Geta]</b>  etc. (Christol et al.)</p>
<i>Caput Viae</i>	(Neocaesaria)
<i>Date</i>	AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with (L.) Septimius Geta (names erased) <i>Caesar</i>

**051. Yağmurlu, form. Ohtap**

<i>Province, Sub-Province + Admin. Code</i>	Tokat 60-00-2
<i>Map</i>	Reşadiye 92-n
<i>Location</i>	In the village; lying in the street, at the foot of a garden wall (house owner, Hüseyin Yılmaz)
<i>Copy</i>	DHF 22.vii.1986. DHF squeeze (drawing, Fig. 6.2.19 [p. 360]) and photos (Pl. 7.1.24 [p. 381]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 60. Tokat 16, Yağmurlu Stone: (1) B/W Neg.: DHF M/86/22.03-04 (2) Col. Slide: DHF 262.28-29
<i>Publication</i>	French 1987, 193 (notice only)
<i>Description</i>	A simple cylinder. Broken below and on right. Hard, white limestone. Top flat.

*Dimensions* Re-used as a *yuvak* or *loğ taş* (roof-roller). Letters: worn  
Ht (ex.) 0.63; diam. 0.46. Letters: (line 5) O 0.05

*Text*

	(vac) <b>Imp</b>
2	<b>Caesar</b> [divi Tra]-
	<b>iani Pa</b> [rthici]
4	<b>fil·diy</b> [i Nervae]
	<b>nepos</b> [Traianus]
6	<b>Had</b> [rianus]
	- - - -

*Caput Viae* [Neocaesaria ?]  
*Date* Hadrianus, (?) year

### 052(A). Gözova 1, form. Omala

*Province, Sub-Province + Admin. Code* Tokat 60-00-2  
*Map* Reşadiye 91-o  
*Location* Not given. Present whereabouts not established (DHF visit 22.vii.1986)  
*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of CIL (Hogarth and Munro)  
*Publication* Hogarth and Munro 1893, 733 (i)  
CIL 3. 12155 (copy sent by Hogarth)  
St. Pont. 1 (Anderson), 60 (no. 464) (notice)  
RRMAM 2, 1. 942 (notice only)  
*Description* “Fragment of Roman milestone” (Hogarth and Munro)  
*Dimensions* Not given

*Text*

	[Imp Caes]
	[C Iul V] <b>er</b> [us]
	[M] <b>axim</b> [inus]
4	[p f] <b>Aug·tr-</b>
	[ibu] <b>niciae</b>
	[pot] <b>estati</b> [s]
	[vi] <b>am res-</b>
8	[tit] <b>ui</b> [t]
	- - - -

line 2: **IM** (CIL)  
line 4: **AVG·PR** (CIL)  
line 7: **AMPES** (CIL)

*Caput Viae* (Comana Pontica)  
*Date* Maximinus *Augustus*, (?)AD 235, Feb./March-09.xii (TRP II 239, 10.xii)

### 052(B). Gözova 2, form. Omala

*Province, Sub-Province + Admin. Code and Map* As 052(A)  
*Location* “ . . . . in the stable of Ibrahim Efendi” (Hogarth and Munro). Present



	whereabouts not established (DHF visit 22.vii.1977)
<i>Copy</i>	Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of CIL (Hogarth and Munro)
<i>Publication</i>	Hogarth and Munro 1893, 733 (ii) (1 and 2) CIL 3. 12156 (copy sent by Hogarth) St. Pont. 1 (Anderson), 60 (no. 465) (notice) RRMAM 2, 1. 943 (notice only)
<i>Description</i>	“On a stone, much broken, . . . (Hogarth and Munro)
<i>Dimensions</i>	Not given
<i>Text</i>	<p>(1) [Impp Caess] 2 [C Au]r Val[erio] <b>Diocletiano</b> - - - -</p> <p>(2) [DD] nñ [Im]p [C]aes Fl̄ V̄a(l) Co[n]- s[ta]n[ti]n[o v]ictori ac [t]riumf semper Aug 4 et Fl Cl Constanti(n)o [et Fl] Iul Constantio [et Fl Iul Constanti] [nobbb Caesss] 8 [ - ]</p>

lines 7-8: (?) perhaps restore with [[Fl Delmatio]] | [nobbbb Caessss], cp. 009. Hatipli

(3) (on the back)

**CH . . . . HUATI**  
**Λ . . . . PAPE**

<i>Caput Viae</i>	(Comana Pontica)
<i>Date</i>	<p>(1) (?)AD 293-305 Diocletianus and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i></p> <p>(2) AD 333, 25.xii-335, 18.ix (?), Constantinus <i>victor Augustus</i> with Constantinus, Constantius and [Constans <i>Caesares</i>]</p> <p>(3) (?)</p>
<i>Commentary</i>	<p>(Text 1) For an intact tetrarchic text, see above, 037(B). Çorum 2.</p> <p>(Text 3) For a replicate text of Constantinus and sons, see above, 10. Niksar</p>

### 053. Kılıçlı, form. Gömenek

<i>Province, Sub-Province + Admin. Code</i>	Tokat 60-00-0
<i>Map</i>	Reşadiye 91-ö
<i>Location</i>	“Dans un cimetière sur le bord de la grande-route au sortir de Comane” (Cumont). Present whereabouts not established (DHF visit 08.vii.1977)
<i>Copy</i>	Cumont from Girard (?date). The stone has not been examined by DHF. Text here of Cumont (facsimile of the printed copy, Fig. 6.1.8 [p. 327])
<i>Publication</i>	<p>Cumont 1902, 312 no. 1</p> <p>RRMAM 2, 1. 948 (notice only)</p> <p>Christol, Drew Bear and Özsait 1993, 161 (text of Cumont and comment)</p>

AE 1993. 1564 (notice of Christol et al. 1993)

*Description & Dimensions* Not given*Text*

[I]mp Caesar [L Septimi]-  
 us Severus P̄iū[s Perti]-  
 nax Aug Aṛab̄ [Adiab]  
 4 Parthi max̄ [p]on̄[tifex] (sic)  
 max trib pote[st VI imp]  
 XI cos II p p pro[cos]  
 [et] Imp Caesar M[arcus]  
 8 (vac) Aurel Aṇ[toninus Aug]  
 [et L S]ēpt̄[imius] [[Geta]]  
 10 [Caesar restitueru]-  
 [nt per - - ]  
 - - - -

*Caput Viae* [Comana Pontica]

*Date* AD 197/198, 10.xii-09.xii (?), L. Septimius Severus and M. Aurelius Antoninus  
 (Caracalla) *Augusti* [with L. Septimius Geta (names erased?) *Caesar*];  
 AD 203 (Cumont, RRMAM 2, 1. 948)

*Commentary* For an intact text of Septimius Severus and sons, see above, 050(B). Boğazbaşı 2**054(A). Tokat 1***Province, Sub-Province + Admin. Code* Tokat 60-00-0*Map* Amasya 90-p

*Location* “Dans les ruines de la citadelle” (Le Bas and Waddington); “Prope arcem inter  
 alia rudera delata eo Comanis” (CIL). Present whereabouts not established (DHF  
 visit 06.vii.1977)

*Copy* Boré 1837. The stone has not been examined by DHF. Text here of CIL (Boré)  
 (facsimile of Boré’s text printed by Le Bas and Waddington, Fig. 6.1.9  
 [p. 327])

*Publication* Boré 1840, 1, 336, 357  
 Le Bas and Waddington 1870, 2, 430 no. 1814a (text of Boré)  
 CIL 3. 307 (text of Boré)  
 RRMAM 2, 1. 952 (notice only)

*Description & Dimensions* Not given*Text*

- - - -  
 [Fl Valerio]  
 [Const]ant̄[io]  
 4 [et] Gal̄·Val  
 Maximiano  
 nobillis·Caess  
 (vac) mil·p  
 8 Aurel [P]riscianus  
 v p pr pr̄[ovinc Po]nti  
 d n m [q eo]rum̄

line 3: “Boré donne deux copies de cette inscription; la seconde (p. 357) est la meilleure, mais la première donne la véritable leçon de la première ligne **ANI** au lieu de **ANO**” (Le Bas and Waddington)

*Caput Viae* (Comana Pontica)  
*Date* AD 293, 21.v(?)–305. 01.v [Diocletianus and Maximianus *Augusti* with] Constantius and Galerius *Caesares*  
*Commentary* For an intact text of the Tetrarchy, on this road, see below, 056(D). Zile 4.

#### 054(B). Tokat 2

*Province, Sub-Province + Admin. Code and Map* As 054(A)  
*Location* “Found in the great square at the lower end of the town” (Hogarth and Munro). Present whereabouts not established (DHF visit 06.vii.1977)  
*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of CIL (Hogarth and Munro)  
*Publication* Hogarth and Munro 1893, 735  
 CIL 3. 12157 (copy, with restorations, sent by Hogarth)  
 RRMAM 2, 1. 953 (notice only)  
*Description* “Almost illegible fragment” (Hogarth and Munro)  
*Dimensions* Not given

*Text*

	[Imp Caes C Aur Val]
	[Diocletiano et]
	<b>Imp</b> [Caes M Aur Val]
4	<b>Ma</b> xim[ia]n[o] p[p ff]
	<b>inv</b> [i]c [A]ugg[et] <b>Flav</b>
	[Val] <b>Constanti</b> [o]
	(vac) <b>et Gal</b> [e]r Va[l]
8	[Maxim]ia[no nobb Caess]
	- - - -

*Caput Viae* [?]  
*Date* AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*  
*Commentary* For an intact text of the Tetrarchy, on this road, see below, 056(D). Zile 4.

#### 054(C)-(E). Tokat 3-5

*Province, Sub-Province + Admin. Code and Map* As 054(A)  
*Location* Not given. Present whereabouts not established (DHF visit 06.vii.1977)  
*Copy* Anderson, Munro and Welch (?) 29 July, 1899  
*Publication* St. Pont. 1 (Anderson), 67 (nos 460–462)  
 RRMAM 2, 1. 954–956  
*Description & Dimensions* Not given

*Text* No visible inscription

#### 054(F). Tokat 6

*Province, Sub-Province + Admin. Code and Map* As 054(A)  
*Location* “Nous avons trouvé à Tokat, dans la cour d’une maison arménienne” (Cumont 1905b). Now in the Sivas Museum [Inv. no. 158]  
*Copy* Cumont 1900; DHF 28.viii.1982. DHF squeeze (drawing, Fig. 6.2.20 [p. 360]) in BIA. No DHF photo. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 60. Tokat 13, Tokat 6  
*Publication* Cumont 1905b, 233 n.1  
 Mitford 1974, 173 and n.93 (notice)  
 RRMAM 2, 1. 957 (notice only)  
*Description* A simple cylinder. Hard, white limestone. The shaft tapers slightly towards the top. Cut to form a *yalak* (water-trough)  
 Letters: very worn in places  
*Dimensions* Ht (ex.) 1.27; diam. (top) 0.45. Letters: (line 4) T of VIT 0.070, (line 6) P of RPR 0.055

*Text*

	[Imp Nerva Caes]
	[Aug pont max]
	[trib potest cos II]
4	<b>p·p·restituit</b> ·[per T]
	<b>Pomponium Ba</b> [ssum]
	<b>Aug·pr pr</b>
	(vac) <b>mil p</b>
8	(v) <b>II</b> (v) <b>β'</b>

*Caput Viae* (Comana Pontica)  
*Date* Either Nerva or Traianus, on the basis of the governor’s name; here restored as Nerva; see above [p. 10], **Notes and Comments 3.1**.  
*Commentary* For the date of this text, see the comment on 041. Abdalata, Tekke

### 054(G). Tokat Museum 1

*Province, Sub-Province + Admin. Code* Tokat 60-00-0  
*Provenance* Not known. Now in the Tokat Museum [Inv. no. 6752]  
*Copy* DHF 06.x.1975; Le Guen-Pollet July 1988. DHF squeeze (drawing, Fig. 6.2.21 [p. 360]) in BIA. No DHF photo. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 60. Tokat 14, Tokat Museum 1  
*Publication* French 1985a, 150 and Fig. 5  
 RRMAM 2, 1. 958 (notice only)  
 Le Guen-Pollet 1989, 82 no. 32  
 AE 1990. 895 (text of French from Le Guen-Pollet)  
 Le Guen-Pollet 1991, 102 (correction to Le Guen-Pollet 1989)  
*Description* A simple cylinder. Broken above, below and behind. Hard, grey limestone.  
 Letters: worn in places, otherwise sharp  
*Dimensions* Ht (ex.) 0.51; diam. (top) 0.46. Letters: 0.045-50

*Text*

	- - - -
2	[- - - - trib]

4      **pot·XIII·imp·XIII·**  
       **p·p·miliaria**  
       **a·Sebastopoli**  
 6      **restituit**  
       **mil·p [ - ]**

*Caput Viae*      Sebastopolis  
*Date*            [Severus Alexander] AD 233, 10.xii-234, 09.xii  
*Commentary*    For the date of this milestone, see the comments (French 1985b, 150-152) which are based on the complete example recorded at Adana (RRMAM 2, 1. 991) and on the arguments of Lorient (1981, 225-229).

### 054(H). Tokat Museum 2

*Province, Sub-Province + Admin. Code*      Tokat 60-00-0  
*Provenance*      Not known  
*Copy*            DHF 06.x.1975. DHF squeeze (drawing, Fig. 6.2.22 [p. 360]) in BIA. No DHF photo. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
                          Squeeze: 60. Tokat 15, Tokat Museum 2  
*Publication*    French 1976, 53 (notice only)  
                          French 1981, 155  
                          AE 1986. 657 (text of French 1981)  
                          RRMAM 2, 1. 959 (notice only)  
*Description*    A simple cylinder. Broken above and below. Hard, grey limestone. Shaft tapers slightly towards top; surface smoothly dressed.  
                          Letters: worn  
*Dimensions*    Ht (ex.) 0.475; diam. (base) 0.36, (top) 0.33. Letters: (line 4) A 0.075, C 0.057

*Text*                                - - - -  
    [ - - - - pont]  
 2      **max·trib·pot·III·p·p·**  
    **proc·a Comana·**  
 4      **mil·p·II·curan-**  
    **te Ael·Quintiano**  
 6      **v·p·pr p P**

line 6: v(iro)·p(erfectissimo)·pr(aeside)·p(rovinciae) P(onti)

*Caput Viae*      Comana  
*Date*            AD 279 Summer-280 Summer Probus *Augustus*  
*Commentary*    For the date of this milestone, see the comment (French 1981, 155) which is based on the complete example (037[C]) now in the Çorum Museum.

### 055(A). Turhal 1

*Province, Sub-Province + Admin. Code*      Tokat, Turhal 60-06-0  
*Map*            Amasya 86-ö  
*Location*      Not given. Present whereabouts not established (DHF visit 28.vii.1986)  
*Copy*            Anderson, Munro and Welch (?) 31 July, 1899

*Publication* St. Pont. 1 (Anderson), 67

RRMAM 2, 1. 960

*Description & Dimensions* Not given

*Text* No visible inscription

## 055(B). Turhal 2

*Province, Sub-Province + Admin. Code and Map* As 055(A)

*Location* “By the side of a street” (St. Pont.). Present whereabouts not established (DHF visit 28.vii.1986)

*Copy* Anderson, Munro and Welch (?) 31 July, 1899. The stone has not been examined by DHF. Text here of CIL (Anderson)

*Publication* CIL 3. 14184<sup>18</sup> (text from Anderson)  
St. Pont. 1 (Anderson), 67, 72 (no. 459) (notice)  
RRMAM 2, 1. 961 (notice only)

*Description & Dimensions* Not given

*Text*

**CAR**  
**AVG**  
**CAR**  
**CE[.]S**  
**NL**  
**M**

(possible restoration)

[Imp Caes M]  
2 [Aur] **Car**[o p f]  
[inv] **Aug** [et M]  
4 [Aur] **Car**[ino]  
[nob] **Ç**⟨a⟩**e**[s C]↓  
6 [Lo]**ng**[inus v p p P]  
**m** [ - ]

*Caput Viae* [?]

*Date* (?) AD 282 Carus *Augustus* with Carinus *Caesar*

## 056(A). Zile 1

*Province, Sub-Province + Admin. Code* Tokat, Zile 60-07-0

*Map* Amasya 84-r

*Location* “Dans un cimetière turc à une demi-heure au sud-est de Zileh” (Cumont). Now in the kale at Zile

*Copy* Cumont (Fr. and E.) April, 1900; Wilson Summer 1958; DHF 07.x.1975. DHF squeeze (drawing, Fig. 6.2.23 [p. 361]) in BIA. No DHF photo. Text here from DHF squeeze

*BIA Collections: Squeeze and Stone Photographs*  
Squeeze: 60. Tokat 18, Zile 1

*Publication* Cumont 1905a, 347 (facsimile, Fig. 6.1.10 [p. 328])  
AE 1905. 132 (text of Cumont)

	St. Pont. 2 (Cumont [Fr. and E.]), 194 (no. 468), and 197 (notice)
	Wilson 1960, 133 no. 1 (text and facsimile) (facsimile, Fig. 6.1.11 [p. 328])
	AE 1961. 25 (text of Wilson)
	French 1981, 167 (comment on the text)
	Christol and Lorient 1986, 16 and n. 22 (comment on ll. 10-11)
	RRMAM 2, 1. 963 (notice only)
	Le Guen-Pollet 1989, 80 no. 31 and n.45 (text of Cumont)
	Dodgeon and Lieu 1991, 23 no. 1.3.2 (Cumont's text and transl. of Wilson's text)
	Le Guen-Pollet 1991, 102 (correction to Le Guen-Pollet 1989)
<i>Description</i>	A simple cylinder. (?)Complete. Hard, grey limestone. Letters: spindly, very worn especially on the right-hand side
<i>Dimensions</i>	Ht (vis.) 1.30; diam. (top) 0.42. Letters: 0.065-80 but Q 0.050
<i>Text</i>	<p>(vac) <b>Imp</b>  (vac)  (vac) <b>Çaesar</b>  <b>M Aur [Se]verus</b>  4 <b>[[Alexander]]</b>  <b>p̄ius felix [in]-</b>  <b>victus Aug</b>  <b>pont·max trib</b>  8 <b>potestas [c]os</b>  <b>p p proco[s]</b>  <b>per·Q Iul Procule-</b>  <b>ianum·leg pr</b>  12 (vac) <b>pr mil I</b>  (vac) <b>Zelit</b></p>

line 13: **Zelit** for (Civitas) **Zelit(anorum)**, cp. Zile 2

There are perhaps traces of an earlier inscription underlying the text here.

<i>Caput Viae</i>	Zela
<i>Date</i>	AD 222, 01.i-09.xii Severus Alexander <i>Augustus</i>
<i>Commentary</i>	Wilson (1960, 133) proposed that the text of this milestone, “the Zile stone”, was a replicate of the text published by Cumont (1905a, 347), “the Ağbaba stone”. I believe that the two stones are one and the same. The texts are as follows:

(Cumont) (facsimile, Fig. 6.1.10 [p. 328])      (Wilson) (facsimile, Fig. 6.1.11 [p. 328])

	[Imp] Caesar	[Imp] Caesar
	M [[A[u]r [Se]v[erus]]]	M [[Aur [S]everu[s]]]
	[[Alexander]]	[[Alexa]n[der]]
	p̄ius felix in-	p̄ius felix in-
5	victus Augu	victus Aug
	pont max trib	pont max trib
	potesta X cos	potestas [c]os
	III procos	p p proco[s]
	per Q Iul Procule-	per Q Iul Procule-
10	ianum leg pr	ianum leg pr

[pr] pa [m]il  
Z

pr mil I  
Zelit

My copy agrees, more-or-less, with that of Wilson. I accepted (French 1981, 167) Wilson's suggestion that Cumont's POTESTA X in his line 7 was a mis-interpretation, X for S, and that the beginning of Cumont's line 8 should read PP rather than III. Cumont's example of his lines 11-12 can be readily emended, as Wilson saw (1960, 134): (space) PA [M]IL I Z, i.e. PR (R for A), [MI]L I ([MI]L I for [M]IL and ZELIT (for Z). In his line 5 Cumont reads AUGV; the final V is no more than a mis-interpretation of the flourish or tail on the bar of G.

For the interpretation, Zelit - Zelit(anorum), see the examples of a genitive plural - Amasenorum - at 040. Saray, 044. Sapa and 046. Ertuğrul; for a discussion of this subject, see above [p. 14], **Notes and Comments 3.7**.

### 056(B). Zile 2

*Province, Sub-Province + Admin. Code and Map* As 056(A)

*Location* Not given. Now in the kale at Zile

*Copy* Grégoire 1907; DHF 07.x.1975, 06.vii.1977. DHF squeeze (drawing, Fig. 6.2.24 [p. 362]) and photos (Pl. 7.1.25 [p. 381]) in BIA. Texts here from DHF squeeze

*BIA Collections:* *Squeeze and Stone Photographs*

Squeeze: 60. Tokat 19, Zile 2

Stone: (1) B/W Neg.: DHF R/77/09.10-11

*Publication* Grégoire 1909, 27

French 1981, 157 and 162 (notice only)

French 1985a, 148 and Fig. 3

Yavi 1986, 163 and Fig. (photo. of text)

RRMAM 2, 1. 964 (notice only)

*Description* A simple cylinder. Complete. Hard, pale limestone. Letters: worn and faint (text 1), worn (text 2); (text 2) broken-bar A

*Dimensions* Ht 1.64; diam. (base) 0.52. Letters: (text 1) (line 2) SE 0.070, (text 2) E of LET 0.060 but generally irregular, c. 0.040-50

*Text* (1) (underneath, and on the l. of, text [2]) (line 1 of text 1- line 3 of text 2)

**Imp** [Caesar] **L**

**Septimius** Se[ve]-

**rus** [Pius Perti]-

4 [nax Aug] **et**

**Imp** [Caes M Aur]

**Antoninus** **Aug**[u]s[tus]

**et** [[L Septimius Geta]]

8 [Caesar restituer]-

**unt** [p]er **Gai-**

**um** **Iu**[l] **Flacc**[um]

**Aelianum** **leg**

12 **Aug** **pro p**[r]

**Civ** **Zel** **M**[..]

**m** (vac) **II**(?)



line 13: **Civ**(itas) **Zel**(itanorum)  
 line 14: **m** for **m**(ilia)

(2) (on the top, and on the r., of text [1])

[Imp] **Ç**aes  
**Ç**aio Aur' Val  
**D**[i]ocletiano  
 4 **pi**[o] **fel**-**inviç** Aug  
**et** Imp **Caes**  
**M**arc Aur [V]al  
**M**aximiano  
 8 **pi**o **fel** **inviç** [A]ug  
**et** Flāv Val'  
**Ç**onstantio  
**et** Gālēr Val  
 12 **M**aximiano  
 [nob]ilissimis  
**Caesaribus**  
**Civ**·**Zel**·<sup>(vac)</sup> **m**[il p - ]  
 16 [Aur] **Priç**cianus  
 [v p] **praes** prov Pont  
 [d n] **m q** eorum

line 1: **IMP** retained from text (1)

line 15: **CIV**·**ZEL** retained from text (1)

line 17: ligature **NT**

<i>Caput Viae</i>	Zela
<i>Date</i>	(1) AD 197/198(?) L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i> (2) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i>
<i>Commentary</i>	(Text 1) For an intact text of Septimius Severus, see above, 050(B), Boğazbaşı 2

### 056(C). Zile 3

<i>Province, Sub-Province + Admin. Code and Map</i>	As 056(A)
<i>Provenance</i>	Now in the kale at Zile
<i>Copy</i>	DHF 07.x.1975. DHF squeeze (drawing, Fig. 6.2.26 [p. 362]) and photos. (Pl. 7.1.26 [p. 382]) in BIA. Texts here from DHF squeeze
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 60. Tokat 20, Zile 3 Stone: (1) B/W Neg.: DHF R/77/09.12 (2) Col. Slide: DHF 260.30-31
<i>Publication</i>	French 1981, 157 and 162 (notice only) RRMAM 2, 1. 965 (notice only)
<i>Description</i>	A simple cylinder. Complete. Grey limestone. Letters: (text 1) damaged and worn, (text 2) worn but clear
<i>Dimensions</i>	Ht (vis.) 1.57; diam. (top) 0.42. Letters: (text 1) (line 6) 0.065-70, (text 2)

	irregular size but well cut shape, (line 3) DI 0.075, (line 14) 0.035-55
<i>Text</i>	<p>(1) (underneath text [2])</p> <p style="text-align: center;">- - - <b>A</b>  - - <b>N·I</b>  - - - -  4    - - - <b>I</b>  <b>Au</b>[gustus pon]t<b>if</b>  <b>m</b>[ - - ] <b>imp XIII</b>  <b>p p</b> [ - - ] <b>I</b>  8    <b>mil·p·I</b></p> <p>line 6: (?) <b>m</b>[ax tr pot XIII] <b>imp XIII</b>  line 7: (?) <b>p p</b> [milia a Zel]i[s] or <b>p p</b> [procos a Zel]i[s]</p> <p>(2) (on the top of text [1])</p> <p style="text-align: center;"><b>Imper Caes</b>  <b>Caio Aur Val</b>  <b>Diocletiano</b>  4    <b>pio fel inv</b>(i)c <b>Aug</b>  <b>et Imper Caes</b>  <b>Mar Aur Val</b>  <b>Maximiano</b>  8    <b>pio fel invic Aug</b>  <b>et Flav Val</b>  <b>Constantio</b>  <b>et Gal Val</b>  12    <b>Maximiano</b>  <b>nobilissimis</b>  <b>Caesaribus</b>  <b>Zelit mil·p·I</b>  16    <b>Aur P<sup>r</sup>is</b>[cianus]  <b>v p praes p</b>[r Pont]  <b>d n m q eq</b>[rum]</p> <p>line 13: <b>MIL·P·I</b> retained from text (1)  line 15: Zelit (and also Zile 1 and 4) for (Civitas) Zelit(anorum), as Zile 2 Civ·Zel(itanorum); cp. 044. Sapa and 046. Ertuğrul (Civitas) Amasenorum; see also the discussion [p. 14], <b>Notes and Comments 3.7</b>.  lines 16-18: for undamaged version, see below, 056(D). Zile 4</p>
<i>Caput Viae</i>	Zela
<i>Date</i>	<p>(1) (?)Hadrianus AD 128/129 or Severus Alexander AD 234</p> <p>(2) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i></p>
<i>Commentary</i>	This milestone, numbered I (as is 054[D]). Zile 4 on the Zela-Tavium road) was evidently erected on one of the other three roads leading out of Zela: Zela-Amasia, Zela-Comana or Zela-Caesaria.
<b>056(D). Zile 4</b>	

Province, Sub-Province + Admin. Code and Map As 056(A)

**Location** Now in Zile, in the garden in front of the *Belediye* (Municipality). In 1992 brought from the Arı Yapı Kooperatifi on the outskirts of Zile by Şükrü Serimer, then *Belediye Başkanı* (Municipal Chairman, Mayor); probably *in situ* as found (deeply buried), c. 1.5 km E of the main square and clock-tower

**Copy** DHF 19.x.1994. DHF squeeze and photos (Pl. 7.1.27 [p. 382]) in BIA. Texts here based on DHF squeeze

**BIA Collections:** *Squeeze and Photograph*

Squeeze: 60. Tokat 21, Zile 4

Stone: (1) B/W Neg.: DHF M/94/18.13

(2) Col. Slide: DHF 403.11

**Publication** French 1995, 1 (notice only)

**Description** A simple cylinder. Complete. Pink and white limestone. The top is flat; the shaft tapers slightly towards the top; the base is now enclosed in cement. The surface was roughly smoothed with a claw-tooth chisel. Inscription (1) starts c. 0.05 from the top. Inscription (2) starts c. 0.14 from the top.

Surface and letters are very worn.

**Dimensions** Ht (vis.) 1.61; diam. (top) 0.32. Letters: (text 1) (line 2) C 0.055, (line 4) 0.070, (line 4) P 0.050, (text 2) 0.035-40

**Text** (1) (on the front of the stone)

**Imper Caes  
Caio Aur Val  
Diocletiano**  
4 **pio fel inv<i>c Aug  
et Imper Caes  
Mar Aur Val  
Maximiano**  
8 **pio fel' invic A<u>g'  
et Flav Valer  
Constantio  
et Galer Val**  
12 **Maximiano  
nobilissimis  
Caesaribus  
Zelit M I**  
16 **Aur Priscianus  
v p praes Ponti  
d n m q eorum  
α'**

line 15: **ZELIT**, an abbreviation for (Civitas) **Zelit**(anorum) as on Zile 2

(2) (on the back of the stone)

**B (vac) F  
DD (vac) nn  
Imp Caes Flav Val**  
4 **Constantino  
p f invic Aug et Val**

**Liciniano Licinio**  
 [p] f invic Aug et  
 8 [ . . . . . ]L...AL  
 - - - -

lines 8 seqq.: (?) [Flav Crispo] e[t V]al | [Liciniano Licinio etc]

*Caput Viae* Zela  
*Date* (1) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with  
 Constantius and Galerius *Caesares*  
 (2) AD 317, 01.iii–324, 19.ix Constantinus and Licinius *Augusti* with (?) Crispus,  
 Licinius and Constantinus *Caesares*  
*Commentary* Text (1) is nearly identical to that of 56(B) and (C). Zile 2 and 3, above.

### 057. Kurupınar

*Province, Sub-Province + Admin. Code* Tokat, Zile 60-07-0  
*Map* Amasya 84-r  
*Location* “In the village cemetery” (St. Pont.). Now built into a tomb (Pl. 7.1.28 [p. 382]),  
 on the opposite side of the road, across from the cemetery  
*Copy* Anderson 01 July, 1899; DHF 07.vii.1977. DHF squeeze and photos (Pl. 7.1.28  
 [p. 382]) in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 60. Tokat 07, Kurupınar  
 Stone: (1) B/W Neg.: DHF R/77/09.08-09 and 10.01  
*Publication* CIL 3. 14184<sup>17</sup> (text from Anderson)  
 CIL 3: (p.) 2328<sup>82</sup> (correction to text)  
 St. Pont. 1 (Anderson), 44 (no. 467) (notice)  
 RRMAM 2, 1. 949 (notice only)  
*Description* A simple cylinder. (?) Broken above. Hard, grey limestone. Surface: rough  
 Letters: worn  
*Dimensions* Ht (ex.) 1.13; diam. (top) 0.38. Letters, uneven and irregular: (text 2) 0.035–55  
*Text* (1) (underneath text [2])  
 traces

(2) (on the top of text [1])

**Imp C<a>es**  
**Fl Constantino**  
**p f m(aximo) victori**  
 4 **semper Aug**  
**et Fl Cl Constantino**  
**et Fl Iul Constantio**  
**et Fl Iul Constante** (sic)  
 8 **nobbss** (vac) <Caess> (sic)  
**Fl Leontius v p**  
**praes pr Helenop**  
**d n m q eorum**

line 8: **nob**(ili)**ss**(imis)

line 10: **HEC/NOP** (CIL 3, 14184<sup>17</sup>); **HEL/NOP** (CIL 3, (p.) 2328<sup>82</sup>)

*Caput Viae*  
*Date*

[Zela]

(1) (?)

(2) AD 333, 25.xii-335, 18.ix Constantinus *maximus victor Augustus* with three sons, Constantinus, Constantius and Constans *Caesares*

**A.12 SEBASTIA - SEBASTOPOLIS (- Tavium)****058. Kargın, Murathanı**

<i>Province, Sub-Province + Admin. Code</i>	Tokat 60-00-1
<i>Map</i>	Amasya 90-ş
<i>Location</i>	At the han; built into the door-way
<i>Copy</i>	Olshausen and Biller (?date). Not seen by DHF 30.xi.1984
<i>Publication</i>	Olshausen and Biller 1984, 228 and Fig. 40 RRMAM 2, 1. 946
<i>Description</i>	“Das Teilstück eines unbeschrifteten Meilensteins ... An der Vorderseite sind verschiedene Kreuz symbole eingeritzt” (Olshausen and Biller)
<i>Dimensions</i>	Ht 1.40; diam. 0.38
<i>Text</i>	No visible inscription

**059. Çamlıbel**

<i>Province, Sub-Province + Admin. Code</i>	Tokat 60-00-1
<i>Map</i>	Amasya 89-s
<i>Location</i>	In the village; at the entrance gate, to the market- area, beside the <i>karakol</i> (gendarmerie)
<i>Copy</i>	DHF 30.xi.1984
<i>Publication</i>	RRMAM 2, 1. 940
<i>Description</i>	A simple cylinder on a plinth. Complete. Hard, grey limestone. Plinth square
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

**060. Kervansaray**

<i>Province, Sub-Province + Admin. Code</i>	Tokat, Tokat 60-00-1
<i>Map</i>	Amasya 90-s
<i>Location</i>	“Au village de Kervan Serai au nord de Tchiflik [Verisa] dans l'Art-Ova ... encastrée dans un mur” (Cumont). Present whereabouts not established (DHF visit 05.vii.1977)
<i>Copy</i>	Cumont from Girard (?1903). The stone has not been examined by DHF. Text here of Cumont (a facsimile of his printed copy is given here, Fig. 6.1.12 [p. 329])
<i>Publication</i>	Cumont 1904, 334 Wilson 1960, 134 (comment on text) RRMAM 2, 1. 947 notice of text; lines 10-11 cited)
<i>Description</i>	Two fragments, of which the second was not certainly part of the same milestone according to Cumont (1904, 334) “. . . sur un autre fragment de colonne qui pourrait avoir fait partie du même milliaire”.
<i>Dimensions</i>	Not given
<i>Text</i>	(Frag. 1) [Imp Caes] <b>divi Tra</b> [iani Pa]- <b>rthici</b> [f divi] 4 <b>Nervae</b> [nepos Tr]- [ai] <b>anus</b> [Hadrian]- <b>us Aug</b> [ustus pont]

**max** [tr p XIII cos]  
 8     [III p p]  
       [civitas Sebast]-  
 (Frag. 2) 10   [o] **p̣oḷiṭ mil** [p]  
               [- ]  
 12     [- ]

line 4: ligature **VA**

line 6: ligature **AV**

line 10: **ZELIT** (?) (Wilson 1960, 134)

lines 10-11: **RESTITVIT MIL** (RECAM 2. 947)

*Caput Viae*        Sebastopolis

*Date*                Hadrianus Augustus, ? AD 128/129

*Commentary*      The restoration proposed here follows the imperial titulature and the lay-out of 048. Akşar.

I have assumed that Kervansaray (in the modern region called the Artova) lies within the territory of ancient Sebastopolis (at Sulusaray) rather than of Zela (at Zile) which lay, at some distance, west of Sulusaray. It is unlikely, I believe, that the territory of Zela included the Artova region (E of Sebastopolis and SE of modern Tokat), *contra* Wilson (1960, 134), who suggests that the stone was perhaps brought to Kervansaray from the region of Zile.

## 061. Sulusaray

*Province, Sub-Province + Admin. Code*        Tokat, Artova 60-02-1

*Map*                Amasya 86-t

*Location*        “In a cemetery beside the bridge” (St. Pont.); in the S wall of the cemetery

*Copy*                Sir Charles Wilson c. 1880; Anderson (?) 19 June, 1899; DHF 05.vii.1977. DHF squeeze and photo. (Pl. 7.1.29 [p. 382]) in BIA. Text here from DHF squeeze

*BIA Collections:* *Squeeze and Stone Photographs*

Squeeze: 60. Tokat 12, Sulusaray

Stone: (1) B/W Neg.: DHF R/77/09.09

*Publication*      CIL 3. 6749 (text of Wilson from Ramsay)

CIL 3. 6894 (text of Wilson from Ramsay)

CIL 3. 14184<sup>16</sup> (text from Anderson)

St. Pont. 1 (Anderson), 34 (no. 472) (notice)

French 1980, 724 no. 29 (text from CIL [Anderson])

French 1981, 167 n.\*2 (comment on text)

Christol and Lorient 1986, 22 (comment)

RRMAM 2, 1. 951 (notice only)

Le Guen-Pollet 1989, 83 no. 33 (text of CIL [Anderson])

*Description*      A simple cylinder. Broken below. Hard, grey limestone. Above inscription: a wreath.

*Dimensions*      Letters: sharp, clear; bar-less A, L with diagonal lower bar, U for V  
 Ht (ex.) 1.02; diam. (top) 0.46. Letters: 0.040-45 but L 0.055, (lines 8a, b) 0.015-25

*Text*

**Imp' Caes**  
 2     **Marcus Anto-**  
       **nus Gordiani**

4    **nepos pius**  
       **felix invictus**  
 6    **Augustus p' p**  
       **trib·potesta-**  
 8    **ti viam resti-** (sic)  
 8a    (vac) **et Sabi Tranqui-**  
 8b    (vac) **llina Aug**  
       **tuit Cl Marc-**  
 10    **elus a Sebas-** (sic)  
       [topoli m p -]

lines 8a, 8b: inscribed in tiny letters between lines 8 and 9

line 9: **tuit G L Marc** (CIL 3. 14184<sup>16</sup> and French 1980)

lines 9-10: **Marclelus** for **Marcellus**?

*Caput Viae*        Sebastopolis  
*Date*                AD 238, 09.v(?)–09.xii Gordianus *Augustus*, then AD 241 with Tranquillina  
                           *Augusta*  
*Comment*        Christol and Lorient (1986, 22 n.49) note the omission (line 3) of the two words  
*Gordianus divi.*

## 062. Dutluca, form. Malumseyit

*Province, Sub-Province + Admin. Code*        Tokat, Artova 60-02-1  
*Map*                Amasya 86-ş  
*Location*        “ . . . . sur le toit d’une maison ” (Cumont). Present whereabouts not established  
                           (DHF visit 05.vii.1977)  
*Copy*                Cumont (Fr. and E.) 02 May, 1900. The stone has not been examined by DHF.  
                           Text here of Cumont  
*Publication*        Cumont 1905a, 347  
                           AE 1905.133 (text of Cumont)  
                           St. Pont. 2 (Cumont [Fr. and E.]), 197 (notice)  
                           Wilson 1960, 135 (comment on text)  
                           French 1981, 167 and n.\*2 (comment on text)  
                           Christol and Lorient 1986, 17 n.22 (comment on ll. 5-6)  
                           RRMAM 2, 1. 941 (notice only)  
                           Le Guen-Pollet 1989, 81-82 (v.s. no. 31) (text of Cumont)  
                           Dodgeon and Lieu 1991, 23 no. 1.3. 2 (transl. of Cumont’s text)  
                           Le Guen-Pollet 1991, 102 (correction to Le Guen-Pollet 1989)  
*Description & Dimensions*        Not given

*Text*                [Imp Caes M Aur]  
                           **Severus** [[Alexander]]  
                           **pius felix invictus**  
 4    **Augustus pont**  
       **maximus trib pot**  
       **cos p p procos**  
       **per Iul Proclianum**  
 8    (vac) **leg pr pr**  
       **A Sebastopoli**



(vac) **mil p V**line 6: **COSIIIPROCOS** (Cumont)

*Caput Viae* Sebastopolis  
*Date* AD 222, 13.iii-09.xii Severus Alexander *Augustus*

**063. Uylubağı**

*Province, Sub-Province + Admin. Code* Tokat, Artova 60-02-1  
*Map* Amasya 85-t  
*Location* In the village  
*Copy* Olshausen and Biller 1976/80. Not seen by DHF 05.vii.1977  
*Publication* Olshausen and Biller 1984, 239 and Fig. 42  
 RRMAM 2, 1. 962  
*Description* “Ein unbeschrifteter Meilenstein” (Olshausen and Biller)  
*Dimensions* Not given  
*Text* No visible inscription

**064. Elmalı**

*Province, Sub-Province + Admin. Code* Yozgat, Çekerek 66-04-2  
*Map* Amasya 85-t  
*Location* “Dans un cimetière au bord de la route entre Qadichehr et Soulou Séray, et à 6 kilomètres à l’ouest de Ouloubagh” (de Jerphanion). Present whereabouts not established (DHF visit 05.vii.1977)  
*Copy* de Jerphanion 19 November, 1911. The stone has not been examined by DHF. Text here of de Jerphanion  
*Publication* de Jerphanion 1914-21, 9 no. 12  
 RRMAM 2, 1. 975 (notice only)  
 Le Guen-Pollet 1989, 84 no. 36 (text of de Jerphanion)  
*Description & Dimensions* Not given

*Text* (1) **DD nn**  
 2 [Flavii Va]ll[er]ii  
 [C]onstan[t]i[ni] e[t V]all  
 4 [L]icinniani Licinii  
 (?vac) **Augg**  
 6 (vac) **η'**

line 3: **VALL** - Valerii (de Jerphanion)

(2) - - - -  
 [Con]stantio  
 - - - -

*Caput Viae* (Sebastopolis)  
*Date* (1) AD 313, Aug/Sept-317, 28.ii Constantinus and Licinius *Augusti*  
 (2) (?)  
*Commentary* Text (1) here follows that of de Jerphanion except for minute differences.

## C. CAPPADOCIA

## C.2 CAESARIA - SEBASTIA

## 065. Kayseri

<i>Province, Sub-Province + Admin. Code</i>	Kayseri 38-00-0
<i>Map</i>	Kayseri 82-Ig
<i>Location</i>	Found in a sand-quarry, near the Çifte Türbe, c. 4 km ENE of the city-centre. Now in the Kayseri Museum [Inv. no. 81.29]
<i>Copy</i>	DHF 24.v.1984. DHF squeeze and photos (Pl. 7.1.30-31 [p. 383]) in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Photograph</i>	Squeeze: 38. Kayseri 36, Kayseri Stone: (1) B/W Neg.: DHF M/84/03.01-04 (2) Col. Slide: DHF 243.27-29
<i>Publication</i>	RRMAM 2, 1. 544 (notice only) French 1989, 39 and Fig. 1 AE 1989. 731 (text of French 1989; revisions and commentary) Christol and Lorient 1993, 210-211 (commentary on text) AE 1993. 1565 (text and emendations of Christol and Lorient) Christol and Lorient 2001, 110 no. 7 (comment on the governor)
<i>Description</i>	A simple cylinder. Poorly shaped but complete. Local tufa. Shaft slightly tapering towards top. Shaped base. Surface worn
<i>Dimensions</i>	Letters: irregular but deeply cut; enhanced with red paint Ht (total) c. 1.70; wi. (top) c. 0.55; (base) ht 0.15; wi. c. 0.61. Letters: (line 1) O 0.035 and S 0.055 in OES, (line 10) P in PRAES 0.060

*Text*

Imp·C/aesar·Marci·  
 Aure(l)i·D(omini) n(ostri)·Antonini·f(il)ius  
 pius /f/elix·Aug di-  
 4 vi·Severi·nepos·di-  
 vi·Antonini·fil imp IIII  
 cos·III·p·p PROSCAES VI  
 et·Marc·Aurel Alexan-  
 8 der·nobilissimus Caes  
 et pius·Aug·n·per·Aur·Basile-  
 um praesidem provinc(iae)·  
 (vac)  
 m II  
 (vac)  
 12 μίλια

line 1: **IMP·OESAR** (lapis)

line 3: **PIVSEELIX** (lapis)

line 5: **IMPIIIII** (lapis), **imp IIII** (sic) (DHF), **p m** (tr)**p IIII** (Christol and Lorient)

line 6: **PROSCAESVI** (lapis), **pro**(co)s **CAESVI** (DHF), **proconsul** (Christol and Lorient)

line 9: **AVG·N·**, **Aug**(ustus) **n**(oster)

line 11: **m for mp**, cp. 056(B) (Sept. Sev.), 079(D), 084, 089(B), 093(H),  
095 and 097(C) (all Gord.), 115 (Prob.); also 104(J), 108(S), 114  
line 12: ligature **MI** and **IA**

*Date* AD 221, 26.vi-09.xii Elagabalus *Augustus* with Severus Alexander *Caesar*  
(Christol and Lorient)

*Commentary* The readings and emendations, proposed by Christol and Lorient (1993, 210-213), are clearly superior to mine (French 1989) (“texte incoherent” AE 1993. 731). Furthermore, for a satisfactory resolution to the subject of the date (Christol and Lorient [1993, 213]), see now RRMAM 3.2 [Galatia] 58(A). Eskiypar 1

## C.3 CAESARIA - MELITENA

## 066. Sakaltutan

<i>Province, Sub-Province + Admin. Code</i>	Kayseri 38-00-6
<i>Map</i>	Kayseri 84-Ih
<i>Location</i>	In the village; at the house of Rüstem Köroğlu. Now in the Kayseri Museum [Inv. no. 84.77]
<i>Copy</i>	DHF 23.v.1984. DHF squeeze and photos in BIA. Texts here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i> Squeeze: 38. Kayseri 35, Kayseri Stone: (2) Col. Slide: DHF 243.27-29
<i>Publication</i>	RRMAM 2, 1. 569 (notice only) French 2008, 125 (text and comments) AE 2008. 1473a-b (text of French) SEG 58. 1662 (text of French)
<i>Description</i>	A simple cylinder, on a square plinth. Broken into three pieces. Hard, black basalt. Top flat. Letters enhanced with red paint. Surface and letters: much worn and damaged.
<i>Dimensions</i>	Letters: (texts 1 and 2) (Greek) lunate <i>epsilon</i> , <i>sigma</i> and <i>omega</i> Ht 0.98 + 0.72 + 0.36; diam. (base) 0.53. Letters: (text 1) (lines 1-5) 0.030-50, (lines 6-12) c. 0.030, (line 13) 0.14-17, (text 2) (line 1) 0.125, (line 5) 0.060 but O 0.035, (line 11) 0.045-55

<i>Text</i>	(1) (on the front face of the shaft)
	[Imp T Caesar divi Vespasiani f Aug] <b>pontif</b> [ex maximus trib pot X] [imp XVII p p cos VIII desig V] <b>IIII censor</b> (vac) [Domitianus Caesar divi Vespas] <b>iani f·cos</b> [VII desig VIII sacerdos] 4 [omnium collegiorum pri] <b>n[ce]ps iuv</b> [entutis] [A Caesennius Gallus cos XVvir s f] <b>leg Aug pro pr stravit</b> [Αὐτοκρ Τ Καῖσα(αρ) Θεοῦ Οὐεσπασιανοῦ υἱὸς Σεβ ἀρχιερ]εὺς μέγιστο[ς] [δημαρχικῆς ἐξουσίας τὸ ι' αὐτοκράτωρ τὸ ιε' πατήρ] πατρίδ(ος) ὑπατ- 8 [ος τὸ η' ἀποδεδειγμένος τὸ θ' τειμη]τή[ς] (vac) [Δομιτιανὸς Καῖσαρ Θεοῦ Οὐεσπασια]νοῦ υἱὸς ὕ(π)ατος τὸ ζ' ἀποδε- [δειγμένος τὸ η' ἱερὲς πάντων ἱερατε]υμάτων ἡγούμενος νεότητος [Α Καισέννιος Γάλλος ὕπατος πεντε]καίδεκα ἀνδρῶν μυστήρεων 12 (vac) [πρεσβευτ]ή[ς]·καὶ·ἀντιστράτηγος ἔστρωσεν (on plinth, in a <i>tabula ansata</i> ) (vac) <b>XVIII ιθ'</b>

line 2: horizontal line over the numerals

line 9: horizontal line over the numeral Z

(2) (on the l. of text [1])

	(vac) <b>Imp</b> (vac) <b>Nerva Caes Aug</b> <b>pon max tr pot</b> [est] 4 <b>cos II p</b> [p] <b>via</b> [s rest]
--	---

per·Pom[po]nium B[assu]m  
 leg·A[ug pr pr]  
 Αὐτοκρ Νέρουακ Καῖς  
 8 Σεβ ἀρχ μεγ δημ ἐξ  
 ὑπ·τὸ β'·π π ὁδοὺς ἀποκ  
 δι (vac) ἀ Πομπωνίου  
 Βάκκου πρεξ [άντ]  
 12 [XVIII]Ι ιθ'

line 4: horizontal line over the numeral II

Text-abbreviations expanded:

(vac) **Imp** (vac)  
 Nerva Caes(ar) Aug(ustus)  
 pon(tifex) max(imus) tr(ibuniciae) pot[est(atu)]  
 4 co(n)s(ul) II p(ater) [p(atriciae)] via[s rest(ituit)]  
 per Pom[po]nium B[assu]m  
 leg(atum) A[ug(usti pr(o) pr(aetore)]  
 Αὐτοκρ(άτωρ) Νέρουακ Καῖς(αρ)  
 8 Σεβ(αστὸς) ἀρχ(ιερεὺς) μέγ(ιστος) δημ(αρχικῆς) ἐξ(ουσίας)  
 ὑπ(ατος) · τὸ β' π(ατήρ) π(ατρίδος) ὁδοὺς ἀποκ(ατέκτησε)  
 διὰ Πομπωνίου  
 Βάκκου πρεξ(βευτοῦ) [άντ(ικτρατήγου)]  
 12 [XVIII]Ι ιθ'

*Caput Viae* (Caesaria)

*Date* (1) AD 81, “seit Mitte Marz”-30.vi Titus *Augustus* with Domitianus *Caesar*  
 (2) AD 96, 18.ix-31.xii Nerva *Augustus*

*Commentary* In text (2) there is a rare instance of the Greek version imitating the Latin text by the wholesale use of abbreviations.

### 067 (A). Özlüce 1, form. Taf

*Province, Sub-Province + Admin. Code* Kayseri, Tomarza 38-08-1

*Map* Kayseri 88-Ig

*Location* In a cluster of 4 milestones (Pl. 7.1.32 [p. 383]) *in situ*, on the S side of the Roman road; c. 2 km NW of the village

*Copy* DHF 10.viii.1974. DHF photo. in BIA

*BIA Collections:* *Squeeze and Stone Photographs*  
 Stone: (1) B/W Neg.: DHF R/74/12.06-09

*Publication* RRMAM 2, 1. 565

*Description* A simple cylinder. Soft, pale limestone. Surface very worn and pitted. Traces of red paint in letters.

*Dimensions* Ht 2.23; diam. (top) 0.72. Letters: 0.16

*Text* - - - -  
 - -  
 λη'

*Caput Viae* (Caesaria)  
*Date* (?)

### 067(B)-(D). Özlüce 2-4, form. Taf

*Province, Sub-Province + Admin. Code, Map, and Location* As 067(A)  
*Publication* RRMAM 2, 1. 566-568  
*Copy* DHF 10.viii.1974. DHF photos in BIA  
*BIA Collections: Squeeze and Stone Photographs*  
 Stone: (1) B/W Neg.: DHF R/74/12.06-09  
 (2) Col. Slide: DHF 129.12  
*Description* Three milestones, in the form of simple cylinders. All soft pale limestone  
 2 - 067(B) complete  
 3 - 067(C) smashed into numerous fragments  
 4 - 067(D) broken into two halves  
*Dimensions* 2 - 067(B) ht 2.23; diam. 0.55  
 3 - 067(C) ht 1.50; diam. c. 0.50  
 4 - 067(D) ht 1.96; diam. 0.70  
*Text* No visible inscription on these three stones

### 068(A). Aslanbeyli Yaylası, Hanboğazı 1

*Province, Sub-Province + Admin. Code* Kayseri, Pınarbaşı 38-05-0  
*Map* Saimbeyli 89/90-Ii (00.45)  
*Location* In the gorge of the Hanboğazı, at a place called Alışlı Burun; c. 3.45 km NW of the İmirzağa-Değirmentaş şose; *in situ*, beside and N of the Roman road, in a cluster with four others (Pl. 7.1.33 [p. 384])  
*Copy* DHF 19.vi.1977, 10.ix.1977. DHF squeeze (drawing, Fig. 6.2.26 [p. 364]) and photos (Pl. 7.1.34 [p. 384]) in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 38. Kayseri 01, Aslanbeyli Yaylası, Hanboğazı 1  
 Stone: (1) B/W Neg.: DHF R/77/18.08-12 and 19.01-07  
*Publication* French 1985b, 150 and n.15 (notice and excerpt from text)  
 RRMAM 2, 1. 505 (notice only)  
*Description* A simple cylinder. Broken above (between the two dates given above). Hard, pale limestone. The shaft tapers slightly towards the top.  
 Letters: neat, sharp, clear; broken-bar A, U for V; pronounced apices  
*Dimensions* Ht 1.60; diam. (top) 0.50, (base) 0.60. Letters: c. 0.050, (line 1) 0.085-90, (line 12) 0.105

*Text*

	<b>Imp</b> (leaf) <b>C</b> [a]-
	<b>esar M</b> (leaf) <b>Au-</b>
	<b>relius Sever-</b>
4	<b>us Alexande-</b>
	<b>r pius fe</b> [l]ix <b>A-</b>
	<b>ug</b> (leaf) <b>trib</b> (leaf) <b>pō-</b>
	<b>test</b> (leaf) <b>cos</b> (leaf)
8	<b>p p</b> (leaf) <b>vias et po-</b>
	<b>ntes vetus-</b>
	<b>tate conlaps-</b>

**as restituit** (leaf)12 (vac) **νγ'**

line 12: **NT** for **NB**. The distance-figure was not correctly inscribed on milestone (A); on stones (B), (C) and (D) of this cluster, the number is unquestionably **NB**.

*Caput Viae* (Caesaria)*Date* Severus Alexander *Augustus*, (?)AD 222, 14(?) .iii-09.xii**068(B). Aslanbeyli Yaylası, Hanboğazı 2***Province, Sub-Province + Admin. Code, Map, and Location* As 068(A)*Copy* DHF 10.ix.1977. DHF squeeze (drawing, Fig. 6.2.27 [p. 364]) in BIA. Text here from DHF squeeze*BIA Collections: Squeeze and Photograph*

Squeeze: 38. Kayseri 02, Aslanbeyli Yaylası, Hanboğazı 2

*Publication* RRMAM 2, 1. 506 (notice only)*Description* A simple cylinder. Complete in two pieces. Hard, blue limestone. The shaft tapers slightly towards the top. Surface and letters: worn and pitted.

Letters: clear but not sharp; broken-bar A

*Dimensions* Ht 1.96; diam. (top) 0.58, (base) 0.65. Letters: 0.050-60, (line 1 c. 0.070), (line 4) O 0.040, (line 13) 0.070*Text*

**Imp Caes  
divi Sever-  
i nep divi M A-  
4 ntonini fil  
M Aur Ἀντων[i]-  
no pio felici Ἀυ-  
g miliar[i]a]  
8 re[s]tituta p-  
er M Ulp  
Ofellium Th-  
eodorum le-  
12 g Aug pr p[r]**

(vac) **νβ'***Caput Viae* (Caesaria)*Date* Elagabalus *Augustus*, (?) AD 218, 16.v–mid-June(?)**068(C). Aslanbeyli Yaylası, Hanboğazı 3***Province, Sub-Province + Admin. Code, Map, and Location* As 068(A)*Copy* DHF 10.ix.1977. DHF squeeze (drawing, Fig. 6.2.28 [p. 365]) in BIA. Text here from DHF squeeze*BIA Collections: Squeeze and Photograph*

Squeeze: 38. Kayseri 03, Aslanbeyli Yaylası, Hanboğazı 3

*Publication* RRMAM 2, 1. 507 (notice only)*Description* A simple cylinder. Broken above; shaft now in two pieces. Hard, grey limestone.

The shaft tapers slightly towards the top. Surface and letters: worn and unclear, otherwise regular.

Letters: broken-bar A, E but (line 12) lunate E

*Dimensions* Ht (max.) 2.05; diam. (top) c. 0.50; (base) 0.61. Letters: 0.050-70, (line 11) O 0.050, (line 13) 0.09+0.10

*Text*

(vac) **Im**[p]  
 (vac) **Caesar** (sic)  
**Marco Anto**[n]-  
 4 **io Gordiano**  
 [p]io f[elici Au]-  
 [g]us[t]o **restit-**  
**uerunt per**  
 8 **[C]uspidium**  
**[F]laminium**  
**[Se]verum leg-**  
 (vac) **[a]tum pro**  
 12 **praetore** μ  
 (vac) **νβ'**

lines 4 and 8: Δ for D

line 13: μ for μ(ἰλῖα), cp. 107(G), 108(D) and 109(C) (Elagabalus), 119(A) (Sev. Alexander), 072(C), 074(C), 075(C), 080(B), 087(B), 098(D), 104(B) and 108(M) (all Gordianus), 085(B) (Maximinus), 119(B) (Philippus); also 112

*Caput Viae* (Caesaria)

*Date* AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*

*Commentary* For the survival of *restituerunt*, see above [p. 12], **Notes and Comments 3.5**  
 Text-form (4).

#### 068(D). Aslanbeyli Yaylası, Hanboğazı 4

*Province, Sub-Province + Admin. Code, Map, and Location* As 068(A)

*Copy* DHF 10.ix.1977. DHF squeeze (drawing, Fig. 6.2.29 [p. 366]) in BIA. Text here from DHF squeeze

*BIA Collections: Squeeze and Photograph*

Squeeze: 38. Kayseri 04, Aslanbeyli Yaylası, Hanboğazı 4

*Publication* RRMAM 2, 1. 508 (notice only)

*Description* A simple cylinder. Broken below. Hard, pale limestone. Top flat. The shaft tapers slightly towards the top. Surface; rough, worn and pitted.  
 Letters: worn and unclear; somewhat irregular in shape, size and alignment; cut with a broad-blade chisel; broken-bar A

*Dimensions* Ht (max.) 1.55; diam. (top) 0.52, (base) 0.60. Letters: 0.040-60, (line 17) 0.070

*Text*

**Imp**  
**Caes M Iu**[lius]  
**Philipp**[us]  
 4 **[p]ius fe**l[ix in]-  
**[v]ictus A**[ug et M]



**Iu̇lius Pḣilip**[pus]  
**nobilissimū**[s]  
 8 [C]aesar [v]i[as et]  
 [p]ontes [v]et[u]-  
**statē conlap-**  
**sas restituer-**  
 12 **unt per Anton-**  
**ium Memmi-**  
**um Hieronem**  
**v c [l]eg Aug**  
 16 (vac) **pr pr**  
 (vac) **υβ'**

*Caput Viae* (Caesaria)

*Date* AD 244, July/Aug.-247, July/Aug. Philippus *Augustus* with Philippus *Caesar*

### 068(E). Aslanbeyli Yaylası, Hanboğazı 5

*Province, Sub-Province + Admin. Code and Map* As 068(A)

*Location* As 068(A) but on the S side of the Roman road

*Copy* DHF 10.ix.1977. DHF squeeze in BIA. Text here from DHF squeeze

*BIA Collections: Squeeze and Photograph*

Squeeze: 38. Kayseri 05, Aslanbeyli Yaylası, Hanboğazı 5

*Publication* RRMAM 2, 1. 509 (notice only)

*Description* A simple cylinder. Complete. Hard, grey limestone. Top flat; the shaft tapers slightly from base but abruptly at top. Surface: rough and worn.

*Dimensions* Letters: very severely worn; (text 1) cut with a broad-blade chisel  
Ht 1.77; diam. (top) 0.26, (base) 0.55. Letters: (text 1) c. 0.050, (text 2) c. 0.035

*Text* A jumble of letters in Latin and Greek

(1) (obscured by wear and text [2])

A Latin text

(2) (at the top of the shaft; cut over the earlier text)

The letters are difficult to read, perhaps:

**Ἐπὶ τῶν Κυ-**

**ρίων - - -**

*Caput Viae* [Caesaria]

*Date* (1) and (2) (?)

*Commentary* There are very few Greek texts on milestones along this road.

### 069. Aslanbeyli Yaylası, Hanyeri

*Province, Sub-Province + Admin. Code* Kayseri, Pınarbaşı 38-05-2 or 3

*Map* Saimbeyli 89/90-Ii (00.37)

*Location* At Aslanbeyli Yaylası; c. 2.90 km W of şose and 0.60 km W of Hanboğazı;  
lying in open ground, partially buried, c. 50 m S of Han ruins

*Copy* DHF 12.ix.1977, 30.vii.1978. DHF squeeze and photo. in BIA. Text here from

	DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i>
	Squeeze: 38. Kayseri 06, Aslanbeyli Yaylası, Hanyeri
	Stone: (1) B/W Neg.: DHF R/77/19.08
<i>Publication</i>	RRMAM 2, 1. 510 (notice only)
<i>Description</i>	A simple cylinder. Broken above and below. Hard, grey limestone. Surface: pitted and worn.
	Letters: worn but legible; broken-bar A
<i>Dimensions</i>	Ht (max.) 1.55; diam. (shaft) 0.61. Letters: c. 0.050-60

<i>Text</i>	[Imp Caes] L [S]eptimius Severus Pius 4 Pertinax Aug Arab·Adiab·Part[h] max·pon/t·max· trib·pot·VI·imp[(XI] 8 cos·II·p p·procos et·Imp·Caes·M Aur[elius Ant]- [oninus Aug et] 12 - - - -
-------------	---

line 6: **MAX·PONP·MAX·** (lapis)

<i>Caput Viae</i>	[Caesaria]
<i>Date</i>	AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> [? with L. Septimius Geta (names erased) <i>Caesar</i> ]
<i>Commentary</i>	The text here can be restored on the basis of numerous, intact examples of the standard text erected along the Caesaria-Melitene road (e.g. 088[B]. Kemer 4); accordingly, the date of this milestone has been assigned to AD 198.

### 070(A). Değirmentaş 1

<i>Province, Sub-Province + Admin. Code</i>	Kayseri, Sarız 38-07-0
<i>Map</i>	Saimbeyli 90-II
<i>Location</i>	In the village; at the cami. Used as a column-support for the verandah; the first (from S) of 4 posts on the front porch
<i>Copy</i>	DHF 08.ix.1977. DHF squeeze in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i>
	Squeeze: 38. Kayseri 07, Değirmentaş 1
<i>Publication</i>	RRMAM 2, 1. 516 (notice only)
<i>Description</i>	A simple cylinder. Broken above and below. Hard, blue limestone.
	Letters: worn and indistinct; (text 2) broken-bar A
<i>Dimensions</i>	Ht (max.) 0.50; diam. (shaft) 0.45. Letters: (text 1) 0.050-55, (text 2) 0.050-60
<i>Text</i>	(1) (underneath text [2]) - - - - 2 [vias] <b>et pontes</b> - - - -

(2) (on the top of text [1])

-----  
 2    - - co Aug  
 -----  
 4    - - icto A

*Caput Viae* [Caesaria]*Date* (1) (?) 3rd cent. AD

(2) (?)

*Commentary* (Text [1]): the repair-formula, *vias et pontes vetustate conlapsas*, on the Caesaria-Melitene road is most commonly found on milestones from Severus Alexander to Trebonianus Gallus (see below, Indices 4.6.6 (24) [p. 315]).

**070(B). Değirmentaş 2***Province, Sub-Province + Admin. Code and Map* As 070(A)*Location* As 068(A); the second post-support from S. (?) Brought from Aslanbeyli, Hanyeri in the Kuruçay pass*Copy* DHF 08.ix.1977*Publication* RRMAM 2, 1. 517 (notice only)*Description* Fragment of a milestone*Dimensions* Not recorded*Text* Lost**070(C). Değirmentaş 3***Province, Sub-Province + Admin. Code and Map* As 070(A)*Location* As 068(A); the third post-support from S (photo., Pl. 7.1.35 [p. 385])*Copy* DHF 19.vi.1977, 08.ix.1977. DHF squeeze (drawing, Fig. 6.2.30 [p. 367]) and photo. in BIA. Text here from DHF squeeze*BIA Collections: Squeeze and Photograph*

Squeeze: 38. Kayseri 08, Değirmentaş 2

Stone: (1) B/W Neg.: DHF R/77/07.08

*Publication* RRMAM 2, 1. 518 (notice only)

Baz 2007, 99 no. 60 (notice of RRMAM 2, 1. 518)

*Description* A simple cylinder. Broken above. Very hard, blue-grey limestone.

Letters: slightly worn but sharp and clear; neat, regular in size, shape and alignment; U for V

*Dimensions* Ht (vis.) 0.90; diam. (top) 0.62. Letters: 0.050-70, (line 7) 0.090*Text*

-----  
 2    [ - vias et]  
      [pontes vetus]-  
 4    **tate conlaps-**  
      **[a]s restituit** (leaf)  
 6    (0.12 gap)  
      **ve'**

*Caput Viae* (Caesaria)

*Date* (?) Severus Alexander  
*Commentary* The repair-formula, *vias et pontes vetustate conlapsas*, on the Caesaria-Melitene road is most commonly found on milestones from Severus Alexander to Trebonianus Gallus (see below, Indices 4.6.6 (24) [p. 315]).

#### 070(D). Değirmentaş 4

*Province, Sub-Province + Admin. Code and Map* As 070(A)  
*Location* As 068(A); the fourth stone from S  
*Copy* DHF 08.ix.1977  
*Publication* RRMAM 2, 1. 519  
*Description & Dimensions* Not recorded  
*Text* No text visible

#### 071(A). Değirmentaş, Arkaçlar Mevkii 1.1

*Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0  
*Map* Saimbeyli 90-II (07.32)  
*Location* *In situ*, beside the Roman road, formerly on E side; now 10 m SW of şose; c. 2 m E of no. 1-2; c. 2 km SW of the village  
*Copy* DHF 09.ix.1977. DHF photo. in BIA  
*BIA Collections: Squeeze and Photograph*  
 Stone: (1) B/W Neg.: DHF R/77/18.06  
*Publication* RRMAM 2, 1. 520  
 Baz 2007, 98 no. 59 (notice of RRMAM 2, 1. 520)  
*Description* A simple cylinder. Complete. Hard, grey limestone. The shaft tapers slightly towards top. No plinth. Worn.  
*Dimensions* Ht 1.93; diam. (top) 0.57, (bottom) 0.66  
*Text* Some worn letters visible; distance figure restored [LV ve']

*Commentary* The distance-figure on the milestone Arkaçlar Mevkii 2.5 is legible: **νς'**. The distance between Mevkii 1 and Arkaçlar Mevkii 2 is exactly one MP. The distance-figure on this stone can, therefore, be safely restored: **ve'**.

#### 071(B). Değirmentaş, Arkaçlar Mevkii 1.2

*Province, Sub-Province + Admin. Code and Map* As 069(A)  
*Location* As no. 069(A) but c. 2 m to W  
*Copy* DHF 07.ix.1977. DHF photo. in BIA  
*BIA Collections: Squeeze and Photograph*  
 Stone: (1) B/W Neg.: DHF R/77/18.07  
*Publication* RRMAM 2, 1. 521  
 Baz 2007, 98 no. 58 (notice of RRMAM 2, 1. 521)  
*Description* A simple cylinder. Complete. Hard, grey limestone. The shaft tapers slightly towards the top. No plinth. Very worn  
*Dimensions* Ht 2.00; diam. (top) 0.45, (bottom) 0.66  
*Text* No text visible; distance figure restored [LV ve']

#### 072(A). Değirmentaş, Arkaçlar Mevkii 2.1

*Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0  
*Map* Saimbeyli 90-II (07.21)  
*Location* *In situ*; on the E side of the Roman road. On a low, barren ridge, c. 3.40 km SSW of the village, together with six other milestones (Pl. 7.1.36 [p. 385])  
*Copy* DHF 10.ix.1977. DHF photo. in BIA  
*BIA Collections:* *Squeeze and Photograph*  
 Stone: (1) B/W Neg.: DHF R/77/18.02  
*Publication* RRMAM 2, 1. 522  
 Baz 2007, 98 no. 55 (notice of RRMAM 2, 1. 522)  
*Description* A simple cylinder. Broken above. Hard, grey limestone. The shaft tapers slightly towards the top. Very worn  
*Dimensions* Ht (max.) 1.10, diam. (shaft) 0.41  
*Text* No text visible; distance figure restored [LVI | vς']

### 072(B). Değirmentaş, Arkaçlar Mevkii 2.2

*Province, Sub-Province + Admin. Code and Map* As 072(A)  
*Location* As 072(A)  
*Copy* DHF 10.ix.1977. DHF photo. in BIA. Text here from DHF notes  
*BIA Collections:* *Squeeze and Photograph*  
 Stone: (1) B/W Neg.: DHF R/77/18.03  
*Publication* RRMAM 2, 1. 523 (notice only)  
 Baz 2007, 98 no. 56 (notice of RRMAM 2, 1. 523)  
*Description* A simple cylinder. Broken above and below right. Hard, grey limestone. No plinth. Surface and letters: worn.  
 Letters: cut with a broad-blade chisel  
*Dimensions* Ht (max.) 1.30, diam. (top) 0.48. Letters: c. 0.060  
*Text*

	----
2	<b>pr pr</b>
	[LVI]
4	[vς']

### 072(C). Değirmentaş, Arkaçlar Mevkii 2.3

*Province, Sub-Province + Admin. Code and Map* As 072(A)  
*Location* As 072(A)  
*Copy* DHF 10.ix.1977. DHF squeeze and photo. in BIA. Text here from DHF squeeze  
*BIA Collections:* *Squeeze and Photograph*  
 Squeeze: 38. Kayseri 11, Değirmentaş, Arkaçlar Mevkii 2.3  
 Stone: (1) B/W Neg.: DHF R/77/18.04  
*Publication* RRMAM 2, 1. 524 (notice only)  
 Baz 2007, 97 no. 53 (notice of RRMAM 2, 1. 524)  
*Description* A simple cylinder. Broken above left. Hard, grey limestone. The shaft tapers very slightly towards the top. No plinth. Surface: worn.  
 Letters: worn, indistinct; irregular in shape, size and alignment; broken-bar A, E but (line 13) lunate E  
*Dimensions* Ht 1.86, diam. (top) 0.54, (base) 0.61. Letters: 0.050-60

<i>Text</i>	(1) and (2)	<b>Imper Caesar M-</b> [arco An]- 4 [tonio Gor]- [diano pio] [f]elici Au- gusto resti- 8 tuerunt per Cuspidi- um Flamini- um Severum 12 leg[a]tum pro prae- [to]re μ [vς']	(sic)
-------------	-------------	---	-------

line 13: μ for μ(ἰλῐα), cp. 107(G), 108(D) and 109(C) (Elagabalus), 119(A) (Sev. Alexander), 068(C), 074(C), 075(C), 080(B), 087(B), 098(D), 104(B) and 108(M) (all Gordianus), 085(B) (Maximinus), 119(B) (Philippus); also 112

(3) (inscribed over the top of ll. 2-6 of text [1-2])

**IMPCAESS** visible between ll. 2-3 of text (1-2)

<i>Caput Viae</i>	[Caesaria]
<i>Date</i>	(1) AD 238, 09.v(?)–09.xii (?), Gordianus <i>Augustus</i> (2) (?) a Tetrarchic text

*Commentary* Restored after the text of 075(C). İmirzağa, Barcın Mevkii 3  
For the survival of *restituerunt*, see above [p. 12], **Notes and Comments 3.5** Text-form (4).

#### 072(D). Değirmentaş, Arkaçlar Mevkii 2.4

<i>Province, Sub-Province + Admin. Code and Map</i>	As 072(A)
<i>Location</i>	As 072(A)
<i>Copy</i>	DHF 10.ix.1977. DHF photo. (Pl. 7.1.37 [p. 385]) in BIA
<i>BIA Collections: Squeeze and Photograph</i>	Stone: (1) B/W Neg.: DHF R/77/17.08
<i>Publication</i>	RRMAM 2, 1. 525 Baz 2007, 98 no. 57 (notice of RRMAM 2, 1. 525)
<i>Description</i>	A simple cylinder. Broken above and on left side. Hard, grey limestone. No plinth. Worn.
<i>Dimensions</i>	Ht (ex.) 1.62; diam. (shaft) 0.52
<i>Text</i>	No visible text

#### 072(E). Değirmentaş, Arkaçlar Mevkii 2.5

<i>Province, Sub-Province + Admin. Code and Map</i>	As 072(A)
<i>Location</i>	As 072(A)
<i>Copy</i>	DHF 10.ix.1977. DHF squeeze and photo. (Pl. 7.1.38 [p. 385]) in BIA. Text

	here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i> Squeeze: 38. Kayseri 12, Değirmentaş, Arkaçlar Mevkii 2.5 Stone: (1) B/W Neg.: DHF R/77/17.09
<i>Publication</i>	French 1985b, 150 and n.16 (notice, and excerpt from text) RRMAM 2, 1. 526
<i>Description</i>	Baz 2007, 96 no. 52 (notice of excerpt [French 1985b], and of RRMAM 2, 1. 526) A simple cylinder. Broken below left. Hard, pale limestone. The shaft tapers very slightly towards the top. No plinth. Surface: worn Letters: worn but legible; neat, large, regular in size, shape and alignment; broken-bar A
<i>Dimensions</i>	Ht 1.92; diam. (top) 0.55, (bottom) 0.60. Letters: 0.070
<i>Text</i>	[Imp] (leaf) <b>Caesa-</b> <b>r M</b> (leaf) <b>Aurelius</b> <b>Severus Ale-</b> <b>xander pius</b> (leaf) 5 <b>felix Aug</b> (leaf) <b>tri-</b> <b>b</b> (leaf) <b>potest</b> (leaf) <b>c-</b> <b>os</b> (leaf) <b>p p</b> (leaf) <b>vias</b> <b>et pontes ve-</b> <b>tustate con-</b> 10 <b>lapsas resti-</b> (vac) <b>tuīt</b> (leaf) (0.14 gap) <b>υς'</b>
<i>Caput Viae</i>	(Caesaria)
<i>Date</i>	Severus Alexander <i>Augustus</i> , AD 222, 14(?).iii-09.xii

**072(F). Değirmentaş, Arkaçlar Mevkii 2.6**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 072(A)
<i>Location</i>	As 072(A)
<i>Copy</i>	DHF 10.ix.1977. DHF squeeze and photo. (Pl. 7.1.39 [p. 386]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i> Squeeze: 38. Kayseri 13, Değirmentaş, Arkaçlar Mevkii 2.6 Stone: (1) B/W Neg.: DHF R/77/17.10
<i>Publication</i>	RRMAM 2, 1. 527
<i>Description</i>	A simple cylinder. (?)Broken above. Hard, pale limestone. No plinth. Surface and letters: pitted and worn. Letters: some clear, others lost; broken-bar A
<i>Dimensions</i>	Ht 1.47; diam. (top) 0.58, (base) 0.59. Letters: c. 0.050
<i>Text</i>	(vac) <b>Imp Caes</b> <b>L Septimius</b> <b>Severus Piu[s]</b> 4 <b>Peṛtinax Aug</b> <b>Arab Adiab Parth</b>

[max pont max]  
 [trib pot VI imp XI]  
 8 [cos II p p procos et]  
 [Imp Caes M Au]re[l]  
 [Antoninus Aug]  
 - - - -

*Caput Viae* [Caesaria]

*Date* AD 197/198(?) L. Septimius Severus [and M. Aurelius Antoninus (Caracalla)  
*Augusti* with L. Septimius Geta (names erased?) *Caesar* ?]

*Commentary* The text here can be restored on the basis of numerous, intact examples of the standard text erected along the Caesaria-Melitene road (e.g. 088[B]. Kemer 4); accordingly, the date of this milestone has been assigned to AD 197/198. The governor would have been C. Iulius Flaccus Aelianus. On the basis of 072(E) the distance-figure here was LVI | vς'

### 072(G). Değirmentaş, Arkaçlar Mevkii 2.7

*Province, Sub-Province + Admin. Code and Map* As 072(A)

*Location* As 072(A)

*Copy* DHF 10.ix.1977. DHF squeeze and photo. (Pl. 7.1.40 [p. 386]) in BIA. Text here from DHF squeeze

*BIA Collections:* *Squeeze and Photograph*

Squeeze: 38. Kayseri 14, Değirmentaş, Arkaçlar Mevkii 2.7

Stone: (1) B/W Neg.: DHF R/77/17.11

*Publication* RRMAM 2, 1. 528

Baz 2007, 97 no. 54 (notice of RRMAM 2, 1. 528)

*Description* A simple cylinder. Broken below. Hard, grey limestone. Surface and letters: pitted and worn.

Letters: some clear, others lost; uneven size, shape and alignment

*Dimensions* Ht 1.15; diam. (shaft) 0.50. Letters: c. 0.030-40

*Text*

Im[pp] Ç[aess]  
 [Q M]eş Tr[a]-  
 iano Decio [Au]-  
 4 g et Q Here[n]-  
 [nio] Etr[usco]  
 [Mess]i[o Decio  
 (vac) Aug et  
 8 [C] V̇alenti H-  
 osṫil̇iano  
 [Mes]si̇(o) Quinto  
 (vac) [nob]il̇  
 12 [Caes]  
 - - - -  
 [ - - - - - ]AF  
 [ - - - - - ]

*Caput Viae* [Caesaria]

*Date* AD 251 Traianus Decius and Herennius Etruscus *Augusti* with Hostilianus *Caesar*

*Commentary* The governor's name (if it was inscribed) cannot be restored with probability. On the other hand the distance-figure can be restored (by association with the milestone, 072[E], on



which the number survives) as LVI | vϣ'

Possible earlier inscription underneath the text above.

### 073. İmirzağa

<i>Province, Sub-Province + Admin. Code</i>	Kayseri, Sarız 38-07-0
<i>Map</i>	Saimbeyli 90-Ii
<i>Location</i>	In the village; at the cami. Used as a support, on the right-hand side of the gate
<i>Copy</i>	DHF 08.ix.1977
<i>Publication</i>	RRMAM 2, 1. 529
<i>Description</i>	A simple cylinder
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

### 074(A). İmirzağa, Eski Harabe Mevkii 1

<i>Province, Sub-Province + Admin. Code</i>	Kayseri, Sarız 38-07-0
<i>Map</i>	Saimbeyli 90-Ii (07.14)
<i>Location</i>	In the <i>dere</i> (gully), beside the stream; buried on the E side of the şose, which runs parallel to the stream c. 150 m N of the cemetery (on E side of the şose); immediately to S of 074(B).
<i>Copy</i>	DHF 08.ix.1977. DHF squeeze and photo. (Pl. 7.1.41 [p. 386]) in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Photograph</i>	Squeeze: 38. Kayseri 15, İmirzağa, Eski Harabe Mevkii 1 Stone: (1) B/W Neg.: DHF R/77/19.09 and 11
<i>Publication</i>	RRMAM 2, 1. 540 (notice only)
<i>Description</i>	A simple cylinder. Complete but chipped at the top. Hard, pale limestone. No plinth. Surface and letters: worn and damaged. Letters: some clear, most faint and indistinct but neat, regular in size, shape and alignment; broken-bar A
<i>Dimensions</i>	Ht 1.60; diam. (top) 0.60, (bottom) 0.66. Letters: c. 0.50, (line 1) 0.080

<i>Text</i>	(vac) <b>İmp Caes</b> <b>L Septimius</b> <b>Se[ve]rus Pius P-</b> 4 <b>eṛtinaḫ</b> (leaf) <b>Aug</b> <b>Arab Adiab Parth</b> [max pont max] [trib pot VI imp XI] 8 [cos II p p] <b>procos</b> <b>et Imp Caes [M]</b> [Aurel] <b>Antoni[nus]</b> <b>Aug</b> [ - - - - ] 12 [ - - - - ] [restituerunt] [per C Iulium] [Flaccum] 16 <b>Aelianum</b>
-------------	--

[leg Aug pro pr]  
**LVII vζ'**

*Caput Viae* (Caesaria)  
*Date* AD 197/198(?) L. Septimius Severus and M. Aurelius Antoninus (Caracalla)  
*Augusti* with L. Septimius Geta (names erased) *Caesar*  
*Commentary* The text here can be restored on the basis of numerous, intact examples of the standard text erected along the Caesaria-Melitene road (e.g. 088[B]. Kemer 4) ; accordingly, the date of this milestone has been assigned to AD 198.

#### 074(B). İmirzağa, Eski Harabe Mevkii 2

*Province, Sub-Province + Admin. Code and Map* As 074(A)  
*Location* As 074(A); immediately to N  
*Copy* DHF 08.ix.1977. DHF photo. (Pl. 7.1.42 [p. 386]) in BIA  
*BIA Collections: Squeeze and Photograph*  
 Squeeze: 38. Kayseri 16, İmirzağa, Eski Harabe Mevkii 2  
 Stone: (1) B/W Neg.: DHF R/77/19.10  
*Publication* RRMAM 2, 1. 541  
*Description* A simple cylinder. Complete. Hard, pale limestone. No plinth. Surface and letters: very worn and pitted; some letters are legible  
*Dimensions* Not recorded  
*Text* At least two, perhaps three inscriptions in a jungle of texts:  
**IMP** at the top of the stone (letters: c. 0.065)

The name **Constanti-** can possibly – but not certainly – be isolated

*Date* (1)-(3) (?)

#### 074(C). İmirzağa, Eski Harabe Mevkii 3

*Province, Sub-Province + Admin. Code and Map* As 074(A)  
*Location* Below the ruins of the han; c. 100 m S of 074(A) and (B); buried in the loose earth or wash, on the W side of the şose (and the Roman road).  
*Copy* DHF 31.vii.1978. DHF squeeze in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Photograph*  
 Squeeze: 38. Kayseri 17, İmirzağa, Eski Harabe Mevkii 3  
*Publication* RRMAM 2, 1. 542 (notice only)  
*Description* A simple cylinder. Broken into (at least) 4 pieces (1 large, 1 small and 2 fragments). Hard (very friable), grey limestone. Roughly shaped. Surface: very worn.  
 Letters: worn but some are clear and legible; broken-bar A, (line 11) lunate E  
*Dimensions* Ht 1.97, diam. (top) 0.58. Letters: c. 0.065, (line 1) 0.10, (line 12) 0.08  
*Text* (vac) **Imp**  
**Caesari Mar-**  
**co Antonio**  
 4 **Gordiano pio**  
**felicij Aug**

**restituerunt**  
**per Cuspidium**  
 8 **Flaminium**  
**Severum leg**  
**pro praeto-**  
 (vac) **re μ**  
 12 **νζ'**

Traces of letters (? text [1]) underneath text (2), e.g. (line 3) under IO

line 11: **μ** for **μ**(ἰλῖα), cp. 107(G), 108(D) and 109(C) (Elag.), 119(A) (Sev. Alex.), 068(C), 072(C), 075(C), 080(B), 087(B), 098(D), 104(B) and 108(M) (all Gordianus), 085(B) (Maximinus), 119(B) (Phil.); also 112

*Caput Viae* (Caesaria)  
*Date* AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*  
*Commentary* For the survival of *restituerunt*, see above [p. 12], **Notes and Comments 3.5**  
 Text-form (4).

#### 074(D). İmirzağa, Eski Harabe Mevkii 4

*Province, Sub-Province + Admin. Code and Map* As 074(A)  
*Location* As 074(C)  
*Copy* DHF 31.vii.1978  
*Publication* RRMAM 2, 1. 543  
*Description* A simple cylinder  
*Dimensions* Not recorded  
*Text* No visible inscription

#### 075(A). İmirzağa, Barcın Mevkii 1

*Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0  
*Map* Saimbeyli 90-II  
*Location* *In situ*, on the E side of the Roman road; on the W of the modern şose, c. 1 km SE of the village, together with eight other milestones (Pl. 7.1.43 [p. 387])  
*Copy* DHF 08.ix.1977. DHF squeeze in BIA. Text here from DHF squeeze  
*BIA Collections:* *Squeeze and Photograph*  
 Squeeze: 38. Kayseri 18, İmirzağa, Barcın Mevkii 1  
*Publication* RRMAM 2, 1. 530 (notice only)  
 Baz 2007, 95 no. 48 (notice of RRMAM 2, 1. 530)  
*Description* A simple cylinder. Broken above; the shaft is broken into two pieces. Hard, blue-grey limestone. No plinth. Surface: worn  
 Letters: worn; some indistinct, others clear; neat, regular in shape, size and alignment; broken-bar A  
*Dimensions* Ht (max.) 0.94 (top fragment) + 1.10; diam. (top) 0.60, (bottom) 0.57. Letters: 0.040–60, (line 1) 0.08, (line 18) 0.10  
  
*Text* (vac) **Imp Cae[s]**  
**L Sept[imius]**  
**Severus Pius**

4     **Pertinax** [Aug]  
       **Arab Adiab Part**[h]  
       **max pont.max**  
       **trib·pot·VI·imp** [XI]  
 8     **cos·II·p·p·procos**  
       **et·Imp·Caes**  
       **M·Aurelius**  
       [Antoni]nus [Aug]  
 12    [ - - - - - ]  
       [ - ] restit[u]-  
       **erunt per C**  
       **Iulium Flac-**  
 16    **cum Aelianum**  
       le⟨g⟩ **pr·pr** (leaf)  
       **LIIX vñ'**

*Caput Viae* (Caesaria)  
*Date* AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus  
(Caracalla) *Augusti* with L. Septimius Geta (names erased) *Caesar*

**075(B). İmirzağa, Barcın Mevkii 2**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 075(A)
<i>Location</i>	As 075(A)
<i>Copy</i>	DHF 08.ix.1977. DHF squeeze in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Photograph</i>	Squeeze: 38. Kayseri 19, İmirzağa, Barcın Mevkii 2
<i>Publication</i>	RRMAM 2, 1. 531 (notice only) Baz 2007, 96 no. 50 (notice of RRMAM 2, 1. 531)
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. The shaft tapers sharply towards the top. No plinth. Surface: very worn. Letters: faint, some illegible
<i>Dimensions</i>	Ht 1.91; diam. (top) c. 0.40, (bottom) c. 0.60. Letters: c. 0.060

*Text*

[Imp Caes]  
[Marcus] **Iu**[lius]  
**Philippu**[s pius]  
4 [felix invictu]s  
[A]**ug** [et Marcus Iu]**liu**[s]  
[Philippus n]**obi-**  
[lissimus Caesar]  
8 **vias et** [pontes] **ve-**  
**tusta**[te conlaps]-  
[as] **restitu**[erunt]  
**per An**[tonium Mem]-  
12 [mium Hieronem]  
[leg Aug pr pr]  
[LVIII vñ']

*Caput Viae* [Caesaria]

*Date* AD 244, July/Aug.-247, July/Aug. Philippus *Augustus* with Philippus *Caesar*  
*Commentary* The text can be restored on the basis of the intact example above, 068(D).

### 075(C). İmirzağa, Barcın Mevkii 3

*Province, Sub-Province + Admin. Code and Map* As 075(A)  
*Location* As 075(A)  
*Copy* DHF 08.ix.1977. DHF squeeze in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Photograph*  
 Squeeze: 38. Kayseri 20, İmirzağa, Barcın Mevkii 3  
*Publication* RRMAM 2, 1. 532 (notice only)  
 Baz 2007, 95 no. 49 (notice of RRMAM 2, 1. 532)  
*Description* A simple cylinder with a (?)square plinth. Chipped above left and below left.  
 Hard, pale limestone. Surface: very worn.  
 Letters: worn, some faint and indistinct, but neat and regular in shape, size and alignment  
*Dimensions* Ht (max.) c. 2.05; diam. (top) 0.52; (plinth) ht 0.30, wi. 0.50. Letters: c. 0.07, (line 1) 0.09

*Text*

	<b>Impe[r]</b>	
	<b>Caesar·Mar-</b>	(sic)
	<b>co Antonio</b>	
4	<b>Gordiano</b>	
	<b>pīo felici Au-</b>	
	<b>gusto res-</b>	
	<b>tituerunt</b>	
8	<b>per Cuspidium</b>	
	<b>Flaminium</b>	
	<b>Severum</b>	
	<b>legatum pro</b>	
12	<b>praetore μ</b>	
	[vη']	

line 12: **μ** for **μ**(ἰλῶ), cp. 107(G), 108(D) and 109(C) (Elagabalus), 119(A) (Sev. Alexander), 068(C), 072(C), 074(C), 075(C), 080(B), 087(B), 098(D), 104(B) and 108(M) (all Gordianus), 085(B) (Maximinus), 119(B) (Philippus); also 112

*Caput Viae* [Caesaria]  
*Date* AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*  
*Commentary* For the survival of *restituerunt*, see above [p. 12], **Notes and Comments 3.5**  
 Text-form (4).

### 075(D). İmirzağa, Barcın Mevkii 4

*Province, Sub-Province + Admin. Code and Map* As 075(A)  
*Location* As 075(A)  
*Copy* DHF 08 and 09.ix.1977. DHF squeeze in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Photograph*  
 Squeeze: 38. Kayseri 21, İmirzağa, Barcın Mevkii 4  
*Publication* RRMAM 2, 1. 533 (notice only)

<i>Description</i>	Baz 2007, 96 no. 51 (notice of RRMAM 2, 1. 533) A simple cylinder, with a roughly shaped plinth. Chipped above left and below left, and on plinth. Hard, pale limestone. The shaft tapers slightly towards the top. Surface and letters: very worn. Letters: faint and indistinct
<i>Dimensions</i>	Ht 2.05; diam. (shaft) 0.52. Letters: NH 0.07
<i>Text</i>	c. 11 lines 12 <b>νη´</b>
<i>Caput Viae</i>	(Caesaria)
<i>Date</i>	(?)

**075(E). İmirzağa, Barcın Mevkii 5**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 075(A)
<i>Location</i>	As 075(A)
<i>Copy</i>	DHF 08.ix.1977
<i>Publication</i>	RRMAM 2, 1. 534 (notice only)
<i>Description</i>	A simple cylinder. Hard, pale limestone. The shaft tapers slightly towards the top. No plinth. Worn
<i>Dimensions</i>	Ht (max.) c. 1.85; diam. (top) 0.52, (bottom) 0.67
<i>Text</i>	No visible inscription

**075(F). İmirzağa, Barcın Mevkii 6**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 075(A)
<i>Location</i>	As 075(A)
<i>Copy</i>	DHF 08.ix.1977
<i>Publication</i>	RRMAM 2, 1. 535
<i>Description</i>	A simple cylinder. Broken above. Hard, pale limestone. The shaft tapers slightly towards the top. No plinth. Worn.
<i>Dimensions</i>	Ht (max.) 1.85; diam. (base) 0.65
<i>Text</i>	A few letters survive; below them the distance-figure <b>LIIIX</b>
<i>Caput Viae</i>	(Caesaria)

**075(G). İmirzağa, Barcın Mevkii 7**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 075(A)
<i>Location</i>	As 075(A)
<i>Copy</i>	DHF 08.ix.1977
<i>Publication</i>	RRMAM 2, 1. 536
<i>Description</i>	A simple cylinder. Broken above; one piece joins on side. Hard, pale limestone. The shaft tapers slightly towards the top. No plinth. Worn.
<i>Dimensions</i>	Ht 1.33; diam. (bottom) 0.64
<i>Text</i>	No visible text

**075(H). İmirzağa, Barcın Mevkii 8**

*Province, Sub-Province + Admin. Code and Map* As 075(A)  
*Location* As 075(A)  
*Copy* DHF 08 and 09.ix.1977. DHF squeeze in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Photograph*  
 Squeeze: 38. Kayseri 22, İmirzağa, Barcın Mevkii 8  
*Publication* French 1985b, 150 and n.17 (notice and excerpt from text)  
 RRMAM 2, 1. 538 (notice only)  
*Description* A simple cylinder. Chipped above. Hard, pale limestone. The shaft tapers slightly towards the top. Surface: rough, worn  
 Letters: some worn but most clear and legible; broken-bar A  
*Dimensions* Ht (max.) 2.00; diam. (top) 0.46, (bottom) 0.58. Letters: 0.040-45, (line 11) 0.06

*Text*

	<b>Imp</b> (leaf) <b>Caesar</b>
	<b>M</b> (leaf) <b>Aurelius S-</b>
	<b>everus Alexa-</b>
4	<b>nder puis fe-</b>
	<b>lix Aug trib</b> (leaf)
	<b>potest</b> (leaf) <b>cos</b> (leaf)
	<b>p p</b> (leaf) <b>vias et pon-</b>
8	<b>tes vetustate co-</b>
	<b>nlapsas restitu-</b>
	(vac) <b>it</b> (leaf)
	(vac) <b>νη'</b>

*Caput Viae* (Caesaria)  
*Date* Severus Alexander *Augustus*, AD 222, 14(?).iii-09.xii

### 075(I). İmirzağa, Barcın Mevkii 9

*Province, Sub-Province + Admin. Code and Map* As 075(A)  
*Location* As 075(A)  
*Copy* DHF 08.ix.1977  
*Publication* RRMAM 2, 1. 539  
*Description* A simple cylinder. Broken into two pieces; the top piece is broken above. Hard, pale limestone. The shaft tapers slightly towards the top. No plinth. Worn  
*Dimensions* Ht 1.47; diam. (bottom) 0.48  
*Text* No visible text

### 076. Çakırlar, form. Elemanlı, Barcın Yayla

*Province, Sub-Province + Admin. Code* Adana, Tufanbeyli 01-11-0  
*Map* Saimbeyli 89-Ij  
*Location* (?) *In situ*. In the Barcın Deresi, c. 250 m S of a yayla in a side gully on the E side of the valley; on E side of and below the şose  
*Copy* DHF 31.vii.1978. DHF squeeze and photos (Pl. 7.1.44 [p. 387]) in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Photograph*  
 Squeeze: 01. Adana 25, Elemanlı, Barcın Yaylası  
 Stone: (1) B/W Neg.: DHF R/78/08.04-06

<i>Publication</i>	French 1985b, 150 and n.20 (notice and excerpt from text) RRMAM 2, 1. 015 (notice only)
<i>Description</i>	A simple cylinder. Broken below. Hard, pale limestone. Surface and letters: extremely worn. Letters: faint and indistinct but neat in size, shape and alignment; broken-bar A
<i>Dimensions</i>	Ht 1.67; diam. (top) 0.52. Letters: c. 0.055-60, distance-numerals 0.080

<i>Text</i>	(vac) [Imp] (leaf) <b>Caesar</b> <b>M</b> (leaf) <b>Aurelius S-</b> 4 <b>everus Alexa-</b> <b>nder pius [fe]-</b> <b>lix Aug</b> (leaf) <b>trib</b> <b>potest</b> (leaf) <b>p</b> 8 <b>p</b> (leaf) <b>vias et [pont]-</b> <b>es vetu[state co]-</b> <b>nlapsas [restitu]-</b> (vac) <b>it</b> 12 <b>vθ'</b>
-------------	---

<i>Caput Viae</i>	(Caesaria)
<i>Date</i>	Severus Alexander <i>Augustus</i> , AD 222, 14(?).iii-09.xii

### 077. Çakırlar, form. Elemanlı, Karapınar 1-3

<i>Province, Sub-Province + Admin. Code</i>	Adana, Tufanbeyli 01-11-0
<i>Map</i>	Saimbeyli 89-Ij
<i>Location</i>	c. 5.5 km N of the village, at the point where the track from Çakırlar reaches the floor of the Barcın Dere
<i>Copy</i>	DHF 01.viii.1978
<i>Publication</i>	RRMAM 2, 1. 019
<i>Commentary</i>	There are said to be three (mile)stones buried in the remains of a modern building on the S side of the track (Bağdat yolu) which represents the ancient road.

### 078(A). Çakırlar, form. Elemanlı, Beşiktaş 1

<i>Province, Sub-Province + Admin. Code</i>	Adana, Tufanbeyli 01-11-0
<i>Map</i>	Saimbeyli 89-Ij
<i>Location</i>	<i>In situ</i> . On E edge of the track (the Bağdat yolu) which represents the ancient road; on S of no. 078(B) (Pl. 7.1.45 [p. 387]); c. 4 km NW of the village
<i>Copy</i>	DHF 01.viii.1978. DHF squeeze and photo. in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Photograph</i>	Squeeze: 01. Adana 32, Elemanlı, Beşiktaş 1 Stone: (1) B/W Neg.: DHF R/78/09.01
<i>Publication</i>	RRMAM 2, 1. 016 (notice only)
<i>Description</i>	A simple cylinder. Complete. Hard, pale pink and white limestone. Roughly shaped base. Surface worn. Letters: worn but generally legible; (both texts) broken-bar A
<i>Dimensions</i>	Ht 1.84, diam. (top) 0.49. Letters: (text 1) c. 0.05, (text 2) 0.055-70



<i>Text</i>	(1) (on the full face of the shaft <div style="text-align: center;"> <b>Imp Caes</b>  <b>divi Severi n[ep]</b>  <b>divi M Anto[ni]-</b>  4    <b>ni filius [M Aur]</b>  <b>Antoninus [pius]</b>  <b>f[elix Aug mi]-</b>  <b>l[ia restituta]</b>  8    <b>p[er M Ulp Ofel]-</b>  <b>lium Theod[or]-</b>  <b>um leg Aug</b>  <b>pr pr</b>  12    (vac) ξα´ </div>
	(2) (on the top of text [1], lines 5-8, on right-hand side) <div style="text-align: center;"> <b>Imp Caes</b>  2    <b>Cai</b>  <b>Dioc</b> </div>
<i>Caput Viae</i>	(Caesaria)
<i>Date</i>	(1) Elagabalus <i>Augustus</i> , (?) AD 218, 16.v–(?) mid-June (2) AD 293-305 Diocletianus and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i>
<i>Commentary</i>	For an explanation of seemingly truncated, Tetrarchic texts, see above [p. 14],
<b>Notes and Comments 3.6</b>	

### 078(B). Çakırlar, form. Elemanlı, Beşiktaş 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 078(A)
<i>Location</i>	As 078(A); on N of 078(A) (Pl. 7.1.45 [p. 387])
<i>Copy</i>	DHF 01.viii.1978. DHF squeeze and photo. in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Photograph</i>	Squeeze: 01. Adana 33, Elemanlı, Beşiktaş 2 Stone: (1) B/W Neg.: DHF R/78/09.01
<i>Publication</i>	RRMAM 2, 1. 017 (notice only) Baz 2007, 95 no. 47 (notice of RRMAM 2, 1. 17)
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. Roughly shaped base. The shaft tapers slightly towards the top. Surface: worn Letters: worn but generally clear and legible, neat in size, shape and alignment, cut with a broad-blade chisel
<i>Dimensions</i>	Ht 2.17; diam. (top) 0.42. Letters: 0.070-80, (line 16) 0.140
<i>Text</i>	(1) (on the full face of the shaft) <div style="text-align: center;"> (vac) <b>Imp</b>  <b>Caesar</b>  [M] <b>Iul Philipp-</b>  4    <b>us pius fel</b>  <b>invictus Aug</b> </div>

[et M Iul Phil]-  
**ippus** [nobiliss]imu[s]  
8 **Ca**[esar vias et] **po-**  
**nt**[es vetust]ate  
**conlapsas resti-**  
**tuerunt per An-**  
12 **tonium Memm-**  
**ium Hieronem**  
**v c leg Aug**  
**pr** (vac) **pr**  
16 (vac) ξα'

(2) (on the top of text [1] lines 6-9)

**Gal Val**  
2 **Maximiano**  
**nobil Caes**

line 3: **NOBIL**

*Caput Viae* (Caesaria)  
*Date* (1) AD 244, July/Aug.-247, July/Aug. Philippus *Augustus* [with Philippus  
*Caesar*]  
(2) AD 293-305 Diocletianus and Maximianus *Augusti* with Constantius and  
Galerius *Caesares*  
*Commentary* For an explanation of seemingly truncated, Tetrarchic texts, see above [p. 14],  
**Notes and Comments 3.6.**

### 078(C). Çakırlar, form. Elemanlı, Beşiktaş 3

*Province, Sub-Province + Admin. Code and Map* As 078(A)  
*Location* As 078(A); on W side of the track, opposite 078(A) and (B)  
*Copy* DHF 01.viii.1978. DHF photo. in BIA  
*BIA Collections: Squeeze and Photograph*  
Stone: (1) B/W Neg.: DHF R/78/09.02  
*Publication* RRMAM 2, 1. 018  
*Description* A simple cylinder. Broken above. The shaft tapers slightly towards the top.  
Roughly shaped base. Very worn  
*Dimensions* Ht 1.36; diam. (top) 0.44  
*Text* No visible inscription

### 079(A). Çakırlar, form. Elemanlı, Barcın Geçidi 1

*Province, Sub-Province + Admin. Code* Adana, Tufanbeyli 01-11-0  
*Map* Saimbeyli 89-Ij  
*Location* *In situ* (Pl. 7.1.46 [p. 387]); in the Barcın Geçidi, c. 2 km NW of the village  
*Copy* Harper 1963 (Notes, Şar. 41); DHF 01.viii.1978. DHF squeeze in BIA. Text here  
from DHF squeeze  
*BIA Collections: Squeeze and Photograph*  
Squeeze: 01. Adana 26, Elemanlı, Barcın Geçidi 1  
Stone: (1) B/W Neg.: DHF R/78/08.08

<i>Publication</i>	RRMAM 2, 1. 008 (notice only)
<i>Description</i>	A simple cylinder with a shaped plinth. Complete. Hard, pale limestone. The shaft tapers towards the top. The plinth is square. Surface and letters: extremely worn.
<i>Dimensions</i>	Ht 2.32; diam. (shaft) 0.65; (plinth) ht 0.70, wi. (at front) 0.80. Letters: IMP c. 0.090, distance numerals 0.090-11
<i>Text</i>	<p><b>Imp(?)</b>  -----  uncertain number of lines  -----  <b>LXII ξβ'</b></p>
<i>Caput Viae</i>	(Caesaria)
<i>Date</i>	(?)
<i>Commentary</i>	This milestone is almost certainly the same as the example which was recorded by Harper in 1963 (Harper Notes Şar. no. 41). His Location and Description (except for the height, “c. 2m.”) agree with my own observations. In a reference to this stone Harper (1972, 165) gave the distance-figure as CLXII POB. His notes, however, are clear: the Latin numeral was read by him as LXII. He did not record the Greek number. The Latin numeral was then restored to [C]LXII and transcribed (in error) into Greek POB (for ΠΕΒ).

#### 079(B). Çakırlar, form. Elemanlı, Barcın Geçidi 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 079(A)
<i>Location</i>	<i>In situ</i> (Pl. 7.1.46 [p. 387]); as 079(A)
<i>Copy</i>	DHF 01.viii.1978. DHF squeeze and photo. in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Photograph</i>	<p>Squeeze: 01. Adana 27, Elemanlı, Barcın Geçidi 2  Stone: (1) B/W Neg.: DHF R/78/08.08</p>
<i>Publication</i>	RRMAM 2, 1. 009 (notice only)
<i>Description</i>	A simple cylinder with a shaped plinth. Broken above. Hard, pale limestone. The plinth is roughly shaped. Surface: worn, pitted and damaged Letters: worn and indistinct, variable in size; broken-bar A
<i>Dimensions</i>	Ht 2.05; diam. (top) 0.54. Letters: 0.045-55
<i>Text</i>	<p>(1) erased except for four lines (- lines 3-7) which were retained and became lines 5-9 of text (2); parts of four lines (lines 3-6 of text [1]) were subsequently erased</p> <p>-----  [[ - - - - ]]  2 [[ - - - - ]]  <b>per</b> (leaf) [[ - - - - ]]  4 [[ - - - - ]]  [[ - - - - ]]  6 [[ - - ] (leaf) <b>leg</b> (leaf)  <b>Aug</b> (leaf) <b>pr pr</b> (leaf)  [LXII ξβ']</p>

lines 3-6: **per** (leaf) [[**Liclinnium** (leaf) | **Serenialnum** (leaf)]]

(2) (on the top of the erased part of text [1])

- - - -  
 [ - - - f] **eliç** [ - - - - ]  
 2 [i] **nvicto** (leaf) **Au**[g]  
**pont** (leaf) **m** (leaf) **trib**  
 4 **potest** (leaf) **p** (leaf) **p** (leaf)  
 [[erased line of text (1)]]  
 [[erased line of text (1)]]  
 5 **per** (leaf) [[ - - - - ]]  
 [[ - - - - ]]  
 [[ - - - - ]]  
 8 [[ - - ] (leaf) **leg** (leaf)  
**Aug** (leaf) **pr pr** (leaf)  
 [LXII ξβ']

lines 5-8: **per** (leaf) [[**Liclinnium** (leaf) | **Serenialnum** (leaf)]]

*Caput Viae* [Caesaria]  
*Date* (1) (AD 234-235?) Severus Alexander  
 (2) AD 235(?), [Maximinus] *Augustus*  
*Commentary* For a comment on the significance of the space between lines 4 and 7, see above [p. 11], **Notes and Comments 3.4.**

### 079(C). Çakırlar, form. Elemanlı, Barcın Geçidi 3

*Province, Sub-Province + Admin. Code and Map* As 079(A)  
*Location* As 079(A)  
*Copy* DHF 01.viii.1978. DHF photo. (Pl. 7.1.46 [p. 386]) in BIA  
*BIA Collections: Squeeze and Photograph*  
 Stone: (1) B/W Neg.: DHF R/78/08.08  
*Publication* RRMAM 2, 1. 010  
*Description* A simple cylinder. Broken above, below and at back. Hard, pale limestone.  
 Surface and letters: very worn  
*Dimensions* Ht 1.46; diam. (top) 0.46  
*Text* No visible inscription

### 079(D). Çakırlar, form. Elemanlı, Barcın Geçidi 4

*Province, Sub-Province + Admin. Code and Map* As 079(A)  
*Location* As 079(A)  
*Copy* DHF 01.08.1978. DHF squeeze and photo. in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Photograph*  
 Squeeze: 01. Adana 28, Elemanlı, Barcın Geçidi 4  
 Stone: (1) B/W Neg.: DHF R/78/08.09  
*Publication* RRMAM 2, 1. 011 (notice only)  
*Description* A simple cylinder. Complete. Hard, pale limestone. The shaft tapers towards the

top. No plinth. Surface: worn.  
 Letters: (both texts) worn but clear and legible; variable in size  
*Dimensions* Ht 1.90; diam. (bottom) 0.55. Letters: (text 1) 0.055-95, (line 10) 0.090, (text 2) c. 0.050

*Text* (1) (on the full face of the shaft)  
 (vac) **Imp**  
**Caesar Marco** (sic)  
**Antonio Gordia-**  
 4 **no pi**[o felici Au]-  
**gust**[us restitue]er-  
 [unt per] **Cuspidi** (sic)  
**Flaminium Sev-**  
 8 **erum lega**(tum) **pro pra-**  
**etore m**  
 (vac) **LXII** ξβ´

line 9: **m** for **milia**, cp. 056(B) (Sept. Sev.), 065 (Elag. + Sev. Alex.), 084, 089(B), 093(H), 095 and 097(C) (all Gordianus), 115 (Probus); also 104(J), 108(F), 114

(2) (over the top of lines 4-6 of text [1])

**Imp Caess**  
 2 **Marco Aur Va**[1]  
 [[ - - - - - ] **p f**  
 4 **invicto Aug**

line 3: [[Maximiano]]

*Caput Viae* (Caesaria)

*Date* (1) AD 238, 09.v(?) - 09.xii (?), Gordianus *Augustus*  
 (2) AD 293-305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*

*Commentary* (Text 1) For the survival of *restituunt*, see above [p. 12], **Notes and Comments 3.5** Text-form (4).

(Text 2) For an explanation of seemingly truncated, Tetrarchic texts, see above [p. 14], **Notes and Comments 3.6**.

### 079(E). Çakırlar, form. Elemanlı, Barcın Geçidi 5

*Province, Sub-Province + Admin. Code and Map* As 079(A)

*Location* As 079(A)

*Copy* DHF 01.viii.1978. DHF squeeze and photo. in BIA. Text here from DHF squeeze

*BIA Collections: Squeeze and Photograph*

Squeeze: 01. Adana 29, Elemanlı, Barcın Geçidi 5

Stone: (1) B/W Neg.: DHF R/78/08.10

*Publication* RRMAM 2, 1. 012 (notice only)

*Description* A simple cylinder. Broken above. Hard, grey limestone. No plinth. Surface: very worn

Letters: worn and indistinct; broken-bar A

<i>Dimensions</i>	Ht 1.56; diam. (top) 0.49. Letters: 0.060-70
<i>Text</i>	(vac) [Imp]
2	(vac) <b>Caes</b>
	[C] <b>Iulio</b> (leaf) <b>Vero</b> (leaf)
4	<b>Maximino</b> (leaf) <b>pio</b> (leaf) <b>felici</b> (leaf)
	<b>invicto</b> (v) <b>Aug</b> (leaf) <b>pont</b> (leaf) <b>m</b> (leaf)
6	<b>trib</b> (v) <b>potest</b> (leaf) <b>p</b> (leaf) <b>p</b> (leaf)
	[[ - - - - - ]]
8	[[ - - - - - ]]
	<b>leg</b> (leaf) <b>Aug</b> (leaf) <b>pr pr</b> (leaf)
10	ξβ'

Note: ll. 6-10 are extremely faint

lines 7-8: [[ per (leaf) Liclinnum (leaf) | Serenialnum (leaf) ]]

<i>Caput Viae</i>	[Caesaria]
<i>Date</i>	AD 235, Feb./March-236, 07.1/16.v Maximinus <i>Augustus</i>
<i>Commentary</i>	Note that one text (079[B]) of Maximinus already exists in the group of milestones at Barçın Geçidi. Is this milestone, therefore, a later version?

#### 079(F). Çakırlar, form. Elemanlı, Barçın Geçidi 6

<i>Province, Sub-Province + Admin. Code and Map</i>	As 079(A)
<i>Location</i>	As 079(A)
<i>Copy</i>	DHF 01.viii.1978. DHF photo. in BIA
<i>BIA Collections: Squeeze and Photograph</i>	Stone: (1) B/W Neg.: DHF R/78/08.11
<i>Publication</i>	RRMAM 2, 1. 013
<i>Description</i>	A simple cylinder. Broken above. Hard, pale limestone. No plinth. Surface and letters: very worn
<i>Dimensions</i>	Ht 1.39; diam. (bottom) 0.64
<i>Text</i>	No visible inscription

#### 079(G). Çakırlar, form. Elemanlı, Barçın Geçidi 7

<i>Province, Sub-Province + Admin. Code and Map</i>	As 079(A)
<i>Location</i>	As 079(A)
<i>Copy</i>	DHF 01.viii.1978. DHF photo. in BIA
<i>BIA Collections: Squeeze and Photograph</i>	Stone: (1) B/W Neg.: DHF R/78/08.12
<i>Publication</i>	RRMAM 2, 1. 014
<i>Description</i>	A simple cylinder. Broken above, chipped at bottom. Hard, pale limestone. No plinth.
<i>Dimensions</i>	Ht 1.43; diam. (bottom) 0.59
<i>Text</i>	No visible inscription

#### 080(A). Çakırlar, form. Elemanlı, Meşelik 1

<i>Province, Sub-Province + Admin. Code</i>	Adana, Tufanbeyli 01-11-0
<i>Map</i>	Saimbeyli 89-Ij

<i>Location</i>	<i>In situ</i> , beside the track which follows the line of the Roman road, on the S side of the road; c. 0.9 km NNW of the village cami
<i>Copy</i>	DHF 02.viii.1978. DHF squeeze and photo. (Pl. 7.1.47 [p. 388]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i> Squeeze: 01. Adana 30, Elemanlı, Meşelik 1 Stone: (1) B/W Neg.: DHF R/78/09.03
<i>Publication</i>	RRMAM 2, 1. 020 (notice only) Baz 2007, 94 no. 44 (notice of RRMAM 2, 1. 20)
<i>Description</i>	A simple cylinder. Broken above, below and on right. Now in three joining pieces (one large, two small, on one of which is the distance-figure) plus one non-joining fragment. Hard, pale limestone. Surface: worn Letters: worn but generally legible; broken-bar A
<i>Dimensions</i>	Ht (max. ex.) 1.09; diam. (shaft) 0.51. Letters: 0.060-80, (line 7) numerals 0.13
<i>Text</i>	<div style="text-align: center;"> <p>-----</p> <p>2    [A]ntoniu[m]       [Me]mmium</p> <p>4    <b>Ḥiẹronem·v c</b>       <b>leg Aug</b></p> <p>6    <b>pr pr</b>       (vac) ξγ'</p> </div>
<i>Caput Viae</i>	(Caesaria)
<i>Date</i>	(?) Philippus <i>Augustus</i> with Philippus <i>Caesar</i> , AD 244, on the basis of the governor's name, cp. above, the text of 068(D)

### 080(B). Çakırlar, form. Elemanlı, Meşelik 2

<i>Province, Sub-Province + Admin. Code and Map</i>	As 080(A)
<i>Location</i>	As 080(A)
<i>Copy</i>	DHF 02.viii.1978. DHF squeeze and photo. (Pl. 7.1.48 [p. 388]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i> Squeeze: 01. Adana 31, Elemanlı, Meşelik 2 Stone: (1) B/W Neg.: DHF R/78/09.04-05
<i>Publication</i>	RRMAM 2, 1. 021 (notice only) Baz 2007, 94 no. 43 (notice of RRMAM 2, 1. 21)
<i>Description</i>	A simple cylinder. Broken at top; now in two pieces. Hard, pale limestone. The shaft tapers slightly towards the top. No plinth. Surface: worn. Letters: some wear but generally clear and legible, neat in size, shape and alignment; broken-bar A
<i>Dimensions</i>	Ht 1.83; diam. (bottom) c. 0.75. Letters: 0.060-70
<i>Text</i>	<div style="text-align: center;"> <p>[Imp] [Caesari Mar]- [co Antonio]</p> <p>4    <b>Gorḍi</b>[ano pio]       <b>felici</b> [Aug]       <b>restitu</b>[erunt]</p> </div>

8      **per Cuspid[ium]**  
**Flaminium**  
**Severum leg pro**  
**prætoroe μ** (sic)  
(gap 0.34)  
(vac) ξγ'

line 10: μ for μ(ῖλῖα), cp. 107(G), 108(D) and 109(C) (Elagabalus), 119(A) (Sev. Alexander), 068(C), 072(C), 074(C), 075(C), 087(B), 098(D), 103(C), 104(B) and 108(M) (all Gordianus), 085(B) (Maximinus), 119(B) (Philippus); also 112

*Caput Viae* (Caesaria)  
*Date* AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*  
*Commentary* For the survival of *restituerunt*, see above [p. 11], **Notes and Comments 3.4**  
*Text-form* (4).

#### 080(C). Çakırlar, form. Elemanlı, Meşelik 3

*Province, Sub-Province + Admin. Code and Map* As 080(A)  
*Location* As 080(A). The stone was not dug out (Pl. 7.1.49 [p. 388])  
*Copy* DHF 02.viii.1978. DHF photo. in BIA  
*BIA Collections: Squeeze and Photograph*  
Stone: (1) B/W Neg.: DHF R/78/09.06  
*Publication* RRMAM 2, 1. 022  
Baz 2007, 94 no. 45 (notice of RRMAM 2, 1. 22)  
*Description* A simple cylinder. Broken above. Hard, pale limestone  
*Dimensions* Ht 1.82, diam. (shaft) 0.53  
*Text* The inscription lay concealed

#### 080(D). Çakırlar, form. Elemanlı, Meşelik 4

*Province, Sub-Province + Admin. Code and Map* As 080(A)  
*Location* As 080(A) but lying on the hill-side 25 m below the others  
*Publication* RRMAM 2, 1. 023 (notice only)  
Baz 2007, 94 no. 46 (notice of RRMAM 2, 1. 23)  
*Copy* DHF 17.viii.1978. Text here from DHF notes  
*Description* A simple cylinder. Complete; chipped at the top. Hard, pale limestone. The shaft tapers slightly. There is a roughly shaped base or plinth. Surface: worn.  
Letters: worn; cut with a broad-blade chisel (breadth c. 0.060), broken-bar A  
*Dimensions* Ht 1.80, diam. (top) 0.43, (base) 0.54. Letters: c. 045

*Text*

	----
2	[ ---- ]IN
	[ ---- ]PAR
4	[ ---- ]
	[ ---- ]OMA
6	<b>Imp Caes</b>
	----
	(vac)
8	ξγ'



*Caput Viae* (Caesaria)  
*Date* (?) Severan

### 080(E). Çakırlar, form. Elemanlı, Meşelik 5

*Province, Sub-Province + Admin. Code and Map* As 080(A)  
*Location* As 080(D)  
*Copy* DHF 17.viii.1978. Text here from DHF notes  
*Publication* RRMAM 2, 1. 024 (notice only)  
 Baz 2007, 93 no. 42 (notice of RRMAM 2, 1. 24)  
*Description* A simple cylinder. Chipped and broken at the top, complete below. Hard but friable, pale limestone. The shaft tapers slightly towards the top. The top is flat. No plinth. Surface: worn  
 Letters: worn, variable in size, shape and alignment, broken-bar A  
*Dimensions* Ht 1.75, diam. (top) c. 0.57, (bottom) 0.61. Letters: 0.045-60

*Text*

[Imp Ca]eş  
 [divi Sev]eři nep  
 [divi M] Antonini fi!  
 4 [M Au]r Anton[ino p]  
 [fe]liçi Aug milia  
 [restit]uta per M Ulp  
 Theo[d]orum leğ  
 8 Aug<sup>(v)</sup> pr pr  
 (gap c. 0.30)  
 ξγ´

*Caput Viae* (Caesaria)  
*Date* Elagabalus *Augustus*, (?) AD 218, 16.v–mid-June(?)

### 081. Çakırlar, form. Elemanlı

In the Interim Catalogue (RRMAM 2, 1. 007) this milestone was listed separately: it is here identified as 077(A), above.

### 082. Şar 1

*Province, Sub-Province + Admin. Code* Adana, Tufanbeyli 01-11-0  
*Map* Saimbeyli 90-Ij  
*Location* *In situ*, lying on the S side of the Roman road and the track from Çakırlar to Şar; c. 2 km NNW of the village  
*Copy* DHF 03.08.1978  
*Publication* RRMAM 2, 1. 029  
 Baz 2007, 93 no. 41 (notice of RRMAM 2, 1. 29)  
*Description* A simple cylinder  
*Dimensions* Not recorded

*Text* No visible inscription; the distance-figure can be restored as [ξδ´]. In error the distance-figure was restored as [vδ´] in RRMAM 2, 1. 029

## 083. Şar 2

<i>Province, Sub-Province + Admin. Code and Map</i>	Adana, Tufanbeyli 01-11-0
<i>Map</i>	Saimbeyli 90-Ij
<i>Location</i>	In the village; built into the SE wall of the house owned by Halit Şahin and facing onto the road
<i>Copy</i>	Clayton 1881; Ramsay with Wilson 1882 (a printed version of Ramsay's copy from Sterrett [1883-84], Fig. 6.1.13 [p. 329]); Harper 1963 (Notes, Şar 39); DHF 03.viii.1978. Harper and DHF squeezes in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i> Squeeze: 01. Adana 48 (RPH), 49 (DHF), Şar 2 Stone: (1) B/W Neg.: DHF R/78/09.12 (2) Col. Slide: DHF 173.29
<i>Publication</i>	Carolides 1882, 67 and drawing Waddington 1883, 140 no. 27 (Clayton text of 1881 and Ramsay text of 1882) Mommsen 1884a, 36 no. 75 (Ramsay text of 1882 <i>apud</i> Waddington) Sterrett 1883-84, 297 no. 348 (Ramsay text of 1882) (facsimile, Fig. 6.1.013 [p. 329]) CIL 3. 6951 (text of Sterrett) CIL 3. 12209 (notice of Carolides 1882) Ramsay 1941, 110 no. 94 (Ramsay text of 1882) Harper 1972, 164 RRMAM 2, 1. 028 (notice only) Baz 2007, 91 no. 40 (text from publications, with commentary) French 2008, 131 (text and comments)
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. The shaft tapers slightly towards the top. The inscribed face is flat. The surface is worn, especially at the top.
<i>Dimensions</i>	Letters: sharp and clear, regular in size, shape and alignment Ht 1.54, wi. (inscribed face) 0.51. Letters: c. 0.050, (line 8) O 0.040, (line 13) c. 0.070-85
<i>Text</i>	(1) erased (and the surface finely smoothed) except for five lines (- lines 10-14 of text [2]) which were retained for text (2); parts (- lines 10-11 of text [2]) of these five lines were subsequently erased  (2) (on the top of the erased part of text [1]) [Imp] [Caes C] I[uli]o (leaf) Ve- 4 ro (leaf) [M]aximino (leaf) pio (leaf) felici (leaf) [i]nvicto (leaf) A[ug] (leaf) p (leaf) m (leaf) trib 8 (leaf) potest (leaf) p p [[ - - - - ]] per [[ - - - - ]] [[ - - - - ]] 12 leg Aug pr pr

**m p · CLVII**(vac) **qvζ'**lines 10-11 : **per** [[[Licinnium | Serenianum]]]*Caput Viae* (Melitena)*Date* (1) (?AD 234-235) Severus Alexander *Augustus*(2) AD 235, ii/iii-236, 07.i/16.v Maximinus *Augustus**Commentary* For the possible, historical significance of the vacant, erased line between lines 8 and 10, see above [p. 11], **Notes and Comments 3.4.**(Text 2) The dates for Maximinus *Augustus* without Maximus *Caesar* are given by Kienast (1996, 183-185).**084. Mollahüseyin 4***Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0*Map* Saimbeyli 90-Ij*Location* *In situ*, beside the Roman road; in the field of İsmail Yıldız; the *şose* (village-road) (to Şar) at this point runs beside and N of the Roman road (the 'Bağdat Yolu'); c. 350 m SSW of the village, exactly at the point where the *şose* leaves the "Bağdat Yolu".*Copy* Harper 1963 (Notes, Şar 32); DHF 15.vi.1977. DHF squeeze and photo. (Pl. 7.1.50 [p. 388]) in BIA. Text here from DHF squeeze*BIA Collections:* *Squeeze and Photograph*

Squeeze: 38. Kayseri 24, Mollahüseyin 4

Stone: (1) B/W Neg.: DHF R/77/06.10

(2) Col. Slide: DHF 156.03

*Publication* Harper 1972, 164 (notice only)

RRMAM 2, 1. 562 (notice only)

Baz 2007, 91 no. 39 (notice of Harper 1972 and RRMAM 2, 1. 562)

*Description* A simple cylinder. Broken below. Hard, pale limestone. (?)The top is rounded. Surface: worn but letters clear and legible.

Letters: cut with a broad-blade chisel (breadth 0.005); regular in shape, size and alignment; A without bar, Δ for D, lunate E, U for V

*Dimensions* Ht 1.75; diam. (top) 0.43, (bottom) 0.63. Letters: 0.06-07, (line 11) 0.07-09*Text***Imper****[Ca]esar Mar[co]**

(sic)

**Antonio Go-**

4

**rdiano pio fe-  
lici Augusto re-  
stituerunt**

8

**per Cuspidium Fla-  
minium Severum le-  
gatum pro pra-  
etore m**

(vac 25 cm)

**CLIII qvγ'**

line 2: possible earlier letters

line 7: **Δ** for **D**

line 10: **m** for **m**(ilia), cp. 056(B) (Sept. Severus), 065 (Elag. + Sev. Alex.), 079(D), 089(B), 093(H), 095 and 097(C) (all Gordianus), 115 (Probus); also 104(J), 108(F), 114

*Caput Viae* (Melitena)

*Date* AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*

*Commentary* Harper (Notes) indicates that in 1963 there were three stones at this point: I saw only one.

For the survival of *restituerunt*, see above [p. 12], **Notes and Comments 3.5** Text-form (4).

### 085(A). Mollahüseyin 1

*Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0

*Map* Saimbeyli 90-Ij

*Location* In the village; “dans la même maison” (- 085[B]) (Waddington); “. . . inside a house forming the posts on each side of the fireplace” (Hogarth and Munro); a milestone (here 085[B]) “. . . in village lying outside house. Said to have been found in digging foundations of the house and another” (here - 085[A]) “left in” (Harper, Notes 2. 11). Present whereabouts not established (DHF visit 15.vi.1977)

*Copy* Ramsay with Wilson 1882. The stone has not been examined by DHF. Text here of Ramsay *apud* Waddington 1883

*Publication* Waddington 1883, 141 no. 29 (Ramsay text of 1882)  
 Mommsen 1884a, 36 no. 73 (text of Ramsay *apud* Waddington)  
 CIL 3. 6950 (text of Ramsay *apud* Waddington)  
 Hogarth and Munro 1893, 690 “153 ?(ii)” (notice)  
 CIL 3. 12208 (note on l. 6)  
 Ramsay 1941, 109 no. 91 (Ramsay text of 1882)  
 RRMAM 2, 1. 559 (notice only)  
 Baz 2007, 90 no. 37 (text from publications, with commentary)

*Description & Dimensions* Not given

*Text*

	<b>Imp Caes L Septimius</b>	
	<b>Severus Pius Per-</b>	
	<b>tinax Aug Arab</b>	
4	<b>Adiab Parth max</b>	
	<b>pontif max trib pot III</b>	(sic)
	<b>imp XI cos III p p</b>	(sic)
	<b>procos et Imp Caes</b>	
8	<b>M Aurel Antoninus</b>	
	[[Aug et L Septim Geta]]	
	<b>Caesa⟨r⟩ resti-</b>	
	<b>tuerunt per C Iul[ium]</b>	
12	<b>Flaccum Aelianum</b>	
	<b>leg pr pr</b>	
	[ - ]	

line 5 : trib pot III (Ramsay), trib pot VI (DHF)

line 6 : cos III (Ramsay); cos II (DHF)

*Caput Viae* [Melitena]  
*Date* “Date 202(!): other mil. date 198” (Ramsay); AD 197/198, 10.xii-09.xii  
 L. Septimius Severus and M. Aurelius Antoninus (Caracalla) *Augusti* with  
 L. Septimius Geta (names erased) *Caesar*

## 085(B). Mollahüseyin 2

*Province, Sub-Province + Admin. Code and Map* As 085(A)  
*Location* “Dans une maison à 5 milles anglais au N.E. de Char” (Waddington); “inside a house, forming the posts on either side of the fireplace” (Hogarth and Munro). In the village; used as a gate-post on the left of the entrance to a garden, opposite the house (no. 14) owned by Osman Yıldız  
*Copy* Ramsay with Wilson 1882 (a printed version of Ramsay’s copy from Sterrett [1883-84], Fig. 6.1.14 [p. 329]); Harper 1963 (Notes, 2.11); DHF 15.vi.1977. DHF squeeze and photo. (Pl. 7.1.51 [p. 389]) in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Photograph*  
 Squeeze: 38. Kayseri 23, Mollahüseyin 2  
 Stone: (1) B/W Neg.: DHF R/77/06.11  
 (2) Col. Slide: DHF 156.04-05  
*Publication* Waddington 1883, 140 no. 28 (Ramsay text of 1882)  
 Ramsay 1883, 328 (comment on text of 1882)  
 Mommsen 1884a, 37 no. 76 (text of Ramsay *apud* Waddington)  
 Sterrett 1883-84, 297 no. 349 (Ramsay text of 1882) (facsimile, Fig. 6.1.12 [p. 328])  
 CIL 3. 6952 (text of Sterrett)  
 Hogarth and Munro 1893, 690 “153 (i)” (notice)  
 CIL 3. 12208 (notice of Hogarth and Munro)  
 Ramsay 1941, 109 no. 90 (Ramsay text of 1882)  
 Harper 1972, 164 (notice only)  
 RRMAM 2, 1. 560 (notice only)  
 Baz 2007, 88 no. 36 (text from publications, with commentary)  
*Description* A simple cylinder. Broken above. Hard, pale limestone. Surface: rough; traces of small-toothed chisel.  
 Letters: worn but mostly clear and sharp; neat in shape, size and alignment; broken-bar A  
*Dimensions* Ht (vis.) 1.47; diam. (top) 0.47. Letters: c. 0.08 but (line 7) I in TRIB 0.06, (line 13) 0.09  
*Text* (1) erased except for four lines (lines 10-14 of text [2]) which were retained for text (2); parts (lines 10-11 of text [2]) of these four lines were subsequently erased. Traces of letters visible underneath l. 13 of text (2)  
 (2) (on the top of the erased part of text [1])  
 (vac) [Imp]  
 [Ca]eş (leaf) G (leaf)  
 [I]ulio (leaf) Vero  
 4 Maximino (leaf)  
 pio (leaf) felici (leaf)  
 invicto (leaf) Aug

(leaf) **p** (leaf) **m** (leaf) **trib** (leaf)  
 8 **potest** (leaf) **p p**  
 [ - - - - ]  
**per** [ - - - - ]  
 [ - - - - ]  
 12 **leg Aug pr pr**  
**μ q** (vac) **ve'**

lines 10-11 : **per** [[Licinnium | Serenianum]]

line 13 : **M.PNT** (Ramsay copy of 1882 [Waddington 1883], and 1941; Sterrett), **MP NE** (DHF); **μ** for **μ(ιλια)**, cp. 107(G), 108(D) and 109(C) (Elag.), 119(A) (Sev. Alex.), 068(C), 072(C), 074(C), 075(C), 080(B), 087(B), 098(D), 103(C), 104(B) and 108(M) (all Gordianus), 119(B) (Philippus); also 112

*Caput Viae* (Melitena)

*Date* (1) (AD 234-235 ?) Severus Alexander *Augustus*  
 (2) AD 235, ii/iii-236, 07.i/16.v Maximinus *Augustus*

*Commentary* (Text 2) For the possible, historical significance of the vacant, erased line between lines 8 and 10, see above [p. 11], **Notes and Comments 3.4**.

The dates for Maximinus *Augustus* without Maximus *Caesar* are given by Kienast (1996, 183-185).

### 085(C). Mollahüseyin 3

*Province, Sub-Province + Admin. Code and Map* As 085(A)

*Location* “ . . . . , dans un champ, à un demi-mille anglais des deux inscriptions precedents” (- nos 085[A] and [B]) (Waddington). Present whereabouts not established (DHF visit 15.vi.1977)

*Copy* Ramsay with Wilson 1882 (a printed version of Ramsay’s copy from Sterrett 1883-84], Fig. 6.1.15 [p. 330]); Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Ramsay *apud* Waddington 1883

*Publication* Waddington 1883, 142 no. 30 (Ramsay text of 1882)  
 Sterrett 1883-84, 294 nos 346-347 (facsimile, Fig. 6.1.015 [p. 330])  
 Mommsen 1884a, 38 no. 79 (Ramsay text of 1882 *apud* Waddington)  
 Mommsen 1884b, 584 no. 1366 (addition to Ramsay text of 1882 *apud* Waddington, from Ramsay)

CIL 3. 6955 (text of Sterrett)

Hogarth and Munro 1893, 690 “152 (i)” (notice)

CIL 3. 12212 (text from Hogarth and Munro)

Ramsay 1941, 110 no. 93 (Ramsay text of 1882)

RRMAM 2, 1. 561 (notice only)

Baz 2007, 86 no. 35 (text from publications, with commentary)

*Description* “Sur une colonne, ....; lettres très frustes” (Waddington)

*Dimensions* Not given

*Text* (1) - - - -  
**vias et pontes**  
**vetustate**  
 4 **conlapsas**  
**restituerunt**

per Antonium  
 Memmium  
 8 Hieronem v c leg  
 Aug pr pr  
 ovß'

(2) Gal Val  
 Maximiano  
 [n]obil C[aess]

*Caput Viae* (Melitena)

*Date* (1) (?) Philippus *Augustus* with Philippus *Caesar* AD 244, on the basis of the governor's name; cp. above, the text of 068(D)

(2) AD 293-305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*

*Commentary* For an explanation of seemingly truncated, Tetrarchic texts, see above [p. 14],  
**Notes and Comments 3.6.**

### 085(D). Mollahüseyin 5

*Province, Sub-Province + Admin. Code and Map* As 085(A)

*Location* In the village, at the house (no. 26) of Hasan Yıldız; used as the support for a column at the SE corner of the house, beside the closet.

*Copy* Harper 1964 (Notes 64/66); DHF 15.vi.1977. DHF photo. (Pl. 7.1.52 [p. 389]) in BIA. Text here from RPH and DHF notes

*BIA Collections: Squeeze and Photograph*

Stone: (1) B/W Neg.: DHF R/77/06.12

(2) Col. Slide: DHF 156.08-09

*Publication* RRMAM 2, 1. 563 (notice only)

Baz 2007, 91 no. 38 (notice of RRMAM 2, 1. 563)

*Description* A simple cylinder. (?) Complete. Hard, pale limestone. Surface: some wear. Letters: clear and sharp, neat in shape, size and alignment; cut with a broad-blade chisel (0.005); broken-bar A

*Dimensions* Ht (vis.) 1.48; diam. (top) 0.50. Letters: 0.060-70 but (line 1) 0.09, (line 11) 0.08

*Text*

(vac) **Imp**  
**Caesar G Iul**  
**Verus Maximinus**  
 4 **p̄ius f[elix inv]i̇ctus**  
**Aug et Ḡ Iul̄ius Verus**  
**[Ma]xi̇mus nobilis-**  
**simus Caesar vias**  
 8 **et pontes vetusta-**  
**te conlabsas res-** (sic)  
**[tit]uerunt**  
**per [ - - - ]**  
 12 **[ - - - ]**  
**[leg] Auḡg pr pr** (sic)  
**[ - ]**

lines 11-12: **per** [[Licinnium | Serenianum]], cp. the intact text of Maximinus with Maximus *Caesar*, at Çomar on the territory of Tavium (RRMAM 3.2 [Galatia]. 057)

*Caput Viae* [Melitena]  
*Date* AD 236, 07.i/16.v-238, mid-April(?) Maximinus *Augustus* with Maximus *Caesar*.  
*Commentary* The dates for Maximinus *Augustus* with Maximus *Caesar* are given by Kienast (1996, 183-185).

### 085(E). Mollahüseyin 6

*Province, Sub-Province + Admin. Code and Map* As 085(A)  
*Location* In the village, at the house of the *muhtar*, Mehmet Karakuş, on the northern, or street, side of the house  
*Copy* DHF 15.vi.1977  
*Publication* RRMAM 2, 1. 564  
*Description* A simple cylinder  
*Dimensions* Not recorded  
*Text* No visible inscription

### 086(A). Kemer 13

*Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0  
*Map* Elbistan 91-Ij  
*Location* *In situ*(?), lying beside and S of the şose between Kemer and Mollahüseyin, on S side of the Roman road; c. 2.50 km (on the şose) W of Kemer and c. 1.30 km E of Mollahüseyin  
*Copy* DHF 15.vi.1977. DHF squeeze and photo. in BIA. Text here from DHF squeeze  
*BIA Collections:* *Squeeze and Photograph*  
 Squeeze: 38. Kayseri 29, Kemer 13  
 Stone: (1) B/W Neg.: DHF R/77/06.02  
*Publication* RRMAM 2, 1. 557 (notice only)  
 Baz 2007, 85 no. 33 (notice of RRMAM 2, 1. 557)  
*Description* A simple cylinder. Probably broken. Limestone. Surface: worn. Letters: worn and faint  
*Dimensions* Ht 1.16; diam. (as visible) 0.55. Letters: 0.060-70

*Text*

	(vac) [Imp]
	[Caes G]
	[Iulio Vero]
4	[Maximino]
	[pio felici]
	<b>in</b> [victo Aug]
	<b>p</b> (leaf) <b>m</b> [trib]
8	<b>p p</b> [ - - - - ]
	<b>per</b> [[Licinnium]]
	[[Serenianum]]
	<b>leg</b> [Aug pr pr]
12	(vac) <b>qvβ'</b>



*Caput Viae* (Melitena)  
*Date* AD 235, ii/iii-236, 07.i/16.v Maximinus *Augustus*, on the basis of the governor's name  
*Commentary* The name of the governor in lines 9-10 and the imperial titles in the preceding lines have been restored on the basis of the near-intact texts found on two milestones (of Maximinus) erected along the Caesaria-Melitena road: 085(B). Mollahüseyn 2 and 098(B). Keklikoluk 2.  
 There is no evidence of an erasure (for the significance of an erasure on milestones of Maximinus, see the discussion above [p. 11], **Notes and Comments 3.4**.  
 The emperor stands alone, i.e. without Maximus *Caesar*. The dates for Maximinus *Augustus* without Maximus *Caesar* are given by Kienast (1996, 183-185).

**086(B). Kemer 14**

*Province, Sub-Province + Admin. Code and Map* As 086(A)  
*Location* As 086(A)  
*Copy* DHF 15.vi.1977  
*Publication* RRMAM 2, 1. 558 (notice only)  
*Description* A simple cylinder, with a roughly shaped plinth. (?)Complete. Limestone  
*Dimensions* Ht 1.76; diam. 0.50; (plinth) ht c. 0.90  
*Text* No visible inscription

**087(A). Kemer 1**

*Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0  
*Map* Elbistan 91-Ij  
*Location* "In the cemetery at Kemer; formerly one mile away in situ by the Shahr road, where R(amsay) copied it in 1882" (Hogarth and Munro). Present whereabouts not established (DHF visit 15.vi.1977)  
*Copy* Ramsay with Wilson 1882; Ramsay 1890. The stone has not been examined by DHF. Text here of Ramsay 1890 *apud* Hogarth and Munro (the printed version of Ramsay's text given by Hogarth and Munro, Fig. 6.1.16 [p. 330])  
*Publication* Waddington 1883, 143 no. 31 (Ramsay text in 1882)  
 Mommsen 1884a, 38 no. 78 (text of Ramsay *apud* Waddington)  
 CIL 3. 6954 (text of Ramsay *apud* Waddington)  
 Hogarth and Munro 1893, 691 "152 (ii)" (Ramsay text in 1890) (facsimile, Fig. 6.1.16 [p. 330])  
 CIL 3. 12211 (Ramsay text in 1890 *apud* Hogarth and Munro)  
 French 1980, 724 no. 27 (text from CIL 3. 12211)  
 French 1985b, 150 and n.18 (excerpt from text of CIL 3. 12211, and emendation)  
 RRMAM 2, 1. 545 (notice only)  
 Baz 2007, 83 no. 32 (text from publications, with commentary)  
*Description & Dimensions* Not given  
*Text*

**Imp Caes-**  
**a[r] M Aur-**  
**elius Sever[us]**  
 4 **Alexand-**  
**er pius felix**  
**Aug** (leaf) **trib** (?leaf) [po]-

8                    **test** (leaf) **cos** (leaf) **p p**  
                       (leaf) **via[s]** **et po-**  
                          [n] **tes vetosta-** (sic)  
                          **te conlapsa-**  
                          **s restitu**(i)t  
 12                   **qvβ´**

line 7: “the restoration in line 8 [procos] (in CIL 3. 12211 and French 1980) should be discarded for lack of space on the stone; the space preceding **via[s]** was probably occupied by a leaf” (French 1985b, 150 n.18)

*Caput Viae* (Melitena)

*Date* Severus Alexander *Augustus*, AD 222, 14(?).iii-09.xii

## 087(B). Kemer 2

*Province, Sub-Province + Admin. Code and Map* As 087(A)

*Location* “In situ one mile from Kemer, on the road to Shahr” (Hogarth and Munro); “between the Avshahr village and Comana; found along with no. 93” (- here 085[C]) (Ramsay 1941); “Kemer in cemetery wall . . . . Now moved from previously recorded site 1/2 mile from (Mollahüseyinlerköyü)” (Harper, Notes 2. 10). Present whereabouts not established (DHF visit 15.vi.1977)

*Copy* Ramsay with Wilson 1882; Ramsay 1890; Hogarth and Munro 1891; Harper 1963 (Notes 2. 10). The stone has not been examined by DHF. Text here of Ramsay 1890 *apud* Hogarth and Munro (the printed version of Ramsay’s text given by Hogarth and Munro, Fig. 6.1.17 [p. 330])

*Publication* Waddington 1883, 144 no. 32 (Ramsay text of 1882)  
 Mommsen 1884a, 37 no. 77 (Ramsay text of 1882 *apud* Waddington)  
 CIL 3. 6953 (Ramsay text of 1882 *apud* Waddington)  
 Hogarth and Munro 1893, 691 “152 (iii)” (Ramsay text of 1890) (facsimile, Fig. 6.1.17 [p. 330])  
 CIL 3. 12210 (Ramsay text of 1890 *apud* Hogarth and Munro)  
 Ramsay 1941, 109 no. 92 (Ramsay text of 1882)  
 RRMAM 2, 1. 546 (notice only)  
 Petolescu 1991, 203 (comment on governor)  
 Baz 2007, 85 no. 34 (text from publications, with commentary)

*Description & Dimensions* Not given

*Text* (1) and (2)

(vac) **Imp**  
**Caesar**  
 4 [ - - - - - ]  
 [ - - - - - ]  
 [ - - - - - ]  
 [ - - - - - ]  
 [ - - - - - ]  
 8 [ - - - - - ]  
**M Antonius [Gor]-**  
**dianus nobilis**(s)imus  
 [C]aesar restituit  
 12 **per Cuspidium /Flam/-**

[ini]um Severum leg  
[pr]o pr(a)etore μ  
ϙνβ´

- lines 1-2: Imp l Caesar (Hogarth and Munro; Imp.Caesar (Ramsay 1941)  
lines 3-8: six lines erased (Hogarth and Munro); five lines erased (Ramsay 1941)  
line 9: Gor- (Ramsay)  
line 10: [Gor]dianus (Hogarth and Munro); nobilis(s)imus (Hogarth and Munro)  
line 11: was IT of RESTITUIT inscribed over ERUNT of RESTITUERUNT ?; cp. the comment of Harper, 091(H). Kemer 12  
line 12: [Fl]a[amini]- (Ramsay); PIAN, [Fl]a[m]- (Hogarth and Munro)  
line 13: um Severum (Ramsay); ini]um Severum (Hogarth and Munro)  
lines 13-14: leglatum pr]opretorem (Hogarth and Munro); leg.[Aug l pr]opretorem (Ramsay)  
line 14: μ for μ(ιλια), cp. 107(G), 108(D) and 109(C) (Elagabalus), 119(A) (Sev. Alexander), 068(C), 072(C), 074(C), 075(C), 080(B), 098(D), 104(B) and 108(M) (all Gordianus), 085(B) (Maximinus), 119(B) (Philippus); also 112  
line 15: iii. m.p. (Ramsay); . . . MP, M.P. (PNB) (Hogarth and Munro)

Restoration (*exempli gratia*) of ll. 3-8

(vac) **Imp**  
**Caesar** [M Clod]-  
[ius Pupienus]  
4 [Maximus et]  
[et Imp Caesar]  
[D Caelius Calv]-  
[inus Balbinus]  
8 [pp ff Augg et]

*Caput Viae* (Melitena)  
*Date* (1) and (2) “Date c.238” (Ramsay); AD 238, 31.i/01.ii-beg. May Pupienus and Balbinus *Augusti* with Gordianus *Caesar* (then [Pupienus and Balbinus erased] AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*)  
*Commentary* For the erasure of Pupienus and Balbinus, see above [p. 12], **Notes and Comments 3.5** Text-form (3).

### 088(A). Kemer 3

*Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0  
*Map* Elbistan 91-Ij  
*Location* “Newly excavated on the hillside [?] min. from Kemer, right of the path to Shahr” (Hogarth and Munro). Present whereabouts not established (DHF visit 15.vi.1977)  
*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of the Hogarth and Munro copy (facsimile of the printed version, Fig. 6.1.18)

	[p. 330])
<i>Publication</i>	Hogarth and Munro 1893, 692 “151 (iii)” (Fig. 6.1.18, [p. 330]) CIL 3. 12206 (text of Hogarth and Munro) RRMAM 2, 1. 547 (notice only) Baz 2007, 82 no. 31 (text from publications, with commentary)
<i>Description</i>	“Very rudely and irregularly inscribed” (Hogarth and Munro)
<i>Dimensions</i>	Not given

<i>Text</i>	<b>Imp</b> [Caesar] [Marc] <b>us</b> [Iul Phil]- [ipp] <b>us pius</b> [felix] 4 <b>invictus Aug</b> [et Marcus Iul] <b>ius</b> [Philippus nobili] <b>ssi</b> [mus] [Caesar vi] <b>a[s] e[t] pont[e]s</b> 8 <b>v[etust]ate</b> [con]- <b>lapsas restitu</b> [erunt] [per Antonium Memmum] [Hier] <b>one</b> [m] <b>le</b> [g Aug] 12 [pro prae] <b>to</b> [re] [ - ]
-------------	---

<i>Caput Viae</i>	[Melitena]
<i>Date</i>	AD 244, July/Aug.-247, July/Aug. Philippus <i>Augustus</i> with Philippus <i>Caesar</i>
<i>Commentary</i>	The text can be restored on the basis of the intact example above, 068(D). Aslanbeyli Yaylası, Hanboğazı 4

#### 088(B). Kemer 4

<i>Province, Sub-Province + Admin. Code and Map</i>	As 088(A)
<i>Location</i>	“In the cemetery at Kemer” (Hogarth and Munro); still in the cemetery but now built into the foundations of the N wall, c. 50 m E of the entrance-gate
<i>Copy</i>	Ramsay 1890; Hogarth 1891 (facsimile of the printed version of his copy, Fig. 6.1.19 [p. 331]); DHF 15.vi.1977. DHF squeeze and photos (Pl. 7.1.53 [p. 389]) in BIA. Text here from DHF squeeze
<i>Publication</i>	Hogarth and Munro 1893, 692 “151 (i)” (facsimile, Fig. 6.1.19 [p. 331]) CIL 3. 12204 (text of Hogarth and Munro) RRMAM 2, 1. 548 (notice only) Baz 2007, 80 no. 29 (text from publications, with commentary)
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 38. Kayseri 26, Kemer 4 Stone: (1) B/W Neg.: DHF R/77/07.01-02 (2) Col. Slide: DHF 156.15-16
<i>Description</i>	A simple cylinder. (?)Complete. Hard, pale limestone. Well preserved. Letters: sharp and clear, slightly uneven in size and alignment; broken-bar A
<i>Dimensions</i>	Ht 1.60; diam. (bottom) c. 0.60. Letters: 0.040-60, (lines 1-2) 0.07-95, (line 3) 0.070-80, (line 17) 0.080-95
<i>Text</i>	<b>Imp Caes</b> <b>L Septimius</b>

4       **Severus Pius**  
       **Pertinax·Aug**  
       **Arab·Adiab·Pa-**  
       **tr̄th·max·pont·**  
       **max·trib·pot VI**  
 8       **imp XI cos II·p p·**  
       **procos·et·Imp**  
       **Caes·M·Aurel·**  
       **Antoninus·Aug** [ - ]  
 12       [ - - - - ]  
       **restituerunt**  
       **per·C·Iulium·Flac-**  
       **cum·Aelianum**  
 16       **le(g)·pr·pr·**  
       **CLI·qva'**

line 11: **Aug et** (Hogarth and Munro)

*Caput Viae*       (Melitena)  
*Date*             AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus  
                       (Caracalla) *Augusti* with L. Septimius Geta (names erased) *Caesar*

#### 088(C). Kemer 5

*Province, Sub-Province + Admin. Code and Map*   As 088(A)  
*Location*        “In the cemetery at Kemer, upside down, fragmentary” (Hogarth and Munro).  
                       Present whereabouts not established (DHF visit 15.vi.1977)  
*Copy*             Ramsay 1890. The stone has not been examined by DHF. Text here of Ramsay  
                       *apud* Hogarth and Munro (facsimile of the printed version of Ramsay’s copy,  
                       Fig. 6.1.20 [p. 331])  
*Publication*     Hogarth and Munro 1893, 692 “151 (ii)” (text of Ramsay)  
                       CIL 3. 12205 (text of Ramsay *apud* Hogarth and Munro)  
                       RRMAM 2, 1. 549 (notice only)  
                       Baz 2007, 80 no. 30 (text from publications, with commentary)  
*Description & Dimensions*   Not given

*Text*                - - - -  
                       **CLI qva'**

*Caput Viae*       (Melitena)  
*Date*             (?)

#### 088(D). Kemer 6

*Province, Sub-Province + Admin. Code and Map*   As 088(A)  
*Location*        “In the cemetery at Kemer” (Hogarth). Present whereabouts not established (DHF  
                       visit 15.vi.1977)  
*Copy*             Ramsay and Hogarth 1890 (facsimile of the printed version of their copy,  
                       Fig. 6.1.21 [p. 331]). The stone has not been examined by DHF. Text here of  
                       Ramsay and Hogarth *apud* Hogarth and Munro  
*Publication*     Hogarth and Munro 1893, 693 “150” (text of Ramsay and Hogarth) (facsimile,

Fig. 6.1.21 [p. 331])

CIL 3. 12203 (text of Ramsay and Hogarth *apud* Hogarth and Munro)

French 1980, 721 no. 20 (text from CIL 3. 12203)

RRMAM 2, 1. 550 (notice only)

Baz 2007, 79 no. 28 (text from publications, with commentary)

*Description & Dimensions* Not given*Text*

**Imp Caes**  
**[L] Septimius**  
**Severus Pius**  
4 **Pertinax Aug**  
**Arab Adiab Parth**  
**[max] pont max**  
**trib pot VI imp XI**  
8 **[cos I]I p p procos**  
**et Imp Caes M Aur**  
**Antoninus Aug**  
**[[ - - - - ]]**  
12 **[[ - - - - ]]**  
(vac) **restit-**  
(vac) **uerunt**  
**per C Iulium**  
16 **Flaccum Aeli-**  
**[a]num le<g> pr [pr]**  
**CL qv'**

*Caput Viae* (Melitena)

*Date* AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus  
(Caracalla) *Augusti* with L. Septimius Geta (names erased) *Caesar*

**089(A). Kemer 7***Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0*Map* Elbistan 91-Ij

*Location* Formerly *in situ*. “By the road side, 27 min. from Kemer, towards Yalak” (Hogarth); now in the cemetery at Kemer in the N wall, c. 25 m E of the gate and built into the foundations.

*Copy* Hogarth and Munro 1891 (facsimile of the printed version of their copy, Fig. 6.1.22 [p. 332]); DHF 15.vi.1977. DHF squeeze and photo. in BIA. Text here from DHF squeeze.

*BIA Collections:* *Squeeze and Stone Photographs*  
Squeeze: 38. Kayseri 27, Kemer 7  
Stone: (1) B/W Neg.: DHF R/77/07.03

*Publication* Hogarth and Munro 1893, 693 “149 (i)” (facsimile, Fig. 6.1.22 [p. 332])  
CIL 3. 12197 (text of Hogarth and Munro)  
RRMAM 2, 1. 551 (notice only)  
Baz 2007, 71 no. 21 (text from publications)

*Description* A simple cylinder. Broken above. Limestone. No plinth. Surface: worn. Letters: worn but legible; neat in shape, size and alignment; cut with a broad-blade chisel (breadth c. 0.001); broken-bar A

*Dimensions* Ht (ex.) 1.70; diam. c. 0.60. Letters: (line 3) 0.080, (line 4) 0.060-65, (lines 5-16) 0.04-50, (line 17) 0.09-10

*Text* (1) (on the full face of the shaft)

**Imp Cae[s]**  
**L·Septimiu[s]**  
**Severus Pius**  
4 **Pertinax·Aug**  
**Arab Adiab Parth**  
**max pont·max**  
**trib·pot·VI·imp XI**  
8 **cos·II·p p·procos**  
**et·Imp·Caes**  
**M·Aurel·Anton-**  
**[in]us Aug [ - - ]**  
12 **[ - - - ] restit-**  
**uerunt·per·**  
**<C> Iul Flac-**  
**cum·Aelianum**  
16 **le<g>·pr·pr**  
**CXLIX quθ'**

lines 14-15: written as one line: uerunt per [G] Iul Flacc- (Hogarth)

(2) (over the top of ll. 2-4)

**Constantio**  
**nobil Caes**

*Caput Viae* (Melitena)

*Date* (1) AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) *Augusti* with L. Septimius Geta (names erased) *Caesar*  
(2) AD 285-305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*

*Commentary* (Text [2]) For an explanation of seemingly truncated, Tetrarchic texts, see above [p. 14], **Notes and Comments 3.6.**

### 089(B). Kemer 8

*Province, Sub-Province + Admin. Code and Map* As 089(A)

*Location* (?) As 089(A). Present whereabouts not established (DHF visit 15.vi.1977)

*Copy* Hogarth and Munro 1891 (facsimile of the printed version of their copy, Fig. 6.1.23 [p. 332]). The stone has not been examined by DHF. Text here of Hogarth and Munro

*Publication* Hogarth and Munro 1893, 694 "149 (ii)" (facsimile, Fig. 6.1.23 [p. 332])  
CIL 3. 12198 (text of Hogarth and Munro)  
RRMAM 2, 1. 552 (notice only)

Baz 2007, 74 no. 23 (text from publications, with commentary)

*Description* Not given. Letters (as given by Hogarth): (line 3) C for G, (lines 4 and 7) Δ for D

*Dimensions* Not given

<i>Text</i>	(vac) <b>Imper</b>	
	<b>Caesar Marc-</b>	(sic)
	<b>o Antonio Go-</b>	
4	<b>rdiano pio fe-</b>	
	<b>lici Augusto resti-</b>	
	<b>tuerunt per</b>	
	<b>Cuspidium Fla-</b>	
8	<b>minium Sev-</b>	
	<b>erum legatu-</b>	
	<b>m pro praet-</b>	
	(vac) <b>ore m</b>	
12	(vac) <b>CXLIX</b>	
	(vac) <b>ϰ μθ'</b>	

line 11: **m** for **m**(ilia), cp. 056(B) (Sept. Sev.), 065 (Elag. + Sev. Alex.), 079(D), 084, 093(H), 095 and 097(C) (all Gordianus), 115 (Probus); also 104(J), 108(F), 114

<i>Caput Viae</i>	(Melitena)
<i>Date</i>	AD 238, 09.v(?)–09.xii (?), Gordianus <i>Augustus</i>
<i>Commentary</i>	For the survival of <i>restituere</i> , see above [p. 12], <b>Notes and Comments 3.5</b> Text-form (4).

### 089(C). Kemer 9

<i>Province, Sub-Province + Admin. Code and Map</i>	As 089(A)
<i>Location</i>	(?) As 089(A). In the SE corner of the field, owned by Kürklü Mehmet, Ali oğlu, Aslan of Dayıoluk (the owner of the house where 090[A]–[D]. Dayıoluk 2–4 are located), c. 2 km from the <i>şose</i> to Kemer along the Roman road and the old track to Yalak; on the W side of the Roman road. The place is called “Hasan Kahya Ören yeri” where Dayıoluk 5 (below, 091) is located (Pl. 7.1.55 [p. 390])
<i>Copy</i>	Hogarth and Munro 1891 (facsimile of the printed version of their copy, Fig. 6.1.24 [p. 332]); DHF 17.vi.1977. DHF squeeze and photos (Pl. 7.1.54 [p. 390]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 38. Kayseri 28, Kemer 9 Stone: (1) B/W Neg.: DHF R/77/06.05 and 07.04 (2) Col. Slide: DHF 156.01–02
<i>Publication</i>	Hogarth and Munro 1893, 694 “149 (iii)” (facsimile, Fig. 6.1.24 [p. 332]) CIL 3. 12199 (text of Hogarth and Munro) RRMAM 2, 1. 553 (notice only) Baz 2007, 75 no. 24 (text from publications, with commentary)
<i>Description</i>	A simple cylinder. Broken above on the right. Hard, pale limestone. The shaft tapers towards the top. Surface: worn and damaged. Letters: worn but mostly clear and legible
<i>Dimensions</i>	Ht (ex.) 1.45; diam. (bottom) c. 0.60. Letters: 0.060–70
<i>Text</i>	---- [----Ca]- es[a]r̄ via[s et]



4     [po]ntes vet[ust]-  
        ate conla[ps]-  
        as r<sup>(vac)</sup> estituer-  
        u<sup>(vac)</sup> nt per Ant[o]-  
 8     n[i]um Memm-  
        ium Hieronem  
        v c leg Aug  
        pr<sup>(v)</sup> pr  
 12     quθ'

*Caput Viae*     (Melitena)

*Date*     AD 244, July/Aug.-247, July/Aug. Philippus *Augustus* with Philippus *Caesar*, on the basis of the governor's name, cp. the intact example above, 068(D)

### 089(D). Kemer 10

*Province, Sub-Province + Admin. Code and Map*     As 089(A)

*Location*     (?) As 089(A). Present whereabouts not established (DHF visit 15.vi.1977)

*Copy*     Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Hogarth (facsimile of the printed version of his copy, Fig. 6.1.25 [p. 333])

*Publication*     Hogarth and Munro 1893, 694 "149 (iv)" (facsimile, Fig. 6.1.25 [p. 333])

CIL 3. 12200 (text of Hogarth and Munro)

RRMAM 2, 1. 554 (notice only)

Baz 2007, 77 no. 25 (text from publications, with commentary)

*Description*     "This fragment bears part of two inscriptions; the upper one has been imperfectly erased, and restituerunt has remained. The lower one is [text (2)]" (Hogarth and Munro)

*Dimensions*     Not given

*Text*     (1) (underneath text [2])

**IVG**

**IB**

-

**restituerunt**

-

-

**IAN**

line 7: (?) [Ael]ian[um] i.e. Iulius Flaccus Aelianus

(2) (on the top of text [1])

**Imp Caes**

2     **Caio Val**

**Δiocletia⟨n⟩o**

line 3: Δ for D

*Caput Viae*     [Melitena]

*Date*     (1) (?) Septimius Severus, AD 198(?)

(2) AD 285-305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*

*Commentary* (Text [1]) If the restoration [Ael]**ian**[um] is correct, the date can be established on the basis of intact texts of Septimius Severus, e.g. 088(B). Kemer 4.  
(Text [2]) For an explanation of seemingly truncated, Tetrarchic texts, see above [p. 14], **Notes and Comments 3.6**.

### 089(E). Kemer 11

*Province, Sub-Province + Admin. Code and Map* As 089(A)

*Location* (?) As 089(A). Present whereabouts not established (DHF visit 15.vi.1977)

*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Hogarth (facsimile of the printed version of Hogarth's copy, Fig. 6.1.26 [p. 332])

*Publication* Hogarth and Munro 1893, 695 "149 (v)" (facsimile, Fig. 6.1.26 [p. 332])  
CIL 3.12201 (text of Hogarth and Munro)  
RRMAM 2, 1. 555 (notice only)  
Baz 2007, 73 no. 22 (text from publications, with commentary)

*Description & Dimensions* Not given

*Text* (1) (underneath text [2])  
**Imp Ca[e]s**  
[Luci]**us Sept[i]m[ius]**  
[Se]**ver**[us - - ]  
- - - -  
[ - - - ]  
[ - - - - ]  
[ - - - - ] **Imp**  
[ - - - c]**os**  
- - - -

(2) (on top of text [1])  
**Imp Ca[e]s**  
[Q Messio]  
[Tr]**aiano** **D[e]cio** **A[ug]**  
4 [et Q Her]**ennio**  
[Etru]**sco Maesi-** (sic)  
**o Decio et**  
[C Val]**enti** **<H>osti-**  
8 [lia]**no Mesio** (sic)  
[Qu]**into no-**  
**bill Caess**  
**quθ'**

*Caput Viae* (Melitena)

*Date* (1) (?) L. Septimius Severus and M. Aurelius Antoninus (Caracalla) with L. Septimius Geta *Caesar*, AD 198 (?)

(2) AD 251 Traianus Decius *Augustus* with Herennius and Hostilianus *Caesares*

*Commentary* (Text [1]) the date can be suggested on the basis of intact texts of Septimius Severus, e.g. 088(B). Kemer 4

**089(F). Kemer 12***Province, Sub-Province + Admin. Code and Map* As 089(A)*Location* (?) As 089(A). Present whereabouts not established (DHF visit 15.vi.1977)*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Hogarth and Munro*Publication* Hogarth and Munro 1893, 695 “149 (vi)”  
CIL 3. 12202 (text of Hogarth and Munro)  
RRMAM 2, 1. 556 (notice only)*Description* Baz 2007, 73 no. 22 (text from publications, with commentary)  
“The stone is fragmentary and the inscription is in hopeless confusion, out of which nothing intelligible can be made” (Hogarth and Munro)*Dimensions* Not given*Text*- - - -  
**CXLIX** ρμθ'*Caput Viae* (Melitena)*Date* (?)**090(A). Dayıoluk 1***Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0*Map* Elbistan 91-Ij*Location* In the village, at the cami; used, upside down, as a gate-support, on the S side of the gate. Said (sc. in 1977) to have been brought from Hasan Kahya Öreni “about 25-30 years previously”*Copy* DHF 15.vi.1977. DHF photo. (Pl. 7.1.56 [p. 390]) in BIA. Text here from DHF notes*BIA Collections: Squeeze and Photograph*  
Stone: (1) B/W Neg.: DHF R/77/06.07*Publication* RRMAM 2, 1. 511 (notice only)  
Baz 2007, 70 no. 18 (notice of RRMAM 2, 1. 511)*Description* A simple cylinder. Complete. Hard, pale limestone.*Dimensions* Ht (vis.) 1.70; diam. (bottom) 0.60. Letters: not recorded*Text*- - - -  
**pr pr**  
(vac) **CXL**[IIX]  
[ρμ]η'*Caput Viae* (Melitena)*Date* (?)**090(B). Dayıoluk 2***Province, Sub-Province + Admin. Code and Map* As 090(A)*Location* In the village, next to and S of the house owned by Mehmet Aslan (as above 090[B]); used as part of the wall of an *ağıl* (sheep-pen), on the W side facing the cami

<i>Copy</i>	DHF 15.vi.1977. DHF squeeze in BIA. Text here from DHF squeeze	
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i>	
	Squeeze: 38. Kayseri 32, Dayıoluk 2	
<i>Publication</i>	RRMAM 2, 1. 513 (notice only)	
	Baz 2007, 70 no. 20 (notice of RRMAM 2, 1 513)	
<i>Description</i>	A simple cylinder. A broken fragment only. Limestone. Surface and letters: worn and damaged.	
	Letters: irregular in shape and size; broken-bar A	
<i>Dimensions</i>	Ht (vis.) 1.18; diam. (top) 0.50. Letters: (text 1) 0.04-65	
<i>Text</i>	(1)	[Imp Caesar]
	2	[L Se]ptimius
		[Sev]erū̄s Piūs
	4	[Per]tinax·Aū̄g
		[Arab Adia]b[-]
	6	- - - -

It has not been possible to disentangle the full text; there is certainly another text [text 2] over the top of the Severan [text 1]

(2) (?)

<i>Caput Viae</i>	[Melitena]
<i>Date</i>	(1) AD 197/198(?), L. Septimius Severus [and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i> ]
	(2) (?)
<i>Commentary</i>	Probably the upper section of milestone 090(A)

### 090(C). Dayıoluk 3

<i>Province, Sub-Province + Admin. Code and Map</i>	As 090(A)
<i>Location</i>	In the village, at the house (said to have been a <i>kilise</i> [church]) of Mehmet Aslan; used in the wall facing the cami (to W)
<i>Copy</i>	DHF 15.vi.1977. DHF photo. (Pl. 7.1.57 [p. 391]) in BIA. Text here from DHF notes
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i>
	Stone: (1) B/W Neg.: DHF R/77/06.08
<i>Publication</i>	RRMAM 2, 1. 512 (notice only)
	Baz 2007, 69 no. 17 (notice of RRMAM 2, 1. 512)
<i>Description</i>	A simple cylinder. A broken fragment only. Limestone. Surface and letters: damaged and worn
	Letters: uneven and irregular. The numerals of the distance-figure were cut with a broad-blade chisel (breadth c. 0.012).
<i>Dimensions</i>	Ht (vis.) c. 1.30; diam. (top) 0.51. Letters: 0.030-40, (numerals) 0.10
<i>Text</i>	- - - -
	[ - - - - ]
	<b>restit</b> [uerunt]
	<b>per C</b> [Iulium]
	<b>Flac</b> [cum]
	<b>Aelianum</b> [leg Augg]

**pr pr**  
**[CXL]IIX ouη'**

<i>Caput Viae</i>	(Melitena)
<i>Date</i>	[L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta <i>Caesar</i> ], (?) AD 198, on the basis of the governor's name
<i>Commentary</i>	Probably the lower section of milestone 090(C)

**090(D). Dayıoluk 4**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 090(A)
<i>Location</i>	As 090(C)
<i>Copy</i>	DHF 15.vi.1977
<i>Publication</i>	RRMAM 2, 1. 514 (notice only)
<i>Description</i>	A simple cylinder. A broken fragment only
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

**091. Dayıoluk 5**

<i>Province, Sub-Province + Admin. Code</i>	Kayseri, Sarız 38-07-0
<i>Map</i>	Elbistan 91-Ij
<i>Location</i>	At Hasan Kahya Öreni where Kemer 9 (above, 089[C]) is located (Pl. 7.1.54 [p. 389]); in the field owned by Kürklü Mehmet, Ali oğlu, Aslan (the owner of the house where 090[A]-[D]. Dayıoluk 2-4 are located)
<i>Copy</i>	DHF 17.vi.1977. Text here from DHF notes
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Stone: (1) B/W Neg.: DHF R/77/06.05-06 (Pl. 7.1.55 [p. 389]) (2) Col. Slide: DHF 156.01-02
<i>Publication</i>	French 1985b, 150 and n.19 (notice, and excerpt from text) RRMAM 2, 1. 515 (notice only) Baz 2007, 70 no. 18 (citation of text-excerpt [French 1985])
<i>Description</i>	A simple cylinder. Broken above. Hard, pale limestone. Surface and letters: worn but letters sharp and clear. Letters: neat and regular; broken-bar A, U for V
<i>Dimensions</i>	Ht c. 1.25; diam. (bottom) c. 0.59. Letters: c. 0.060, (line 10) 0.10-11
<i>Text</i>	(1) (underneath text [2]) lost  (2) (on the top of text [1]) [Imp Caes] [M Aurelius] [Severus Alex]- 4 <b>nder</b> (leaf) <b>p</b> <b>Au</b> (g) (leaf) <b>t</b> [rib po]- <b>test</b> (leaf) <b>cos</b> (leaf) <b>p p</b> <b>vias et pontes v-</b> 8 <b>etustate conlap-</b> <b>sas restituit</b> (leaf)

**ϠϠϠ'**

*Caput Viae* (Melitena)  
*Date* (1) (?)  
 (2) Severus Alexander *Augustus*, AD 238, 14(?).iii-09.xii  
*Commentary* The text can be established on the basis of intact examples, e.g. 068(A).  
 Aslanbeyli Yaylası, Hanboğazı 1

**092(A). Yalak 5**

*Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0  
*Map* Elbistan 91-Ij  
*Location* “By the roadside, 52 min. from Kemer toward Yalak, lying face downwards beside another milestone” [= 092[B]. Yalak 6] (Hogarth and Munro). Present whereabouts not established (DHF visit 15.vi.1977)  
*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Hogarth (facsimile of the printed version of Hogarth’s copy, Fig. 6.1.27 [p. 332])  
*Publication* Hogarth and Munro 1893, 695 “147” (facsimile, Fig. 6.1.27 [p. 332])  
 CIL 3. 12207 (text of Hogarth and Munro)  
 RRMAM 2, 1. 574 (notice only)  
 Baz 2007, 78 no. 27 (text from publications, with commentary)  
*Description* “We had no time to dig it out, and could only read the following letters on the under side” (Hogarth)  
*Dimensions* Not given  
*Text* See facsimile (Fig. 6.1.27 [p. 332])

(Hogarth)		(possible restoration)
		-----
<b>PI</b>		[io Gordiano] <b>pi-</b>
<b>GUS</b>		[o felici Au] <b>gus-</b>
<b>RV</b>		[to restitue] <b>ru-</b>
<b>N</b>	5	[nt per Cuspi] <b>di-</b>
<b>V</b>		[um Flamini] <b>u-</b>
<b>IE</b>		[m Severum] <b>le-</b>
<b>ME</b>		[gatum pro pr] <b>ae-</b>
		[tore] (vac)
	10	[ - ] (vac)

*Caput Viae* [Melitena]  
*Date* “The inscription seems to be either of Gordian or Philip” (Hogarth); (?)AD 238  
 Gordianus III (DHF)  
*Commentary* If the restoration of the governor’s name is correct, the text can be established on the basis of intact examples, e.g. 075(C). İmirzağa, Barcın Mevkii 3

**092(B). Yalak 6**

*Province, Sub-Province + Admin. Code and Map* As 092(A)  
*Location* As 092(A). Yalak 5: “By the roadside, 52 min. from Kemer towards Yalak, lying

face downwards beside another milestone [= here, 092(A)]” (Hogarth and Munro). Present whereabouts not established (DHF visit 15.vi.1977)

*Copy* Hogarth and Munro 1891

*Publication* Hogarth and Munro 1893, 695 “147”  
RRMAM 2, 1. 575 (notice only)

*Description & Dimensions* Not given

### 092(C)-(D). Yalak 7-8

*Province, Sub-Province + Admin. Code and Map* As 092(A)

*Location* “Two milestones in situ, which we had not time to dig out” (Hogarth and Munro).  
Present whereabouts not established (DHF visit 15.vi.1977)

*Copy* Hogarth and Munro 1891

*Publication* Hogarth and Munro 1893, 695 “148”  
RRMAM 2, 1. 576 and 577 (notice only)  
Baz 2007, 69 nos 15-16 (notice of Hogarth and Munro)

*Description & Dimensions* Not given

### 093(A). Yalak 1

*Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0

*Map* Elbistan 91-If

*Location* “In the cemetery” (Sterrett); in the cemetery “Yalaklıların Kışla önü ve eski çardaklı mezarlık”, c. 2.50 km SW of Yalak and c. 750 m W of Kışla and an old church. Situated on the “Bağdat yolu”, the Baghdad road, which represents the line of the Roman road.

*Copy* Sterrett 25 July, 1884 (facsimile of the printed version of Sterrett’s copy, Fig. 6.1.28 [p. 333]); Hogarth and Munro 1891; DHF 19.vi.1977. DHF squeeze in BIA. Text here from DHF squeeze.

*BIA Collections: Squeeze and Stone Photographs*  
Squeeze: 38. Kayseri 30, Yalak 1

*Publication* Sterrett 1883-84, 259 no. 295 (facsimile, Fig. 6.1.28 [p. 333])  
Sterrett 1885, 25 no. 23  
CIL 3. 6947 (text of Sterrett)  
Hogarth and Munro 1893, 695 “146 (i)” (notice)  
RRMAM 2, 1. 570 (notice only)  
Baz 2007, 66 no. 12 (text from publications)

*Description* A simple cylinder. Broken above. Hard, pale limestone. Surface: worn and damaged.  
Letters: worn, some faint, some legible; cut with a broad-blade chisel (breadth c. 0.005)

*Dimensions* Ht (vis.) 1.07; diam. (top) 0.39. Letters: 0.050-70

*Text*

- - - -

Març[us Iul Phi]-  
lippus n[obili]-  
4 ssimus Cae-  
sar vias e[t p]-  
ontes ve[tu]-  
state con[la]-

8     **psas r[estitu]-**  
        **erunt** [per Ant]-  
        **onium M[emm]-**  
        **ium Hie[rone]-**  
 12     **m v** [c leg]  
        **Aug** [pr pr]  
        [ - ]

*Caput Viae*         [Melitena]

*Date*                 AD 244, July/Aug.-247, July/Aug. [Philippus *Augustus*] with Philippus *Caesar*

*Commentary*       The full text can be restored on the basis of the intact example above, 068(D).  
 Aslanbeyli Yaylası, Hanboğazı 4

### 093(B). Yalak 2

*Province, Sub-Province + Admin. Code and Map*    As 093(A)

*Location*           As 093(A). Present whereabouts not established (DHF visit 15.vi.1977)

*Copy*                Sterrett 25 July, 1884; Hogarth and Munro 1891. The stone has not been  
 examined by DHF 19.06.1977. Text here of Sterrett (facsimile of the printed  
 version of Sterrett's copy, Fig. 6.1.29 [p. 334])

*Publication*       Sterrett 1883-84, 260 no. 296 (facsimile, Fig. 6.1.29 [p. 334])

Sterrett 1885, 25 no. 24

CIL 3. 6948 (text of Sterrett)

Hogarth and Munro 1893, 695 "146 (ii)" (notice)

RRMAM 2, 1. 571 (notice only)

Baz 2007, 68 no. 13 (text from publications)

*Description & Dimensions*    Not given

*Text*                 Consult the facsimile (Fig. 6.1.29 [p. 333])

*Date*                 (?)

*Commentary*       "Possibly this is to be restored as an inscription of Constantinus and Licinius, but  
 the indications are too slight to justify it" (Sterrett 1883-84)

### 093(C). Yalak 3

*Province, Sub-Province + Admin. Code and Map*    As 093(A)

*Location*           As 093(A). Present whereabouts not established (DHF visit 15.vi.1977)

*Copy*                Sterrett 25 July, 1884; Hogarth and Munro 1891. The stone has not been  
 examined by DHF 19.vi.1977. Text here of Sterrett (facsimile of the printed  
 version of Sterrett's copy, Fig. 6.1.30 [p. 334])

*Publication*       Sterrett 1883-84, 260 no. 297 (facsimile, Fig. 6.1.30 [p. 334])

Sterrett 1885, 25 no. 25

CIL 3. 6949 (text of Sterrett)

Hogarth and Munro 1893, 696 "144" (notice)

IGRR 3. 131 (text from CIL 3. 6949)

RRMAM 2, 1. 572 (notice only)

Baz 2007, 65 no. 11 (text from publications)

French 2008, 126-127 (text and comments)

AE 2008. 1474 (text of French)



## SEG 58. 1661 (text of French)

*Description & Dimensions* Not given

*Text* [ - - - - - δημα]-  
 [ρχικῆς ἐξου]σίας ὑπατο[ς τὸ β' πα]-  
 3 [τὴρ πατρίδ]ος τὰς ὁδοὺς [ἀποκατ]-  
 [έστησε διὰ] Πομπ[ωνί]ου [Βάσσου]  
 [πρεσβευτοῦ καὶ ἀ]ντιστ[ρατήγου]  
 6 [CXLIV] ρμδ'

*Caput Viae* (Melitena)*Date* (?)AD 96 Nerva*Commentary* Sterrett's text is here restored after the Nervan text at Sakaltutan, above 066. Perhaps, like the Sakaltutan text, this milestone too was bilingual.**093(D). Yalak 4***Province, Sub-Province + Admin. Code* Kayseri, Sarız 38-07-0*Map* Elbistan 91-Ij*Location* In the village; at the house (no. 76) of Ahmet Uzunlu*Copy* DHF 18.vi.1977. DHF squeeze and photo. (Pl. 7.1.58 [p. 391]) in BIA. Text here from DHF squeeze*BIA Collections:* Squeeze and Photograph

Squeeze: 38. Kayseri 31, Yalak 4

Stone: (1) B/W Neg.: DHF R/77/07.07

*Publication* RRMAM 2, 1. 573 (notice only)

Baz 2007, 69 no. 14 (notice of RRMAM 2, 1. 573)

*Description* A simple cylinder. Broken below. Hard, pale limestone. Surface and letters: worn.

Letters: indistinct and faint; cut with a broad-blade chisel; broken-bar A

*Dimensions* Ht (ex.) c. 1.25; diam. c. 0.48. Letters: 0.045-70*Text* (1) (in part underneath text [2])

**Imp**  
**Caes·Ma-**  
**rco Iul Philip-**  
 4 **pus·pius·feli-**  
**x[ - - - ]**  
**[ - - - ]**  
**[ - - - ]**  
 8 **simus Caesar v-**  
**ias et pontes ve-**  
**tustate conl-**  
**apsas rest[it]ue[r]-**  
 12 **unt pē[r - - ]**  
**- - - -**

(2) (over the top of [1], lines 5-7)

**Gal Val**

**Maximiano  
nobil Caes**

*Caput Viae* [Melitena]  
*Date* (1) AD 244, July/Aug.-247, July/Aug. Philippus [*Augustus*] with [Philippus]  
*Caesar*  
 (2) 293-305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius  
*Caesares*  
*Commentary* (Text [1]) the full text can be restored on the basis of the intact example above, 068(D). Aslanbeyli Yaylası, Hanboğazı 4.  
 (Text [2]) For an explanation of seemingly truncated, Tetrarchic texts, see above [p. 14], **Notes and Comments 3.6.**

**093(E). Yalak 9**

*Province, Sub-Province + Admin. Code and Map* As 093(A)  
*Location* As 093(A); “Yalak cemetery” (Harper). Present whereabouts not established (DHF visit 15.vi.1977)  
*Copy* Harper 1963 (Notes 2. 14). The stone has not been examined by DHF. Text here of Harper  
*Description & Dimensions* Not recorded

*Text*

	----
2	[per] <b>An</b> [ton]-
	[i] <b>um</b> [Memm]-
4	[iu] <b>m Hie</b> [ro]-
	[nem] <b>v c</b> [leg]
6	<b>Aug pr pr</b>
	<b>εμν'</b>

*Caput Viae* (Melitena)  
*Date* AD 244(?) Philippus *Augustus* with Philippus *Caesar*, on the basis of the governor's name; cp. the intact text above, 068(D). Aslanbeyli Yaylası, Hanboğazı 4

**093(F). Yalak 10**

*Province, Sub-Province + Admin. Code and Map* As 093(A)  
*Location* As 093(A); “Yalak cemetery” (Harper). Present whereabouts not established (DHF visit 15.vi.1977)  
*Copy* Harper 1963 (Notes 2. 14). The stone has not been examined by DHF. Text here of Harper  
*Description* “Very mossy at r.” (Harper)  
*Dimensions* Not given

*Text*

	<b>Imp C</b> [aes]
	<b>divi Seve</b> [ri]
	<b>nep diyi M</b> [Ant]-
4	<b>onini</b> [fil M Aur]
	[A] <b>ntoni</b> [no pio]

**felici Aug [mili]-**  
**a restituta per**  
 8 **M Ulp Ofellium**  
**Theodorum [leg]**  
**Aug pr pr**  
**ϠϠ'**

*Caput Viae* (Melitena)  
*Date* Elagabalus *Augustus*, (?) AD 218, 16.v–mid-June

### Yalak

“In the cemetery. Near it” (here - 093[A]) “is a defaced milliarium” (Sterrett 1883-84, 259)

### 093(G). Yalak 11

*Province, Sub-Province + Admin. Code and Map* As 093(A)  
*Location* As 093(A); “Yalak cemetery” (Harper). Present whereabouts not established (DHF visit 19.vi.1977)  
*Copy* Harper 1963 (Notes 2. 15). The stone has not been examined by DHF. Text here of Harper  
*Description & Dimensions* Not recorded

*Text*

**Imp [Caes]**  
**[Marcu]s Iul P[hilippus]**  
**[pius felix] i[n]victus Aug**  
 4 **[et Marc]us [Iul Philippus]**  
**[nobili]ssimus Caesar**  
**vias et pontes vet-**  
**[ustat]e conlapsa[s]**  
 8 **[restitu]erunt**  
**[per Antonium Mem]-**  
**[mum Hieronem v c]**  
**[leg Aug] pr pr**  
 12 **ϠXLV**

line 12: **CXLV** [ - ] is possible, if not probable

*Caput Viae* (Melitena)  
*Date* AD 244, July/Aug.-247, July/Aug. Philippus *Augustus* with Philippus *Caesar*  
*Commentary* The full text can be restored on the basis of the intact example above, 068(D). Aslanbeyli Yaylası, Hanboğazı 4

### 093(H). Yalak 12

*Province, Sub-Province + Admin. Code and Map* As 093(A)  
*Location* “Yalak W of mound . . . ., freshly dug up for me though existence known to villagers” (Harper). Present whereabouts not established (DHF visit 19.vi.1977)  
*Copy* Harper 1963 (Notes 2. 02). The stone has not been examined by DHF. Text here of Harper

*Description & Dimensions* Not recorded

*Text* (1) and (2) (below text [3])  
 [Imp]  
 [Caesar] **M A-**  
 ----  
 4 ----  
 ----  
 ----  
 8 **ntonius Gordia-**  
**nus nobilissimu[s]**  
**Caesar restituit**  
**per Cuspidium [F]-**  
**laminium Sever[u]-**  
 12 **m legat pr[o praeto]-**  
**re m**  
**CLV que'**

line 14: **m** for **m**(ilia), cp. 056(B) (Sept. Sev.), 065 (Elag. + Sev. Alex.), 079(D), 084, 089(B), 095 and 097(C) (all Gordianus), 115 (Probus); also 104(J), 108(F), 114

Harper: "Doubly inscribed - note especially the recutting correction of ERVNT to IT"

For a suggested restoration of ll. 5-8, see the version above, 087(B). Kemer 2

(3) (above text [1])  
 [Imp Caes]  
 [Marco] **Aur**  
 [Maximi] **ano p f**  
**invicto Aug**

restored after the text of 093. Doğankonak, Kumocağı

*Caput Viae* (Melitena)  
*Date* (1) AD 238, 31.i/01.ii-beg. May Pupienus and Balbinus *Augusti* with Gordianus *Caesar*, then (2) (Pupienus and Balbinus erased) AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*  
 (3) AD 293–305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*  
*Commentary* (Text 1) For the erasure of Pupienus and Balbinus, see above [p. 12], **Notes and Comments 3.5** Text-form (3).  
 (Texts [2] and (3)) For an explanation of seemingly truncated, Tetrarchic texts, see above [p. 14], **Notes and Comments 3.6**.

#### 094(A). Doğankonak 1, form. Haydan

*Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-0  
*Map* Elbistan 91-Ik  
*Location* In the village, at the house of Şemsettin Bilgici, at the foot of the stairs. Brought from the Roman road at a point c. 3 km N of the Sakaltutan Boğazı (or

<i>Copy</i>	Karaboğaz); the area is called “Köye gözen mevkii”, c. 1 km E of the village. DHF 09.viii.1978. DHF squeeze and photo. (Pl. 7.1.59 [p. 392]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 46. Maraş 05, Doğankonak 1 Stone: (1) B/W Neg.: DHF R/78/11.02
<i>Publication</i>	RRMAM 2, 1. 722 (notice only)
<i>Description</i>	A simple cylinder. Broken at the top. Hard, pale limestone. The shaft tapers slightly towards the top. Surface: slightly worn. Letters: well preserved, sharp and clear, neat in shape, size and alignment, cut with a broad-blade chisel (breadth c. 0.005); broken-bar A
<i>Dimensions</i>	Ht (max.) c. 0.95; diam. (bottom) 0.61. Letters: 0.06-75, (line 10) 0.075 (L) + 95 (Gk)

*Text*

- - - -  
 2 [ - - nobilissi]-  
   **muş** [Caesar vias]  
 4 **et pontes vēt**[us]-  
   **tate conlapsas**  
 6 **restituerunt**  
   **per** [[ - - - - ]]  
 8 [[ - - - - ]]  
   **leg Augg pr pr** (sic)  
   **CXL**[III] **quy'**

lines 7-8: (?) **per** [[Licinnium | Serenianum]]

<i>Caput Viae</i>	(Melitena)
<i>Date</i>	(?) Maximinus <i>Augustus</i> with Maximus <i>Caesar</i> , AD 236, 07.i/16.v-238, mid. iv
<i>Commentary</i>	The lost lines can be restored on the basis of the intact example above, 085(D). Mollahüseyin 4, where, as here, the name of the legate has been erased. For the governorship of Licinnius Serenianus, see the discussion above [p. 11], <b>Notes and Comments 3.4</b> . For the double g in <b>Augg</b> (line 9) there is a parallel on Göksun 3 (below, 104[C] line 14), a milestone of Maximinus as sole Augustus with Maximus <i>Caesar</i> . I have rejected the possibility (based on the text of 098[A]. Keklikoluk 1) that the milestone here, 094. Doğankonak 1, can be dated to Philippus with Philippus <i>Caesar</i> . So far as is known, the name of the governor, Antonius Memmius Hiero, under Philippus was never erased. The dates for Maximinus <i>Augustus</i> with Maximus <i>Caesar</i> are given by Kienast (1996, 183-185).

**094(B). Doğankonak 2, form. Haydan**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 094(A)
<i>Location</i>	In the village, at the cami; at the NE corner of the courtyard wall
<i>Copy</i>	DHF 09.viii.1978. DHF squeeze and photo. (Pl. 7.1.60 [p. 392]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 46. Maraş 06, Doğankonak 2 Stone: (1) B/W Neg.: DHF R/78/11.01
<i>Publication</i>	RRMAM 2, 1. 723 (notice only)

<i>Description</i>	A simple cylinder. Broken at the top and at the bottom. Hard, pale limestone. Surface and letters: some wear and damage.
<i>Dimensions</i>	Letters: worn but legible, variable and inconsistent in size; broken-bar A Ht (ex.) c. 0.70; diam. (est.) c. 0.58. Letters: 0.045-60
<i>Text</i>	[Imp Caes] <b>divi Severi</b> [nep] <b>divi·M Antoni-</b> 4 <b>ni</b> (vac) <b>fil·M Aur</b> <b>Antonino pio f[eli]-</b> <b>ci Aug milia res-</b> <b>tituta per M Ulp</b> 8 <b>Ofellium Theodor[um]</b> <b>leg Aug pr pr</b> [ - ]
<i>Caput Viae</i>	[Melitena]
<i>Date</i>	Elagabalus <i>Augustus</i> , (?) 218, 16.v-(?) mid-June

**094(C). Doğankonak 3, form. Haydan**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 094(A)
<i>Location</i>	In the village cemetery; at the head of a grave (Pl. 7.1.62 [p. 392])
<i>Copy</i>	DHF 11.viii.1978. DHF squeeze and photos (Pl. 7.1.61 [p. 392]) in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 46. Maraş 07, Doğankonak 3 Stone: (1) B/W Neg.: DHF R/78/12.03-04
<i>Publication</i>	RRMAM 2, 1. 724 (notice only)
<i>Description</i>	A simple cylinder. Broken at the top, shaft damaged. Hard, pale limestone. Surface: worn. Letters: where preserved, sharp and clear; broken-bar A, U for V
<i>Dimensions</i>	Ht (vis.) 1.53; diam. (top) 0.44. Letters: 0.060-80, (line 5) N 0.095, O 0.040
<i>Text</i>	----- 2 <b>v[ias et pontes v]e<u>t</u>u<u>s</u>-</b> <b>ta[te conlaps]as resti-</b> 4 <b>tueru[nt per A]nto-</b> (vac) <b>nium Memmium Hiero-</b> 6 <b>nem v c leg Aug pr pr</b> (vac) <b>ουγ'</b>
<i>Caput Viae</i>	(Melitena)
<i>Date</i>	AD 244-247 Philippus <i>Augustus</i> with Philippus <i>Caesar</i> , on the basis of the governor's name
<i>Commentary</i>	The text here can be restored on the basis of the intact example above, 068(D). Aslanbeyli Yaylası, Hanboğazı 4

**094(D). Doğankonak 4, form. Haydan***Province, Sub-Province + Admin. Code and Map* As 094(A)*Location* As 09(C). Doğankonak 3, at the foot of the same grave (Pl. 7.1.62 [p. 392])*Copy* DHF 11.viii.1978*Publication* RRMAM 2, 1. 725 (notice only)*Description* A simple cylinder. Broken at the top. Hard, pale limestone. Surface and letters: very worn*Dimensions* Ht (vis.) 1.17; diam. (top) 0.49*Text* illegible*Date* (?)**095. Doğankonak, form. Haydan, Kumocağı***Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-0*Map* Elbistan 91-Ik*Location* Now at Yalak; in the fore-court of the petrol-station, on the Kayseri-K. Maraş road, N of the Tufanbeyli junction. Brought by the owner, Osman Altinkaya, from a sand-quarry at Karaboğaz, c. 4 km SSE of the village.*Copy* DHF 15.vi.1977, 18.vi.1977. DHF squeeze and photo. (Pl. 7.1.63 [p. 393]) in BIA. Text here from DHF squeeze*BIA Collections:* *Squeeze and Stone Photographs*

Squeeze: 46. Maraş 08, Doğankonak, Kumocağı

Stone: (1) B/W Neg.: DHF R/77/07.09

*Publication* RRMAM 2, 1. 726 (notice only)*Description* A simple cylinder. Complete except for a new break at the top. Very hard, blue limestone. No plinth. Surface: some wear and damage.

Letters: mostly legible; irregular in shape and size

*Dimensions* Ht c. 1.70; diam. (top) 0.25. Letters: (text 1) 0.05-60, (text 2) 0.050-70*Text* (1) (in part underneath text [2])**Imper****Caesar M Au-**

(sic)

**re<li>o Anto[nio]**

4

**Gordiano**

[pio felici]

[Augusto]

[resti]tuerunt

8

**per Cuspidium**

[Fl]aminium S-

**everum lega-**

[tum] pro pra-

12

**etore m**

(vac)

**CXLI**

(vac)

**qua'**

line 8: Δ for D

line 12: **m** for **m**(ilia), cp. 056(B) (Sept. Sev.), 065 (Elag. + Sev. Alex.), 079(D), 084, 089(B), 093(H) and 097(C) (all Gordianus), 115 (Probus); also 104(J), 108(F), 114

(2) (over the top of lines 5-6 of text [1])

**Imp Caes  
Marco Aur  
Maximiano p f  
invicto Aug**

*Caput Viae* (Melitena)

*Date* (1) AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*

(2) AD 293–305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*

*Commentary* (Text [1]) For the survival of *restituerunt*, see above [p. 12], **Notes and Comments 3.5** Text-form (4).

(Text [2]) For an explanation of seemingly truncated, Tetrarchic texts, and here of Maximianus' apparent isolation from his colleagues, see above [p. 14], **Notes and Comments 3.6**.

### 096. Doğankonak, form. Haydan, Sakaltutan Boğazi

*Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-0

*Map* Elbistan 91-Ik

*Location* In the defile of Sakaltutan Boğazi, on the W side of the valley; c. 4 km SSE of the village

*Copy* DHF 10.viii.1978. DHF squeeze and photo. (Pl. 7.1.64 [p. 393]) in BIA. Text here from DHF squeeze

*BIA Collections: Squeeze and Stone Photographs*

Squeeze: 46. Maraş 09, Doğankonak, Sakaltutan Boğazi

Stone: (1) B/W Neg.: DHF R/78/11.10

*Publication* RRMAM 2, 1. 727 (notice only)

*Description* A simple cylinder. Broken above. Hard, blue limestone. The shaft tapers towards the top. No plinth. Surface: worn and damaged. Letters: worn; both texts were cut with a broad-blade chisel; (text 2) broken-bar A, diagonal-bar L

*Dimensions* Ht 1.74; diam. (top) 0.40, (bottom) 0.61. Letters: (text 1) c. 0.050, (distance numerals) P 0.080, (text 2) 0.055–65

*Text* (1) (on the full face of the shaft, from the top)

**Imp Çæş**  
[ - - - - ]  
[ - - - - ]  
4 [ - - - - ]  
[ - - - - ]  
[ - - - - ]  
[ - - - - ]  
8 [ - - - - ]  
**CANO**  
**. . T TOC**  
- - - -  
12 **quδ'**



(2) (on the top of text [1], l. 3 downwards)

**Gal Val**  
**2 Maximiano**  
**nobil Caes**

line 3: letters NobIL

*Caput Viae* (Melitena)*Date* (1) (?)(2) AD 293-305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares**Commentary* (Text [2]) For an explanation of seemingly truncated, Tetrarchic texts, and here of Galerius' apparent isolation from his colleagues, see above [p. 14], **Notes and Comments 3.6.****097(A). Doğankonak, form. Haydan, Şabanağa Mevkii 1***Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-0*Map* Elbistan 91-Ik*Location* *In situ*, on the N side of the Roman road; c. 2.2 km SE of the village.*Copy* DHF 09.viii.1978. DHF squeeze and photos (Pl. 7.1.65 [p. 393]) in BIA. Text here from DHF squeeze*BIA Collections:* *Squeeze and Stone Photographs*

Squeeze: 46. Maraş 10, Doğankonak, Şabanağa Mevkii 1

Stone: (1) B/W Neg.: DHF R/78/10.09 and 11.05

*Publication* RRMAM 2, 1. 728 (notice only)*Description* A simple cylinder. Complete. Hard, coarse crystalline, grey limestone. The shaft tapers slightly towards the top. No plinth. Surface: slightly worn, some damage. Letters: sharp and clear, neat in shape, size and alignment; broken-bar A, cursive F*Dimensions* Ht 1.77; diam. (top) 0.54, (bottom) 0.69. Letters: 0.060-70, (line 1) 0.090-11, (line 9) O 0.055, (line 13) 0.11 + 90*Text*

**Imp Caes**  
**divi Seve-**  
**ri nep divi**  
**4 M Antonini fil**  
**M Aur Añ-**  
**tonino pio feli-**  
**ci Aug milia**  
**8 restituta**  
**per M Ulp Ofel-**  
**lium Theod-**  
**orum leg Au-**  
**12 g pr pr**  
**ouß'**

*Caput Viae* (Melitena)*Date* Elagabalus *Augustus*, (?) AD 218, 16.v-(?) mid-June

**097(B). Doğankonak, form. Haydan, Şabanağa Mevkii 2**

*Province, Sub-Province + Admin. Code and Map* As 097(A)

*Location* As 097(A)

*Copy* DHF 09.viii.1978. DHF squeeze and photo. (Pl. 7.1.66 [p. 393]) in BIA. Text here from DHF squeeze

*BIA Collections: Squeeze and Stone Photographs*

Squeeze: 46. Maraş 11, Doğankonak, Şabanağa Mevkii 2

Stone: (1) B/W Neg.: DHF R/78/11.06

*Publication* RRMAM 2, 1. 729 (notice only)

*Description* A simple cylinder. (?)Complete. Friable, very coarse crystalline, grey limestone. The shaft tapers towards the top. No plinth. Surface and letters: extremely badly worn, some damage.

Letters: variable in size and alignment; (line 4) vertical cross for X, U for V

*Dimensions* Ht 1.82; diam. (bottom) 0.62. Letters: 0.50-65, (line 1) 0.075

*Text*

**Imp**  
[C]aes[ari G]  
**Iuli**[o Vero]  
4 **Maximino pio**  
**felici** (leaf) **inv**  
**Aug p m** (leaf) **tri-**  
[b pote]**st** (leaf) **p p**  
8 [[ - - - - ]]  
[[ - - - - ]]  
**leg Aug [pr] pr**  
**ρμβ'**

lines 8-9: [[per Licinnium | Serenianum]]

? traces of an earlier text, AU between ll. 1 and 2 on r., cut with a broad-blade chisel

*Caput Viae* (Melitena)

*Date* AD 235, ii/iii-236, 07.i/16.v Maximinus *Augustus*

*Commentary* For a near-complete text of Maximinus with the intact name of the governor, see below 107(D). Yağmurlu 4.

For the governorship of Licinnius Serenianus, see the discussion above [p. 11], **Notes and Comments 3.4.**

The dates for Maximinus *Augustus* without Maximus *Caesar* are given by Kienast (1996, 183-185).

**097(C). Doğankonak, form. Haydan, Şabanağa Mevkii 3**

*Province, Sub-Province + Admin. Code and Map* As 097(A)

*Location* As 097(A)

*Copy* DHF 09.viii.1978. DHF squeeze in BIA. Text here from DHF squeeze

*BIA Collections: Squeeze and Stone Photographs*

Squeeze: 46. Maraş 12, Doğankonak, Şabanağa Mevkii 3

*Publication* RRMAM 2, 1. 730 (notice only)

*Description* A simple cylinder. Complete. Hard, pale limestone. The shaft tapers towards the

top. No plinth. Surface: worn.

Letters: neat in shape, size and alignment, cut with a broad-blade chisel; Δ for D (lines 4 and 7), lunate E throughout

*Dimensions* Ht 2.21; diam. (bottom) 0.63. Letters: 0.055-70

*Text*

	<b>Imper</b>	
	<b>Caesar M-</b>	(sic)
	(9 cm space)	
	<b>arco Antoni-</b>	
4	<b>o Gordiano pi-</b>	
	<b>o felici Augus-</b>	
	<b>t (vac) o restitue-</b>	
	<b>runt per Cuspid-</b>	
8	<b>ium Flaminium</b>	
	<b>Severum legatu-</b>	
	<b>m pro praetor-</b>	
	<b>e m CXLII</b>	
12	<b>ουβ'</b>	

line 1: possible traces of earlier letters

line 11: **m** for **m**(ilia), cp. 056(B) (Sept. Sev.), 065 (Elag. + Sev. Alex.), 079(D), 084, 089(B), 093(H) and 095 (all Gordianus), 115 (Probus); also 104(J), 108(F), 114

*Caput Viae* (Melitena)

*Date* AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*

*Commentary* For the survival of *restituerunt*, see above [p. 12], **Notes and Comments 3.5**

Text-form (4). The text of this milestone is exceptionally well cut; there are no visible signs of erasure and re-cutting.

#### 097(D). Doğankonak, form. Haydan, Şabanağa Mevkii 4

*Province, Sub-Province + Admin. Code and Map* As 097(A)

*Location* As 097(A)

*Copy* DHF 10.viii.1978. DHF squeeze in BIA

*BIA Collections: Squeeze and Stone Photographs*

Squeeze: 46. Maraş 13, Doğankonak, Şabanağa Mevkii 4

*Publication* RRMAM 2, 1. 731 (notice only)

*Description* A simple cylinder. (?) Complete. The shaft is roughly worked. One inscription on a smooth, prepared surface; a second on the rough surface on the left of the first. Surface and letters: badly worn

*Dimensions* Ht 1.94; diam. (top) 0.35

*Text* (1) and (2)

both illegible

#### 097(E-F). Doğankonak, form. Haydan, Şabanağa Mevkii 5-6

*Province, Sub-Province + Admin. Code and Map* As 097(A)

*Location* As 097(A)

*Copy* DHF 09.viii.1978

*Publication* RRMAM 2, 1. 732 and 733 (notice only)

<i>Description</i>	(1) (= 5) a simple cylinder. Broken into two pieces, one large, one small (the upper piece). The shaft tapers slightly towards the top. (2) (= 6) a simple cylinder. Broken above and below. Hard, pale limestone. No plinth. The shaft tapers slightly towards the top.
<i>Dimensions</i>	(1) (= 5) ht 1.46; diam. (bottom) 0.52; (2) (= 6) ht 1.61; diam. (bottom) 0.43
<i>Text</i>	(1) and (2) no visible inscription

**098(A). Keklikoluk 1**

<i>Province, Sub-Province + Admin. Code</i>	K. Maraş, Göksun 46-04-0
<i>Map</i>	Elbistan 91-Ik
<i>Location</i>	“At Kürdkieu (called Kekli oghlu on the old map)” (Sterrett). Present whereabouts not known (DHF visit 10.viii.1978)
<i>Copy</i>	Sterrett 25 July, 1884. The stone has not been examined by DHF. Text here from Sterrett (facsimile of the printed version of Sterrett’s copy, Fig. 6.1.31 [p. 334])
<i>Publication</i>	Sterrett 1883-84, 256 no. 292 (facsimile, Fig. 6.1.31 [p. 334]) Sterrett 1885, 24 no. 21 CIL 3. 6946 (text of Sterrett) Hogarth and Munro 1893, 697 “137” (notice) Ramsay 1941, 97 no. 67 (text of Sterrett) French 1980, 725 no. 30 (text of CIL 3. 6946) RRMAM 2, 1. 806 (notice only) Loriot 1996, 226 n.17 and 227 no. 7 (comment on text of CIL 3. 6946) Baz 2007, 63 no. 10 (text from publications)
<i>Description</i>	“The stone never had numerals” (Sterrett)
<i>Dimensions</i>	Not given
<i>Text</i>	[Imp] Cae[s]- ar Marcu[s Iul] 4 Philippus pius f[elix] [i]nvictus Aug [et] [M]arcus Iul Philipp[us] [no]bilissimus Caes[ar] 8 [vi]as et pontes vet[us]- [t]ate conlapsas res[t]- [itueru]nt per Anton[i]u[m] [Mem]mium Hieronem 12 [v c l]eg Augg pr (sic) pr [ - ]

line 12: **AVGG**, “erreur de gravure - ou de lecture” (Loriot)

<i>Caput Viae</i>	[Melitena]
<i>Date</i>	AD 244, July/Aug.-247, July/Aug. Philippus <i>Augustus</i> with Philippus <i>Caesar</i>

**098(B). Keklikoluk 2**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 098(A)
<i>Location</i>	The stone is now at Göksun in the Kayabaşı or Eastern cemetery
<i>Copy</i>	Sterrett 25 July, 1884 (facsimile of the printed version of Sterrett's copy, Fig. 6.1.32 [p. 334]); DHF 03.viii.1978. DHF squeeze and photo. (Pl. 7.1.67 [p. 394]) in BIA. Text here from DHF squeeze.
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 46. Maraş 38, Keklikoluk 2 Stone: (1) B/W Neg.: DHF R/78/10.01
<i>Publication</i>	Sterrett 1883-84, 257 no. 293 (facsimile, Fig. 6.1.32 [p. 334]) Sterrett 1885, 24 no. 22 CIL 3. 6945 (text of Sterrett) Hogarth and Munro 1893, 697 "138" (notice) RRMAM 2, 1. 807 (notice only) Baz 2007, 62 no. 9 (text from publications)
<i>Description</i>	A simple cylinder. Broken at the top. Hard, blue limestone. The shaft tapers towards the top. No plinth. Surface and letters: well preserved but some damage to the surface. Letters: sharp and clear; broken-bar A
<i>Dimensions</i>	Ht (max.) 1.66; diam. (top) 0.44, (bottom) 0.66. Letters: 0.050-90, (line 4) O 0.040
<i>Text</i>	<p>[Imp Cae]şa- [ri G Iul] (leaf) <b>Ve-</b> [ro] <b>M̄a</b>[x]i- 4 <b>mino</b> (leaf) <b>pio</b> <b>felici</b> (leaf) <b>Aug</b> <b>tri</b>/b/ (leaf) <b>p</b> (leaf) [[p̄e]]- [[r Liçinnium]] 8 [[Serenian]]- [[um leg]] (leaf) <b>Aug</b> <b>pr pr</b> <b>ϥλη´</b></p>

line 6: R for B

<i>Caput Viae</i>	(Melitena)
<i>Date</i>	AD 235, ii/iii-236, 07.i/16.v Maximinus Augustus
<i>Commentary</i>	The dates for Maximinus Augustus without Maximus Caesar are given by Kienast (1996, 183-185).

### 098(C). Keklikoluk 6

<i>Province, Sub-Province + Admin. Code and Map</i>	As 098(A)
<i>Location</i>	In the village, in front of the house (no. 33) of Süleyman Duran
<i>Copy</i>	DHF 10.viii.1978. DHF squeeze in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 46. Maraş 39, Keklikoluk 6
<i>Publication</i>	RRMAM 2, 1. 811 (notice only)
<i>Description</i>	A simple cylinder. Broken into 3 pieces, one large, two small. Hard, pale

limestone. No plinth. Surface and letters: worn.

Letters: slightly irregular in shape, size and alignment; broken-bar A

*Dimensions* Ht (max.) 1.04; diam. (shaft) 0.52. Letters: 0.040-50

*Text*

-----  
 [ - - - - - ] **Au**[g]  
 [ - - - - - ] **mus**  
 -----  
 [ - - - - ] **M·Aurel·**  
 [Ant]**oninus·Aug**  
 [ - - - - - ]  
 [ - - - - ] **rest**  
 [ituerunt] **per·C·**  
**Iuliu**[m] **Flacc**  
**cum·[Ael]ianum·**  
**leg** [pr pr]  
 [ - ]

*Caput Viae* [Melitena]

*Date* AD 197/198(?), L. Septimius Severus and M. Aurelius Antoninus (Caracalla)  
*Augusti* with L. Septimius Geta *Caesar*, on the basis of the governor's  
 name. For an intact text of Septimius Severus, see above, 088(B). Kemer 4

#### 098(D). Keklikoluk 7

*Province, Sub-Province + Admin. Code and Map* As 098(A)

*Location* In the village; at the house of Bay Azimet Duman

*Copy* Necaddin Boybeyi (?date). Copy given to Dr Melih Arslan (of the Ankara  
 Museum) and conveyed to DHF 13.9.1990. Not seen by DHF 10.viii.1978

*Publication* Boybeyi and Probst 2008, 135 (text, photograph and comments)

SEG 58. 1663 (text of Boybeyi and Probst)

*Description* Not given. Letters (recorded in copy): Λ (= A), Δ for D, lunate E, V

*Dimensions* Ht 2.50

*Text*

**Imper**  
**Caesari Mar-**  
**co Antonio**  
 4 **Gordiano pi-**  
**o felici Aug-**  
**usto restitu-**  
**erunt per Cu-**  
 8 **spidium Fla-**  
**minium Severu**[m]  
**legatum pr pr-**  
**aetore** /μ/  
 (vac)  
 12 Ϡλζ'

line 11: /I/ (lapis); μ for μ(ίλια), cp. 107(G), 108(D) and 109(C) (Elagabalus), 119(A)  
 (Severus Alex.), 068(C), 072(C), 074(C), 075(C), 080(B), 087(B), 104(B) and 108(M)

(all Gordianus), 085(B) (Maximinus), 119(B) (Philippus); also 112

*Caput Viae* (Melitena)

*Date* AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*

*Commentary* For the survival of *restituerunt*, see above [p. 12], **Notes and Comments 3.5**

*Text-form* (4).

For the date of Gordianus' *dies imperii*, Summer AD 238, see Boybeyi and Probst (2007, 137 n.12)

### 099. Keklikoluk 3

*Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-0

*Map* Elbistan 91-Ik

*Location* “Half an hour S of Kürdkieu there is a milliarium almost entirely buried, and it was impossible for us to unearth it” (Sterrett)

*Copy* Sterrett 25 July, 1884

*Publication* Sterrett 1883-84, 256

RRMAM 2, 1. 808 (notice only)

*Description & Dimensions* Not given

*Text* No visible text

### 100(A). Keklikoluk 4

*Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-0

*Map* Elbistan 91-Ik

*Location* “One mile from Keklik oğlu, on the road towards Gyüksun” (Hogarth and Munro). Present whereabouts not known (DHF visit 10.viii.1978)

*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Hogarth and Munro (facsimile of the printed version of their copy, Fig. 6.1.33 [p. 334])

*Publication* Hogarth and Munro 1893, 697 “136 (i)” (facsimile, Fig. 6.1.33 [p. 334])

CIL 3. 12195 (text of Hogarth and Munro)

RRMAM 2, 1. 809 (notice only)

*Description* “Upper part erased” (Hogarth and Munro)

*Dimensions* Not given

*Text*

[Imp Caes]

[G Iulio Vero]

[Max]imino pio

4 [fel]ici Aug trib

[pot pont max]

[pe]r L[ici]n[nium]

[Serenianum leg] Aug

8 pr pr

ρλς'

*Caput Viae* (Melitena)

*Date* AD 235, ii/iii–236, 07.i/16.v Maximinus *Augustus*

*Commentary* The name of the governor in lines 6–7 and the imperial titles in the preceding lines have been restored on the basis of the near-intact texts found on two milestones (of Maximinus) erected along the Caesaria-Melitena road: 085(B). Mollahüseyin 2 and 098(B). Keklikoluk 2.

The dates for Maximinus *Augustus* without Maximus *Caesar* are given by Kienast (1996, 183-185).

### 100(B). Keklikoluk 5

*Province, Sub-Province + Admin. Code and Map* As 100(A)

*Location* As 098(A). Present whereabouts not known (DHF visit 10.viii.1978)

*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Hogarth and Munro (facsimile of the printed version of their copy, Fig. 6.1.34 [p. 335])

*Publication* Hogarth and Munro 1893, 697 “136 (ii)” (facsimile, Fig. 6.1.34 [p. 335])  
CIL 3. 12196 (text of Hogarth and Munro)  
French 1980, 725 no. 32 (text from CIL 3. 12196)  
RRMAM 2, 1. 810 (notice only)

*Description & Dimensions* Not given

*Text*

Im[p]  
Cae[sar]  
[G] **Vivi**[us Trebo]-  
4 n[ianus] **Gal**[lus]  
e[t I]**mp** [Caesar]  
[G] **Vivius**  
[V]elmun[ia]- (sic)  
8 [n]us **Volu**[sia]-  
[n]us **pīi felice**[s in]-  
[vict] **Aug**[g vias]  
[e]t **pontes** [vet]-  
12 **ustate con**[l]-  
[a]psas **restitu**[e]-  
r[u]nt per A V[irgilium]  
**Maximum** [v c]  
16 [leg] **Aug**[g] **pr** [pr]  
(leaf)  
[ - ]

lines 3 and 6-7: for the mis-spellings, **Vivius** for **Vibius**, see below, 108(L).  
Kanlıkavak 12 and 141. Yıldıztepe

*Caput Viae* [Melitena]

*Date* AD 251, Aug.(?)-253, Aug.(?) Trebonianus Gallus and Volusianus *Augusti*

### 101(A)-(E). Keklikoluk, Kayapınar Mevkii 1-5

*Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-0

*Map* Elbistan 91-Ik

*Location* *In situ*, on W side of the Roman road; c. 2.5 km S of the village

*Copy* DHF 10.viii.1978. DHF photo. in BIA

*Publication* RRMAM 2, 1. 812-816 (notice only)

*Description* (1) A simple cylinder with a square plinth. Complete but chipped at the top.  
Hard, white crystalline limestone. The shaft tapers towards the top. Surface and letters: very worn (Pl. 7.1.68 [p. 394])  
(2)-(5) a simple cylinder



<i>Dimensions</i>	(1) Ht 1.97; diam. (top) 0.44; (2)-(5) not recorded
<i>Text</i>	All are illegible but the distance-figure may be restored as $\rho\lambda\eta'$

**Keklikoluk**

“There are also two uninscribed stones at Kürdkeui” (Sterrett 1883-84, 258). “Also, two uninscribed stones are at Kekli Oghlou” (Sterrett 1885, 24)

**102(A)-(C). Mürsel 1-3**

<i>Province, Sub-Province + Admin. Code</i>	K. Maraş, Göksun 46-04-0
<i>Map</i>	Elbistan 91-II
<i>Location</i>	In the village: (1) in the front of a house on the NE side of the cami, (2) buried at the corner of the house of Mehmet Gök, (3) at the house of Mustafa Topuz
<i>Copy</i>	DHF 11.viii.1978
<i>Publication</i>	(1) and (2) RRMAM 2, 1. 819-820 (notice only)
<i>Description &amp; Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

**102(D)-(G). Mürsel 4-7**

In 1974 I observed four inscribed milestones lying *in situ* beside the Roman road at a point c. 50 m W of the modern highway (to Göksun) and c. 400 m N of the road-bridge over the bed of a gully, a little to the N of a group of road-side houses and structures c. 1.80 km due E of Mürsel. When I returned in 1978 (with a permit and a Ministry representative) the four stones had disappeared. Since the distance-figure may be restored as  $\rho\lambda\zeta'$  the milestone (096[D]. Keklikoluk 7) now at Keklikoluk may perhaps be one of the four. In 1974, I noted the name Philippus on one.

**103(A). Mehmetbey 1**

<i>Province, Sub-Province + Admin. Code</i>	K. Maraş, Göksun 46-04-0
<i>Map</i>	Elbistan 91-Ik
<i>Location</i>	“In the cemetery” (Sterrett); “in the graveyard near Mehmetbey, on the high road to Gyusun; right of the road” (Hogarth and Munro). In a grove of poplars, c. 25 m NW of the old cemetery where 101(B) is located; c. 50 m W of the modern road to Göksun; owned by Rifat Arıcı
<i>Copy</i>	Sterrett 25 July, 1884; Hogarth and Munro 1891; DHF 11.viii.1978. DHF squeeze and photo. (Pl. 7.1.69 [p. 394]) in BIA. Text here of Sterrett (facsimile of the printed version of Sterrett’s copy, Fig. 6.1.35 [p. 335]), and Hogarth and Munro (facsimile of the printed version of their copy, Fig. 6.1.36 [p. 335]) and from DHF squeeze.
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 46. Maraş 41, Mehmetbey 1 Stone: (1) B/W Neg.: DHF R/78/12.05
<i>Publication</i>	Sterrett 1883-84, 254 nos 288-289 (facsimile, Fig. 6.1.35 [p. 335]) Sterrett 1885, 23 no. 19 CIL 3. 6944 (text of Sterrett) Hogarth and Munro 1893, 698 “131” (facsimile, Fig. 6.1.36 [p. 335]) RRMAM 2, 1. 817 (notice only) French 2008, 133 (text [2] and comments)

*Description* A simple cylinder. Broken at the top. Hard, white crystalline limestone. No plinth. Surface and letters: very worn. Letters: faint and indistinct

*Dimensions* Ht (vis.) 1.51; diam. (top) 0.42. Letters: (text 1) c. 0.045, (text 2) c. 0.075

*Text* (1) (on the full face of the shaft)

[I]m̄p̄ Cae[s]  
 2 [ - - - - - ]  
 P̄h̄ilipp̄us p̄iū[s felix]  
 4 in̄v̄[i]c̄[t]ūs [Augustus et]  
 [Marc]ūs Iūli[us Philippus]  
 6 nobilis[simus Caes]ar  
 vias [et pontes ve]tus-  
 8 tate cō[nlapsas res]tit-  
 uerunt p[er Antoniu]m Me-  
 10 mmium Hie[ro]nem v c leg  
 g A[ug pr pr]  
 12 [ - ]

(2) (on the top of the lines 3-7 of text [1])

Imp CC C  
 2 diocletiano  
 p f  
 4 Augg

line 1: **Imp**(eratoribus) **C**(esaribus)

*Caput Viae* [Melitena]

*Date* (1) AD 244, July/Aug.-247, July/Aug. Philippus *Augustus* with Philippus *Caesar*  
 (2) AD 293-305 Diocletianus and Maximianus *Augusti* with Constantinus and Galerius *Caesares*

*Commentary* (Text [1]) the full text can be restored on the basis of the intact example above, 068(D). Aslanbeyli Yaylası, Hanboğazı 4.

(Text [2]) For an explanation of seemingly truncated, Tetrarchic texts, see above [p. 14], **Notes and Comments 3.6**.

### 103(B). Mehmetbey 2

*Province, Sub-Province + Admin. Code and Map* As 103(A)

*Location* In a disused cemetery, now an orchard; c. 25 m SE of the poplar grove where 101(A) is located. Beside and W of the modern road to Göksun. The orchard is owned by Behzat Polat.

*Copy* Sterrett 25 July, 1884 (facsimile of the printed version of Sterrett's copy, Fig. 6.1.37 [p. 335]); Hogarth and Munro 1891; DHF 11.viii.1978. DHF squeeze in BIA. Text here from DHF squeeze

*BIA Collections:* *Squeeze and Stone Photographs*

Squeeze: 46. Maraş 42, Mehmetbey 2

*Publication* Sterrett 1883-84, 255 nos 290-291 (facsimile, Fig. 6.1.37 [p. 335])

Sterrett 1885, 23 no. 20

CIL 3. 6942/3 (text of Sterrett)

Hogarth and Munro 1893, 698 "130 ?(i)" (notice)

	Cousin 1905, 365 RRMAM 2, 1. 818 (notice only) French 2008, 133 (text [2] and comments)
<i>Description</i>	A simple cylinder. Broken below. Hard, fine crystalline limestone. The shaft tapers slightly towards the top. Surface and letters: worn. Letters: (text 1) some faint and indistinct, mostly legible; neat in shape, size and alignment, (text 2) clear, cut with a broad-blade chisel, broken-bar A, cursive F, U for V
<i>Dimensions</i>	Ht (ex.) 1.51; diam. (top) 0.42. Letters: (text 1) 0.040-50, (text 2) c. 0.060 but F and SS 0.10
<i>Text</i>	(1) (in part underneath text [2]) <div style="text-align: center;"> <b>Imp Caes -</b>  <b>ar Marcus</b>  <b>[I]ul Philippus piu-</b>  4 <b>[s] felix invictus</b>  <b>Aug et Marcus Iul</b>  <b>[P]hilippus nobilissi-</b>  <b>[m]us Caesar vias</b>  8 <b>[et] pontes vetus-</b>  <b>[tat]e conlapsas r-</b>  <b>[es]tituer&lt;unt&gt; per An-</b>  <b>[ton]ium Memmium Hie-</b>  12 <b>[ron]em v c [leg Aug]</b>  <b>[pr pr]</b>  <b>[ - ]</b> </div> (2) (on the top of lines 12-14 of text [1]) <div style="text-align: center;"> <b>et F' Val</b>  <b>Constantio</b>  <b>nob Ca[e] -</b>  <b>ss</b> </div>

line 1: **F'** for **F**(lavius)

lines 3-4: **NOB**; **nob Caelss** for **nob<b> Caelss**, cp. 105(C). Göksun 10, where it occurs below Galerius' name

<i>Caput Viae</i>	[Melitena]
<i>Date</i>	(1) AD 244, July/Aug.-247, July/Aug. Philippus <i>Augustus</i> with Philippus <i>Caesar</i> (2) AD 293-305 Diocletianus and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i>
<i>Commentary</i>	For an explanation of seemingly truncated, Tetrarchic texts, see above [p. 14],
<b>Notes and Comments 3.6.</b>	

### 104(A). Göksun 1

<i>Province, Sub-Province + Admin. Code</i>	K. Maraş, Göksun 46-04-0
<i>Map</i>	Elbistan 91-Im
<i>Location</i>	" . . . in the western cemetery" (Sterrett); "at Gyuksun" (Hogarth and Munro). Present whereabouts not known (DHF visit 10.viii.1978)

<i>Copy</i>	Clayton 1881; Sterrett 23 July, 1884; Hogarth and Munro 1891. The stone has not been examined by DHF 04.viii.1978. Text here of Sterrett (facsimile of the printed version of Sterrett's copy, Fig. 6.1.38 [p. 336]) and from CIL (copy of Clayton and Sterrett).
<i>Publication</i>	Waddington 1883, 145 (copy of Clayton) Mommsen 1884a, 36 no. 74 (text of Clayton <i>apud</i> Waddington) Sterrett 1883-84, 240 no. 269 (facsimile, Fig. 6.1.38 [p. 336]) Sterrett 1885, 20 no. 13 Hogarth and Munro 1893, 698 "133" (notice) CIL 3. 6930 (text of Sterrett and Clayton) RRMAM 2, 1. 750 (notice only)
<i>Description &amp; Dimensions</i>	Not given

<i>Text</i>	<b>Imp</b> <b>Caes</b> <b>divi Severi nep</b> 4 <b>divi M Antonini</b> (vac) <b>fil</b> (vac) <b>M Aur Antonino</b> <b>pio felici Aug</b> 8 <b>milia restituta-</b> <b>per M Ulp Ofelli-</b> <b>um Theodorum</b> <b>leg Aug</b> 12 <b>pr pr</b> <b>Ϡλγ'</b>
-------------	---

<i>Caput Viae</i>	(Melitena)
<i>Date</i>	Elagabalus <i>Augustus</i> , (?) AD 218, 16.v-(?) mid-June

**104(B). Göksun 2**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 104(A)
<i>Location</i>	As 104(A). Present whereabouts not known (DHF visit 10.viii.1978)
<i>Copy</i>	Sterrett 23 July, 1884 (facsimile of the printed version of Sterrett's copy, Fig. 6.1.39 [p. 336]); Hogarth and Munro 1891. The stone has not been examined by DHF (visit 04.viii.1978). Text here of Sterrett
<i>Publication</i>	Sterrett 1883-84, 241 nos 270-271 (facsimile, Fig. 6.1.39 [p. 336]) Sterrett 1885, 21 no. 14 AE 1888. 181 (text of Sterrett) CIL 3. 6934/5 (text of Sterrett) Hogarth and Munro 1893, 696 "141 (ii)" (notice) RRMAM 2, 1. 751 (notice only)
<i>Description</i>	"Stone very rough and inscription hard to read" (Sterrett 1883-84)
<i>Dimensions</i>	Not given
<i>Text</i>	(1) and (2) (CIL 6934) ----- <b>Antonius Gordia-</b> <b>nus [n]obilis(s)imus</b>

4 [Ca]esar restituit  
 (vac) per Cuspidi-  
 [um Fl]aminium Se-  
 verum legat pr (sic)  
 8 (vac) pr(a)etore μ  
 quā'

lines 4-5: was **RESTITUERUNT** recut to **RESTITUIT**, i.e. **-erlunt** to **-it** | (vac); cp. the remarks of Harper on 094(H). Yalak 12

line 8: **PRETOREM** (Sterrett); μ for μ(ιλια), cp. 107(G), 108(D) and 109(C) (Elagabalus), 119(A) (Severus Alexander), 068(C), 072(C), 074(C), 075(C), 080(B), 087(B), 098(D) and 108(M) (all Gordianus), 085(B) (Maximinus), 119(B) (Philippus); also 112

For a restoration of the missing lines, see the version above, 087(B). Kemer 2

(3) (CIL 6935) (? above text [1])  
 [et?] Gal Val  
 [Ma]ximiano  
 [no]bil Caes[?s]

*Caput Viae* (Melitena)  
*Date* (1) AD 238, 31.i/01.ii-beg. May Pupienus and Balbinus *Augusti* with Gordianus *Caesar*, then (2) (Pupienus and Balbinus erased) AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*  
 (2) AD 293–305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*  
*Commentary* (Text 1) For the erasure of Pupienus and Balbinus, see above [p. 12], **Notes and Comments 3.5** Text-form (3).  
 (Text 2) For an explanation of seemingly truncated, Tetrarchic texts and for the apparent isolation of individuals from their colleagues in the Tetrarchy, see above [p. 14], **Notes and Comments 3.6**.

### 104(C). Göksun 3

*Province, Sub-Province + Admin. Code and Map* As 104(A)  
*Location* “In the southern cemetery” (Sterrett 1883–84 and 1885). The southern cemetery is called ‘Kerpetenlik mezarlığı’.  
*Copy* Sterrett 23 July, 1884 (facsimile of the printed version of Sterrett’s copy, Fig. 6.1.40 [p. 336]); Hogarth and Munro 1891; DHF 04.viii.1978. DHF squeeze and photo. (Pl. 7.1.70 [p. 395]) in BIA. Text here from DHF squeeze.  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 15, Göksun 3  
 Stone: (1) B/W Neg.: DHF R/78/10.02  
*Publication* Sterrett 1883–84, 244 nos 272–273 (facsimile, Fig. 6.1.40 [p. 336])  
 Sterrett 1885, 21 no. 15  
 CIL 3. 6933 (text of Sterrett)  
 Hogarth and Munro 1893, 696 “141 (iii)” (notice)  
 RRMAM 2, 1. 752 (notice only)  
*Description* A simple cylinder. Complete. Hard, pale limestone. The shaft tapers towards the top. Surface: very worn.

Letters: (text 1) worn but clear and legible, neat in shape, size and alignment;  
(both texts) cut with a broad-blade chisel (both texts) broken-bar A, (text 2) lunate E

*Dimensions* Ht 1.92; diam. (top) 0.46. Letters: (text 1) 0.060-70 but 0.13 (line 1), (text 2) 0.060-70

*Text* (1) (in part underneath text [2])

**Imp**  
**Caesar G Iul**  
**Verus Maximinu[s]**

4 [ - - - - ]  
[ - - - - ]  
[ - - - - ]  
[ - - - - ]

8 **nobilissimus Caes[ar]**  
**vias et pontes vetu-**  
**state conlabsas res-**  
**tituerunt** (sic)

12 **per** [[ - - - - ]]  
[[ - - - - ]] **leg**  
**Augg pr pr** (sic)  
**CXLI ρμϱ'**

lines 12-13: **per** [[Licinnium]] | [[Serenianum]] **leg**

(2) (on top of lines 4-7 of text [1])

**Imp Caes**  
**Gaio Val**  
**Diocletiano**  
**p f invicto Aϰ[g]**

*Caput Viae* (Melitena)

*Date* (1) AD 236, 07.i/16.v-238, mid. iv Maximinus *Augustus* with Maximus *Caesar*  
(2) AD 293-305 Diocletianus and Maximianus *Augusti* with Constantius and  
Galerius *Caesares*

*Commentary* (Text [1]) The lost lines can be restored on the basis of the intact example above, 085(D). Mollahüseyin 4, where, as here, the name of the legate has been erased. For the governorship of Licinnius Serenianus, see the discussion above [p. 11], **Notes and Comments 3.4**. For the double g in **Augg** (line 9) there is a parallel on Göksun 3 (below, 104[C] line 14), a milestone of Maximinus as sole Augustus with Maximus *Caesar*. The dates for Maximinus *Augustus* with Maximus *Caesar* are given by Kienast (1996, 183-185). (Text [2]) For an explanation of seemingly truncated, Tetrarchic texts and for the apparent isolation of individuals from their colleagues in the Tetrarchy, see above [p. 14], **Notes and Comments 3.6**.

#### 104(D). Göksun 4

*Province, Sub-Province + Admin. Code and Map* As 104(A)

*Location* As 104(C)

*Copy* Sterrett 23 July, 1884 (facsimile of the printed version of Sterrett's copy,

Fig. 6.1.41 [p. 336]); DHF 04.viii.1978. DHF squeeze and photo. (Pl. 7.1.71 [p. 395]) in BIA. Text here from DHF squeeze.

*BIA Collections:* *Squeeze and Stone Photographs*

Squeeze: 46. Maraş 14, Göksun 4

Stone: (1) B/W Neg.: DHF R/78/10.05

*Publication* Sterrett 1883-84, 245 nos 274-275 (facsimile, Fig. 6.1.41 [p. 336])

Sterrett 1885, 22 no. 16

CIL 3. 6931 (text of Sterrett)

Hogarth and Munro 1893, 699 “125 ?(i)” (notice)

RRMAM 2, 1. 753 (notice only)

*Description* A simple cylinder. At the bottom, broken diagonally across the shaft. Hard, pale limestone. The shaft tapers slightly towards the top. Surface and letters: very slightly worn. Letters: (text 1) sharp and clear but uneven in shape, size and alignment; broken-bar A, (text 2) variable in size, shape and alignment

*Dimensions* Ht (max.) 1.53; diam. (top) 0.42, (bottom) 0.52. Letters: (text 1) 0.040-70, (line 1) 0.080-10, (text 2) 0.070-90

*Text* (1) (on the full face of the shaft)

**Imp Caes**  
**divi Severi**  
**nep divi M**  
4 **Antonini fil**  
**M Aur Anton-**  
**ino pio fe-**  
8 **lici Aug**  
**milia re-**  
**stituta per**  
**M Ulp Ofel-**  
**lium Th[eod]-**  
12 **o[rum leg Aug]**  
**[pr pr]**  
**[ - ]**

(2) over the top of ll. 3-7 of text [1])

**et Gal Val**  
2 **Maximiano**  
**nobb Cae-**  
**ss**

*Caput Viae* [Melitena]

*Date* (1) Elagabalus *Augustus*, (?) AD 218, 16.v-(?) mid-June

(2) AD 293-305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*

*Commentary* For an explanation of seemingly truncated, tetrarchic texts, see above [p. 14],  
**Notes and Comments 3.6.**

### 104(E). Göksun 5

*Province, Sub-Province + Admin. Code and Map* As 104(A)

*Location* As 104(C)

*Copy* Sterrett 23 July, 1884 (facsimile of the printed version of Sterrett's copy,

Fig. 6.1.42 [p. 336]); DHF 04.viii.1993. DHF squeeze and photo. (Pl. 7.1.72 [p. 395]) in BIA. Text here from DHF squeeze

*BIA Collections:* *Squeeze and Stone Photographs*

Squeeze: 46. Maraş 17, Göksun 5

Stone: (1) B/W Neg.: DHF R/78/10.06

*Publication* Sterrett 1883-84, 246 no. 276 (facsimile, Fig. 6.1.42 [p. 336])

Sterrett 1885, 22 no. 17

CIL 3. 6940 (text of Sterrett)

Hogarth and Munro 1893, 699 “130 (ii)” (notice)

RRMAM 2, 1. 754 (notice only)

*Description* A simple cylinder. Broken at top left. Hard, pale limestone. The shaft tapers towards the top. No plinth. Surface: very worn.

Letters: some clear and sharp, others faint and indistinct, irregular in size; diagonal-bar A

*Dimensions* Ht 2.09; diam. (top) 0.41, (bottom) 0.62. Letters: 0.055-70 but O (line 10) 0.040

*Text*

[I]mp Cae[s]  
[d]ivi Severi  
nep divi [M]  
4 Antonin[i]  
f[il M Aur]  
[Antonino]  
pio felici [Aug]  
8 [m]ilia resti[tut]-  
a per M [U]-  
lpium Ofelli[um]  
[Th]eodorum leg  
12 pr pr  
ολδ'

*Caput Viae* (Melitena)

*Date* Elagabalus *Augustus*, (?) AD 218, 16.v-(?) mid-June

#### 104(F). Göksun 6

*Province, Sub-Province + Admin. Code and Map* As 104(A)

*Location* As 104(C)

*Copy* Sterrett 23 July, 1884 (facsimile of the printed version of Sterrett's copy, Fig. 6.1.43 [p. 337]); Hogarth and Munro 1891 (facsimile of the printed version of Hogarth and Munro's copy, Fig. 6.1.43 [p. 337]); DHF 04.viii.1978. DHF squeeze and photo. (Pl. 7.1.73 [p. 395]) in BIA. Text here Sterrett, Hogarth and Munro, and from DHF squeeze.

*BIA Collections:* *Squeeze and Stone Photographs*

Squeeze: 46. Maraş 18, Göksun 6

Stone: (1) B/W Neg.: DHF R/78/10.07

*Publication* Sterrett 1883-84, 247 no. 277 (facsimile, Fig. 6.1.43 [p. 337])

Sterrett 1885, 22 no. 18

CIL 3. 6939 (text of Sterrett)

Hogarth and Munro 1893, 699 “125 (ii)” (facsimile, Fig. 6.1.44 [p. 337])

CIL 3. 12187 (text of Hogarth and Munro)



	French 1985b, 151 and n.21 (notice, and excerpt from text) RRMAM 2, 1. 755 (notice only)
<i>Description</i>	A simple cylinder. Broken at the top. Hard, pale limestone. No plinth. Surface: very worn. Letters: very worn in patches, especially on the right-hand side, some letters clear, others faint or illegible; variable in size, shape and alignment; broken-bar A
<i>Dimensions</i>	Ht 1.68; diam. (top) 0.47. Letters: (text 1) c. 0.050, (text 2) 0.050-80, O (line 7) 0.040
<i>Text</i>	(1) (underneath [2]) <div style="text-align: center;"> <b>Imp Cae[s]</b>  [divi Severi nep]  [divi M Antonini  4 [fil M] <b>Aureli[us]</b>  [Antoni]n[us]  [pius felix]  [i]nv[ict Aug]  8 - - - - </div> (2) (lines 1-5 on the top of text [1]) <div style="text-align: center;"> <b>Imp Cae[s]</b>  [M] (leaf) [Aure]lius S-  [everus Alex]-  4 [ander pius]  <b>fe[lix Aug]</b>  <b>trib</b> (leaf) <b>ῥο[test]</b>  <b>cos</b> (leaf) <b>ῑ ῑ</b> (leaf) <b>vias et pon-</b>  8 <b>tes vettusta[te co]-</b> (sic)  <b>nlapsas restitu-</b>  <b>it</b> (leaf) <b>ῥϛς'</b> </div>

line 8: for the mis-spelling **vettustate**, see also 118(C), 119(A) and Bolatcık (RRMAM 3. 58), all texts of Severus Alexander

<i>Caput Viae</i>	(Melitena)
<i>Date</i>	(1) Elagabalus <i>Augustus</i> , AD 218, 16.v-(?) mid-June (2) AD 222, 14(?).v-09.xii Severus Alexander <i>Augustus</i>
<i>Commentary</i>	Hogarth and Munro (1893, 699 n.) read the two texts as one and deciphered the whole as a milestone of Aurelianus. My squeeze shows clear indication of alterations for which there is a parallel at Izgın, Çatburun Boğazı 3 (116[C], below). Mommsen (in CIL ) also came to the same conclusion, cp. the remarks of Hogarth and Munro (l.c.): “Prof. Mommsen (in Addit. Suppl., vol. iii, CIL) is of <the> opinion that this stone has been miscopied, and should be ascribed to Alexander Severus and read as No.152ii [- here 085(A). Kemer 1] “

### 104(G). Göksun 7

<i>Province, Sub-Province + Admin. Code and Map</i>	As 104(A)
<i>Location</i>	“In the southern cemetery at Gyuksun” (Hogarth and Munro). Present whereabouts not known (DHF visit 10.viii.1978)
<i>Copy</i>	Hogarth and Munro 1891. The stone has not been examined by DHF

	04.viii.1978. Text here of Hogarth and Munro (facsimile of the printed version of Hogarth and Munro's copy, Fig. 6.1.45 [p. 337])
<i>Publication</i>	Hogarth and Munro 1893, 696 "141 (i)" (facsimile, Fig. 6.1.45 [p. 337]) CIL 3. 12190 (text of Hogarth and Munro) RRMAM 2, 1. 756 (notice only)
<i>Description</i>	"Much defaced" (Hogarth and Munro)
<i>Dimensions</i>	Not given
<i>Text</i>	(1) Consult the facsimile (Fig. 6.1.45 [p. 336])
	(2) "On the opposite side the following letters of another inscription can be read:- ,,

- - - -  
 [ - - - - p]er  
 [M Ulpiu]m Theo-  
 [dorum - - ]  
 - - - -

<i>Date</i>	(1) (?) (2) AD 218 Elagabalus, on the basis of the governor's name; cp. the intact text, 068(B). Aslanbeyli Yaylası, Hanboğazı 2
-------------	---

#### 104(H). Göksun 19

<i>Province, Sub-Province + Admin. Code and Map</i>	As 104(A)
<i>Location</i>	In the southern cemetery, Kerpetenlik mezarlığı
<i>Copy</i>	DHF 05.viii.1978. DHF squeeze and photo. (Pl. 7.1.74 [p. 396]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 46. Maraş 21, Göksun 19 Stone: (1) B/W Neg.: DHF R/78/10.04
<i>Publication</i>	RRMAM 2, 1. 768 (notice only)
<i>Description</i>	A simple cylinder. Broken at the top front and at the bottom front. Hard, grey limestone. The shaft tapers slightly towards the top. No plinth. Surface: very worn. Letters: faint and indistinct
<i>Dimensions</i>	Ht 1.73; diam. (top) 0.41. Letters: 0.050-80
<i>Text</i>	- - - - M . IO 4 .. P [milia resti]- [t]ut[a per] M Ulp Ofelliu[m] 8 Theodorum leg Aug pr [pr] [ - ]

<i>Caput Viae</i>	[Melitena]
<i>Date</i>	AD 218 Elagabalus <i>Augustus</i> , on the basis of the governor's name; cp. the intact text, 068(B). Aslanbeyli Yaylası, Hanboğazı 2
<i>Commentary</i>	Perhaps the same stone as 102(G) (The stone has not been examined by DHF)

**104(I). Göksun 13**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 104(A)
<i>Location</i>	“In the eastern cemetery at Gyüksun” (Hogarth and Munro). The eastern cemetery is called ‘Kayabaşı mezarlığı’. Present whereabouts not known (DHF visit 10.viii.1978)
<i>Copy</i>	Hogarth and Munro 1891. The stone has not been examined by DHF 04.viii.1993. Text here of Hogarth and Munro (facsimile of the printed version of Hogarth and Munro’s copy, Fig. 6.1.46 [p. 338])
<i>Publication</i>	Hogarth and Munro 1893, 698 “134” (facsimile, Fig. 6.1.46 [p. 338]) CIL 3. 12188 (text of Hogarth and Munro) RRMAM 2, 1. 762 (notice only)
<i>Description</i>	“Much defaced” (Hogarth and Munro)
<i>Dimensions</i>	Not given
<i>Text</i>	Consult the facsimile (Fig. 6.1.46 [p. 338])
<i>Date</i>	(?)

**104(J). Göksun 14**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 104(A)
<i>Location</i>	As 104(I). Present whereabouts not known (DHF visit 04.viii.1978)
<i>Copy</i>	Hogarth and Munro 1891. The stone has not been examined by DHF 04.viii.1978. Text here of Hogarth and Munro
<i>Publication</i>	Hogarth and Munro 1893, 698 “132” CIL 3. 12189 (text of Hogarth and Munro) RRMAM 2, 1. 763 (notice only)
<i>Description</i>	“Only the numeral is legible” (Hogarth and Munro)
<i>Dimensions</i>	Not given
<i>Text</i>	<p>-----  <b>m CXXXII</b> ϰλ[β’]</p> <p><b>m</b> for <b>m</b>(ilia), cp. 056(B) (Sept. Severus), 065 (Elagabalus + Severus Alexander), 079(D), 084, 089(B), 093(H), 095 and 097(C) (all Gordianus), 115 (Probus); also 108(F), 114</p>

<i>Caput Viae</i>	(Melitena)
<i>Date</i>	(?)

**104(K). Göksun 17**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 104(A)
<i>Location</i>	“Brücke . . . ; auf der Strasse nach Seiton” (Grothe). Present whereabouts not

	known (DHF visit 04.viii.1978)
<i>Copy</i>	Grothe 1906/07. The stone has not been examined by DHF. Text here of Grothe (facsimile of the printed version of Grothe's copy, Fig. 6.1.47 [p. 338])
<i>Publication</i>	Grothe 1911, 1, LXXXV no. 41 (facsimile, Fig. 6.1.47 [p. 338]) AE 1912. 290 (text of Grothe) RRMAM 2, 1. 766 (notice only)
<i>Description</i>	"Meilenstein, aus Marmor, schlecht erhalten" (Grothe)
<i>Dimensions</i>	Not given
<i>Text</i>	Consult the facsimile (Fig. 6.1.47 [p. 337])
<i>Date</i>	(?)

**104(L). Göksun 18**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 104(A)
<i>Location</i>	"Gökssun, nahe Brücke über Gökssün-ssu auf der Strasse nach Seitun" (Grothe). Present whereabouts not known (DHF visit 04.viii.1978)
<i>Copy</i>	Grothe 1906/07. The stone has not been examined by DHF 04.viii.1978. Text here of Grothe (facsimile of the printed version of Grothe's copy, Fig. 6.1.48 [p. 338])
<i>Publication</i>	Grothe 1911, 1 LXXXV no. 42 (facsimile, Fig. 6.1.48 [p. 338]) RRMAM 2, 1. 767 (notice only)
<i>Description</i>	"Die Abschrift gibt die unterstrichenen Buchstaben" (Grothe)
<i>Dimensions</i>	Not given
<i>Text</i>	<div style="display: flex; align-items: center;"> <div style="margin-right: 20px;"> <p>[Imp C]<u>ae</u>[sar]</p> <p>2 [L Septimius S]<u>everus</u></p> <p>[Pius Pertina]<u>x Aug</u> [Arab Adiab]</p> <p>4 [Parth max p]<u>on</u>[t] <u>m</u>[ax trib pot VI]</p> <p>[imp XI cos III p p ] <u>proco</u>[s]</p> <p>6 - - - -</p> </div> </div>

<i>Caput Viae</i>	[Melitena]
<i>Date</i>	AD 198/197(?), L. Septimius Severus [and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta <i>Caesar</i> ]
<i>Commentary</i>	Grothe (1911, 1, LXXXV no. 42) wrote: "Veröffentlicht: CIL 3. 12186", but this stone (CIL 3. 12186, here 103[A]) was found in a cemetery E of Göksun. Moreover it was (and still is) in an excellent state of preservation. Accordingly, I have assigned a separate number to Grothe's stone no. 41. For an intact text of Septimius Severus and sons, see above, 088(B). Kemer 2

**105(A). Göksun 8**

<i>Province, Sub-Province + Admin. Code and Map</i>	K. Maraş, Göksun 46-04-0
<i>Map</i>	Elbistan 92-Im
<i>Location</i>	" . . . in an old cemetery by the road side, forty minutes to the eastward of Göksun" (Sterrett); "In a small cemetery 40 min. east of Gyusun" (Hogarth and Munro). This cemetery lies on the old road from Göksun to Afşin. It is situated on the N side of the old road (now a track only), on the land of Ortatepe village

	(the boundary of which is the track itself); located in the field of Yakup Özden. The track runs between two ridges, c. 1 km NW of Göksun Yem Fabrikası. The cemetery lies in the plain on the W side of the saddle between the two ridges; the area is called Çatal Tepe mevkii. The stone is now at Alicılıbucak (form. Kömürsuyu), at the house of Gül Ali Özgürsoy; used as a post for the garden-gate.
<i>Copy</i>	Sterrett 28 July, 1884 (facsimile of the printed version of Sterrett's copy, Fig. 6.1.49 [p. 339]); Hogarth and Munro 1891 (facsimile of the printed version of Hogarth and Munro's copy, Fig. 6.1.50 [p. 339]); DHF 16.viii.1978. DHF squeeze and photos (Pl. 7.1.75 [p. 396]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 46. Maraş 19, Göksun 8 Stone: (1) B/W Neg.: DHF R/78/13.04 (2) Col. Slide: DHF 174.24-25
<i>Publication</i>	Sterrett 1883-84, 264 no. 300 (facsimile, Fig. 6.1.49 [p. 339]) Sterrett 1885, 27 no. 26 CIL 3. 6928 (text of Sterrett) Hogarth and Munro 1893, 700 "124 ?(i)" (facsimile, Fig. 6.1.50 [p. 339]) CIL 3. 12186 (text of Hogarth and Munro) RRMAM 2, 1. 757 (notice only)
<i>Description</i>	A simple cylinder. Complete. Hard, pale limestone. No plinth. Surface: slightly worn.
<i>Dimensions</i>	Letters: (text 2) worn but legible, neat in shape, size and alignment, broken-bar A Ht 1.49; diam. (top) 0.50. Letters: (text 1) 0.050, (text 2) c. 0.04 but IMP (line 1) 0.080-90
<i>Text</i>	(1) (underneath text [2]) (vac) [Imp] <b>Caes</b> - - - -  (2) (on the top of text [1]) (vac) <b>Imp Caes</b> <b>L Septimius·Severus</b> <b>Pius·Pertinax·Aug·Arab Adiab</b> 4 <b>Parth·max·pont·max·trib·pot·VI</b> <b>imp·XI·cos·II·p·p·procos·et·Imp·Caes</b> <b>M·Aurel·Antoninus·Aug</b> <b>et·L·Septimius AVGG es·restituerunt</b> (sic) 8 <b>per·C·Iulium·Flaccum·Aelianum·leg·pr·pr</b> [ - ]  line 7: <b>AVGG</b> inscribed in large letters over [[[Geta Ca]]], cp. Hogarth and Munro l.c.
<i>Caput Viae</i>	[Melitena]
<i>Date</i>	(1) (?) (2) AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i>

**105(B). Göksun 9**

*Province, Sub-Province + Admin. Code and Map* As 105(A)  
*Location* As 105(A); “deeply buried by the side of 300” (= 105[A]) . . . . “In this cemetery there is still a fourth milliarium, deeply imbedded” (Sterrett). Present whereabouts not known (DHF visit 16.viii.1978)  
*Copy* Sterrett 28 July, 1884. The stone has not been examined by DHF.  
*Publication* Sterrett 1883-84, 264, 267  
 RRMAM 2, 1. 758 (notice only)  
*Description & Dimensions* Not given  
*Text* (?)

### 105(C). Göksun 10

*Province, Sub-Province + Admin. Code and Map* As 105(A)  
*Location* As 105(A). Present whereabouts not known (DHF visit 16.viii.1978)  
*Copy* Sterrett 28 July, 1884 (facsimile of the printed version of Sterrett’s copy, Fig. 6.1.51 [p. 339]); Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Sterrett  
*Publication* Sterrett 1883-84, 265 no. 301 (facsimile, Fig. 6.1.51 [p. 339])  
 Sterrett 1885, 27 no. 27  
 CIL 3. 6938 (text of Sterrett)  
 Hogarth and Munro 1893, 700 “124 (iv)” (notice)  
 RRMAM 2, 1. 759 (notice only)  
*Description & Dimensions* Not given  
*Text* **Maximian[o]**  
**nob Cae-**  
 (vac) **SS**

*Caput Viae* [Melitena]  
*Date* AD 293-305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*  
*Commentary* For an explanation of the seemingly truncated, Tetrarchic texts and for the apparent isolation of individuals from their colleagues in the Tetrarchy see above [p. 14], **Notes and Comments 3.6**.  
 It is noteworthy that the form **NOB CAEISS** is also used, on 101(B). Mehmetbey 2, under Constantius’ name.

### 105(D). Göksun 11

*Province, Sub-Province + Admin. Code and Map* As 105(A)  
*Location* As 105(A). Present whereabouts not known (DHF visit 16.viii.1978)  
*Copy* Sterrett 28 July, 1884 (facsimile of the printed version of Sterrett’s copy, Fig. 6.1.52 [p. 339]); Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Sterrett  
*Publication* Sterrett 1883-84, 265 nos 302-304 (facsimile, Fig. 6.1.52 [p. 339])  
 Sterrett 1885, 27 no. 28  
 CIL 3. 6936 (text of Sterrett)  
 Hogarth and Munro 1893, 700 “124 ?(iii)” (notice)  
 RRMAM 2, 1. 760 (notice only)  
*Description & Dimensions* Not given

*Text* (1) (below and underneath text [2])

[I]mper  
 Çae[sari Mar]-  
 co Anton[io]  
 4 Gordiano pio fe-  
 lici Augu[s]to  
 restit[u]erunt  
 per Cuspidim [Fla]-  
 8 minium Severum [le]-  
 gatum p<r>o praë-  
 tor[e]  
 [ - ]

line 1: [I]MPER, cp. 087(B). line 1

line 7: for the Greek delta in CVSPIA, cp. 087(B). line 7

Note in Sterrett's copy (facsimile, Fig. 6.1.52 [p. 338]) the broken-bar A (but not in line 2) and the lunate E throughout

(2) (above, and on top of, text [1])

Imp [Caes]  
 M Au[r]  
 Maxim[iano]

*Caput Viae* [Melitena]

*Date* (1) AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*

(2) AD 293–305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*

*Commentary* (Text 1) For the survival of *restituerunt*, see above [p. 12], **Notes and Comments 3.5** Text-form (4).

(Text 2) For an explanation of the seemingly truncated, Tetrarchic texts and for the apparent isolation of individuals from their colleagues in the Tetrarchy, see above [p. 14], **Notes and Comments 3.6**.

## 105(E). Göksun 12

*Province, Sub-Province + Admin. Code and Map* As 105(A)

*Location* Formerly as 105(A). Now at Ortatepe, lying at the bottom of a gully, below and W of the house of İbrahim Yıldırım; below and E of the village şose and S of the house owned by Mehmet Güvenç. Brought from the cemetery E of Göksun c. 15–16 years ago (i.e. c. 1962)

*Copy* Hogarth and Munro 1891 (facsimile of the printed version of Hogarth and Munro's copy, Fig. 6.1.53 [p. 340]); DHF 16.viii.1978. DHF squeeze and photo. (Pl. 7.1.76 [p. 396]) in BIA. Text here from DHF squeeze

*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 20, Göksun 12  
 Stone: (1) B/W Neg.: DHF R/78/13.05

*Publication* Hogarth and Munro 1893, 700 “124 ?(ii)” (facsimile, Fig. 6.1.53 [p. 340])  
 CIL 3. 12191 (text of Hogarth and Munro)  
 RRMAM 2, 1. 761 (notice only)

*Description* A simple cylinder. Broken at the top and bottom. Hard but friable, pale limestone. The shaft tapers towards the top. Surface: very worn.  
*Dimensions* Letters: faint and indistinct, variable; diagonal-bar A  
Ht 1.20; diam. (bottom) 0.59. Letters: 0.045-60

*Text*

(vac) I[mp]  
(vac) Caes  
Seve[ri]  
4 nep divi M [An]-  
(vac) tonini  
(vac) fil  
M Aur An[to]-  
8 nino pio felic[i]  
(vac) Aug  
milia restitu-  
ta per M Ulp Ofell-  
12 ium Theodorum  
(vac) leg Aug  
(vac) pr pr  
[ - ]

*Caput Viae* [Melitena]  
*Date* Elagabalus *Augustus*, (?) AD 218, 16.v-(?) mid-June

### 106(A). Göksun 15

*Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-0  
*Map* Elbistan 92-Im  
*Location* “In a roadside cemetery about 70 min. east of Gyüksun” (Hogarth and Munro); perhaps the same as Sterrett (1883-84: 267, “In a cemetery 1 h. 5m. east of Göksün there are two more milliaria; one nearly buried, the other erect but illegible”). At 70 mins E of Göksun along the old road (now a track only) to Afşin there is a *çeşme* (fountain) at the point where the old *Kayseri caddesi* (the Kayseri highway) reaches the plain after descending the ridge on the N; here there is a spring and a grove of poplars. The cemetery lies of the N side of the modern Göksun-Afşin *yöse* (a minor road). Present whereabouts not known (DHF visit 16.viii.1978)  
*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Hogarth and Munro (facsimile of the printed version of Hogarth and Munro’s copy, Fig. 6.1.54 [p. 340])  
*Publication* Hogarth and Munro 1893, 701 “123 (i)” (facsimile, Fig. 6.1.54 [p. 340])  
CIL 3. 12192 (text of Hogarth and Munro)  
RRMAM 2, 1. 764 (notice only)  
*Description & Dimensions* Not given  
*Text*

[Imp Caes]  
[Marc]us Iu[l Phil]-  
[ippus piu]s f[elix in]-  
4 [victus A]u[g] et [Marcus]  
[Iul Phili]p[us nobili]-



[ss]i[mu]s [Caesar vias]  
 [et p]o[ntes vetustate]  
 8    **conl**[a]p[s]a[s rest]-  
       [itueru]nt **per** [Anton]-  
       [ium] **Memmium** [Hieronem]  
       (vac) **leg Au**[g]  
 12    (vac) **pr pr**  
       [ - ]

*Caput Viae*        [Melitena]

*Date*                AD 244, July/Aug.-247, July/Aug. Philippus *Augustus* with Philippus *Caesar*; cp. the intact text above, 068(D). Aslanbeyli Yaylası, Hanboğazı 4

### 106(B). Göksun 16

*Province, Sub-Province + Admin. Code and Map*    As 106(A)

*Location*        As 106(A). Present whereabouts not known (DHF visit 16.viii.1978)

*Copy*              Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Hogarth and Munro (facsimile of the printed version of Hogarth and Munro's copy, Fig. 6.1.55 [p. 340])

*Publication*     Hogarth and Munro 1893, 701 "123 (ii)" (facsimile, Fig. 6.1.55 [p. 340])  
                       CIL 3. 12193 (text of Hogarth and Munro)  
                       RRMAM 2, 1. 765 (notice only)

*Description & Dimensions*    Not given

*Text*                Consult the facsimile (Fig. 6.1.55 [p. 339])

*Date*                (?)

### 107(A). Yağmurlu 1, form. Aziz

*Province, Sub-Province + Admin. Code*        K. Maraş, Göksun 46-04-0

*Map*                Elbistan 91-II

*Location*        "In an old cemetery by the roadside, one hour and forty minutes to the eastward of Göksün" (Sterrett). This location is the village cemetery on the S side of the old road to Afşin from Göksun, just below and SE of the village (Pl. 7.1.77 [p. 397]). Present whereabouts not known (DHF visit 12.viii.1978)

*Copy*              Sterrett 28 July, 1884. The stone has not been examined by DHF. Text here of Sterrett (facsimile of the printed version of Sterrett's copy, Fig. 6.1.56 [p. 340])

*Publication*     Sterrett 1883-84, 267 no. 305 (facsimile, Fig. 6.1.56 [p. 340])  
                       Sterrett 1885, 28 no. 29  
                       CIL 3. 6941 (text of Sterrett)  
                       Hogarth and Munro 1893, 701 "121 ?(ii)" (notice)  
                       RRMAM 2, 1. 824 (notice only)

*Description & Dimensions*    Not given

*Text*                - - - -  
                       **per Memm-**  
                       [ium ? - - ]

*Caput Viae* [Melitena]  
*Date* (?)AD 244 Philippus *Augustus* with Philippus *Caesar*, on the basis of the governor's name; cp. the intact text above, 068(D). Aslanbeyli Yaylası, Hanboğazı 4

### 107(B). Yağmurlu 2, form. Aziz

*Province, Sub-Province + Admin. Code and Map* As 107(A)  
*Location* As 107(A)  
*Copy* Sterrett 28 July, 1884 (facsimile of the printed version of Sterrett's copy, Fig. 6.1.57 [p. 340]); DHF 12.viii.1978. DHF squeeze in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 47, Yağmurlu 2  
*Publication* Sterrett 1883-84, 267 no. 306 (facsimile, Fig. 6.1.57 [p. 340])  
 Sterrett 1885, 28 no. 30  
 CIL 3. 6927 (text of Sterrett)  
 Hogarth and Munro 1893, 701 "122 ?(i)" (notice)  
 RRMAM 2, 1. 825 (notice only)  
*Description* A simple cylinder. Broken at top right and on right side. Hard, pale limestone. No plinth. The top is flat. Surface: very worn. Letters: worn but mostly legible, variable in shape, size and alignment; broken-bar A, Y for V  
*Dimensions* Ht 1.19; diam. (top) 0.56. Letters: 0.035-60  
*Text*

- - - -

[Par]**th max pont m**[ax trib pot VI]  
 [i]m[p] **XI cos III p** [p] **pro**[cos]  
 4 [et] **Imp** [Caes M] **Aure**[l] **Antoninus** [Aug]  
 [et L Septimius Geta Caesar restituerunt]  
**per C Iulium Flaccum Aelia**(n)**um** [l]eg  
 [Aug pr pr]  
 8 [ - ]

*Caput Viae* [Melitena]  
*Date* AD 197/198(?), L. Septimius Severus and M. Aurelius Antoninus (Caracalla) *Augusti* [with L. Septimius Geta (names erased) *Caesar*]  
*Commentary* For an intact text of Septimius Severus and sons, see above, 088(B). Kemer 4

### 107(C). Yağmurlu 3, form. Aziz

*Province, Sub-Province + Admin. Code and Map* As 107(A)  
*Location* As 107(A). Present whereabouts not known (DHF visit 12.viii.1978)  
*Copy* Sterrett 28 July, 1884. The stone has not been examined by DHF. Text here of Sterrett (facsimile of the printed version of Sterrett's copy, Fig. 6.1.58 [p. 341])  
*Publication* Sterrett 1883-84, 268 no. 307 (facsimile, Fig. 6.1.58 [p. 341])  
 Sterrett 1885, 28 no. 31  
 CIL 3. 6929 (text of Sterrett)  
 Hogarth and Munro 1893, 701 "121 ?(i)" (notice)  
 RRMAM 2, 1. 826 (notice only)

*Description & Dimensions* Not given

*Text*

(vac) **Im**[p Caesar]  
**L Se**[ptimius Severus]  
**Pius** [Pertinax Aug Arab Adiab]  
4 **Parth** [max pont max trib pot VI]  
**imp XI** [cos III p p procos et Imp Caes]  
**M Aure**[l Antoninus Aug]  
**et L Se**[ptimius Geta Caes restituerunt]  
8 **per C Iul**[ium Flaccum Aelianum leg pr pr]  
[ - ]

*Caput Viae* [Melitena]

*Date* AD 197/198(?), L. Septimius Severus and M. Aurelius Antoninus (Caracalla)  
*Augusti* with L. Septimius Geta (the name Geta only erased?) *Caesar*

*Commentary* For an intact text of Sept. Severus and sons, see above, 088(B). Kemer 4

### 107(D). Yağmurlu 4, form. Aziz

*Province, Sub-Province + Admin. Code and Map* As 107(A)

*Location* As 107(A)

*Copy* Sterrett 28 July, 1884 (facsimile of the printed version of Sterrett's copy, Fig. 6.1.59 [p. 341]); DHF 12.viii.1978. DHF squeeze and photo. (Pl. 7.1.78 [p. 397]) in BIA. Text here from DHF squeeze.

*BIA Collections: Squeeze and Stone Photographs*  
Squeeze: 46. Maraş 48, Yağmurlu 4  
Stone: (1) B/W Neg.: DHF R/78/12.07

*Publication* Sterrett 1883-84, 269 no. 309 (facsimile, Fig. 6.1.59 [p. 341])  
Sterrett 1885, 29 no. 33  
CIL 3. 6932 (text of Sterrett)  
Hogarth and Munro 1893, 701 "122 (ii)" (notice)  
RRMAM 2, 1. 827 (notice only)

*Description* A simple cylinder. Complete but once used as a *yuvak* or *loğ taş* (roof-roller).  
Hard, pale limestone. The top is flat. No plinth. The shaft tapers slightly towards the top. Surface: worn.

Letters: some faint, mostly clear, neat in shape, size and alignment; broken-bar A, (line 9) short-bar K

*Dimensions* Ht 1.79; diam. (top) 0.46. Letters: 0.050-60, (line 8) 0.080

*Text*

[Imp C]aes  
**Gaio Iulio**  
**Vero Maximi-**  
4 **no pio felici A-**  
**ug trib p per Li-**  
**cinnium Sereni-**  
**anum leg Aug**  
8 **pr pr**  
(gap 0.27)  
**ϞϞβ'**

*Caput Viae* (Melitena)  
*Date* AD 235, ii/iii-236, 07.i/16.v Maximinus Augustus  
*Commentary* The dates for Maximinus Augustus without Maximus Caesar are given by Kienast (1996, 183-185).

### 107(E). Yağmurlu 5, form. Aziz

*Province, Sub-Province + Admin. Code and Map* As 107(A)  
*Location* As 107(A)  
*Copy* Sterrett 28 July, 1884 (facsimile of the printed version of Sterrett's copy, Fig. 6.1.60 [p. 341]); Hogarth and Munro 1891; DHF 12.viii.1978. DHF squeeze in BIA. Text here from DHF squeeze  
*BIA Collections:* *Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 49, Yağmurlu 5  
*Publication* Sterrett 1883-84, 269 no. 308 (facsimile, Fig. 6.1.60 [p. 341])  
 Sterrett 1885, 28 no. 32  
 CIL 3. 6937 (text of Sterrett)  
 Hogarth and Munro 1893, 701 "121 ?(iii)" (notice)  
 RRMAM 2, 1. 828 (notice only)  
*Description* A simple cylinder. Complete but once used as a *yuvak* or *loğ taş* (roof-roller); there is a deep horizontal cut on the left side. Hard, pale limestone. No plinth. Surface: worn.  
 Letters: worn but legible, variable in size; diagonal bar A, (line 3) lunate E but (lines 7 and 9) E, cursive F, L with diagonal lower bar, U for V  
*Dimensions* Ht 1.91; diam. (top) 0.44. Letters: 0.030-50  
*Text*

	[Impp Caess]
	[C Aur Val]
	<b>diocletiano</b>
4	[et M Aur Val]
	[Maximiano]
	<b>pp ff invi Augg</b>
	<b>et Flavi Val</b>
8	<b>Constantio</b>
	<b>et Gal Val</b>
	<b>Maximiano</b>
	<b>nob Caess</b>
12	[ - ]

line 3: **d** for **D**  
 line 6: **p**(iis) **f**(elicibus) **invi**(ctis) **Aug**(ustis)

*Caput Viae* [Melitena]  
*Date* AD 293, 21.v(?) - 305, 01.v Diocletianus and Maximianus Augusti with Constantius and Galerius Caesares

### 107(F). Yağmurlu 6, form. Aziz

*Province, Sub-Province + Admin. Code and Map* As 107(A)  
*Location* As 107(A)

*Copy* DHF 12.viii.1978. DHF squeeze in BIA. Text here from DHF squeeze  
*BIA Collections:* *Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 50, Yağmurlu 6  
*Publication* RRMAM 2, 1. 829 (notice only)  
*Description* A simple cylinder. Broken at right side. Once used as a *yuvak* or *loğ taş* (roof-roller). Hard, pale limestone. No plinth. Surface: very worn.  
 Letters: worn but legible, neat in shape, size and alignment; broken-bar A  
*Dimensions* Ht 1.57; diam. (top) 0.53. Letters: 0.035-40

*Text*

-----  
 [A]rab **Adiaḅ** [Parth max p m]  
**trib·pot V**[I imp XI cos II p p procos et]  
 4 **Imp Caes** [M Aurel Antoninus Aug]  
 [[et L Septimius Geta Caesar]]  
 [r]estituer[unt per C Iulium Flaccum Aeli]-  
 8 **anum leg** [pr pr]  
 [ - ]

*Caput Viae* [Melitena]  
*Date* AD 197/198(?), L. Septimius Severus and M. Aurelius Antoninus (Caracalla)  
*Augusti* with L. Septimius Geta (names erased) *Caesar*  
*Commentary* For an intact text of Septimius Severus and sons, see above, 088(B). Kemer 4

**107(G). Yağmurlu 7, form. Aziz**

*Province, Sub-Province + Admin. Code and Map* As 107(A)  
*Location* As 107(A)  
*Copy* DHF 12.viii.1978. DHF squeeze in BIA. Text here from DHF squeeze  
*BIA Collections:* *Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 51, Yağmurlu 7  
*Publication* RRMAM 2, 1. 830 (notice only)  
*Description* A simple cylinder. Broken at top and bottom; once used as a *yuvak* or *loğtaş* (roof-roller). Hard, pale limestone. Surface: very worn.  
 Letters: worn and indistinct; broken-bar A, (line 13) short-bar K  
*Dimensions* Ht 1.67; diam. (top) 0.44. Letters: 0.050-60, (lines 1-3) 0.080-90, (line 13) 0.10

*Text*

**Imp**  
**Caes**  
**ḍiḃi Severi**  
 4 [nep divi An]-  
 [tonini fil M]  
 [Aurelio Ant]-  
 [onino] **pio fe-**  
 8 **lici Aug milia**  
**restituta per**  
**M Ulp Ofellium**  
**Theodorum**  
 12 **leg Aug**  
**pr pr**  
 (gap 0.090)

## μ ρχα'

line 13: μ for μ(ἰλια), cp. 107(G), 108(D) and 109(C) (Elagabalus), 119(A) (Sev. Alexander), 068(C), 072(C), 074(C), 075(C), 080(B), 087(B), 098(D), 104(B) and 108(M) (all Gordianus), 085(B) (Maximinus), 119(B) (Philippus); also 112

*Caput Viae* (Melitena)  
*Date* Elagabalus *Augustus*, (?) AD 218, 16.v–(?) mid-June  
*Commentary* For an intact text of Elagabalus, see above, 068(B). Aslanbeyli Yaylası, Hanboğazı 2

**108(A). Kanlıkavak 1**

*Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-0  
*Map* Elbistan 92-II  
*Location* “In the cemetery which is on the main road leading from Göksun to Yarpuz and about twenty minutes to the southeastward of Kanlı Kavak” (Sterrett). The village cemetery is still located in this position, at the junction of the village road with the road to Afşin, on the N side of the latter.  
*Copy* Sterrett 28-29 July, 1884 (facsimile of the printed version of Sterrett’s copy, Fig. 6.1.61 [p. 341]); DHF 14.viii.1978. DHF squeeze and photo. (Pl. 7.1.79 [p. 397]) in BIA. Text here from DHF squeeze.  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 31, Kanlıkavak 1  
 Stone: (1) B/W Neg.: DHF R/78/12.10  
*Publication* Sterrett 1883-84, 270 no. 310 (facsimile, Fig. 6.1.61 [p. 341])  
 Sterrett 1885, 29 no. 34  
 AE 1888. 182 (text of Sterrett)  
 CIL 3. 6914 (text of Sterrett)  
 Hogarth and Munro 1893, 703 (xii) (notice)  
 RRMAM 2, 1. 781 (notice only)  
*Description* A simple cylinder. Complete. Hard, white crystalline limestone. The shaft tapers towards the top. No plinth. Surface and letters: very worn and damaged, especially towards the top and left-hand side.  
 Letters: neat in shape, size and alignment  
*Dimensions* Ht 2.10; diam. (top) 0.49. Letters: 0.045-55, (line 7) O 0.030

*Text*

-----  
 [Ma]rcu[s] [Iulius]  
 [Philippus] nobi[lis]sim[us]  
 4 [Caes]ar vias et pon-  
 t[is] vetustate  
 conlapsas restituer-  
 [un]t per Antonium  
 8 [M]emmium Hieronem  
 v c leg Augg  
 pr pr  
 [ - ]

*Caput Viae* [Melitena]

*Date* AD 244-247 [Philippus *Augustus* with] Philippus *Caesar*; cp. the intact text above, 068(D). Aslanbeyli Yaylası, Hanboğazı

### 108(B). Kanlıkavak 2

*Province, Sub-Province + Admin. Code, Map and Location* As 108(A)

*Copy* Sterrett 28-29 July, 1884 (facsimile of the printed version of Sterrett's copy, Fig. 6.1.62 [p. 341]); Hogarth and Munro 1891; DHF 13.viii.1978. DHF squeeze and photo. (Pl. 7.1.80 [p. 398]) in BIA. Text here from DHF squeeze.

*BIA Collections: Squeeze and Stone Photographs*  
Squeeze: 46. Maraş 32, Kanlıkavak 2  
Stone: (1) B/W Neg.: DHF R/78/12.08

*Publication* Sterrett 1883-84, 271 no. 311 (facsimile, Fig. 6.1.62 [p. 341])  
Sterrett 1885, 30 no. 35  
CIL 3. 6925 (text of Sterrett)  
Hogarth and Munro 1893, 701 "120" (notice)  
RRMAM 2, 1. 782 (notice only)

*Description* A simple cylinder, on a roughly squared plinth. Complete but the surface has been damaged. Grey, crystalline limestone.  
Letters: very worn except for a few letters on the right-hand side; (line 10) short-bar K

*Dimensions* Ht 2.02; diam. (top) c. 0.40. Letters: 0.050-60, (line 10) PK 0.075

*Text*

	[ - - - - ]A
2	[ - - - - ]O
	[ - - - - ]
4	[ - - - - ]
	[ - - ]NN
6	[ - - ]CR
	VN[ - ]AN
8	[ - - - - ]
	<b>pr pr</b>
	(gap 0.21)
10	<b>qx'</b>

*Caput Viae* (Melitena)

*Date* (?)

### 108(C). Kanlıkavak 3

*Province, Sub-Province + Admin. Code, Map and Location* As 108(A)

*Copy* Sterrett 28-29 July, 1884. The stone has not been re-found and examined by DHF 14.viii.1978. Text here of Sterrett (facsimile of the printed version of Sterrett's copy, Fig. 6.1.63 [p. 341])

*Publication* Sterrett 1883-84, 272 no. 312 (facsimile, Fig. 6.1.63 [p. 341])  
Sterrett 1885, 30 no. 36  
AE 1888. 184 (text of Sterrett)  
CIL 3. 6924 (text of Sterrett)  
Hogarth and Munro 1893, 699 "125 (iii)" (notice)  
Townsend 1955, 41-42 (comment)

RRMAM 2, 1. 783 (notice only)  
 Christol and Lorient 1993, 218 and n.46 (comment on text)  
 French 2008, 127 no. 2 (text and comments)  
 AE 2008. 1475 (text of French)

*Description & Dimensions* Not given

*Text* Consult the facsimile (Fig. 6.1.63 [p. 340])

2     - - - -  
       **ANI**[<sup>2</sup>.]**ONO**  
       [ - ]**lissimo Casa**[ - ] (sic)  
 4     **Cat Clement**[ - ]  
       **pr pr provinci**a[e]  
 6     (vac) **IMP**  
       (v) **ϣϣϵ'**

lines 2-3: for the dative case -**O** (followed by **PER**), see above, 097(A).

Doğankonak, Şabanağa Mevkii 1, a text of Elagabalus, AD 219-222.

line 3: . . . [nobi]**lissimo Ca**[e]**sari** (Sterrett)

line 4: [per] **Cat Clement**[em] (Sterrett), [per] **Cat Clement**[inum] (Townsend)

line 5: **CRCRCROVINCIAE** (i.e. **C** for **P**), [leg(atum) Aug(ustorum) p]r(o)  
 [p]r(aetore) [p]rovincia[e] (Sterrett); [leg(atum) Aug(usti) pr(o)] **pr**(aetore)  
**pr**(aesidem) **provincia**[e] (DHF); for the formula, cp. RRMAM 2, 1. 861  
 Eminlik 1 *leg Aug pr pr praesid provinc Capp* (AD 222 Severus  
 Alexander), RRMAM 3. 74 Ağsaklı *legatus eius pr pr praeses provinciae*  
*Galatae* (under Elagabalus) and here, 056(A). *leg pr pr* (under Severus  
 Alexander).

line 6: “I have a note to the effect that I was doubtful while in the presence of the  
 stone as to whether line 5 should read **IMP** or **IHP**” (Sterrett)

lines 6-7: **IMP** for {i}m p, i.e. m(ilia) p(assuum), perhaps {i}m p | [CXXV] **ϣϣϵ'**  
 (DHF)

Restored text (French 2008):

[Imp Caes M] [[Opellio]]  
 [Severo] [[Macrino]]  
 [pio felici Aug - - p m - - - ]  
 [ - - trib pot - - - cos - - - ]  
 5     [ - p p - procos - et M] [[Opel]]-  
       [[lio]] **Ant**[on]<sub>\*</sub>**ino** [[Diadumeni]]-  
       [[ano]] [nobi]**lissimo Ca**(e)**sa**[ri]  
       [per .] **Cat Clement**[ - - leg]  
 10     [Aug pr] **pr pr provinci**a[e]  
       (vac) {i}m p  
       (vac) **ϣϣϵ'**

line 6: a line of 20 letters, as restored; after **ANT** there is a space (on the  
 basis of Sterret's copy) for 2 letters only (here ON), not 5 – GORDI –  
 as Townsend; here I for **Q**, not A for **Q**, as Townsend

line 7: a line of 20 letters



line 9: [per .] Cat(ium) Clement[em leg(atum)], a line of 19 letters

line 10: [Aug pro] pr(aetore) pr(aesidem) provincia[e], a line of 20 letters

*Caput Viae* (Melitena)

*Date* AD 238 Maximus *Caesar* (CIL); Gordianus *Caesar* (Townsend, *contra* Groag [PIR<sup>2</sup> C 564]); (?) mid-217–end of May, 218 [Macrinus *Augustus* with] Diadumenianus *Caesar* (DHF)

*Commentary* Comments by Thomasson (1984, 274 no. 45; 2007, 110 no. **29:37a**) on the date of the governor; the governorship is listed by Rémy (1989, 239 no. 188).

On the alternative proposal (AD mid-217–218, end of May, Diadumenianus *Caesar*, not yet *Augustus*) for the date of this milestone, see above [p. 10], **Notes and Comments 3.3**.

#### 108(D). Kanlıkavak 4

*Province, Sub-Province + Admin. Code, Map and Location* As 108(A)

*Copy* Sterrett 28-28 July, 1884. The stone has not been re-found and examined by DHF 14.viii.1978. Text here of Sterrett (facsimile of the printed version of Sterrett's copy, Fig. 6.1.64 [p. 342])

*Publication* Sterrett 1883-84, 272 no. 313 (facsimile, Fig. 6.1.64 [p. 342])  
Sterrett 1885, 30 no. 37  
AE 1888. 180 (text of Sterrett)  
CIL 3. 6912 (text of Sterrett)  
Hogarth and Munro 1893, 703 (xiv) (notice)  
RRMAM 3. 784 (notice only)

*Description & Dimensions* Not given

*Text*

**Imp**  
**divi Severi**  
**nep divi M An-**  
4 **tonini fil**  
**M Aur [Antoni]-**  
**no pio felici**  
(vac) **Aug**  
8 **milia restituta [per]**  
**M [U]p Ofellium**  
**Theodorum**  
(?vac) **leg Aug pr pr**  
12 **μ ρξ.'**

line 5: "I have a note to the effect that I was doubtful while in the presence of the stone as to whether line 5 should read IMP or IHR" (Sterrett 1883-84, 272)

line 12: **μ** for **μ**(ίλια), cp. 107(G) and 109(C) (Elagabalus), 119(A) (Severus Alexander), 068(C), 072(C), 074(C), 075(C), 080(B), 087(B), 098(D), 104(B) and 108(M) (all Gordianus), 085(B) (Maximinus), 119(B) (Philippus); also 112; **ρξ**[ε'] or **ρξ**[η'] (Sterrett); **ρξγ'** (?) (Hogarth); **ρξ**[β'] also possible

*Caput Viae* (Melitena)

*Date* Elagabalus *Augustus*, (?) AD 218, 16.v–(?) mid-June

**108(E). Kanlıkavak 5**

<i>Province, Sub-Province + Admin. Code, Map and Location</i>	As 108(A)
<i>Copy</i>	Sterrett 28-29 July, 1884; (facsimile of the printed version of Sterrett's copy, Fig. 6.1.65 [p. 342]) (?)Hogarth and Munro 1891 (facsimile of the printed version of Hogarth and Munro's copy, Fig. 6.1.66 [p. 342]). The stone has not been re-found and examined by DHF 14.viii.1978. Text here of Sterrett
<i>Publication</i>	(?)Sterrett 1883-84, 273 no. 314 (facsimile, Fig. 6.1.65 [p. 342]) (?)Sterrett 1885, 31 no. 38 (?)CIL 3. 6926 (text of Sterrett) Hogarth and Munro 1893, 702 (ii) (notice) (facsimile, Fig. 6.1.66 [p. 342]) Hogarth and Munro 1893, 703 (vii) (notice) CIL 3. 12173 (text from Hogarth and Munro) RRMAM 2, 1. 785 (notice only)
<i>Description</i>	"The stone is very much worn, and may be identical with Sterrett, no. 314, where only the last line is given - 'C.I.L.', 6926" (Hogarth and Munro)
<i>Dimensions</i>	Not given
<i>Text</i>	Consult the facsimiles (Fig. 6.1.65, 66 [p. 342])
<i>Caput Viae</i>	[Melitena]
<i>Date</i>	(?)
<i>Commentary</i>	"Mr Haverfield suggests Maximin, as the only sole ruler who inscribes leg. aug. on his stones; but calls attention to this unique occurrence of cos. procos. here among milestones on this road" (Hogarth and Munro)

**108(F). Kanlıkavak 6**

<i>Province, Sub-Province + Admin. Code, Map and Location</i>	As 108(A)
<i>Copy</i>	Sterrett 28-29 July, 1884. The stone has not been re-found and examined by DHF 14.viii.1978. Text here of Sterrett (facsimile of the printed version of Sterrett's copy, Fig. 6.1.67 [p. 342])
<i>Publication</i>	Sterrett 1883-84, 273 nos 315-316 (facsimile, Fig. 6.1.67 [p. 342]) Sterrett 1885, 31 no. 39 CIL 3. 6913 (text of Sterrett) Hogarth and Munro 1893, 703 (xiii) (notice) RRMAM 2, 1. 786 (notice only)
<i>Description &amp; Dimensions</i>	Not given
<i>Text</i>	(vac) <b>Imp Caesari Ma- rco Antoni- o Gordiano pi- o felici Augus- to restitueru- nt per Cuspid- ium Flamini- um Severum legatum pro p-</b>

**rae** (leaf) **tore M**

12 [ - ]

lines 4 and 7: Δ for **D**line 11: **M** for **m**(ilia) or **μ** for **μ**(ίλια)

<i>Caput Viae</i>	[Melitena]
<i>Date</i>	AD 238, 09.v(?)–09.xii (?), Gordianus <i>Augustus</i>
<i>Commentary</i>	For the survival of <i>restituerunt</i> , see above [p. 12], <b>Notes and Comments 3.5</b> Text-form (4).

**108(G). Kanlıkavak 7**

<i>Province, Sub-Province + Admin. Code, Map and Location</i>	As 108(A)
<i>Copy</i>	Sterrett 28–29 July, 1884. The stone has not been re-found and examined by DHF 14.viii.1978. Text here of Sterrett (facsimile of the printed version of Sterrett’s copy, Fig. 6.1.68 [p. 342])
<i>Publication</i>	Sterrett 1883–84, 275 no. 317 (facsimile, Fig. 6.1.68 [p. 342]) Sterrett 1885, 31 no. 40 CIL 3. 6917 (text of Sterrett) Hogarth and Munro 1893, 703 (x) (notice) RRMAM 2, 1. 787 (notice only)
<i>Description</i>	“The two inscriptions are so inscribed on and over each other that it is perhaps impossible to disentangle them, but the lines given below can be read” (Sterrett 1883–84)
<i>Dimensions</i>	Not given
<i>Text</i>	(1) (?)  (2) <b>Imp</b> 2 <b>Caes Marcus</b> <b>Iul Philippus</b> 4 <b>pius felix</b> [invictus Aug] 6 - - - -

<i>Caput Viae</i>	[Melitena]
<i>Date</i>	(1) (?) (2) (?) AD 244–247 Philippus <i>Augustus</i> [with Philippus <i>Caesar</i> ]
<i>Commentary</i>	For a near-intact text of Philippus and son, see above, 068(B). Aslanbeyli Yaylası, Hanboğazi 2.

**108(H). Kanlıkavak 8**

<i>Province, Sub-Province + Admin. Code, Map and Location</i>	As 108(A)
<i>Copy</i>	Sterrett 28–29 July, 1884. The stone has not been re-found and examined by DHF 14.viii.1978. Text here of Sterrett (facsimile of the printed version of Sterrett’s copy, Fig. 6.1.69 [p. 343])
<i>Publication</i>	Sterrett 1883–84, 275 nos 318–319 (facsimile, Fig. 6.1.69 [p. 343]) Sterrett 1885, 31 no. 41

CIL 3. 6921/2 (text of Sterrett)  
 Hogarth and Munro 1893, 703 (ix) (notice)  
 RRMAM 2, 1. 788 (notice only)

*Description & Dimensions* Not given

*Text* (1) (below and underneath text [2])

[Imp] **Caes[ar]**  
 [L Septimius] **Severus**  
 [Pius Pertinax Aug Arab]  
 [Part] **h max pont max trib pot VI**  
 5 [i] **mp XI cos II p p procos et Imp Caes**  
**M Aurel·Antoni-**  
**nus Aug** [ - - - - ]  
 [ - - ] **restituerunt**  
**per C·Iulium Flac-**  
 10 **cum Aelianum leg pr pr**  
 [ - ]

(2) (above and on the top of text [1])

**Impp** [Caess C Aur Val]  
 [Di]o[cle]t[ian]o]  
**et M Aur Val**  
**Maximiano**  
 5 **pp ff inv Aug** (sic)  
**et Flavi Val** (sic)  
**Constantio**  
 (vac) **et [G]al Val**  
**Maximiano**  
 10 [nobb Caess]

line 5: **p(iis) f(elicibus) inv(ictis) Aug(ustis)**

*Caput Viae* [Melitena]

*Date* (1) AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus  
 (Caracalla) *Augusti* with L. Septimius Geta (names erased) *Caesar*  
 (2) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with  
 Constantius and Galerius *Caesares*

*Commentary* “I have a note to the effect that lines 8, 9, 10 of A are written together, and are so mixed up as to be exceedingly doubtful. By some mistake, which I am unable to explain, line 11 of inscription A does not appear in the Preliminary Report. It must be noted especially that lines 9 and 11 of inscription A certainly belong to inscription B, which see below” (Sterrett 1883–84, 276)

### 108(I). Kanlıkavak 9

*Province, Sub-Province + Admin. Code, Map and Location* As 108(A)

*Location* As 108(A). Now in the village; at the Yeni Cami. Used as a support for a wooden post of the verandah, at the SW corner

*Copy* Sterrett 28–29 July, 1884 (facsimile of the printed version of Sterrett’s copy, Fig. 6.1.70 [p. 343]; DHF 14.viii.1978. Text here of Sterrett and from DHF

	squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i>
	Squeeze: 46. Maraş 33, Kanlıkavak 9
<i>Publication</i>	Sterrett 1883-84, 277 nos 320-321 (facsimile, Fig. 6.1.70 [p. 343]) Sterrett 1885, 32 no. 42 AE 1888. 179 (text of Sterrett) CIL 3. 6911 (text of Sterrett) Hogarth and Munro 1893, 703 (xv) (notice) RRMAM 2, 1. 789 (notice only) Christol, Drew Bear and Özsaıt 1993, 161 n.10 (comment)
<i>Description</i>	A simple cylinder. Hard, pale limestone. The text is obscured. A squeeze was taken of lines 4-8 but only of the r. and l. ends of the lines.
<i>Dimensions</i>	Ht (vis.) c. 0.30 Letters: (text 1) (line 5) IMP 0.030, (line 7) ETL 0.040, (line 8) PER 0.035
<i>Text</i>	(1) (underneath and below text [2]) <div style="margin-left: 100px;"> <b>Imp Caes</b>  <b>L Septimius Severus</b>  <b>Pius Pertinax Aug Arab Adiab</b>  4 <b>Parth max pont max trib pot VI</b>  <b>imp XI cos III p p procos·et·Imp Caes</b>  <b>M Aurel Antoninus Aug</b>  <b>et·L·Sept[imi]us [[Geta]] Caes [r]estituerunt</b>  8 <b>per·C·Iulium Flaccum Aelianum·leg·pr·pr</b>  [ - ] </div> (2) (above, and on the top of, text [1]) <div style="margin-left: 100px;"> <b>Impp</b>  <b>diocletiano</b>  <b>et</b>  4 <b>Maximiano</b>  <b>pp ff inv [Augg]</b>  [et Fl Val]  [C]onst[antio]  8 <b>et Gal Va[l]</b>  [Ma]ximiano  <b>nobb Caess</b> </div> line 1: <b>Imp</b> (eratoribus) line 2: <b>d</b> for <b>D</b> line 5: <b>p</b> (iis) <b>f</b> (elicibus) <b>inv</b> (ictis) [Aug(ustis)] line 10: <b>NObb</b> (squeeze); <b>nob</b> (ilissimis) <b>Caes</b> (aribus)

*Commentary* “The two inscriptions are badly confused on the stone, in as much as the later inscription of Diocletian-Maximian-Constantius-Galerius Maximian (*B*) has been incised over the older inscription of L. Septimius Severus (*A*) in such fashion as to make the whole unintelligible at the first glance. It is impossible to present the inscriptions accurately in uncial text, but I have tried to give at least an approximate idea of the truth. Let us endeavor to disentangle the inscriptions! Lines 1 and 2 belong wholly to *B*. Of line 3 IMPCAES belongs to *A*, and MAVRCAL to *B*. Besides this a T was inserted after the E of CAES and the ET thus obtained belongs to *B*.

MAXIMIANO was inserted between lines 3 and 4, and belongs to *B*. All of line 4 belongs to *A* excepting the closing AVG, which belongs to *B*, and follows the PP[F]E///INV which is inserted between lines 4 and 5. In this lines the A of AVG has been so carved as to resemble a ligature with the closing S of SEVERVS. Lines 5, 6, 7 belong wholly to *A*, only perhaps at the close of line 6 a disturbing effect has been produced by the incision of something belonging to *B*. The letters between lines 6-7 and 7-8 belong to *B*. The NO at the close of line 8 probably originally followed the name of P. Septimius Geta in line 9, that being the only theory upon which I can account for its presence, which is certified by the impression. Lines 9, 10 belong to *A*, with the exception of the NObbCAESS in the middle of line 9, which belongs to *B*, and was incised in the place made vacant by the erasure of the name of Geta” (Sterrett 1883-84, 277- 278)

*Caput Viae* [Melitena]

*Date* AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) *Augusti* with L. Septimius Geta (names erased) *Caesar*  
(2) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*

*Comment* There are minor differences between Sterrett’s copy and the DHF squeeze. These differences are indicated in the text here.

### 108(J). Kanlıkavak 10

*Province, Sub-Province + Admin. Code and Map* As 108(A)

*Location* As 108(A)

*Copy* Sterrett 28-29 July, 1884; DHF 14.viii.1978. Text here of Sterrett (facsimile of the printed version of Sterrett’s copy, Fig. 6.1.71 [p. 344]) and DHF notes

*Publication* Sterrett 1883-84, 279 nos 322-323 (facsimile, Fig. 6.1.71 [p. 344])  
Sterrett 1885, 32 nos 43-44  
CIL 3. 6915/6 (text of Sterrett)  
Hogarth and Munro 1893, 703 (xi) (notice)  
RRMAM 2, 1. 790 (notice only)

*Description* A simple cylinder. Broken at the top. Hard, pale limestone. Surface and letters: slightly worn. The texts are obscured.

*Dimensions* Ht (vis.) 1.05; diam. (top) c. 0.48

*Text* (1) (6915)

Im-  
p Caes Ma-  
cus Iul P-  
4 hilippus piu-  
s felix invi-  
ctus Aug e-  
t Marcus  
8 Iulius Phi-  
lippus no-  
bilissimus  
Caesar via-  
12 s et ponte-  
[s] yetustat-  
[e con]lapsas  
[resti]tuer-  
16 [unt pe]r A-

[ntonium]  
 [Memmium]  
 [Hieronem]  
 20 [v c leg Aug]  
 [pr pr]  
 [ - ]

lines 17-21: cp. the intact text above, 068(D). 068(D). Aslanbeyli Yaylası,  
 Hanboğazi

(2) (6916) (“On the other side of the stone” [Sterrett])

**Impp CC C Aur**  
**diocletiano**  
**et M Aur Val**  
 4 **Maximiano**  
**pp ff invi Aug** (sic)  
 [et Fla]vi Val  
**Constantio**  
 8 **et Gal [V]a[l]e**  
**Maximiano**  
 10 **nobb Caess**

line 1: **Imp**(eratoribus) **C**(aesaribus) **C**(aio) **Aur**  
 line 2: **d** for **D**  
 line 5: **p**(iis) **f**(elicibus) **inv**(ictis) **Aug**(ustis)  
 line 10: **nob**(ilissimis) **Caes**(aribus)

*Caput Viae* [Melitena]

*Date* (1) AD 244, July/Aug.-247, July/Aug. Philippus *Augustus* with Philippus *Caesar*  
 (2) 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with Constantius  
 and Galerius *Caesares*

### 108(K). Kanlıkavak 11

*Province, Sub-Province + Admin. Code, Map and Location* As 108(A)

*Copy* Sterrett 28-29 July, 1884 (facsimile of the printed version of Sterrett’s copy,  
 Fig. 6.1.72 [p. 344]); DHF 14.viii.1978. DHF squeeze in BIA. Text here  
 of Sterrett and from DHF squeeze.

*BIA Collections: Squeeze and Stone Photographs*

Squeeze: 46. Maraş 34, Kanlıkavak 11

*Publication* Sterrett 1883-84, 281 no. 324 (facsimile, Fig. 6.1.72 [p. 344])

Sterrett 1885, 33 no. 45

CIL 3. 6923 (text of Sterrett)

Hogarth and Munro 1893, 703 (vi) (notice)

RRMAM 2, 1. 791 (notice only)

*Description* A simple cylinder. Broken at the top. Hard, grey and white, crystalline  
 limestone. The shaft tapers towards the top. Surface and letters: very worn.  
 Letters: broken-bar A, U for V

*Dimensions* Ht 1.97; diam. (top) 0.54, (bottom) 0.66. Letters: c. 0.040

<i>Text</i>	[Impp CC C Aur] [diocletiano] <b>et [G]al Val</b> (sic) 4 <b>Maximiano</b> <b>pp ff invi Aug</b> (sic) <b>et Flavi Val</b> <b>Constantio</b> 8 <b>et G(a)l Valer</b> <b>Maximiano</b> <b>nobb Caess</b> <b>q[ - ]</b>
-------------	---

line 5: **p(iis) f(elicibus) invi(ctis) Aug(ustis)**  
line 10: **NObb, nob(ilissimis) Caes(aribus)**

<i>Caput Viae</i>	[Melitena]
<i>Date</i>	AD 293, 21.v(?)–305, 01.v [Diocletianus] and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i>

### 108(L). Kanlıkavak 12

<i>Province, Sub-Province + Admin. Code, Map and Location</i>	As 108(A)
<i>Copy</i>	Sterrett 28–29 July, 1884. The stone has not been re-found and examined by DHF 14.viii.1978. Text here of Sterrett (facsimile of the printed version of Sterrett's copy, Fig. 6.1.73 [p. 345])
<i>Publication</i>	Sterrett 1883–84, 282 nos 325–327 (facsimile, Fig. 6.1.73 [p. 345]) Sterrett 1885, 34 nos 46–48 AE 1888. 183 (text of Sterrett) CIL 3. 6918/20 (text of Sterrett) Hogarth and Munro 1893, 703 (viii) (notice) RRMAM 2, 1. 792 (notice only)
<i>Description</i>	“Milliarium with three inscriptions inscribed on and over each other” (Sterrett)
<i>Dimensions</i>	Not given

<i>Text</i>	(1)	---- [milia] <b>restituta</b> 4 [p]er M Ulp <b>Ofellium</b> <b>Theodoru-</b> <b>m leg Aug</b> 8 <b>pr pr</b> <b>[q]μ'</b>
	(2)	(vac) <b>Imp Ca-</b> <b>esar G Vivius Trebo-</b> <b>n Gallus et Imp Caes-</b> 4 <b>ar G Vivius Veldum{i}-</b> <b>nianus Volusianu[s]</b> <b>pīi felic invicti Augg vias</b>



8 **et pontes vetustate con-**  
**lapsas restituerunt per A**  
**Vergilium Maximum v c**  
 [leg A]ugg pr pr  
 [ - ]

lines 2-4: Vivius for Vibius; cp. the mis-spellings on 100(B) and 140

(3) **Impp CC**  
 <C Aur Val>  
**diocletiano**  
 4 **et M Aur V<a>le**  
**Maximiano**  
**pp ff invi Aug** (sic)  
**et Flavi Val**  
 8 **Constantio**  
**et Gal Val**  
**Maximiano**  
**nobb Caess**

line 1: **Imp**(eratoribus) **C**(esaribus)

line 2: **d** for **D**

line 6: **p**(iis) **f**(elicibus) **invi**(ctis) **Aug**(ustis)

line 10: **nob**(ilissimis) **Caes**(aribus)

*Caput Viae*  
*Date*

(Melitena)

(1) AD 218 Elagabalus *Augustus*, on the basis of the governor's name; cp. the intact text above, 068(D). Aslanbeyli Yaylası, Hanboğazı 4

(2) AD 251, Aug.(?)-253, Aug.(?) Trebonianus Gallus and Volusianus *Augusti*

(3) AD 293, 21.v(?)-305, 01.v Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*

### 108(M). Kanlıkavak 13

*Province, Sub-Province + Admin. Code, Map and Location* As 108(A)

*Copy* Hogarth and Munro 1891. The stone has not been re-found and examined by DHF 14.viii.1978. Text here of Hogarth and Munro (facsimile of the printed version of their copy, Fig. 6.1.74 [p. 345])

*Publication* Hogarth and Munro 1893, 702 "118 (i)" (facsimile, Fig. 6.1.74 [p. 345])  
 CIL 3. 12176 (text of Hogarth and Munro)  
 RRMAM 2, 1. 793 (notice only)  
 Christol and Lorient 1993, 218 (citation of text)

*Description & Dimensions* Not given

*Text*

[Imp Caes]  
 [Marco A]n[ton] -  
 [io G]o[rdi]a[no] p̣io f[el]-  
 4 [ici Au]gusto re[sti]-  
 [tuerunt p]er Cus[pidium]  
 [Fla]minium [Severum]

[leg]atūm pro pr[ae]-  
 8 [tor]e μ  
 (vac) ϣϵ'

line 8: μ for μ(ιλια), cp. 107(G), 108(D) and 109(C) (Elagabalus), 119(A) (Sev. Alexander), 068(C), 072(C), 074(C), 075(C), 080(B), 087(B), 098(D), and 104(B) (all Gordianus), 085(B) (Maximinus), 119(B) (Philippus); also 112

*Caput Viae* (Melitena)  
*Date* AD 238, 09.v(?)–09.xii (?), Gordianus *Augustus*  
*Commentary* For the survival of *restituerunt*, see above [p. 12], **Notes and Comments 3.5**  
 Text-form (4).

### 108(N). Kanlıkavak 14

*Province, Sub-Province + Admin. Code, Map and Location* As 108(A)  
*Copy* Hogarth and Munro 1891. The stone has not been re-found and examined by DHF 14.viii.1978. Text here of Hogarth and Munro  
*Publication* Hogarth and Munro 1893, 702 “118 (ii)”  
 CIL 3. 12177 (text of Hogarth and Munro)  
 RRMAM 2, 1. 794 (notice only)  
*Description & Dimensions* Not given

*Text* - - - -  
 ϣϵ'

*Caput Viae* (Melitena)  
*Date* (?)

### 108(O). Kanlıkavak 15

*Province, Sub-Province + Admin. Code, Map and Location* As 108(A)  
*Copy* Hogarth and Munro 1891. The stone has not been re-found and examined by DHF 14.viii.1978. Text here of Hogarth and Munro (facsimile of the printed version of Hogarth and Munro's copy, Fig. 6.1.75 [p. 346])  
*Publication* Hogarth and Munro 1893, 702 (i) (facsimile, Fig. 6.1.75 [p. 346])  
 CIL 3. 12180 (text of Hogarth and Munro)  
 RRMAM 2, 1. 795 (notice only)  
*Description & Dimensions* Not given

*Text* - - - -  
 2 [p]e[r] Cuspi[dium]  
 [Fla]min[ium Se]verum\*  
 4 [leg] pr p[r]  
 [ - ]

line 3: **IERON** (Hogarth and Munro); Se]verum (DHF)

*Caput Viae* [Melitena]

*Date* AD 238 Pupienus and Balbinus, or Gordianus, on the basis of the governor's name; cp. the intact text above, 084. Mollahüseyin 4  
*Commentary* "The name of [Ant. Memmianus] Hieron[em], Philip's legate, also appears on the stone" (Hogarth and Munro).

**108(P). Kanlıkavak 16**

*Province, Sub-Province + Admin. Code, Map and Location* As 108(A)  
*Copy* Hogarth and Munro 1891. The stone has not been re-found and examined by DHF 14.viii.1978. Text here of Hogarth and Munro (facsimile of the printed version of their copy, Fig. 6.1.76 [p. 346])  
*Publication* Hogarth and Munro 1893, 702 (iii) (facsimile, Fig. 6.1.76 [p. 346])  
 CIL 3. 12182 (text of Hogarth and Munro)  
 RRMAM 2, 1. 796 (notice only)  
*Description & Dimensions* Not given

*Text* - - - -  
**Vol[usianus pii felic]**  
**invicti** [Augg]  
 - - - -

*Caput Viae* [Melitena]  
*Date* AD 251 [Trebonianus Gallus and] Volusianus *Augusti*  
*Commentary* Probably part of the other (upper) half of 108(Q)

**108(Q). Kanlıkavak 17**

*Province, Sub-Province + Admin. Code, Map and Location* As 108(A)  
*Copy* Hogarth and Munro 1891. The stone has not been re-found and examined by DHF 14.viii.1978. Text here of Hogarth and Munro (facsimile of the printed version of their copy, Fig. 6.1.77 [p. 346])  
*Publication* Hogarth and Munro 1893, 703 (iv) (facsimile, Fig. 6.1.77 [p. 346])  
 CIL 3. 12184 (text of Hogarth and Munro)  
 RRMAM 2, 1. 797 (notice only)  
*Description & Dimensions* Not given

*Text* - - - -  
 [vias et pon]t[es vetus]-  
 [tate co]n[l]aps[as]  
 4 [resti]tu[er]unt [per A]  
 [Vir]gil[ium Maxi]-  
**mum** [virum] c[lari]s[simum]  
 [le]g **Augg**  
 8 **pr pr**  
 [ - ]

*Caput Viae* [Melitena]  
*Date* AD 251-253 Trebonianus Gallus and Volusianus *Augusti*, on the basis of the governor's name; cp. the text above, 108(L)  
*Commentary* Probably the other (lower) half of 108(P)

**108(R). Kanlıkavak 18**

<i>Province, Sub-Province + Admin. Code, Map and Location</i>	As 108(A)
<i>Copy</i>	Hogarth and Munro 1891. The stone has not been re-found and examined by DHF 14.viii.1978. Notice here of Hogarth and Munro
<i>Publication</i>	Hogarth and Munro 1893, 703 (v) CIL 3. 12183 (notice of Hogarth and Munro) RRMAM 2, 1. 798 (notice only)
<i>Description &amp; Dimensions</i>	Not given
<i>Text</i>	Not given
<i>Date</i>	(1) (?) (2) AD 235 (?) Maximinus (3) AD 244 Philippus (4) AD 293-305 Diocletianus and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i>
<i>Caput Viae</i>	[Melitena]
<i>Commentary</i>	“A stone on which four inscriptions are hopelessly entangled” (Hogarth and Munro)

**108(S). Kanlıkavak 19**

<i>Province, Sub-Province + Admin. Code, Map and Location</i>	As 108(A)
<i>Copy</i>	DHF 13. viii.1978. DHF squeeze and photo. (Pl. 7.1.81 [p. 398]) in BIA
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 46. Maraş 35, Kanlıkavak 19 Stone: (1) B/W Neg.: DHF R/78/12.09
<i>Publication</i>	RRMAM 2, 1. 799 (notice only)
<i>Description</i>	A simple cylinder. Complete. Hard, white crystalline limestone. The top is flat. Underneath the base there is a shaped tenon. Surface and letters: very worn.
<i>Dimensions</i>	Ht 1.96; diam. (top) 0.57. Letters: 0.070-90
<i>Text</i>	<p style="text-align: center;">- - - -  <b>m CXX ρϰ'</b></p> <p><b>m</b> for <b>m</b>(ilia), cp. 056(B) (Sept. Sev.), 065 (Elag. + Sev. Alex.), 079(D), 084, 089(B), 093(H), 095 and 097(C) (all Gord.), 115 (Prob.); also 104(J), 114</p>
<i>Caput Viae</i>	(Melitena)
<i>Date</i>	(?)

**Kanlıkavak**

“In the cemetery by the roadside 20m southeast of Kanlı Kavak we found no less than twenty-six milliaria, many of which were never inscribed. The inscribed stones cost us a day and a half of hard work in deciphering and copying the inscriptions” (Sterrett 1883-84, 270)

**109(A). Yeniyapan 1**

<i>Province, Sub-Province + Admin. Code</i>	K. Maraş, Göksun 46-04-0
<i>Map</i>	Elbistan 93-II
<i>Location</i>	“In a small cemetery about half an hour east of Kanlı Kavak, to the left of the modern road” (Hogarth and Munro). Now in the village of Yeniyapan; at the cami, on the right-hand side of the entrance to the courtyard.
<i>Copy</i>	Hogarth and Munro 1891; DHF 14.viii.1978. DHF squeeze in BIA. Text here of Hogarth and Munro (facsimile of the printed version of their copy, Fig. 6.1.78 [p. 346]) and from DHF squeeze.
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 46. Maraş 54, Yeniyapan 1
<i>Publication</i>	Hogarth and Munro 1893, 704 “115 (i)” (facsimile, Fig. 6.1.78 [p. 346]) CIL 3. 12178 (text of Hogarth and Munro) RRMAM 2, 1. 835 (notice only)
<i>Description</i>	A simple cylinder. Complete but chipped. Hard, white crystalline limestone. The shaft tapers slightly towards the top. Surface: worn. Letters: worn, some indistinct, others clear and legible, neat in size, shape and alignment; broken-bar A
<i>Dimensions</i>	Ht (vis.) 1.67; diam. (top) 0.46. Letters: 0.045-50, (line 1) 0.090
<i>Text</i>	<p style="text-align: center;"> <b>Imp Ca[esar]</b>  <b>L·Septi⟨m⟩ius·Seve[r]us</b>  <b>Pius·Per⟨ti⟩nax·Aug·Arab·Adiab</b>  4        <b>Parthi ⟨max⟩ pont·max·trib·pot·VI</b>  <b>imp·XI·co⟨s II⟩ p p·procos·et·Imp·Caes·</b>  <b>M·Aurel ⟨A⟩ntoninus·Aug·</b>  [ - - - - - re]stituere[n]t  8        <b>per·C·Iul⟨ium Flacc⟩um Aelianum·leg·pr·pr</b>  [ - ] </p>
<i>Caput Viae</i>	[Melitena]
<i>Date</i>	AD 197/198, 10.xii-09.xii L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i>

**109(B). Yeniyapan 2**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 109(A)
<i>Location</i>	As 109(A) (described by Hogarth and Munro); an old <i>mezarlık</i> , Değirmenönü mevkii (Pl. 7.1.82 [p. 398]), c. 1.5 km SE of the village and c. 0.4 km E of the village şose.
<i>Copy</i>	Hogarth and Munro 1891 (facsimile of the printed version of their copy, Fig. 6.1.79 [p. 346]); DHF 15.viii.1978. DHF squeeze and photo. in BIA. Text here from DHF squeeze.
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 46. Maraş 55, Yeniyapan 2 Stone: (1) B/W Neg.: DHF R/78/12.11-12 and 13.02
<i>Publication</i>	Hogarth and Munro 1893, 704 “115 (ii)” (facsimile, Fig. 6.1.79 [p. 346]) CIL 3. 12179 (text of Hogarth and Munro)

<i>Description</i>	RRMAM 2, 1. 836 (notice only)
	A simple cylinder. Broken at the top. Hard, pale, crystalline limestone. Surface: worn.
<i>Dimensions</i>	Letters: worn but clear and legible, variable in size, otherwise neat in shape and alignment; broken-bar A
	Ht. (vis.) 0.90; diam. (top) 0.58. Letters: 0.050-60
<i>Text</i>	<p>-----</p> <p>2    [ - - - - res]tit[uerunt]-</p> <p>      <b>per</b> (leaf) <b>G</b> (leaf) [Iul]i<b>um</b> (leaf) <b>Fla-</b></p> <p>4    <b>cum</b> (leaf) <b>Aelianum</b> (leaf) <b>le</b>[g pr pr]</p> <p>      [ - ]</p>
<i>Caput Viae</i>	[Melitena]
<i>Date</i>	(?)AD 198 Sept. Severus and Caracalla <i>Augusti</i> with Geta <i>Caesar</i> , on the basis of the governor's name; cp. the intact text above, 105(A). Göksun 8

### 109(C). Yeniyapan 3

<i>Province, Sub-Province + Admin. Code and Map</i>	As 109(A)
<i>Location</i>	Formerly as 109(A) (described by Hogarth and Munro). Now in the village, at the cami; built into the NW corner of the courtyard wall.
<i>Copy</i>	Hogarth and Munro 1891; DHF 14.viii.1978. No squeeze. Text here from Hogarth and Munro (facsimile of the printed version of their copy, Fig. 6.1.80 [p. 347]) and DHF notes
<i>Publication</i>	Hogarth and Munro 1893, 704 "115 (iii)" (facsimile, Fig. 6.1.80 [p. 347]) CIL 3. 12174 (text of Hogarth and Munro) French 1980, 723 no. 25 (text from CIL 3. 12174) RRMAM 2, 1. 837 (notice only)
<i>Description</i>	Not given by Hogarth and Munro. A simple cylinder. (?)Broken at the top. White, crystalline limestone. Surface and letters: worn.
<i>Dimensions</i>	Ht (vis.) 1.08; diam. (top) 0.39. Letters: not recorded

<i>Text</i>	<p><b>Imp</b></p> <p><b>Caes·di-</b></p> <p><b>vi Severi</b></p> <p>4    <b>nep divi M An-</b></p> <p>      <b>tonini fil M</b></p> <p>      <b>Aurel Ant[oni] -</b></p> <p>      <b>no pio felici</b></p> <p>8    <b>Aug milia</b></p> <p>      <b>restituta per [M]</b></p> <p>      <b>Ulp Ofellium</b></p> <p>      <b>Theodorum leg</b></p> <p>12   <b>Aug pr pr</b></p> <p>      <b>μ ϰιϵ´</b></p>
-------------	--

line 13: **μ** for **μ**(ίλια), cp. 107(G) and 108(D) (Elagabalus), 119(A) (Severus Alexander), 072(C), 074(C), 075(C), 080(B), 087(B), 098(D), 104(B) and 108(M) (all Gordianus), 085(B) (Maximinus), 119(B) (Philippus);

also 112

*Caput Viae* (Melitena)  
*Date* Elagabalus *Augustus*, (?) AD 218, 16.v–(?) mid-June

**109(D). Yeniyapan 4**

*Province, Sub-Province + Admin. Code, Map and Location* As 109(A)  
*Copy* Hogarth and Munro 1891. The stone has not been re-found and examined by DHF 14 and 15.viii.1978. Text here from Hogarth and Munro (facsimile of the printed version of their copy, Fig. 6.1.81 [p. 347])  
*Publication* Hogarth and Munro 1893, 705 “115 (iv)” (facsimile, Fig. 6.1.81 [p. 347])  
 CIL 3. 12181 (text of Hogarth and Munro)  
 RRMAM 2, 1. 838 (notice only)  
*Description & Dimensions* Not given

*Text*

	----
2	<b>c[onl]apsas r[estituerunt]</b>
	<b>per Anto[nium Memmi]-</b>
4	<b>[um H]ie[r]onem [v c leg]</b>
	<b>[Aug pr pr]</b>
6	<b>[ - ]</b>

*Caput Viae* [Melitena]  
*Date* (?)AD 244-247 Philippus *Augustus* with Philippus *Caesar*, on the basis of the governor's name; cp. the intact text above, 068(D). Aslanbeyli Yaylası, Hanboğazı

**109(E). Yeniyapan 5**

*Province, Sub-Province + Admin. Code, Map and Location* As 109(A)  
*Copy* Hogarth and Munro 1891; DHF 15.viii.1978. DHF squeeze and photo. (Pl. 7.1.83 [p. 399]) in BIA. Text here from DHF squeeze.  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 56, Yeniyapan 5  
 Stone: (1) B/W Neg.: DHF R/78/13.01  
*Publication* Hogarth and Munro 1893, 705 “115 (v)”  
 CIL 3. 12175 (text of Hogarth and Munro)  
 RRMAM 2, 1. 839 (notice only)  
*Description* “Stump with only the numeral left” (Hogarth and Munro). A simple cylinder. Broken at the top. Hard, friable, white limestone. Surface: worn.  
 Letters: clear and legible; lunate E  
*Dimensions* Ht 1.27; diam. (bottom) 0.52. Letters: c. 0.055, lunate E 0.030

*Text*

	----
2	<b>[Cuspidium Flaminium Seve]-</b>
	<b>rum [leg]atum p[ro prae]-</b>
4	<b>toꝛe m</b>
	<b>[ - ]</b>

line 4: **PIE** (Hogarth and Munro)  
*Caput Viae* [Melitena]  
*Date* (?) AD 238 Pupienus and Balbinus, or Gordianus, on the basis of the governor's name, cp. the intact text above, 084(D). Mollahüseyn 4

### 109(F). Yeniyapan 6

*Province, Sub-Province + Admin. Code, Map and Location* As 109(A)  
*Copy* Hogarth and Munro 1891. The stone has not been re-found and examined by DHF 15.viii.1978  
*Publication* Hogarth and Munro 1893, 705 “115 (vi)” (facsimile, Fig. 6.1.82 [p. 347])  
 CIL 3. 12185 (text of Hogarth and Munro)  
 RRMAM 2, 1. 840 (notice only)  
*Description & Dimensions* Not given  
*Text* Consult the facsimile (Fig. 6.1.82 [p. 347])  
*Date* (?)

### Yeniyapan

There are two milestones at the cami in the village: (1) on the left-hand side of the entrance into the courtyard; upside down; tenon under base; (2) at the NE corner of the courtyard wall. Because of their position, neither can now be read. It is impossible to determine whether or not they have been published (DHF 14.viii.1978)

### 110. Karaömer 1

*Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-1  
*Map* Elbistan 93-II  
*Location* “By the roadside, 1 mile from the Duniyat Bel stone” (Hogarth and Munro); “près du village Kara Omerle” (de Jerphanion and Jalabert). Present whereabouts not known (DHF visit 15.viii.1978)  
*Copy* Hogarth and Munro 1891; de Jerphanion July-September 1907. The stone has not been examined by DHF 15.viii.78. Text here of Hogarth and Munro (facsimile of the printed version of their copy, Fig. 6.1.83 [p. 347])  
*Publication* Hogarth and Munro 1893, 705 “113” (facsimile, Fig. 6.1.83 [p. 347])  
 de Jerphanion and Jalabert 1908, 458 no. 27 (facsimile, Fig. 6.1.84 [p. 347])  
 CIL 3. 12171 (text of Hogarth and Munro)  
 RRMAM 2, 1. 800 (notice only)  
*Description* “Broken R.” (Hogarth and Munro)  
*Dimensions* Not given  
*Text* [Imp Caes]  
**L Septimius** [Severus]  
**Pius Pertin**[ax Aug Arab Adiab]  
 4 **Parth max pon**[t max trib pot VI]  
**imp XI·cos·II·p p pr**[ocos et Imp Caes]  
**M Aurel·Anto**[ni]-  
**nus Aug et** [ - - - ]



8 [ - - - - ] **res**[tituerunt]  
**per C Iulium** [Flac]-  
**cum** <Aeli>**anum·leg** [Aug pr pr]  
 [ - ]

line 6: AVRELI (de Jerphanion and Jalabert)

*Caput Viae* [Melitena]  
*Date* AD 197/198(?), L. Septimius Severus and M. Aurelius Antoninus (Caracalla)  
*Augusti* with L. Septimius Geta (names erased) *Caesar*  
*Commentary* “Il ne serait pas impossible que le texte relevé par le P. de Jerphanion soit le milliaire 113 de la voie, d’après Hogarth (C.I.L., III, 12171); je ne le crois cependant pas: il n’y a pas de localité du nom de Duniyat Bel dans les environs de l’endroit où le texte a été trouvé par le P. de J.; de plus, C.I.L., 12171 porte: imp.XI, cos.II.” (de Jerphanion and Jalabert 1908, 459). I suggest that ‘Duniyat’ is a rendering of Dügünürdu, the name of the village nearest to the head of the valley.

### 111(A). Karaömer 2

*Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-1  
*Map* Elbistan 93-II  
*Location* In the village; at the house of Ali Örer. Used as a gate-post, on the right-hand side of the entrance  
*Copy* DHF 15.viii.1978. DHF squeeze in BIA  
*BIA Collections:* *Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 36, Karaömer 2  
*Publication* RRMAM 2, 1. 801 (notice only)  
*Description* A simple cylinder. Complete. Hard, pale limestone. Surface and letters: very worn. Letters: very faint and obscure  
*Dimensions* Ht (vis.) 1.83; diam. (top) 0.48. Letters: c. 0.05

*Text*

- - - -  
 - - - - **ET** - -  
 - - **GORDIA** -  
 - - - -  
 - - - -  
 - - - -  
 - - - - **ET** - -  
 - - - -  
 indistinct lines

*Date* (?)

### 111(B). Karaömer 3

*Map, Province, Sub-Province + Admin. Code and Location* As 111(A); but on the left-hand side of the entrance.  
*Copy* DHF 15.viii.1978  
*Publication* RRMAM 2, 1. 802  
*Description & Dimensions* Not recorded

*Text* No visible inscription

## 112. Düğün-yurdu

*Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-1  
*Map* Elbistan 93-II  
*Location* “ . . . . in the Duniyat Bel” (Hogarth and Munro). Present whereabouts not known (DHF visit 15.viii.1978)  
*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Hogarth and Munro (facsimile of the printed version of their copy, Fig. 6.1.85 [p. 348])  
*Publication* Hogarth and Munro 1893, 705 “114” (facsimile, Fig. 6.1.85 [p. 348])  
 CIL 3. 12172 (text of Hogarth and Munro)  
 RRMAM 2, 1. 734 (notice only)  
*Description* “Lower fragment of a stone” (Hogarth and Munro)  
*Dimensions* Not given

*Text* - - - -  
 pr  
 μ ριδ'

μ for μ(ιλια), cp. 107(G), 108(D) and 109(C) (Elagabalus), 119(A) (Severus Alexander), 068(C), 072(C), 074(C), 075(C), 080(B), 087(B), 098(D), 103(C), 104(B) and 108(M) (all Gordianus), 085(B) (Maximinus), 119(B) (Philippus)

*Caput Viae* (Melitena)  
*Date* (?)

## 113(A). Karaömer, Kızılçık-suyu Mevkii 1

*Province, Sub-Province + Admin. Code* K. Maraş, Göksun 46-04-1  
*Map* Elbistan 93-II  
*Location* *In situ*; in the field of Mehmet Ali Bala, c. 15 m S of the road to Afşin and c. 0.8 km W of the bridge over the Kızılçık-suyu. The area is called ‘Taşköprü mevkii’  
*Copy* DHF 15.viii.1978. DHF squeeze and photo. (Pl. 7.1.084 [p. 399]) in BIA  
*Publication* RRMAM 2, 1. 803 (notice only)  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 37, Karaömer, Kızılçık-suyu Mevkii 1  
 Stone: (1) B/W Neg.: DHF R/78/13.03  
*Description* A simple cylinder. Broken at the top and bottom. White crystalline limestone. The shaft tapers towards the top. Surface and letters: very worn.  
 Letters: very faint; broken-bar A  
*Dimensions* Ht 1.59; diam. (top) 0.43, (bottom) 0.54. Letters: c. 0.045, (line 1) 0.055

*Text* **Imp Caesar C** [Iul Vero]  
 2 [M]aximino [pio fel inv Aug]  
**trib·p·per** [ - - - ]  
 4 - - - -

*Caput Viae* [Melitena]  
*Date* AD 235 Maximinus, cp. the text above, 098(B). Keklikoluk 2

### 113(B)-(C). Karaömer, Kızılçaksuyu Mevkii 2-3

*Province, Sub-Province + Admin. Code, Map and Location* As 113(A)  
*Copy* DHF 15.viii.1978  
*Publication* RRMAM 2, 1. 804 and 805  
*Description & Dimensions* Not recorded  
*Text* No visible inscription

### 114. Ördek

*Province, Sub-Province + Admin. Code* K. Maraş, Afşin 46-01-0  
*Map* Elbistan 95-Ik  
*Location* In the village; in the wall of the orchard owned by the *muhtar*, Osman Gökkaya  
*Copy* DHF 20.viii.1982. DHF squeeze in BIA. Text here from DHF squeeze (drawing, Fig. 6.2.31 [p. 367])  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 43, Ördek  
*Publication* French 1983, 87 (notice only)  
 French 1985b, 147 and Fig. 1  
 AE 1986. 690 (text of French 1985b)  
 Christol and Lorient 1986, 17 (comment on text ll. 6-7)  
 RRMAM 2, 1. 821 (notice only)  
 AE 1990. 982 (text of French 1985b)  
*Description* A simple cylinder. Broken at the top. Pale limestone. The shaft tapers slightly towards the top. Surface: rough.  
 Letters: sharp and clear, variable in size, shape and alignment  
*Dimensions* Ht (ex.) c. 1.15; diam. not recorded. Letters: 0.040-60, (line 8) M and C 0.090 and 0.145  
*Text* (1) (underneath text [2])  
 obliterated  
 (2) (on the top of text [1])  
 - - - -  
 [...]ON[ - - - - ]  
**cons p p** [vias et pontes]  
 4 **vetustate c**[onlapsas]  
**restituit·mi**[liaria re]-  
**stituta per Q Iul** [...]-  
**anum leg Aug pr** [pr]  
 8 **m CIII**  
 line 8: **m** for **m**(ilia), cp. 056(B) (Sept. Severus), 065 (Elagabalus + Sev. Alexander), 079(D), 084, 089(B), 093(H), 095 and 097(C) (all Gordianus), 115 (Probus); also 104(J), 108(F)  
*Caput Viae* (Melitena)  
*Date* (1) (?)

## (2) (?) Severus Alexander

*Commentary* Previously (French 1985), on the basis of the Zile 1 milestone (see above, 056[A]) on which the names both of the emperor and of the governor are fully preserved, the governor's name was restored in the Ördek text as Q. Iul(ius) [Procli]anus. This restoration would be thrown into doubt if, from the early years of Severus Alexander, Zela was a city within the province of Pontus, not of Cappadocia. By the final years of Severus Alexander Amasia – and therefore Zela ? – had been incorporated into the province of Pontus (French 1986a, 82 = AE 1986.653) but see now Christol and Lorient (2001, 101 and n.27) who state emphatically that Q. Iulius Proclianus was governor of Cappadocia, not of Pontus.

**115. Alımpınar**

<i>Province, Sub-Province + Admin. Code</i>	K. Maraş, Afşin 46-01-0
<i>Map</i>	Elbistan 95-Ik
<i>Location</i>	In the village cemetery; on the N side of the old Göksun-Afşin road
<i>Copy</i>	DHF 21.viii.1982. DHF squeeze in BIA. Text here from DHF squeeze (drawing, Fig. 6.2.32 [p. 368])
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i>
	Squeeze: 46. Maraş 4, Alımpınar
<i>Publication</i>	French 1983, 87 (notice only) RRMAM 2, 1. 718 (notice only)
<i>Description</i>	A simple cylinder. Now broken on all sides. Hard, white limestone. Surface: rough, damaged and worn. Letters: worn but legible, neat in shape, variable in size; diagonal-bar A, U for V
<i>Dimensions</i>	Ht (ex.) c. 1.25. Letters: 0.050-65
<i>Text</i>	(1) (underneath text [2]) obliterated  (2) (on the top of text [1]) <div style="text-align: center;"> <b>Imp</b>  2    <b>Caes</b>  <b>Ma·Au[r]</b>  4    <b>Pro/b/ο</b>  <b>p f invi</b>  6    <b>Aug</b>  <b>m CV</b> </div> line 3: <b>Ma</b> for <b>Ma</b> (rco) line 4: <b>R</b> for <b>B</b> , cp. above, 037(B). Çorum Museum and RRMAM 3.4 Pontus et Bithynia 43. Boyabat 2 line 7: <b>m</b> for <b>m</b> (ilia), cp. 056(B) (Sept. Sev.), 065 (Elag. + Sev. Alex.), 079(D), 084, 089(B), 093(H), 095 and 097(C) (all Gordianus); also 104(J), 108(F), 114
<i>Caput Viae</i>	(Melitena)
<i>Date</i>	AD 276 (?), Probus <i>Augustus</i>

**116(A). Afşin 1**

<i>Province, Sub-Province + Admin. Code</i>	K. Maraş, Afşin 46-01-0
<i>Map</i>	Elbistan 95-Ij
<i>Location</i>	“In the cemetery” (Sterrett). Present whereabouts not established (DHF visit 21.viii.1982)
<i>Copy</i>	Sterrett 31 July, 1884; de Jerphanion July-September, 1907. The stone has not been examined by DHF (visit 21.viii.78). Text here of Sterrett (facsimile of the printed version of Sterrett’s copy (Fig. 6.1.86 [p. 348]))
<i>Publication</i>	Sterrett 1883-84, 285 no. 329 (facsimile, Fig. 6.1.86 [p. 348]) Sterrett 1885, 35 no. 50 CIL 3. 6908 (text of Sterrett) Hogarth and Munro 1893, 706 “99 to 95 (i)” (notice) (?) de Jerphanion and Jalabert 1908, 457 s. no. 24 RRMAM 2, 1. 715 (notice only)
<i>Description</i>	“So superscribed as to be hopelessly illegible” (Sterrett)
<i>Dimensions</i>	Not given
<i>Text</i>	<p>-----</p> <p><b>nobilissimi</b></p> <p><b>Caes</b></p>
<i>Caput Viae</i>	[Melitena]
<i>Date</i>	(?)

**116(B). Afşin 2**

<i>Province, Sub-Province + Admin. Code, Map and Location</i>	As 116(A)
<i>Copy</i>	Sterrett 31 July, 1884; de Jerphanion July-September, 1907. The stone has not been examined by DHF (visit 21.viii.1982). Text here of Sterrett (facsimile of the printed version of Sterrett’s copy (Fig. 6.1.87 [p. 348]))
<i>Publication</i>	Sterrett 1883-84, 285 no. 330 (facsimile, Fig. 6.1.87 [p. 348]) Sterrett 1885, 36 no. 51 CIL 3. 6909 (text of Sterrett) Hogarth and Munro 1893, 706 “99 to 95 (ii)” (notice) (?) de Jerphanion and Jalabert 1908, 457 s. no. 24 RRMAM 2, 1. 716 (notice only)
<i>Description</i>	“Illegible” (Sterrett)
<i>Dimensions</i>	Not given
<i>Text</i>	<p>-----</p> <p><b>conlap</b></p> <p>-----</p>
<i>Caput Viae</i>	[Melitena]
<i>Date</i>	(?) 3rd cent. AD

**116(C). Afşin 3**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 116(A)
<i>Location</i>	“Dans le cimetière” (de Jerphanion and Jalabert). Present whereabouts not established (DHF visit 21.viii.82)

<i>Copy</i>	de Jerphanion July–September, 1907. The stone has not been examined by DHF. Text here of de Jerphanion and Jalabert (facsimile of the printed version of Jalabert’s copy (Fig. 6.1.88 [p. 348])
<i>Publication</i>	de Jerphanion and Jalabert 1908, 457 no. 24 (facsimile, Fig. 6.1.88 [p. 348]) RRMAM 2, 1. 717 (notice only)
<i>Description &amp; Dimensions</i>	Not given
<i>Text</i>	See facsimile (Fig. 6.1.88 [p. 348])
<i>Caput Viae</i>	[Melitena]
<i>Date</i>	(?)

**117(A). Emirli 1**

<i>Province, Sub-Province + Admin. Code</i>	K. Maraş, Afşin 46-01-0
<i>Map</i>	Elbistan 95-Ij
<i>Location</i>	“In the old cemetery between Emirli and Ziyaret Serai” (Sterrett). Present whereabouts not established (DHF visit 21.viii.1982)
<i>Copy</i>	Sterrett 31 July, 1884. The stone has not been examined by DHF. Text here of Sterrett (facsimile of the printed version of Sterrett’s copy (Fig. 6.1.89 [p. 348])
<i>Publication</i>	Sterrett 1883-84, 288 no. 337 (facsimile, Fig. 6.1.89 [p. 348]) Sterrett 1885, 35 no. 49 CIL 3. 6910 (text of Sterrett) Hogarth and Munro 1893, 706 “100 (ii)” (notice) RRMAM 2, 1. 749 (notice only)
<i>Description &amp; Dimensions</i>	Not given
<i>Text</i>	<p>-----</p> <p>2    <b>imp trib pot via-</b>       [s] <b>et [po]nte-</b></p> <p>4    <b>s r[e]stituerun[t]</b>       [...] <b>C IVLI[...]</b>OCI[...]</p> <p>6    [leg] <b>Aug [pr] pr</b>       (vac) <b>C</b></p>

line 5: (?) [per] **C Iul I[...]**oci[...]

<i>Caput Viae</i>	(Melitena)
<i>Date</i>	(?)

*Commentary* The titlature in line 2 is unusual. On the other hand the central position of **C** (if correctly recorded by Sterrett) suggests a narrow inscription of short lines. In the standard text of Septimius Severus, for example, the acclamation *imp* always follows the tribunician power *trib pot*. Other Emperors do not inscribe the acclamation *imp* on their milestones (of the Caesaria-Melitena road) but cf. the milestones of Severus Alexander at Adana in Cilicia (RRMAM 1. 64) and at Tokat (054[G]). Only on some milestones of Maximinus does the tribunician power, *tribunicie potestate* (sic) stand alone at the end of the Imperial titlature. The phrase restored in lines 2-4, *vias et pontes restituerunt*, is not certainly attested on the Caesaria-Melitena road. The usual form of the repair-formula is *vias et pontes vetustate conlapsas restituit/erunt*: Severus Alexander, Philippus with Philippus Caesar and Trebonianus Gallus. It is not found in the standard Severan text, cp. above, 105(A). Göksun 8.

The plural verb (line 4) *restituerunt* requires a plural subject, either two Emperors or an Emperor with a Caesar or Caesars. Only Valerianus and Gallienus are not represented on the Caesaria-Melitena road. The known titular formulae of other 3rd-century Emperors cannot be matched with the Emirli text.

Sterrett (1883-84, 288) wrote: “The name of the legate is probably C. Julius Flaccus Aelianus, and consequently the inscription belongs to Septimius Severus. Still the data are too insignificant to make this certain”. If so, the copy (as he himself admits) is defective.

### 117(B). Emirli 2

*Province, Sub-Province + Admin. Code and Map* As 117(A)

*Location* In the old village-cemetery; c. 0.5 km W of the village, on the N side of the road to Eshabikeyf

*Copy* DHF 21.viii.1982

*Description* Extremely worn

*Dimensions* Not recorded

*Text*

----  
CI

*Caput Viae* (Melitena)

*Date* (?)

### 118(A). Izgın, Çatburun 1

*Province, Sub-Province + Admin. Code* K. Maraş, Elbistan 46-03-0

*Map* Elbistan 96-Ik

*Location* Probably *in situ*, on the S side of the Roman road. Lying on the S side of the newly built şose to Izgın; c. 5.80 km E of Afşin

*Copy* DHF 22.viii.1982. DHF squeeze in BIA. Text here from DHF squeeze

*BIA Collections: Squeeze and Stone Photographs*  
Squeeze: 46. Maraş 27, Izgın, Çatburun 1  
Stone: (1) B/W Neg.: DHF M/82/10.13  
(2) Col. Slide: DHF 229.34

*Publication* RRMAM 2, 1. 777 (notice only)

*Description* A simple cylinder. Broken at the bottom. Hard, white limestone. The shaft tapers towards the top. Surface: damaged, worn and pitted.

Letters: worn but mostly legible, neat in shape, size and alignment; broken-bar A  
*Dimensions* Ht (ex.) 1.10; diam. (bottom) c. 0.51. Letters: 0.070-10, (line 1) 0.13

*Text*

Imp Caes  
2 D n Gaio  
(vac)  
Iulio Vero  
4 Maximino  
[pi]o fel[ici]  
6 [Au]g  
----

*Caput Viae* [Melitena]

*Date* AD 235 Maximinus *Augustus*, cp. the text above, 098(B). Keklikoluk 2

### 118(B). Izgın, Çatburun 2

*Province, Sub-Province + Admin. Code and Map* As 118(A)

*Location* “In an old cemetery one hour and four” (= forty [DHF]) “minutes E of Yarpuz” (Sterrett); “At Ziyaret Serai” (Hogarth and Munro). In an old cemetery (Pl. 7.1.85 [p. 399]), on the S side of the old track, now a şose, from Afşin to Izgın; c. 7 km E of Afşin and c. 10 km W of Izgın

*Copy* Sterrett 04 August, 1884 (facsimile of the printed version of Sterrett’s copy (Fig. 6.1.90 [p. 348]); DHF 22.viii.1982. DHF squeeze in BIA. Text here from DHF squeeze.

*BIA Collections: Squeeze and Stone Photographs*

Squeeze: 46. Maraş 28, Izgın, Çatburun 2

*Publication* Sterrett 1883-84, 291 no. 341 (facsimile, Fig. 6.1.90 [p. 348])

Sterrett 1885, 36 no. 52

CIL 3. 6907 (text of Sterrett)

Hogarth and Munro 1893, 686, 706 “100 (i)” (notice)

RRMAM 2, 1. 778 (notice only)

*Description* A simple cylinder. (?)Broken at the bottom. Hard, pink and white limestone. The shaft tapers slightly towards the top. Surface: damaged, worn and pitted. Letters: worn and damaged, some faint and indistinct; broken-bar A

*Dimensions* Ht (ex.) 1.42; diam. (max.) c. 0.46. Letters: 0.035-45

*Text* (1) underneath text (2)  
traces of letters underneath line 1 of text (2)

(2) (on the full face of the shaft)

.

.

**Pertinax**

.

4

.

.

.

.

8

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

.

**·M·Aurel·Antoni-**  
**n(u)s·[Aug] [et L. Septimius]**  
**[[Geta·Caes]]·restit-**  
**uerunt·per·**  
**[C] Iulium·Flac-**  
**cum·Aelianum·le(g)·pr·pr**  
(vac) **mil p[ - ]**

(sic)

*Caput Viae* (Melitena)

*Date* (1) (?)

(2) [L. Septimius Severus and] M. Aurelius Antoninus (Caracalla) *Augusti* with L. Septimius Geta (names erased) *Caesar*, (?) AD 197/198, cp. the intact text above, 105(A). Göksun 8



**118(C). Izgın, Çatburun 3**

*Province, Sub-Province + Admin. Code and Map* As 118(A)

*Location* “In an old cemetery, one hour and forty minutes east of Yarpuz” (Sterrett); “In a cemetery about 4 miles E of Yarpuz” (Hogarth and Munro); “Kirchhof zwischen Jarpuss und Albisstan” (Grothe). Present location as 118(B).

*Copy* Sterrett 04 August, 1884 (facsimile of the printed version of Sterrett’s copy (Fig. 6.1.91 [p. 348]); Hogarth and Munro 1891 (facsimile of the printed version of their copy (Fig. 6.1.92 [p. 349]); Grothe 1906/7; DHF 22.viii.1982. DHF squeeze in BIA. Text here from DHF squeeze (drawing, Fig. 6.2.33 [p. 368])

*BIA Collections:* *Squeeze and Stone Photographs*  
Squeeze: 46. Maraş 29, Izgın, Çatburun 3

*Publication* Sterrett 1883-84, 292 no. 342 (facsimile, Fig. 6.1.91 [p. 348])  
Sterrett 1885, 36 no. 53  
CIL 3. 6906 (text of Sterrett)  
Hogarth and Munro 1893, 686, 706 “94 (i)” (facsimile, Fig. 6.1.92 [p. 349])  
CIL 3. 12169 (text of Hogarth and Munro)  
Grothe 1911, 1, LXXXIV no. 36  
French 1985b, 147 and Fig. 2  
RRMAM 2, 1. 779 (notice only)

*Description* “Broken at the bottom” (Hogarth and Munro). “Umgestürzter schw. saulenstein; . . . Schlecht erhalten, Abklatsch unmöglich” (Grothe). A simple cylinder. Broken into two large pieces. Hard, blue limestone. The shaft tapers slightly towards the top. Surface: slightly worn. Letters: slightly worn but clear and legible, neat in shape, size and alignment; broken-bar A, U for V

*Dimensions* “. . . h 1,25m; Buchstaben 0.07m.” (Grothe). Ht (ex.) 0.83 + 0.60; diam. (max.) 0.53. Letters: c. 0.045-50, (line 1) 0.050-70, (line 6) O 0.35

*Text* (1) (underneath text [2])  
Some letters were incorporated into text (2)

(2) (on the top of text [1])

**Imp** (leaf) **Caes** [(leaf)]

**M** (leaf) **Aurelius Se-**  
**verus Alex̄ander**

4 **p̄ius felix̄ Aug** (leaf) **tr-**  
**ib** (leaf) **potest** (leaf) **cos** (leaf)

**p p** (leaf) **vias et pont-**  
**es vettustate**

(sic)

8 **[con]lapsas rest-**

**[itu]it** (leaf)

**[ - ]** (leaf)

*Caput Viae* [Melitena]

*Date* (1) AD 218 Elagabalus *Augustus* ?

(2) AD 222, 14(?).iii-09.xii Severus Alexander *Augustus*

*Commentary* For **vettustate**, see also 104(F), 119(A) and Bolatcık (RRMAM 3, 2 [Galatia]. 56), all milestones of Severus Alexander.

For the re-cutting of an earlier text, see above, 104(F), and below, 119(A), where an inscription of

Elagabalus was altered in order to accommodate the name of Severus Alexander.

#### 118(D). İzgın, Çatburun 4

*Province, Sub-Province + Admin. Code, Map and Location* As 118(C)

*Copy* Hogarth and Munro 1891 (facsimile of the printed version of their copy (Fig. 6.1.93 [p. 349]); DHF 22.viii.1982. DHF squeeze in BIA. Text here from DHF squeeze

*BIA Collections: Squeeze and Stone Photographs*

Squeeze: 46. Maraş 30, İzgın, Çatburun 4

*Publication* Hogarth and Munro 1893, 686, 706 “94 (ii)” (facsimile, Fig. 6.1.93 [p. 349])  
CIL 3. 12170 (text of Hogarth and Munro)  
RRMAM 2, 1. 780 (notice only)

*Description* A simple cylinder. Hard, white limestone. The shaft tapers towards the top. The surface is rough, particularly at the top. Surface: worn and damaged.

Letters: very deeply and broadly cut; broken-bar A

*Dimensions* Ht 1.46; diam. (max.) 0.48. Letters: 0.070-80

*Text*

**Imp Caes**  
(vac)  
**Gaio [Iu]-**  
**lio Vero Ma-**  
4 **ximino p**  
**felic** (vac) **Aug**  
[p m trib p per]  
[Licinnium]  
8 [Serenianum]  
10 **leg** [Aug pr pr]  
[ - ]

*Caput Viae* [Melitena]

*Date* AD 235 Maximinus *Augustus*, cp. the text above, 098(B). Keklikoluk 2

#### 119(A). Çağılhan 1

*Province, Sub-Province + Admin. Code* K. Maraş, Afşin 46-01-0

*Map* Elbistan 96-Ik

*Location* In the cemetery; c. 0.5 km S of the village, on the N side of the Göksun şose.

*Copy* DHF 24.viii.1982. No squeeze. No photo. Text here from DHF notes

*Publication* French 1985b, 151 and n.22 (notice, and excerpt from text)  
RRMAM 2, 1. 719 (notice only)

*Description* A simple cylinder. Broken below and behind. Hard, pale limestone.

*Dimensions* Ht 1.06; diam. (bottom) 0.48

*Text*

[Imp Caesar]  
[M Aurelius Se]-  
**verus** [Alexander]  
4 **pius felix Aug** [trib]  
**potest** (leaf) **cos** [p p]  
**vias et pontes ve-**

8 **ttustate con-** (sic)  
**lapsas resti-**  
**tuit** (leaf)  
 μ ϣζ'

line 10: μ for μ(ίλια), cp. 107(G), 108(D) and 109(C) (Elag.), 068(C) (Sev. Alex.), 072(C), 074(C), 075(C), 080(B), 087(B), 098(D), 104(B) and 108(M) (all Gordianus), 085(B) (Maximinus), 119(B) (Philippus); also 112

*Caput Viae* (Melitena)  
*Date* AD 222, 14(?) iii-09.xii Severus Alexander *Augustus*  
*Commentary* For **vettustate**, see above, 104(F), 118(C) and RRMAM 3: 56

### 119(B). Çağilhan 2

*Province, Sub-Province + Admin. Code, Map and Location* As 119(A)  
*Copy* DHF 24.viii.1982. No squeeze. No photo. Text here from DHF notes  
*Publication* RRMAM 2, 1. 720 (notice only)  
*Description* A simple cylinder. Hard, white limestone. A tenon under the base.  
*Dimensions* Ht (vis.) 1.28 (without tenon); diam. (bottom) 0.50; (tenon) ht 0.10

*Text*

-----  
**Aug et M**  
**Iul Philippus**  
 4 **nobilissimus Cae-**  
**sar vias et po-**  
**ntes vetustate**  
**conlapsas res-**  
 8 **tituerunt**  
**per <A>nton[ium]**  
**Memm[ium H] -**  
**iero-**  
 12 **nem leg**  
**pr pr**  
 μ ϣη'

line 14: μ for μ(ίλια), cp. 107(G), 108(D) and 109(C) (Elag.), 119(A) (Sev. Alex.), 068(C), 072(C), 074(C), 075(C), 080(B), 087(B), 098(D), 104(B) and 108(M) (all Gordianus), 085(B) (Maximinus); also 112

*Caput Viae* (Melitena)  
*Date* AD 244, July/Aug.-247, July/Aug. Philippus *Augustus* with Philippus *Caesar*, cp. the near-intact text above, 068(D). Aslanbeyli Yaylası, Hanboğazı 4

### 120(A). İzgın 1

*Province, Sub-Province + Admin. Code* K. Maraş, Elbistan 46-03-0  
*Map* Elbistan 96-Ij

<i>Location</i>	“In the cemetery” (Sterrett). The cemetery is located on the W edge of the village.
<i>Copy</i>	Haynes (in the place of an ill Sterrett) 04 August, 1884; DHF 22.viii.1982. DHF squeeze in BIA. Text here of Sterrett (facsimile of the printed version of Haynes’ copy (Fig. 6.1.94 [p. 349]) and from DHF squeeze.
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 46. Maraş 24, Izgın 1
<i>Publication</i>	Sterrett 1883-84, 293 no. 343 (facsimile, Fig. 6.1.94 [p. 349]) Sterrett 1885, 37 no. 54 CIL 3. 6904 (text of Sterrett) RRMAM 2, 1. 775 (notice only)
<i>Description</i>	A simple cylinder. Broken at the top. Hard, white limestone. Surface: well preserved. Letters: (text 2) bright, sharp, very neat in shape, size and alignment; broken-bar A
<i>Dimensions</i>	Ht (ex.) 0.99; diam. (bottom) 0.51. Letters: (text 1) 0.045-50
<i>Text</i>	(1) (underneath text [2]) obliterated  (2) (on the top of text [1]) <div style="text-align: center;"> <p>-----</p> <p>[cos] II·p p·procos·</p> <p>et·Imp·Caes·M·Aurel·</p> <p>4 Antoninus·Aug</p> <p>et [[L·Septimius]]</p> <p>[[Geta Caes]] restit-</p> <p>[u]erunt·per·C·Iulium</p> <p>8 Flaccum·Aelianum</p> <p>le(g)·pr·pr</p> <p>[ - ]</p> </div> <div style="text-align: right;">(sic)</div>
<i>Caput Viae</i>	[Melitena]
<i>Date</i>	(1) (?) (2) [L. Septimius Severus] and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (names erased) <i>Caesar</i> , (?) AD 197/198, cp. the intact text above, 105(A). Göksun 8

## 120(B). Izgın 2

<i>Province, Sub-Province + Admin. Code, and Map</i>	As 120(A)
<i>Location</i>	“At Izgın” (Hogarth and Munro)
<i>Copy</i>	J. H. Haynes (in the place of an ill Sterrett) 04 August, 1884 (facsimile of the printed version of Haynes’ copy (Fig. 6.1.095 [p. 349]); Hogarth and Munro 1891 (facsimile of the printed version of their copy (Fig. 6.1.96 [p. 350]); DHF 22.viii.1982. DHF squeeze in BIA. Text here from DHF squeeze.
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 46. Maraş 25, Izgın 2
<i>Publication</i>	Sterrett 1883-84, 293 no. 344 (facsimile, Fig. 6.1.95 [p. 349]) Sterrett 1885, 37 no. 55

	CIL 3. 6905 (text of Sterrett)
	Hogarth and Munro 1893, 707 “93 to 59 (i)” (facsimile, Fig. 6.1.96 [p. 350])
	CIL 3. 12168 (text of Hogarth and Munro)
	RRMAM 2, 1. 776 (notice only)
<i>Description</i>	A simple cylinder. Blue and white limestone. The top is flat. The base has been roughly hollowed. There is a deep groove near the top, probably natural. Surface and letters: worn.
	Letters: some faint and indistinct, cut with a broad-blade chisel (c. 0.006 in breadth), variable in size, lunate E but not throughout
<i>Dimensions</i>	Ht 1.53; diam. (bottom) 0.55. Letters: 0.040-60
<i>Text</i>	<p><b>Imp Caes</b>  <b>M Ant</b>[onius]  <b>Gordianu</b>  4 <b>p</b>&lt;i&gt;us felix  <b>Aug pontif</b>  <b>ma</b>[xi]mus  <b>trib potest</b>  8 <b>p p rest</b>[ituit]  <b>per Cuspidium</b>  <b>Flaminium</b>  [Severu]m <b>l</b>e<sup>g</sup> [Aug]  12 [pr pr]  [ - ]</p>

*Date* AD 238, 09.v(?)–09.xii Gordianus *Augustus* (NB Gordianus not yet COS)

*Commentary* “Of this only a fragment is published in ‘C.I.L.’ The formula of Gordian is fairly complete. Confused with it is that of another emperor, who records his tribunician power, and therefore is not Diocletian, but almost certainly Maximin” (Hogarth and Munro).

For the epigraphic transition from Pupienus and Balbinus *Augusti* to Gordianus *Augustus*, see above [p. 12], **Notes and Comments 3.5** Text form (5).

## 121. Yapraklı, form. Burtu

<i>Province, Sub-Province + Admin. Code</i>	K. Maraş, Elbistan 46-03-0
<i>Map</i>	Elbistan 97-Ij
<i>Location</i>	In the village cemetery
<i>Copy</i>	DHF 25.viii.1982
<i>Publication</i>	RRMAM 2, 1. 831
<i>Description &amp; Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

## 122. Hasankendi

<i>Province, Sub-Province + Admin. Code</i>	K. Maraş, Elbistan 46-03-0
<i>Map</i>	Elbistan 97-Ij
<i>Location</i>	In the village; erected in the garden in front of the school.
<i>Copy</i>	DHF 25.viii.1982
<i>Publication</i>	RRMAM 2, 1. 774
<i>Description &amp; Dimensions</i>	Not recorded

*Text* No visible inscription

### 123(A). Elbistan 1

*Province, Sub-Province + Admin. Code* K. Maraş, Elbistan 46-03-0  
*Map* Elbistan 97-Ik  
*Location* “In the cemetery” (Sterrett; Hogarth and Munro). Present whereabouts not established (DHF visit 24.viii.12)  
*Copy* Sterrett 05-07 August, 1884; Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Sterrett (facsimile of the printed version of Sterrett’s copy (Fig. 6.1.97 [p. 350]) and of Hogarth and Munro (facsimile of the printed version of their copy (Fig. 6.1.98 [p. 350])  
*Publication* Sterrett 1883-84, 294 no. 345 (facsimile, Fig. 6.1.97 [p. 350])  
 Sterrett 1885, 37 no. 56  
 CIL 3. 6903 (text of Sterrett)  
 Hogarth and Munro 1893, 707 “93 to 59 (iii)” (facsimile, Fig. 6.1.98 [p. 350])  
 CIL 3. 12163 (text of Hogarth and Munro)  
 RRMAM 2, 1. 735 (notice only)  
*Description & Dimensions* Not given

*Text*

[Imp]  
**Caes**  
 [divi Se]ver[i] **nep**  
 4 [divi M Antonin]i **fil**  
 \* \*\*\*  
 [M Aur A]n~~ton~~[ino]  
 [pio f]e[lici] **Aug**  
 [milia] **restitut**[a]  
 8 [per] **M Ulp Ofelli**[um]  
**Theodorum**  
 [leg] **Aug pr pr**  
 [ - ]

*Caput Viae* [Melitena]  
*Date* Elagabalus *Augustus*, (?) AD 218, 16.v–(?) mid-June, cp. the intact text above, 068(B). Aslanbeyli Yaylası, Hanboğazı 2

### 123(B). Elbistan 2

*Province, Sub-Province + Admin. Code, Map and Location* As 123(A)  
*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Hogarth and Munro (facsimile of the printed version of their copy (Fig. 6.1.99 [p. 350])  
*Publication* Hogarth and Munro 1893, 707 “93 to 59 (iv)” (facsimile, Fig. 6.1.99 [p. 350])  
 CIL 3. 12164 (text of Hogarth and Munro)  
 RRMAM 2, 1. 736 (notice only)  
*Description* “Intentionally defaced. A few letters have been overlooked by the defacer on the extreme left” (Hogarth and Munro).  
*Dimensions* Not given  
*Text* - - - -

[Sev]er[us Pius Pertinax Aug]  
 [Ar]ab [Adiab Parth max pont max trib]  
 [p]o[t - - - ]  
 - - - -

*Caput Viae* [Melitena]  
*Date* (?) L. Septimius Severus and M. Aurelius Antoninus (Caracalla) *Augusti* with L. Septimius Geta (names erased) *Caesar*, (?) AD 197/198, cp. the intact text above, 105(A). Göksun 8

### 123(C). Elbistan 3

*Province, Sub-Province + Admin. Code, Map and Location* As 123(A)  
*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Hogarth and Munro (facsimile of the printed version of their copy (Fig. 6.1.100 [p. 350])  
*Publication* Hogarth and Munro 1893, 707 “93 to 59 (v)” (facsimile, Fig. 6.1.100 [p. 350]) CIL 3. 12165 (text of Hogarth and Munro)  
 RRMAM 2, 1. 737 (notice only)  
*Description* “Intentionally defaced” (Hogarth and Munro)  
*Dimensions* Not given

*Text* - - - -  
 [vetust]ate co[n]lapsas]  
 re[stitui]t [per]  
 [Antoni]um M[emmium] Hier[onem]  
 [v c leg] Aug [pr pr]  
 [ - ]

*Caput Viae* [Melitena]  
*Date* AD 244 Philippus *Augustus* with Philippus *Caesar*, on the basis of the governor’s name; cp. the intact text above, 068(D). Aslanbeyli Yaylası, Hanboğazı 4

### 123(D). Elbistan 4

*Province, Sub-Province + Admin. Code, Map and Location* As 123(A)  
*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here of Hogarth and Munro (facsimile of the printed version of their copy (Fig. 6.1.101 [p. 349])  
*Publication* Hogarth and Munro 1893: 708 “93 to 59 (vi) and (vii)” (facsimile, Fig. 6.1.101 [p. 350])  
 CIL 3. 12166 (text of Hogarth and Munro)  
 RRMAM 2, 1. 738 (notice only)  
*Description* “Half buried, upside down. Traces of red in the lettering” (Hogarth and Munro)  
*Dimensions* Not given

*Text* (1) Consult the facsimile (Fig. 6.1.101 [p. 350])

(2) - - - -  
 [et Flav]io V[alerio]

**Co**n[st]antio [et]  
 [Galer]i<sup>o</sup> V[alerio]  
 [Maximiano]  
**no**b[ilissimis Caess]  
 [ - ]

*Caput Viae* [Melitena]  
*Date* (1) (?)  
 (2) AD 293, 21.v(?)–305, 01.v [Diocletianus and Maximianus *Augusti* with]  
 Constantius and Galerius *Caesares*

### 123(E). Elbistan 5

*Province, Sub-Province + Admin. Code, Map and Location* As 123(A)  
*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here  
 here of Hogarth and Munro (facsimile of the printed version of their copy  
 (Fig. 6.1.102 [p. 351])  
*Publication* Hogarth and Munro 1893, 708 “93 to 59 (viii)” (facsimile, Fig. 6.1.102 [p. 351])  
 CIL 3. 12167 (text of Hogarth and Munro)  
 RRMAM 2, 1. 739 (notice only)  
*Description & Dimensions* Not given  
*Text* Consult the facsimile (Fig. 6.1.102 [p. 351])

*Caput Viae* [Melitena]  
*Date* (?)

### 123(F). Elbistan 6

*Province, Sub-Province + Admin. Code, Map and Location* As 123(A)  
*Copy* Hogarth and Munro 1891. The stone has not been examined by DHF. Text here  
 of Hogarth and Munro (facsimile of the printed version of their copy  
 (Fig. 6.1.103 [p. 351])  
*Publication* Hogarth and Munro 1893, 708 “58” (facsimile, Fig. 6.1.103 [p. 351])  
 CIL 3. 12162 (text of Hogarth and Munro)  
 RRMAM 2, 1. 740 (notice only)  
*Description* “Surface deliberately damaged. The numeral, however, is clear” (Hogarth and  
 Munro)  
*Dimensions* Not given  
*Text* Consult the facsimile (Fig. 6.1.103 [p. 351])  
*Caput Viae* [Melitena]  
*Date* (?)

### 123(G)-(N). Elbistan 7-14

*Province, Sub-Province + Admin. Code and Map* As 123(A)  
*Location* “At Elbistan” (Sterrett)  
*Copy* Sterrett 05-07 August, 1884



<i>Publication</i>	Sterrett 1883-84, 294 RRMAM 2, 1. 741-748
<i>Description</i>	“Uninscribed or illegible” (Sterrett)

**Elbistan**

“We found nine milliaria at Albistan, some of which were never inscribed and the rest with the single exception of no. 345” (here - 121[A]) “are wholly illegible” (Sterrett 1883-84, 294)

**124(A)-(B). Demircilik 1-2**

<i>Province, Sub-Province + Admin. Code</i>	K. Maraş, Elbistan 46-03-0
<i>Map</i>	Elbistan 99-Ij
<i>Location</i>	Not given
<i>Copy</i>	Hogarth and Munro 1891
<i>Publication</i>	Hogarth and Munro 1893, 686 RRMAM 2, 1. 721
<i>Description</i>	“Two milestones, both illegible, . . . .” (Hogarth and Munro)

**125(A). Gücük 1**

<i>Province, Sub-Province + Admin. Code</i>	K. Maraş, Elbistan 46-03-1
<i>Map</i>	Elbistan 100-Ij
<i>Location</i>	(?) <i>In situ</i> ; lying beside and E of the modern road. At the village boundary; c. 2.30 km S of the turning for Gücük.
<i>Copy</i>	DHF 25.viii.1982
<i>Publication</i>	RRMAM 2, 1. 772
<i>Description &amp; Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

**125(B). Gücük 2**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 125(A)
<i>Location</i>	(?) <i>In situ</i> ; c. 100 m E of the modern road and c. 0.30 km N of the junction for Kantarma and Topkiran, c. 3.80 km N of the turning for Gücük.
<i>Copy</i>	DHF 25.viii.1982
<i>Publication</i>	RRMAM 2, 1. 773
<i>Description &amp; Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

**126. Sevdilli, Büyükköy Mezraası**

<i>Province, Sub-Province + Admin. Code, and Map</i>	K. Maraş, Elbistan 46-03-1
<i>Map</i>	Elbistan 101-Ij
<i>Location</i>	On the W side of the <i>mezraa</i> (hamlet); in an orchard, owned by Şiho Doğan.
<i>Copy</i>	DHF 26.viii.1982. DHF squeeze in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 46. Maraş 45, Sevdilli, Büyükköy Mezraası
<i>Publication</i>	RRMAM 2, 1. 822 (notice only)
<i>Description</i>	A simple cylinder. (?)Complete. Friable basalt. Flat top. No plinth. Surface:

worn.

Letters: worn, faint and indistinct, variable in size

*Dimensions* Ht 1.89; diam. (top) 0.56. Letters: c. 0.0.065-80, (line 10) 0.090*Text*

[Imp Caes]  
 [D n Gaio]  
**Iūlio Vero** [Ma]-  
 4 **ximin**[o] **p f**[e]-  
 [l]ici **Aug** pō-  
 [n]**tifi**[ci] **max**  
**tribunicie** (sic)  
 8 [po]**testate**  
 [[ - - - - ]]  
 [[ - - - - ]]  
 [[ - - - - ]]  
 10 (vac) **νη'**

line 9-11: [[per Licinnium | Serenianum | leg Aug pr pr]] (?)

*Caput Viae* (Melitena)*Date* AD 235, Feb.-March-09.xii(?) Maximinus *Augustus**Commentary* For the erasure of Licinnius Serenianus' name, see above [p. 11], **Notes and Comments 3.5.****127. Sevdilli, Gölpınar Mezraası***Province, Sub-Province + Admin. Code* K. Maraş, Elbistan 46-03-1*Map* Elbistan 100-Ij*Location* In the village cemetery; c. 0.50 km S of Gölpınar. On the W side of the şose to Gölpınar and on the S side of the Roman road.*Copy* DHF 26.viii.1982. DHF squeeze in BIA. Text here from DHF squeeze*BIA Collections:* *Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 46, Sevdilli, Gölpınar Mezraası*Publication* RRMAM 2, 1. 823 (notice only)*Description* A simple cylinder. Broken at the bottom. Hard, red basalt. The shaft tapers towards the top. Surface: worn*Dimensions* Letters: worn but legible, variable in size; lunate E  
 Ht (ex.) 1.20; diam. (bottom) 0.63. Letters: 0.060-80*Text*(1) (underneath text [2])  
 obliterated except for a few letters

(2) (on the top of text [1])  
 [Imp Caes]  
 [D n Gaio]  
 [Iulio Vero] **M**-  
 4 [aximino p]  
 [felici Aug] **pon**-  
**tifici maximo**

tribunicie po-  
 8 testat[e per]  
 - - - -

(sic)

line 8: **tribunicie**, see the text above, 126. Sevdilli, Büyükköy Mezraası,  
 line 7

line 9 seqq.: (?) [Licinnium | Serenianum | leg Aug pr pr]

*Caput Viae* [Melitena]

*Date* (1) (?)

(2) AD 235, Feb.-March-09.xii(?) Maximinus *Augustus*, on the basis of the  
 text above, 126. Sevdilli, 0.Büyükköy Mezraası

### 128(A). Yaztopallı 1

*Province, Sub-Province + Admin. Code* K. Maraş, Elbistan 46-03-1

*Map* Adıyaman 101-II

*Location* In the cemetery (Beko mezarlığı, Hofular muhiti [or mevkii]), c. 1 km W of the  
 village and on the S side of the modern road

*Copy* Mitford (? date); DHF 26.viii.1982. DHF squeeze and photo. in BIA. Text here  
 from DHF squeeze

*BIA Collections:* *Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 52, Yaztopallı 1  
 Stone: (1) B/W Neg.: DHF 35/73/06.04

*Publication* Mitford 1974, 175 n.102 (notice)  
 Hild 1977, 98 and Fig. 66 (right-hand stone) (photo. only)  
 Wagner 1985, 49 and Fig. 19 (centre stone) (photo. only)  
 RRMAM 2, 1. 832 (notice only)

*Description* A simple cylinder. Broken into three pieces, 1 large, 2 small (at another grave).  
 Basalt. The shaft tapers towards the top. Oval in plan. A tenon under the base.  
 Surface: numerous, vertical cracks; very worn.

*Dimensions* Letters: worn and faint, variable in size; narrow, thin lettering  
 Ht 1.22 + 0.08; diam. 0.45. Letters: 0.060-80

*Text* (1) - - - -  
 IVMA

(2) (upside down to text [1])

Imp C-  
 aes C  
 Mess[iu]-  
 4 ş Tra-  
 ianu[s]  
 Deciu[s]  
 p f [ - ]  
 8 [ - - - - ]  
 vς'

*Caput Viae* (Melitena)

*Date* (1) (?)

(2) AD 249 Traianus Decius *Augustus***128(B). Yaztopallı 2**

<i>Province, Sub-Province + Admin. Code, Map and Location</i>	As 128(A)
<i>Copy</i>	Mitford (? date); DHF 26.viii.1982. DHF squeeze in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i>
	Squeeze: 46. Maraş 53, Yaztopallı 2
<i>Publication</i>	Mitford 1974, 175 n.102 (notice) Hild 1977, 98 and Fig. 66 (left-hand stone) (photo. only) Wagner 1985, 49 and Fig. 19 (left-hand stone) (photo. only) RRMAM 2, 1. 833 (notice only) French 2008, 133 (text [2] and comments)
<i>Description</i>	A simple cylinder. Complete. Basalt. The top is flat. There is a round tenon under the base. Surface: worn and pitted. Letters: worn, some faint, others clear and legible; (text 2) variable in size, (text 4) broken-bar A, lunate E, U for V
<i>Dimensions</i>	Ht 1.72 + (tenon) 0.10; diam. (base) 0.66, (tenon) 0.27. Letters: (text 2) 0.045, (line 12) N 0.11, lunate E 0.065, (text 4 ) 0.035-45
<i>Text</i>	(1) (underneath text [2]) letters on the r. of text (2)

(2) (on the top of text [1])

**Imp**  
**Caes**  
[G] **Iulio Vero**  
4 [M]a<sup>x</sup>i<sup>m</sup>[ino]  
[p fe]l<sup>i</sup>c<sup>i</sup> **Au**g<sup>u</sup>  
[pontifici max]  
[trib]u<sup>n</sup>ic<sup>i</sup>e]  
8 [pote]s<sup>t</sup>a<sup>t</sup>e  
[[per Licinnium]]  
[[Serenianum]]  
[[leg Aug pr pr]]  
12 (vac) **ve'**

(3) (underneath text [4])

obliterated

(4) (on the back and at the top of the stone)

**et Flavio**  
2 **Valerio**  
**Constantio**  
4 **nobilisim**  
**Caesari**

line 4: **NOb**

- Caput Viae* (Melitena)  
*Date* (1) (?)  
 (2) AD 235, Feb.-March-09.xii(?) Maximinus *Augustus*  
 (3) (?)  
 (4) AD 293-305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*
- Commentary* (Text [2]) cp. the text above, 126. Sevdilli, Büyükköy Mezraası; for the erasure of Licinnius Serenianus' name, see above [p. 11], **Notes and Comments 3.4**.  
 (Text [4]) for an explanation of seemingly truncated, Tetrarchic texts and for the apparent isolation of individual from their colleagues in the Tetrarchy, see above [p. 14], **Notes and Comments 3.6**.

The full series of texts here may be completed as follows:

Imp Caes C	et Imp C M	<b>et Flavio</b>	et Galerio
Aurelio	Aurelio	<b>Valerio</b>	Valerio
Valerio	Valerio	<b>Constantio</b>	Maximiano
Diocletiano	Maximiano	<b>nobilissim</b>	is
pp ff inv	Augg	<b>Caesari</b>	bus

### 128(C). Yaztopallı 3

- Province, Sub-Province + Admin. Code, Map and Location* As 128(A)  
*Copy* DHF 26.viii.1982; Wagner (? date). Text here from DHF notes  
*Publication* Wagner 1985, 49 and Fig. 19 (right-hand stone) (photo. only)  
 RRMAM 2, 1. 834 (notice only)  
*Description* A simple cylinder. Basalt. The shaft tapers towards the top. Oval in plan. Two large, regular-shaped holes in the back.  
*Dimensions* Ht (vis.) 1.48; diam. (top) 0.45
- Text* - - - -  
 vς'

- Caput Viae* [Melitena]  
*Date* (?)

### 129(A). Gözecik 1

- Province, Sub-Province + Admin. Code* K. Maraş, Elbistan 46-03-1  
*Map* Adıyaman 101-II  
*Location* *In situ*; on the N side of the Roman road (here under the modern road), c. 0.55 km W of the village and c. 1.70 km NE of the turning for Topallı  
*Copy* DHF 25.v.1974 and 27.viii.1982. DHF squeeze and photo. (Pl. 7.1.86 [p. 400]) in BIA  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 46. Maraş 22, Gözecik 1  
 Stone: (1) B/W Neg.: DHF 35/73/06.04  
*Publication* RRMAM 2, 1. 769 (notice only)  
*Description* A simple cylinder. (?)Broken at right-hand side. Pale red basalt. The shaft tapers slightly towards the top. Surface and letters: very worn and pitted.

*Dimensions* Letters: (text 2) worn but legible, variable in size; (text 2) broken-bar A, U for V  
Ht 1.86; diam. (top) 0.42, (bottom) 0.59. Letters: (line 1) P of IMP 0.07, (line 3)  
N of NO 0.07, (line 4) P of PF 0.115. Letters: (text 1) 0.060-80, (text 2) 0.040-60

*Text* (1) (underneath text [2])

-----  
[ - - - - ]  
**tribuni**  
[ - - - - ]  
5 -----  
(vac) **ϐϐ'**

lines 3 seqq.: (?) **tribuni**(cie | potestate | per - - - - ], cp. the text above, 126.  
Sevilli, Büyükköy Mezraası

(2) (above the existing lines of text [1] and over the top of the uppermost lines,  
now lost, of text [1])

**Imp Caesari**  
2 **Gaio Val**  
**Diocletiano**  
4 **p f**

*Caput Viae* (Melitena)

*Date* (1) (?) AD 235 Maximinus *Augustus*

(2) (?) AD 293-305 Diocletianus and Maximianus *Augusti* with Constantius and  
Galerius *Caesares*

*Commentary* A text (no. 2) of Diocletianus, was cut above and over the top of an earlier  
inscription (no. 1). In the titlature of Diocletianus the formula *trib pot* is never used on milestones  
of Asia Minor: on the other hand, on this section of the road there seems to be an extensive series of  
milestones erected in the name of Maximinus, an Emperor who did employ *trib pot* in his titlature.  
For an explanation of seemingly truncated, Tetrarchic texts and for the apparent isolation of  
individuals from their colleagues in the Tetrarchy see above, 101(B) and [p. 14] **Notes and**  
**Comments 3.6.**

### 129(B). Gözecik 2

*Province, Sub-Province + Admin. Code, and Map* As 129(A)

*Location* Among the ruins of the old village, c. 0.30 km W of the present village; on the N  
side of the stream.

*Copy* DHF 27.viii.1982

*Publication* RRMAM 2, 1. 770

*Description & Dimensions* Not recorded

*Text* No visible inscription

### 129(C). Gözecik 3

*Province, Sub-Province + Admin. Code, and Map* As 129(A)

*Location* In the village cemetery; c. 0.20 km W of the village and above the stream.

*Copy* DHF 27.viii.1982. DHF squeeze in BIA

*BIA Collections: Squeeze and Stone Photographs*  
Squeeze: 46. Maraş 23, Gözecik 3

<i>Publication</i>	RRMAM 2, 1. 771 (notice only)
<i>Description</i>	A simple cylinder. The top is broken; the base is chipped (originally so). Hard, pale limestone. Surface and letters: very worn.
<i>Dimensions</i>	Letters: faint and indistinct, neat in shape, size and alignment; broken-bar A Ht 1.75; diam. (bottom) 0.45. Letters: c. 0.050, (line 1) 0.08, numerals (line 11) 0.090

<i>Text</i>	<b>Imp Caes</b> [divi] <b>Severi</b> ṇ[ep] <b>divi M Aur</b> [An]- 4 <b>tonini fil</b> [M Aur] <b>Antonino pio</b> [f]elici <b>Aug mil</b> [ia] [res]tituta <b>per</b> 8 [M U]lpium <b>Ofellium</b> [Th]eodorum [leg] <b>Aug pr pr</b> (vac) (vac) <b>ϛϛ'</b>
-------------	--

<i>Caput Viae</i>	(Melitena)
<i>Date</i>	Elagabalus <i>Augustus</i> , (?) AD 218, 16v–(?) mid-June

**130. Darica**

<i>Province, Sub-Province + Admin. Code</i>	Malatya, Akçadağ 44-01-1
<i>Map</i>	Adıyaman 101-Ij
<i>Location</i>	Set up on the E side of the modern road (to Elbistan), c. 0.90 km W of the junction on the modern highway (Kayseri - Malatya) (Pl. 7.1.87 [p. 400])
<i>BIA Collections: Squeeze and Stone Photographs</i>	Stone: (1) B/W Neg.: DHF 35/73/06.05
<i>Publication</i>	Hild 1977, 98 n.201 and Fig. 67 RRMAM 2, 1. 685
<i>Description &amp; Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

**C.4 SEBASTIA- MELITENA****131. Şekerpınar**

*Province, Sub-Province + Admin. Code* Sivas, Kangal 58-06-0  
*Map* Gürün 98-Iç  
*Location* *In situ*; beside the modern track and the ancient Roman road; c. 150 m S of stone quarries located c. 2.75 km SE of the village  
*Copy* DHF 10.x.1978. No squeeze. DHF photos in BIA (Pl. 7.1.88 [p. 401]). Text here from DHF note  
*BIA Collections: Squeeze and Stone Photographs*  
 Stone: (1) B/W Neg.: DHF R/78/21.02  
 (2) Col. Slide: DHF 179. 21-22  
*Publication* RRMAM 2, 1. 935 bis (notice only)  
*Description & Dimensions* Not recorded

*Text*

2      - - - -  
          LXXXVI  
          πς'

*Caput Viae* (Sebastia)  
*Date* (?)

**132. Fethiye, form. Hasanbadrik**

*Province, Sub-Province + Admin. Code* Malatya 44-00-4  
*Map* Malatya 106-Iğ Sultanmurathanı Hr.  
*Location* “About seven miles from the Tokhmah Su we came to another stream named the Chamurlu Su, flowing through a deep narrow valley . . . I passed in the plain a column of stone, which marks the half-distance between Constantinople and Baghdad. There was likewise in the plain a ruined han” (Brant). The ruined han - Sultanmurat Hanı, c. 11 km NW of the Kırkgöz bridge and c. 13 km SE of Fethiye  
*Copy* Brant 1835  
*Publication* Brant 1836, 212  
 Ritter 1843, 863 (notice of Brant)  
 Yorke 1898, 319 (notice of Brant *apud* Ritter)  
 RRMAM 2, 1. 687 (notice only)  
*Description & Dimensions* Not given  
*Text* (?) not inscribed



## C.13 CYBISTRA - PYLAE

## 133(A). Porsuk 1

<i>Province, Sub-Province + Admin. Code</i>	Niğde, Ulukışla 51-05-0
<i>Map</i>	Ulukışla 75-İş
<i>Location</i>	In the old cemetery, near the 54 km stone, beside and N of the modern road and c. 1 km SE of the village. Seen in Ulukışla by Jacopi (1936). Now (08.viii.1974) used as the right-hand gate-post for the entrance into the garden of the Ulukışla <i>hapishane</i> (jail)
<i>Copy</i>	Hogarth and Headlam 1890; Ramsay 1896; Jacopi late-Summer 1936; DHF 08.viii.1974. DHF squeeze in BIA. The text here, based on DHF squeeze, is a revision of the version published earlier (RRMAM 1. 60[A])
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 51. Niğde 08, Porsuk 1
<i>Publication</i>	Ramsay 1903, 401-402 (discussion of the distance-figure in l. 12) CIL 3. 12214 (copy of Hogarth and Headlam in 1890; Ramsay) Jacopi 1938, 33 Ballance 1964, 144 n.8 (discussion of distance-figure in ll. 12-13; notice of Jacopi 1938) French 1976, 52 (notice only) RRMAM 1. 60(A) (text only) RRMAM 2, 1. 867 (notice only) Drew Bear 1991, 131 (text from photographs of Coindoz) AE 1991. 1542 (text of Coindoz <i>apud</i> Drew Bear 1991) IK 55, 1 (Berges and Nollé eds). 125 (documentation of Coindoz <i>apud</i> Drew Bear 1991 and edition of Drew Bear; citation of earlier publications; discussion and comments) Christol and Drew-Bear 2009, 243 (comments on text and road)
<i>Description</i>	A re-used column. Broken above. Hard, pale limestone. Surface: the upper part is very worn but the lower section is less damaged by wear; lines 9-12 are better preserved than lines 1-8
<i>Dimensions</i>	Ht (vis.) 1.40; diam. (top) 0.48. Letters: 0.030-40, (line 12) P 0.050

## Text

	<b>Imp·Caeſar·</b>	
	<b>divi</b> [Antonini]	
	<b>Pi·m</b> [agni f d]i[v]i·	(sic)
4	<b>Severi·nepoſ·</b>	
	<b>M·[Au]reliuſ·</b>	
	<b>Antoninuſ·Piuſ·</b>	
	<b>felix·invictuſ·</b>	
8	<b>Auguſtuſ·pon-</b>	
	<b>tifex max</b> [imus]	
	<b>trib pot·coſ·</b>	
	<b>procoſ·</b>	
12	<b>A P m XXXVI λ</b>	
	(vac) ε´	(sic)

line 3: **Pi**(i)line 12: **A P**(ylis)

line 13: **A P m XXXVIII** | ε´ (Ramsay); **A P m XXXV**⟨I⟩ λε´ (Ballance);  
 a mis-understanding of the Latin XXXVI by a Greek-speaking stone-  
 mason (Drew Bear and Nollé). Most probably the lunate *epsilon*  
 (*lapis*, in error ?) represents the lunate form of a Greek *stigma*, i.e. Ϛ;  
 the Greek distance-figure would, therefore, read λ|Ϛ´, the equivalent  
 of the Latin XXXVI.

*Caput Viae* Pylae  
*Date* AD 218, 14.vii-09.xii M. Aurelius Antoninus (Elagabalus) *Augustus*

### 133(C). Porsuk 3

*Province, Sub-Province + Admin. Code* Niğde, Ulukışla 51-05-0  
*Map* Ulukışla 75-Iş  
*Location* As recorded by Ramsay (1903 and 1904), in the old cemetery near the 54 km  
 stone; beside and N of the modern road; c. 1 km SE of the village  
*Copy* Ramsay 1902; Jacopi late-Summer 1936; DHF 20.xi.1976. DHF squeeze in  
 BIA. No DHF photo. Text here from DHF squeeze  
*BIA Collections:* *Squeeze and Stone Photographs*  
 Squeeze: 51. Niğde 09, Porsuk 3  
*Publication* Ramsay 1903, 401 (notice only)  
 Ramsay 1904, 111  
 Jacopi 1938, 33  
 Ballance 1964, 144 and n.9 (notice of Ramsay 1904 and Jacopi 1938)  
 AE 1974. 640 (text of Jacopi 1936)  
 RRMAM 1. 60(C) (text only)  
 RRMAM 2, 1. 869 (notice only)  
 Drew Bear 1991, 134 and n.17 (notice of text)  
 IK 55, 1 (Berges and Nollé eds). 126 (edition of RRMAM 1.60[C]; citation of  
 earlier publications)  
 AE 2000. 1479 (text in IK)  
*Description* A simple cylinder, on a small, round plinth. Complete. Hard, white, coarse-  
 crystalline, granular marble. The surface in the middle, and on the right-hand  
 side, of the inscription has been almost completely obliterated but where not  
 damaged, the letters are well cut, sharp and clear  
*Dimensions* Ht 2.14, (plinth) 0.23; diam. 0.55. Letters: 0.035-40, (line 1) 0.040, (line 2) 0.030  
*Text*

	<b>Imp Caesar</b> [M A]η-
	to[nius Gordianus] <b>p̄ius</b>
	<b>feliḫ</b> [inv Aug po]η-
4	<b>tifex m[a]x</b> [trib po]-
	<b>tes çoş</b> [procos per Cu]ş-
	<b>pidium</b> [Flaminium] <b>Şeve-</b>
	<b>rum</b> <b>le</b> [g Aug pr pr]
8	[ - - - - ]

*Caput Viae* [Pylae ?]  
*Date* AD 239(?) Gordianus *Augustus*

**C.14 TYANA - PYLAE****133(B). Porsuk 2**

<i>Province, Sub-Province + Admin. Code</i>	Niğde, Ulukışla 51-05-0
<i>Map</i>	Ulukışla 75-Iş
<i>Location</i>	In the old cemetery near the 54 km stone; beside and N of the modern road; c. 1 km SE of the village. Present whereabouts not established (DHF visit 20.xi.1976)
<i>Copy</i>	Hogarth 1890; Ramsay 1891. The stone has not been examined by DHF. Text here of Hogarth and Ramsay in CIL
<i>Publication</i>	CIL 3. 12213 (copy of Hogarth in 1890 and of Ramsay in 1891) Ramsay 1903, 401-402 (discussion of the distance-figure in l. 8) Ballance 1964, 144-145 and n.9 (notice of Ramsay 1904 and Jacopi 1838) RRMAM 1. 60(B) (text, in CIL, of Hogarth and of Ramsay) RRMAM 2, 1. 868 (notice only) Drew Bear 1991, 134 and n.16 (notice of text) IK 55, 1 (Berges and Nollé eds). 127 (text, in CIL, of Hogarth and of Ramsay; discussion and comments)
<i>Description &amp; Dimensions</i>	Not given
<i>Text</i>	<p>-----</p> <p>[tri]b potest·cos·p·p  [p]ro cos·praes·pro-  4   vinc Clodio Satur-  nino leg·Aug·pr·pr·  Faustinianae Col  XXIII·a·Tuan·  8            ⲛⲓ</p> <p>line 7: <b>a·Tuan</b>(is)  lines 6-8: (translation) “23 miles from Tyana towards (the boundaries) of  Colonia Faustiniana</p>
<i>Caput Viae</i>	Tyana
<i>Date</i>	(?) Gordianus III, AD 239-241. For the date of this milestone, see the comments and discussion of Nollé (IK 55, 1, [p.] 284) and the accompanying citations.

**F. IN PONTUM ET BITHYNIAM****F.1 CAESARIA - ZELA - AMASIA (- Amisus)****134. Akbenliçiftlik**

*Province, Sub-Province + Admin. Code*      Yozgat, Sarıkaya 66-05-0  
*Map*      Yozgat 80-Ib  
*Location*      In the village cemetery (on the S side of the village)  
*Copy*      DHF 15.x.1977  
*Publication*      RRMAM 2, 1. 969 (notice only)  
*Description & Dimensions*      Not recorded  
*Text*      No visible inscription

**135. İzibüyük**

*Province, Sub-Province + Admin. Code*      Yozgat, Akdağmadeni 66-01-0  
*Map*      Akdağmadeni 88-u  
*Location*      “In the cemetery . . . at an old site called Ushakli Hüyük” (St. Pont.)  
*Copy*      Anderson 17 June, 1899  
*Publication*      St. Pont. 1 (Anderson), 31  
                          RRMAM 2, 1. 978  
*Description & Dimensions*      Not given  
*Text*      No visible inscription

**136. Kabalı**

*Province, Sub-Province + Admin. Code*      Yozgat, Çekerek 66-04-2  
*Map*      Amasya 83-t  
*Location*      “In the cemetery at Kabalı” (St. Pont.)  
*Copy*      Anderson 17 June, 1899  
*Publication*      St. Pont. (Anderson) 1, 32 and n.1  
                          RRMAM 2, 1. 979  
*Description & Dimensions*      Not given  
*Text*      No visible inscription

**137. Kadişehri**

*Province, Sub-Province + Admin. Code*      Yozgat, Çekerek 66-04-2  
*Map*      Amasya 84-t  
*Location*      “A la porte du Tekké, . . . .” (de Jerphanion and Jalabert). Now in the garden of the Primary School  
*Copy*      de Jerphanion July-September, 1907; DHF 04.vii.1977. DHF squeeze (drawing, Fig. 6.2.34 [p. 369]) and photo. (Pl. 7.1.89 [p. 401]) in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
                          Squeeze: 66. Yozgat 08, Kadişehri  
                          Stone: (1) B/W Neg.: DHF R/77/09.1  
*Publication*      de Jerphanion and Jalabert 1908, 452 no. 13  
                          de Jerphanion 1914-21, 9 (notice only)

	de Jerphanion 1928, 34 n.1 (comment on text) RRMAM 2, 1. 980 (notice only) Le Guen-Pollet 1989, 83 no. 34 (text of de Jerphanion and Jalabert)
<i>Description</i>	A simple cylinder. Complete. Hard, grey limestone. Above inscription: a wreath. Letters: worn; letters of text (1) were cut with a narrow-pointed chisel but the letters of text (2) were cut, in an even shape and size, with a broad blade, c. 0.001 wide; (both texts) broken-bar A
<i>Dimensions</i>	Ht 1.72; diam. (top) 0.95. Letters: (text 1) c. 0.035, (text 2) 0.040-50 but (line 7) O in TIO 0.030
<i>Text</i>	<p>(1) (underneath text [2]; some letters on l. of lines 1-7 of text [2])</p> <p>[ - - - - ] [ - - - - ] [ - - - - ] 4 [ - - - - ] [ - - - - ] [ - - - - ] [ - - - ] <b>TI</b> 8 <b>S</b>[ - - - - ] [ - - - - ] [ - - - - - - - ] <b>P</b> <b>ROCEL..A·PÇ</b> 12 (vac) <b>μί</b>[λΙΑ] <b>κα'</b></p> <p>(between ll. 8 and 9 of text [2])) (below line 9 of text [2]) (below line 10 of text [2])</p> <p>line 12: line over numeral KA</p> <p>(2) (on top of of text (1))</p> <p><b>Imp Caēs C Au(r) Va(l)</b> <b>Diocletiano p f</b> <b>invict·Aug et</b> 4 <b>Imp Cae(s) M Au(r) Va(l)</b> <b>Maximiano p f in'</b> <b>Aug et F(l) Va(l)'</b> <b>Constantio et</b> 8 <b>Gal Va(l) Maximiano</b> (vac) <b>nnll CC</b> (vac) <b>κα'</b></p> <p>line 9: <b>nnll CC</b> - <b>n</b>(obi)<b>l</b>(issimis) <b>C</b>(aesaribus) line 10: horizontal bar over <b>KA</b></p>
<i>Caput Viae</i>	(Sebastopolis)
<i>Date</i>	(1) (?) (2) AD 293, 21.v(?) - 305, 01.v Diocletianus and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i>

## 138. Çamsaray form. Dabana

<i>Province, Sub-Province + Admin. Code</i>	Yozgat, Çekerek 66-04-2
<i>Map</i>	Amasya 84-ş
<i>Location</i>	In the village; in the <i>ahır</i> (stable or byre) at the house of Seyfi Avcı. Brought from his field c. 2.5 km N of the village. Formerly <i>in situ</i> in the field, on the E side of the Roman road.
<i>Copy</i>	DHF 04.vii.1977. DHF squeeze and photo. (Pl. 7.1.90-91 [p. 401]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 66. Yozgat 02, Çamsaray Stone: (1) B/W Neg.: DHF R/77/09.06
<i>Publication</i>	French 1981, 153 no. 5 Magioncalda 1984/5, 127 (comment) Christol and Lorient 1986, 24 (comment) AE 1986. 654 (text of French from Christol and Lorient) RRMAM 2, 1. 972 (notice only)
<i>Description</i>	A simple cylinder. Complete but in two pieces plus the supporting plinth or base (the upper half together with the plinth remains in the field). Hard, pale limestone. Above the inscription: a wreath. Surface: worn Letters: some wear and damage; lunate <i>epsilon</i> , U for V
<i>Dimensions</i>	Ht 1.36 + 0.89 (the lower fragment); diam. (top) 0.39, (base) 0.37; (plinth) c. 0.90 x 0.83, (socket for the shaft) c. 0.50. Letters: irregular shape and size; 0.030-35, (line 7) O 0.025
<i>Text</i>	<p><b>Imp Caes M Iul Philip-</b>  <b>po p f i[nvi]cto Aug</b>  <b>u procos trib pot p p et</b>  4 <b>Imp Caes M Iul Philip-</b>  <b>p/o/ p f invict Aug</b> (sic)  <b>ii procos tri[b pot]</b>  <b>p p et M Otacil S[e]-</b> (sic)  8 <b>verae Aug n et m[a]-</b>  <b>tri castrorum</b>  <b>curante Cl Aur Tibe-</b>  <b>ri v e praes p P</b>  (vac)  12 <b>κε'</b></p> <p>line 3: <b>u</b>, (?) - <b>n</b>(ostro)  line 5: <b>PC</b> (lapis)  line 6: <b>ii</b>, (?) - <b>n</b>(ostro)  line 11: <b>v</b>(iro) <b>e</b>(minentissimo) <b>praes</b>(ide) <b>p</b>(rovinciae) <b>P</b>(onti)</p>
<i>Caput Viae</i>	(Sebastopolis)
<i>Date</i>	AD 247, July/Aug.-249, Sept./Oct. Philippus and Philippus <i>Augusti</i> and Otacilia Severa <i>Augusta</i>
<i>Commentary</i>	On Cl. Aurelius Tiberius, see Magioncalda (1984/5).

**139. Özükkavak**

<i>Province, Sub-Province + Admin. Code</i>	Yozgat, Çekerek 66-04-2
---	-------------------------

<i>Map</i>	Amasya 83-t
<i>Location</i>	In the village; at the mosque. Built into the retaining wall of the courtyard, on the southern, outer side which faces the lane
<i>Copy</i>	Undated photograph from Le Guen-Pollet; DHF 26.x.1994. No DHF squeeze. DHF photos (Pl. 7.1.92 [p. 402]) in BIA. Text here from DHF notes
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i>
	Stone: (1) B/W Neg.: DHF M/94/18.14 (2) Col. Slide: DHF 403.16
<i>Publication</i>	French 1995, 2 (notice only)
<i>Description</i>	A simple cylinder. (?) Complete. Hard, pale limestone. The top is flat, the shaft straight and simple. Surface: slightly worn. The inscription begins c. 0.245 from the top. Letters: worn
<i>Dimensions</i>	Ht (visible) 0.93. Letters: (line 1) M c. 0.05
<i>Text</i>	(1) (on the l. of text [2] and almost wholly concealed in the retaining wall) <div style="margin-left: 100px;">             .              2 .              .              4 .              .              6 [-]T              [-]IT (vac) I           </div> (2) (on the r. of text [1] and partly concealed in the retaining wall) <div style="margin-left: 100px;"> <b>Imper</b>[atori Caesar]i  <b>M Aureli</b>[o Probo p f in]-  <b>victo Av</b>[g pont max]              4 <b>trib pot</b> [.. p p procos]  <b>A Sebast</b>[opoli mil ..]  <b>curant</b>[e Claudio]  <b>Longino</b> [v p pr p P]              8 ?[ - ]           </div> lines 6-7: for a more complete version of Longinus' titles, see above, 016. Yerkozlu (Carus with Carinus and Numerianus)

<i>Caput Viae</i>	Sebastopolis
<i>Date</i>	(1) (?) (2) (?) Probus, (?) between AD 280-282
<i>Commentary</i>	For Claudius Longinus on Pontic milestones of Carus, see the list, RRMAM 2, 2: (p.) 508 and for Aelius Quintianus on Pontic milestones of Probus in AD 279, see the list, RRMAM 2, 2: (p.) 504. Text (2) has been completed according to the titulature and formulae which have survived on Proban milestones of Northern Cappadocia, e.g. 037(C) in the Çorum Museum. On surviving milestone texts of Carus, the title 'trib pot' seems not to have been employed, whereas in the titulature of Probus this title <i>plus</i> the tribunician year is prominent. If correctly restored, therefore, the Özükevâk milestone indicates that Claudius Longinus succeeded Aelius Quintianus (named on milestones of Probus in the year AD 279) and remained in office after the death of the Emperor. Longinus thus held the governorship of Pontus first under Probus and then under Carus.

**140(A). Güzelbeyli 1, form. Silis**

<i>Province, Sub-Province + Admin. Code</i>	Tokat, Zile 60-07-1
<i>Map</i>	Amasya 85-s
<i>Location</i>	“Dans le cimetière qui occupe le sommet du monticule se dresse, visible au loin, une colonne milliaire fichée dans le sol” (St. Pont.). Now in the village; at the house (no. 241) of Şahin Eryiğit, at the foot of the stairs.
<i>Copy</i>	Cumont (Fr. and E.) 01 May, 1900; DHF 07.vii.1977. DHF squeeze and photo. (Pl. 7.1.93 [p. 402]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 60. Tokat 04, Güzelbeyli 1 Stone: (1) B/W Neg.: DHF R/77/10.03
<i>Publication</i>	St. Pont. 2 (Cumont [Fr. and E.]), 196 (no. 469) and Fig. RRMAM 2, 1. 944 (notice only)
<i>Description</i>	A simple cylinder. Complete. Hard, grey limestone. Top flat. Tenon under the base. Surface: worn. Letters: worn and indistinct
<i>Dimensions</i>	Ht 1.45; diam. (top) 0.52. Letters: (line 1) 0.055, (lines 11-17) irregular size, c. 0.035-55, (line 18) L 0.055

<i>Text</i>	<b>Impera A cletiano</b>
	•
4	•
	•
	•
	•
8	•
	•
	•
	<b>aler Valer</b>
12	<b>[Ma]ximiano</b>
	<b>nobilissimis</b>
	<b>Caesaribus</b>
	<b>Aur' Priscianus</b>
16	<b>v p praes prov Pont</b>
	<b>d 'n' m' q' eorum</b>
	<b>mil p [ - ]</b>

lines 16-18: **v**(ir) **p**(erfectissimus) **praes**(es) | **prov**(inciae) **Pont**(i) |  
**d**(evotus) **n**(umini) **m**(aiestati)**q**(ue) **eorum**

For an intact text of the Tetrarchy, see above, 056(D). Zile 4

<i>Caput Viae</i>	(Zela)
<i>Date</i>	AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i>

**140(B). Güzelbeyli 2, form. Silis**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 139(A)
---	-----------



<i>Location</i>	“Une seconde, . . . , est utilisée comme borne à la porte d’une demeure” (St. Pont.). Present whereabouts not established (DHF visit 07.vii.1977)
<i>Copy</i>	Cumont (Fr. and E.) 01 May, 1900. Not re-found by DHF
<i>Publication</i>	St. Pont. 2 (Cumont [Fr. and E.]), 196 (no. 470) RRMAM 2, 1. 945
<i>Description &amp; Dimensions</i>	Not given
<i>Text</i>	No visible inscription

#### 141. Yıldıztepe

<i>Province, Sub-Province + Admin. Code</i>	Tokat, Zile 60-07-1
<i>Map</i>	Amasya 84-s
<i>Location</i>	In the village; in the cemetery
<i>Copy</i>	DHF 30.vii.1986. DHF squeeze and photos (Pl. 7.1.94 [p. 402]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 60. Tokat 17, Yıldıztepe Stone: (1) B/W Neg.: DHF M/86/24.06 (2) Col. Slide: DHF 263.22-23
<i>Publication</i>	French 1987, 193 (cited under “Boztepe”) (notice only)
<i>Description</i>	A simple cylinder. The top is perhaps broken; it is now roughly pointed. The base is flat but the edges are chipped. The surface is roughly smoothed. Hard, grey and white limestone. Letters: worn and indistinct; (text 3) broken-bar A
<i>Dimensions</i>	Ht 1.62; diam. (bottom) 0.48. Letters: (text 1) irregular shape and size, 0.070-85, (text 2) irregular size, c. 0.040-45, (text 3) irregular size, 0.045-55, (line 1) 0.050-55, (line 2) 0.030 (O of NO)-50 (A of TA)
<i>Text</i>	(1) (on the face behind texts [2] and [3]) <div style="text-align: center;"> <b>Imp Caē[s]</b>  <b>[G] Vib' Treb</b>  <b>Gallus p f</b>  4 <b>Aug p'p' et G' Vīb</b>  <b>mnian Beldo</b>  <b>[Vo]lusianus</b>  <b>nob Caes</b>  8 <b>cos</b>  <b>[ - ]</b> </div> line 1: ligature <b>MP</b> line 2: <b>Treb</b> (onianus) lines 4-6: the names of the <i>Caesar</i> have been distorted, mistakenly arranged and mis-spelt, G V l mnian Beldo l olusianus for G V(ibius) l Veldumnian(us) l (V)olusianus; cp. the mis-spellings on 100(B). Keklikoluk 5 and 108(L). Kanlıkavak 12  (2) (on the column-face behind text [1]) (below text [3]; line 1 of text [2] underneath line 8 of text [3]) <div style="text-align: center;"> <b>- - - -</b>  <b>et Flav Valer</b> </div>

4       **Constantio**  
           **et Galer Valer** (sic)  
           **Max[imiano]**  
           **nobilissimis**  
           **Caesaribus**  
 8       **Zelit mil p [VIII]**  
           **Aur Priscianus**  
           **v p praes prov Pont**  
           **d n m q eorum**

line 8: **Zelit** for (Civitas) **Zelit(anorum)**, as Zile 1, 3 and 4; cp. 040. Saray, 044. Sapa and 046. Ertuğrul: (Civitas ?) **Amasenorum**; see the discussion of this subject, [p. 14] **Notes and Comments 3.7**

line 10: ligature **NT**

lines 10-11: **v(ir) p(erfectissimus) praes(es) l prov(inciae) Pont(i) l d(evotus) n(umini) m(aiestati)q(ue) eorum**

For an intact text of the Tetrarchy, see above, 056(D). Zile 4

(3) (above and on top of text (2))

**Imper Caes**  
           **Fl Constantino**  
           **p f m victori**  
 4       **semper [A]ug**  
           **et Fl Cl Constantino**  
           **et Fl Iul Constantio**  
           **et Fl Iul Const(anti)**  
 8       [nobb Caess]

line 1: for the abbreviation **Imper**, see above, 082. Mollahüseyin 4, a text of AD 238

<i>Caput Viae</i>	Zela
<i>Date</i>	(1) AD 251, Aug.(?)-253, Aug.(?) Trebonianus Gallus <i>Augustus</i> with Volusianus <i>Caesar</i> (2) AD 293, 21.v(?)-305, 01.v Diocletianus and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i> (3) AD 333, 25.xii-335, 18.ix Constantinus <i>maximus victor Augustus</i> with three sons, Constantinus, Constantius and Constans <i>Caesares</i>

## 142. Alayurt, form. Araplar

<i>Province, Sub-Province + Admin. Code</i>	Tokat, Zile 60-07-1
<i>Map</i>	Amasya 84-s
<i>Location</i>	At a revered tomb, the <i>Çam Dedesi</i> (Pl. 7.1.95 [p. 403]), c. 0.5 km S of the village, on the E side of the track running S to the main road.
<i>Copy</i>	DHF 03.vii.1986. DHF squeeze and photos in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i>
	Squeeze: 60. Tokat 02, Alayurt
	Stone: (1) B/W Neg.: DHF M/86/24.10

	(2) Col. Slide: DHF 263.27-31
<i>Publication</i>	French 1987, 193 (notice only)
<i>Description</i>	A simple cylinder. Broken into several pieces, large and small; repaired with concrete. Hard, white limestone. The top of the shaft has been flattened. Letters: worn but clear; (text 2) broken-bar A
<i>Dimensions</i>	Ht 0.82; diam. (top) 0.35. Letters: (text 2) 0.035-60

*Text* (1) (on one piece)

----  
nob  
Caes

(2) (on three pieces)

----  
et Fl Cl [Consta]ntino  
et Fl Iul [Cons]tantio  
4 et Fl Iul [Co]stanti  
nob[b] Caess  
Fl Leontius v p  
praes pr Helenop  
(vac)  
8 d n m q ɛo[rum]  
(vac)  
(vac) θ'

lines 6-8: v(ir) p(erfectissimus) | praes(es) pr(ovincia) Helenop(onti)

For an intact text (of Constantinus with his three sons) which names the governor, see above, 029(B). Boğazkaya 2(2)

<i>Caput Viae</i>	(Zela)
<i>Date</i>	(1) (?) (2) AD 333, 25.xii-335, 18.ix Constantinus <i>maximus victor Augustus</i> with three sons, Constantinus, Constantius and Constans <i>Caesares</i>

### 143. Akyazi

<i>Province, Sub-Province + Admin. Code</i>	Amasya 05-00-0
<i>Map</i>	Amasya 83-ö
<i>Location</i>	An the village; at the house of Ahmet Demirel. In front of a wooden <i>anbar</i> (store-shed) (Pl. 7.1.096 [p. 403]), facing the main street
<i>Copy</i>	DHF 08.vii.1986. DHF squeeze and photos in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 05. Amasya 02, Akyazi Stone: (1) B/W Neg.: DHF M/86/14.09-10 (2) Col. Slide: DHF 260.38-39 and 261.03-05
<i>Publication</i>	French 1987, 192 (notice only)
<i>Description</i>	A simple cylinder. Complete. Hard, white limestone. The top is flat. The surface is smooth.

<i>Dimensions</i>	Letters: worn, some surface damage; broken-bar A Ht (vis.) 1.25; diam. (top) 0.43. Letters: (lines 4 and 9) 0.035 then (lines 3 and 10) 0.045-0.50, (line 12) 0.040, (lines 16-18) 0.020-25
<i>Text</i>	<p>[I]mp Cæs C·Aur·Val Diocletiano</p> <p>4 p·fel·inv·Aug et·Imp·Cæs M·Aur·Val· [[Maxim[iano]]]</p> <p>8 p·fel·inv·Aug et·Fl·Valer· Constantio et·Gal·Val·</p> <p>12 Maximiano nobill·Caess mil·p te'</p> <p>(vac)</p> <p>16 Aur' Priscianus v p·praes pr P d n m q eorum</p>

line 13: **nobill·Caess**, **nobil**(issimi) **Caes**(ares)

lines 17-18: **v**(ir) **p**(erfectissimus) **praes**(es) | **pr**(ovinciae) **P**(onti) |  
**d**(evotus) **n**(umini) **m**(aiestati)**q**(ue) **eorum**

<i>Caput Viae</i>	(Amasia)
<i>Date</i>	AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus <i>Augusti</i> with Constantius and Galerius <i>Caesares</i>

#### 144. Mahmatlar

<i>Province, Sub-Province + Admin. Code</i>	Amasya 05-00-0
<i>Map</i>	Amasya 84-n
<i>Location</i>	In the village. Said to have been in the village for 60 years. Formerly used as the support for a wooden column in a house. Now lying in the street near the cami.
<i>Copy</i>	DHF 22.x.1994. DHF squeeze and photos (Pl. 7.1.97 [p. 404]) in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Photograph</i>	Squeeze: 05. Amasya 15, Mahmatlar Stone: (1) B/W Neg.: DHF M/94/18.07 (2) Col. Slide: DHF 403.09
<i>Publication</i>	French 1995, 2 (notice only)
<i>Description</i>	A simple cylinder. Broken below and chipped on the surface. Hard, pale limestone. The top is flat but chipped around the edges. The surface of the stone had been smoothed. The inscription begins c. 0.245 from the top. Letters: very worn and damaged; two forms of A (both straight- and broken-barred), U for V
<i>Dimensions</i>	Ht (ex.) 0.83; diam. (top) 0.48, (middle) 0.50. Letters: (line 1) I 0.037, (line 3) D

0.055, (line 5) T 0.03

*Text*

**Imp Caes**  
**C Au[r] Val** (leaf)  
**Dio[cl]etiano**  
**p** (leaf) **f[el inv] Aug** (leaf)  
5 **et Im[p] Caes**  
**M [Au]r Val·**  
**[[Maximiano]]**  
**p fel [i]nv Aug**  
**et** (leaf) **Fl Valer** (leaf)  
10 **C[on]stant[io]**  
[et Gal Valer]  
[Maximiano]  
[nobb Caess]  
- - - -

For an intact text of the Tetrarchy, see above, 056(D). Zile 4

*Caput Viae* [Amasia]  
*Date* AD 293, 21.v-305, 01.v Diocletianus and Maximianus *Augusti* with Constantius  
and Galerius *Caesares*

**145(A). Uygur 1**

*Province, Sub-Province + Admin. Code* Amasya 05-00-0  
*Map* Amasya 85-o  
*Location* Brought from the village to the museum 26.02.1990, from property of Ahmet Duran. Found in his field (*parsel* [plot] no. 2010) beside main road to Turhal; c. 0.75 m below surface. Now in Amasya Museum [Inv. no. A.90.32]  
*Copy* DHF 12.vi.1990. DHF squeeze and photos (Pl. 7.1.98 [p. 404]) in BIA. Text here from DHF squeeze  
*BIA Collections:* *Squeeze and Stone Photographs*  
Squeeze: 05. Amasya 19, Uygur 1  
Stone: (1) B/W Neg.: DHF M/90/09.07-08  
(2) Col. Slide: DHF 316.08-09  
*Publication* Yüce 1992, 209 and Pl.1a-d  
AE 1992. 1674 (text of Yüce 1992)  
French 1992, 150 (notice only)  
*Description* A simple cylinder. Complete but broken at top (?a re-used column). Pink-and-white limestone. Shaft simple and straight. No base. Letters: worn; note the broken-bar form of the letter A (text 2)  
*Dimensions* Ht 1.10; diam. (top) 0.32. Letters (text 1) (line 3) C of COS 0.041, O of COS 0.019, (text 2) (line 1) I of IMP 0.044, (line 4) O of CON 0.049  
*Text* (1) (on r. and partly underneath ll. 2-3 of text [2])

- - - -  
[- - trib]  
2 **potēsta[.]**  
**p·p·cos·**

4     **procos·**  
           (vac)

**κα'**

(below the O of IO in l. 7 of text [2])

(2) (on l., and [ll. 2-3] partly on top, of text [2])

**B F**

**DD nn**

**Imp Caes Fl Val**

4     **Constantino**

**p f invic Aug et**

**Imp Caes Val**

**Liciniano Licinio**

8     **p f inv Aug**

lines 1-2: **B**(onae) **F**(ortunae) | **D**(ominis) **n**(ostris)

*Caput Viae*     (Amasia)

*Date*     (1) (?)

(2) AD 313, Aug./Sept.-317, 28.ii Constantinus and Licinius *Augusti*

*Commentary*     Text (1) cannot be dated but is probably third century. On the other hand, (2) is a standard text of Constantinus and Licinius (for other milestones of these two emperors see RRMAM 2, (p.) 472). The distance figure (in Greek only) is 21 miles, i.e. from Amasia.

## 145(B). Uygur 2

*Province, Sub-Province + Admin. Code and Map*     As 145(A)

*Location*     As no. 145(A). Now in the Amasya Museum [Inv. no. A.90.31]

*Copy*     DHF 13.vi.1990. DHF squeeze and photo. in BIA. Text here from DHF squeeze

*BIA Collections:* *Squeeze and Stone Photographs*

Squeeze: 05. Amasya 20, Uygur 2

Stone: (1) B/W Neg.: DHF M/90/09.09

*Publication*     Yüce 1992, 210 and Pl.2 a-f

AE 1992. 1675 (text of Yüce 1992)

French 1992, 150 (notice only)

*Description*     A simple shaft. Broken at top right. The shaft is now broken into two pieces. Friable, pale grey limestone. (?) A re-used mullion (window-post); the section is a flattened oval, somewhat rectangular. The front and back faces are flat, the sides rounded. Roughly shaped base at front only. Top and base flat. Inscription (2) on front, and (1) on right side (starts 0.06 from top).

Letters: (text 1) A, U, (text 2) V

*Dimensions*     Ht 0.93 + 1.03 (upper frag.); wi. (top) 0.53; depth (top) 0.43. Letters (text 1) (line 7) D of UDI 0.048, (line 9) A of KA 0.086, (text 2) (line 1) I of IMP 0.036, (line 3) C of DIOC 0.06

*Text*     (1) (partly underneath, partly on r. of text [2])

[Imp Caes] **ṣarī·C·**

[Iu] **liō Vero Ma-**

**ṣimino·pio fe** (vac) **I**

4     **Aug·tribunīc**

p̄ōtest·p̄ p̄·co⟨s⟩  
 p̄rōcos·p̄er·Cl̄  
 [a]ūdianum·p̄ra-  
 8 ēsīd·p̄rovinc̄  
 (vac)  
 ⲕⲁ

line 8: **praesid(em) provinc(iae Ponti)**

(2) (partly on top, partly on l., of text [1])

Imp'̄ C̄aes̄  
 C'̄ Aur'̄ Val̄  
 Dioc̄letianō  
 4 p̄ fel̄ in̄v̄ Auḡ  
 et̄ Imp'̄ C̄aes̄  
 M̄ Aur̄ Val̄  
 [[Maximiano]]  
 8 p'̄ fel̄ in̄v̄ Auḡ  
 et̄ Fl̄ Val̄  
 Con̄stantiō  
 et̄ Gal̄ Val̄  
 12 Max̄imianō  
 nob̄ill̄ C̄aes̄s̄  
 (vac) m̄il̄ p̄  
 (vac) ⲕⲁ  
 (vac)  
 16 Aur̄ Pr̄isc̄ianus̄  
 v̄ p̄ p̄raes̄[es] p̄r'̄ P̄  
 d̄ n̄ m̄ q̄ eor̄um̄

lines 3, 7, 10 and 12: the letters in these lines are consistently larger and taller than those in all other lines

lines 17-18: **v(ir) p(erfectissimus) praes[es] pr(ovincia) P(onti) l**  
**d(evotus) n(umini) m(aiestati)q(ue) eorum**

*Caput Viae* (Amasia)

*Date* (1) AD 235, Feb.-March–09.xii(?) Maximinus *Augustus*

(2) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with  
 Constantius and Galerius *Caesares*

*Commentary* Text (1) can be dated to the first year of Maximinus' reign (there is no mention of Maximinus' son, Maximus). There is a duplicate text from Hamdi near Çorum, now in the Çorum Museum [Inv. no. 31.1.87] (above, 043). On the latter milestone, the governor's name appears to be *Claudianus*. Here there is a stop mark after Cl. Nevertheless the now accepted form is *Claudianus*; see Demougin (2005, 182–183).

Inscription (2) is a standard text of Diocletianus and his colleagues. The governor is Aurelius Priscianus, *praeses Ponti*. Maximianus' name has been erased (most probably in the Byzantine period), a not uncommon feature. The name of the Emperors and Caesars is written in letters larger than those of the remaining lines. This practice is a striking feature of the Amasya region. Similar examples are found on the milestones found at Akyazı (here 142), Çakırsu (here 015), Çiğdemlik (here 018), Kapıkaya 4 (here 146[D]) and Yerkozlu (here 016).

*General Commentary* Both milestones, 144(A-B), are numbered 21, i.e. 21 Roman miles from Amasia i.e. approximately 31 km, almost exactly the distance from modern Amasya. Both are perhaps in situ on a road running towards modern Turhal through the valley of the Ezinepazarözü. Together with a third milestone, at Ezinepazar (French 1988, 192), they may be evidence for an otherwise unattested Roman road running eastwards from Amasia to Comana (Gömenec near Tokat) by an alternative route. On the other hand, the shorter known route to Comana passes through Zile (ancient Zela), not through Turhal. The difference between the two distances is approximately 6 km. A second possibility is that the three milestones were carried to their modern location from an original point either on the Amasia-Neocaesaria road or on the Amasia-Zela road, the solution adopted here.

#### 146. Ezinepazar

<i>Province, Sub-Province + Admin. Code</i>	Amasya 05-00-3
<i>Map</i>	Amasya 85-n
<i>Location</i>	In the lower section of the village, Hanlar Mahallesi (beside the main road); in the courtyard of the cami. Brought from the cemetery on the W side of village.
<i>Copy</i>	DHF 10.vii.1986. DHF squeeze and photos (Pl. 7.1.99 [p. 405]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 05. Amasya 10, Ezinepazar Stone: (1) B/W Neg.: DHF M/86/15.03 (2) Col. Slide: DHF 261.06
<i>Publication</i>	French 1987, 192 (notice only)
<i>Description</i>	A simple cylinder. Broken at the top. Hard, white limestone. The base is flat. The surface is smoothed.
<i>Dimensions</i>	Letters: worn but clear; letters well shaped but irregular in size; broken-bar A Ht 1.50; diam. (top) 0.46. Letters: 0.035-55

<i>Text</i>	[Im]p̄er·Çaēs·Fl·Val· Constantio·et Gal·Val·Maximiano 4 p·p·f·f·invictt Augg et Fl Val [[Ş̄e[vero]]] et Gal Val [[Maximino]] nobill·Ça/e/ş̄ 8 iθ Aure(l)i(us) Hierax v p /p/raes proy Pa- flag d n (vac) m q 12 eorum mil·p·
-------------	---

line 4: **p·p·f·f·invictt·Augg**, p(iis) f(elicibus) **invict**(is) **Aug**(usti)

line 7: **CAFSS** (lapis); **nobill** Caess, **nobil**(issimis) **Caes**(aribus)

line 10: **RAES** (lapis)

lines 10-12: **praes**(es) **prov**(inciae) **Palflag**(oniae) **d**(evotus) **n**(umini)  
**m**(aiestati)q(ue) **eorum**

*Caput Viae* (Amasia)



*Date* AD 305, 01.v-306, 25.vii Constantius and Galerius *Augusti* with Severus and Maximinus  
(names of both erased) *Caesares*

### 147(A). Kapıkaya 1

*Province, Sub-Province + Admin. Code* Amasya 05-00-0  
*Map* Amasya 83-n  
*Location* “ . . . . , dans un cimetière près de la mosquée” (St. Pont.). Present whereabouts not established (DHF visit 25.viii.1984)  
*Copy* Cumont (Fr. and E.) 04 April, 1900. The stone has not been examined by DHF  
*Publication* St. Pont. 2 (Cumont [Fr. and E.]), 185 (no. 458) (notice only)  
 RRMAM 2, 1. 067  
*Description & Dimensions* Not given  
*Text* Not given  
*Caput Viae* (Amasia)  
*Date* AD 283, vi-vii (Carus and Carinus *Augusti*)

### 147(B). Kapıkaya 2

*Province, Sub-Province + Admin. Code and Map* As 146(A)  
*Location* In the village. Now in the Amasya Museum [Inv. no. 82.17.1]  
*Copy* DHF 25.viii.1984. DHF squeeze and photo. (Pl. 7.1.100 [p. 405]) in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 05. Amasya 03, Kapıkaya 2  
 Stone: (1) B/W Neg.: DHF M/84/08.12  
*Publication* RRMAM 2, 1.068  
*Description* A simple column. Broken at the top and bottom. Hard, white limestone. Letters: thin and sharp; U for V  
*Dimensions* Ht (ex.) 0.54; diam. (top) 0.31. Letters: 0.040-60 but (line 3) U 0.025

*Text*

	<b>Imp Caes M C/I/</b>
2	<b>Tacito p f in-</b>
	<b>v&lt;i&gt;cto Aug p p c-</b>
4	<b>os p mil /p/</b>
	<b>ια'</b>

lines 3-4: **p(atri) p(atriae) clos p(rocos)**  
 lines 1 and 4: I (lapis)

*Caput Viae* (Amasia)  
*Date* AD 275, Nov/Dec(?)-276, July(?) Tacitus *Augustus*

### 147(C). Kapıkaya 3

*Province, Sub-Province + Admin. Code, Map and Location* As 146(B) [Inv. no. 79.7.1]  
*Copy* DHF 25.viii.1984. DHF photos (Pl. 7.1.101 [p. 405]) in BIA. Text here from DHF notes  
*BIA Collections: Squeeze and Stone Photographs*

	Stone: (1) B/W Neg.: DHF M/84/08.13 (2) Col. Slide: DHF 245.12
<i>Publication</i>	RRMAM 2, 1. 069 (notice only)
<i>Description</i>	A simple cylinder. (?)A re-used column. Broken into three pieces. Hard, white limestone; red staining in fracture-surfaces.
<i>Dimensions</i>	Ht 0.43 + 0.30 + 0.20; diam. (top) 0.34
<i>Text</i>	<p style="text-align: center;"><b>Imp Caes L D</b></p> <p style="text-align: center;">2     <b>Aureliano</b></p> <p style="text-align: center;">      <b>p f invicto E</b> <span style="float: right;">(sic)</span></p> <p style="text-align: center;">4     <b>Aug cos</b></p> <p style="text-align: center;">      <b>p p procos</b></p> <p style="text-align: center;">- - - -</p> <p style="text-align: center;">line 1: L(ucio) D(omitio)</p>

<i>Caput Viae</i>	[Amasia]
<i>Date</i>	AD 271 Aurelianus <i>Augustus</i>
<i>Commentary</i>	For the date, Aurelianus COS (I), see Kienast (1996, 235)

**147(D). Kapıkaya 4**

<i>Province, Sub-Province + Admin. Code, Map</i>	As 146(B)
<i>Location</i>	Brought from the village to the museum [Inv. no. 83.7.8]
<i>Copy</i>	DHF 25.viii.1984. DHF squeeze (photo. of ll. 10-11, Pl. 7.2.2 [p. 409]) and photos (Pl. 7.1.102 [p. 406]) in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Stone Photographs</i>	Squeeze: 05. Amasya 13. Kapıkaya 4 (photo. B/W Neg.: DHF M/85/10.10, 15) Stone: (1) B/W Neg.: DHF M/84/08.06
<i>Publication</i>	French 1986a, 78, 79, Fig. 6 and photo., Pl. 6 AE 1986. 665 (text of French) RRMAM 2, 1. 070 (notice only)
<i>Description</i>	A simple cylinder. Chipped at the back, broken at the bottom. Hard, grey limestone. The top is flat. Surface and letters: worn. Letters of text (1) are thin
<i>Dimensions</i>	Ht (vis.) c. 1.10; diam. (top) c. 0.40. Letters: (text 1) 0.050-60, (text 2) 0.040-60, (text 2) (lines 1-2) c. 0.030 but (line 3) 0.040-50, (text 4) c.0.040
<i>Text</i>	<p>(1) (at the top of the column; underneath and on r. and l. of text [3])</p> <p style="text-align: center;">[Imp] <b>Caesar L Se-</b>  <b>ptimius Severus Piu[s]</b>  <b>Pertinax Aug Arabicus</b>  4     <b>Adiab Parthicus maximus</b>  [pontifex max] <b>trib pot V[I]</b>  [imp XI cos p p] <b>procos</b>  [et Imp Caes M Aur] <b>e[us]</b>  8     [Antoninus Aug et L Septim]-  [ius Geta Caesar] <b>restitu-</b>  [erunt (vac) per] <b>C Iul Flac-</b>  [cum Aelianum] <b>leg pr</b>  12     [pr]</p>

[mil -]  
[ - ]

For an intact version, see above, 050(B). Boğazbaşı 2

- (2) (on top of text [1]; underneath text [4] and ? text [3]; begins? below line 6 of text [3]; righthand letters of ll.1-2 on top of ll. 6-7 of text [1])

[ - - - - - ] **OI**  
2 [ - - - - . . . ] **IO**  
[ - - - - - - - ]  
4 [ - - - - - - - ]  
[ - - - - - - - ]  
6 [ - - - - - ] **Ant-**  
[ - ] **s v p pr pr**  
8 [Pont] **d n m q**  
[eoru] **m**

**v(ir) p(erfectissimus) pr(aeses) pr(ovincia) | [Pont(i)] d(evotus) n(umini)**  
**m(aiestati)q(ue) | [eoru]m**

- (3) (on top of text [1]); lines 1-6 over lines 1-4 of text [1]

**Imp·Caes**  
**C·Aur·Val·**  
**Diocletiano**  
4 **p·fel·inv·Aug**  
**et Imp (vac) Caes**  
**M·Aur (vac) Val**  
[[Maximiano]]  
8 [[p fel inv Aug]]  
[[et Fl Val]]  
[[Constantio]]  
[[et Gal Val]]  
12 [[Maximiano]]  
[[nobb Caess]]  
**mil p [ - ]**  
[ - ]  
(vac)  
16 [Aur Prisci] **anus v [p]**  
[praes prov Pont]  
[d n m q eorum]

lines 7-18: these lines can be restored on the basis of the undamaged text, 056(D). Zile 4

- (4) (below line 6, and on top of lines 7-13, of text [2])

**Imp Caes [ - ]**  
**Constantino**  
**p f invic semp Aug**  
4 **et Fl Cl Constantino**  
**et Fl Iul Constantio**

[et Fl Iul Constanti]  
[Fl Leontius]  
8 [pr]aes  
- - - -

For an intact version, see above, 029(B). Boğazkaya 2(2)

*Caput Viae* (Amasia)  
*Date* (1) AD 197/198(?), L. Septimius Severus and M. Aurelius Antoninus (Caracalla)  
*Augusti* with L. Septimius Geta (? names erased) *Caesar*  
(2) (?)  
(3) AD 293, 21.v(?)–305, 01.v Diocletianus and Maximianus *Augusti* with  
Constantius and Galerius *Caesares*  
(4) AD 333, 25.xii–335, 18.ix Constantinus *Augustus* with three sons,  
Constantinus, Constantius and Constans *Caesares*  
*Commentary* Text (2) is almost certainly 3rd century; the formula **DNMQEORUM** is not  
earlier (on milestones of Cappadocia) than Probus (see below, Indices 4.6.6 no [2]) but otherwise is  
found under Maximinus (CIL 3 3. 14429) and, in Moesia Superior, under Sept. Severus (CIL 3.  
14428).

#### 148. Suluova

*Province, Sub-Province + Admin. Code* Amasya, Suluova 05-04-0  
*Map* Samsun 82-1  
*Location* “In a cemetery near the roadside at Alevi, 15 miles NNW of Amasya” (St. Pont.).  
Present whereabouts not established (DHF visit 30.vii.1989)  
*Copy* Anderson 17 July, 1899. The stone has not been examined by DHF. Text here  
from CIL (Anderson).  
*Publication* St. Pont. 1 (Anderson), 50 (no. 447) (notice)  
CIL 3. 14184<sup>22</sup> (text from Anderson)  
RRMAM 2, 1. 071 (notice only)  
*Description & Dimensions* Not given  
*Text*

2 **Imp Caes**  
**Aurel Val**  
**Diocle[tiano]**  
4 - - - -

For an intact text of the Tetrarchy, see above, 056(D). Zile 4

*Caput Viae* [Amasia]  
*Date* (?) AD 293–305 Diocletianus and Maximianus *Augusti* with Constantius and  
Galerius *Caesares*

**F.2 NEOCAESARIA ([- Pompeiopolis] - Nicomedia)****149(A). Uluköy 1, form. Sonusa**

<i>Province, Sub-Province + Admin. Code</i>	Amasya, Taşova 05-05-0
<i>Map</i>	Samsun 88-1
<i>Location</i>	In the village, in a pile of stones and rubble beside the Ulucami. Brought to this location from the area of the dam-lake. Found when an electricity pylon was erected. Now in the Amasya Museum [Inv. no. 82.2.2]
<i>Copy</i>	DHF 25.viii.1984. DHF squeeze and photos (Pl. 7.1.103 [p. 406]) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 05. Amasya 17, Uluköy 2 Stone: (1) B/W Neg.: DHF M/84/09.02 (2) Col. Slide: DHF 245.10-11
<i>Publication</i>	French 1985b, 145 and Fig. 7 French 1986a, 77 no. 3 and Pl. 6 AE 1986. 664 (text of French) RRMAM 2, 1. 072 (notice only)
<i>Description</i>	A simple cylinder. Broken at the top and bottom. Hard, dark grey and red limestone. Letters: very sharp and clear; well cut and even in shape and size; A without bar, U for V
<i>Dimensions</i>	Ht (vis.) 0.94; diam. (top) 0.35. Letters: 0.035-40

<i>Text</i>	<p> -----  [ - - - - ]  [p p] <b>procos</b>  [et I]<b>mp·Caes·M</b>  5 <b>Aur·Antoninus</b>  <b>Aug·et·L·Septi-</b>  <b>mius Geta Caesar</b>  <b>restituerunt</b>  <b>per C Iulium</b>  10 <b>Flaccum Ae-</b>  <b>lianum leg</b>  (vac) <b>pr·pr</b>  (vac) <b>mil(v)[p]</b>  (vac)  (vac) <b>XXXVI</b> </p>
-------------	--

For an intact version (but with Geta erased), see above, 050(B). Boğazbaşı 2

<i>Caput Viae</i>	(Neocaesaria)
<i>Date</i>	AD 197/198(?), L. Septimius Severus and M. Aurelius Antoninus (Caracalla) <i>Augusti</i> with L. Septimius Geta (name not erased!) <i>Caesar</i>
<i>Commentary</i>	Almost uniquely among the milestones of Asia Minor, the names of Severus' younger son were not erased when the <i>damnatio memoriae</i> was imposed (AD 211, Dec. ?) on Geta. Perhaps the erasure was not carried out and, instead, the stone was deliberately broken into two or more pieces.

For the unequivocal L (line 6) in L. Septi-, see above [p. 10], **Notes and Comments 3.2**. The distance-figure, MP XXXXVI (= 53.46 km, if MP I = 1.485 km) was measured from Neocaesaria (modern Niksar). The modern, direct distance from Uluköy to Niksar is c. 50 km

### 149(B). Uluköy 2, form. Sonusa

*Province, Sub-Province + Admin. Code and Map* As 149(A)  
*Location* In the village; at the cami  
*Copy* DHF 26.viii.1984. DHF squeeze in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 05. Amasya 18, Uluköy 2  
*Publication* French 1985b, 145 (notice only)  
 RRMAM 2, 1. 073 (notice only)  
*Description* A simple cylinder. (?)A re-used column (there is a channel for lead on the top surface). Broken at the top right. Hard, grey limestone. Surface: rough. Letters: worn and damaged  
*Dimensions* Ht 1.17; diam. (top) 0.46. Letters: c. 0.040 but (line 6) 0.050-55

*Text*

	(vac) <b>Imp</b>
	[Ne]rva Cae[sar Aug]
	[pontif] <b>max tri</b> [b potest]
4	[cos III p p] <b>restituit</b>
	[per] <b>Pomponium</b>
	[Bass]um leg Aug pr pr
	(vac) <b>mil p</b> [XXXVII]
8	(vac) [λ]ζ'

line 4: restorations *exempli gratia*

*Caput Viae* (Neocaesaria)  
*Date* AD 97, 01.i-17.ix Nerva *Augustus*

### 149(C). Uluköy 3, form. Sonusa

*Province, Sub-Province + Admin. Code and Map* As 149(A)  
*Location* In the village  
*Copy* DHF 26.viii.1984  
*Publication* RRMAM 2, 1. 074 (notice only)  
*Description & Dimensions* Not recorded  
*Text* No visible inscription

### 150(A). Ilıca 1

*Province, Sub-Province + Admin. Code* Amasya, Taşova 05-05-3  
*Map* Samsun 86-1 (approx. 28.07)  
*Location* Brought by Nafiz Firat from the village to the Amasya Museum  
*Copy* DHF 27.x.1998. DHF squeeze (29.x.1998) in BIA. Text here from DHF squeeze  
*BIA Collections: Squeeze and Stone Photographs*  
 Squeeze: 05. Amasya 138, Ilıca 1

<i>Description</i>	A milestone, in the form of a re-used column. Upside-down, i.e. the column tapers downwards. Hard, grey limestone. Text (3) was cut immediately below the top of the column. Surface and letters: worn.
<i>Dimensions</i>	Letters: (text 3) cursive F, (text 4) diagonal-bar A, U for V Ht c. 1.10; diam. 0.37. Letters: (text [2]) 0.028-35, (text [3]) c. 0.05, P (line 3) 0.055, (text [4]) 0.055-7
<i>Text</i>	<p>(1) (underneath text [2]) text obliterated</p> <p>(2) (at the top of the shaft; on top of text [1]; underneath and partly below line 3 of text [3], and partly below the line-ends of text [4]; line 6 partly underneath line 1 of text [4])</p> <p style="text-align: center;"><b>Imp Cae(s) Fl Val</b></p> <p style="text-align: center;">2     <b>Constantino inv Au(g) et</b></p> <p style="text-align: center;">         <b>Imp Cae(s) [[Val Licinio]]</b></p> <p style="text-align: center;">4     <b>[[Liciniano inv Aug]]</b></p> <p style="text-align: center;">         <b>[[ - - - - ]]</b></p> <p style="text-align: center;">6     <b>[[ - - - - ]]OC</b></p> <p>(3) (on the top of lines 2-4, and on l., of text [2])</p> <p style="text-align: center;"><b>Imp·Caes</b></p> <p style="text-align: center;">2     <b>D N Cl Iuliano</b></p> <p style="text-align: center;">         <b>p f invic·Aug</b></p> <p>(4) (to the l. of and below text [3], and partly over ll. 4-6 of text [2]; top of letters in line 1 are partly erased)</p> <p style="text-align: center;"><b>Impp Cae(s) dd nn</b></p> <p style="text-align: center;">2     <b>Fl Valentiniano</b></p> <p style="text-align: center;">         <b>et Fl Valente</b></p> <p style="text-align: center;">4     <b>Augg</b></p> <p style="text-align: center;">line 1: <b>Imp(eratoribus) Caes(aribus) d(ominis) n(ostris)</b></p>
<i>Caput Viae</i>	[Amasia]
<i>Date</i>	<p>(1) (?)</p> <p>(2) Constantinus and Licinius <i>Augusti</i>, AD 313 ?</p> <p>(3) AD 361, 03.xi-363, 26/27.vi Claudius Iulianus <i>Augustus</i></p> <p>(4) AD 364, 28.iii-367, 24.viii Flavius Valentinianus and Flavius Valens <i>Augusti</i></p>

**150(B). Ilıca 2**

<i>Province, Sub-Province + Admin. Code and Map</i>	As 150(A)
<i>Location</i>	As 149(A)
<i>Copy</i>	DHF 27.x.1998. DHF squeeze (29.x.1998) in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i>
	Squeeze: 05. Amasya 11, Ilıca 2
<i>Description</i>	A simple cylinder. Broken at the top; otherwise complete. Hard, grey limestone.

*Dimensions* The shaft tapers slightly towards the top. Surface and letters: worn and damaged  
Ht (ex.) 1.15; diam. (top) 0.38. Letters: 0.035-65

*Text*

-----  
2     **p f** [ - - - - et Fl V]al  
      **Consta**[nti]o et  
4     **Gal Val Maximi**[i]ano  
      **nobiliss** C[ae]ss  
      (vac)  
6     **mp XXXXV**  
      ·μίλ·με´  
8     **Aur Priscianu**[s] v p  
      **praes pr P d** [n m q]  
10    **eorum**

lines 9-10: **praes(es) pr(ovinciae) P(onti) d(evotus) [n(umini)**  
**m(aiestati)q(ue)] l eorum**

For an intact text of the Tetrarchy, see above, 056(D). Zile 4

*Caput Viae* (Amasia)  
*Date* AD 293, 21.v(?) - 305, 01.v [Diocletianus and Maximianus *Augusti*] with  
Constantius and Galerius *Caesares*



**F.5 NICOPOLIS - COLONIA (- Cerasus)****151. Şebinkarahisar**

<i>Province, Sub-Province + Admin. Code</i>	Giresun, Şebinkarahisar 28-08-0
<i>Map</i>	Şebinkarahisar 106-ö
<i>Location</i>	“ . . . . in the court of the citadel (near the gate)” (Taylor). Present whereabouts not established (DHF visit 05.ix.1982)
<i>Copy</i>	Taylor 17.08.1866; de Courtois 1866. The stone has not been examined by DHF. Text here of Taylor (facsimile of the printed version of his copy (Fig. 6.1.104 [p. 351]))
<i>Publication</i>	Taylor 1868, 294-295 and Fig. (facsimile, Fig. 6.1.104 [p. 351]) Waddington in Le Bas and Waddington 1870, 431 no.1814h (text of de Courtois) CIL 3. (p. 975) 6053 (text of de Courtois <i>apud</i> Le Bas and Waddington 1870)
<i>Description</i>	“On part of a circular, hollow stone . . . . (Taylor). (?) An <i>ezgi taş</i> or <i>soku taş</i> (a very large mortar used for crushing or bruising wheat-grains and other products); ancient, cylindrical stones, particularly columns and milestones, are often cut down and shaped for this purpose.
<i>Dimensions</i>	Not given
<i>Text</i>	<div style="text-align: center;"> <p>-----</p> <p>[ - - - - - viam]</p> <p>[re]sti[tuerunt]</p> <p>(vac) <b>per O</b>[.....]</p> <p>-----</p> </div> <p>or possibly</p> <div style="text-align: center;"> <p>-----</p> <p>[ - - - - milia]</p> <p>[re]sti[tuta]</p> <p>(vac) <b>per O</b>[...]</p> <p>-----</p> </div>
<i>Caput Viae</i>	(?)
<i>Date</i>	(?)
<i>Commentary</i>	Not certainly a milestone, nor recognized as such by Mommsen

**L. DE PONTO ET BITHYNIA PER CAPPADOCIAM AD SYRIAM USQUE****L.1 TRAPEZUS - SATALA - per ripam ad Melitenam (- Samosata)****152. Elmelik**

<i>Province, Sub-Province + Admin. Code</i>	Gümüşhane, Kelkit 29-02-0
<i>Map</i>	Erzincan 115-p
<i>Location</i>	In a field, below (i.e. N of) the village and on the N side of the modern road, Kelkit to Eskiyo; near to the junction for Tütenli
<i>Copy</i>	DHF 08.ix.1982
<i>Publication</i>	RRMAM 2, 1. 378 (notice only)
<i>Description</i>	One piece was taken to the village by the owner
<i>Dimensions</i>	Not recorded
<i>Text</i>	No visible inscription

**153. Sadak**

<i>Province, Sub-Province + Admin. Code</i>	Gümüşhane, Kelkit 29-02-0
<i>Map</i>	Erzincan 116-p
<i>Location</i>	“In the village” (Yorke)
<i>Copy</i>	Hogarth and Yorke 1894
<i>Publication</i>	Yorke 1898, 324 Mitford 1972, 3, no. 206 RRMAM 2, 1. 379 (notice only)
<i>Description</i>	“We also found a milestone in the village, but it is in such bad condition that little more than the letters IMP could be made out” (Yorke)
<i>Dimensions</i>	Not given
<i>Text</i>	-- ? -- IMP -- ? --
<i>Date</i>	(?)

**154. Tütenli, form. Elbizim**

<i>Province, Sub-Province + Admin. Code</i>	Gümüşhane, Kelkit 29-02-0
<i>Map</i>	Erzincan 115-p
<i>Location</i>	“Auf dem Friedhof . . . .” (Ohlshausen and Biller)
<i>Copy</i>	Ohlshausen and Biller 1980
<i>Publication</i>	Ohlshausen and Biller 1984, 238 and Fig. 41 RRMAM 2, 1. 380 (notice only)
<i>Description</i>	“ . . . . ein unbeschrifteten Meilenstein . . . .” (Ohlshausen and Biller)
<i>Dimensions</i>	Not given
<i>Text</i>	No visible inscription
<i>Commentary</i>	“ . . . . , vermutlich von der Strasse von Neokaisareia nach Satala” (Ohlshausen and Biller)

**155. Eski Malatya**

<i>Province, Sub-Province + Admin. Code</i>	Malatya 44-00-4
<i>Map</i>	Malatya 107 Ih
<i>Location</i>	“ . . . . forty minutes on the road from Malatya (Eski Sheyr) to the bridge of Kirkgeuz Keupru” (Yorke); “ . . . . , rep. inter Malatiam et Kirkgöz Köprü . . . . super fluvium Tochma-su in via a Melitene ad Sebasteam (Sivas)” (CIL 3. 6893); “ . . . . auf dem Weg kurz hinter Eski-Malatia, links auf der schnurgerade Chaussee Malatia – Sivas, . . . . ” (Lehmann)
<i>Copy</i>	W. Fischbach 1883 (copy sent by Mordtmann to Mommsen); Hogarth and Yorke 1894; Lehmann 1897(?) (copy and squeeze)
<i>Publication</i>	Mommsen 1884b, 584 no. 1369 (copy of Fischbach) Yorke 1898, 319 no. 33 CIL 3. 6893 (text of Fischbach) CIL 3. 13642 (copy of Hogarth) (= 6893; “eandem iudicat Hogarth”) Lehmann 1903, 392 n.3 (notice only) Mitford 1972, 3, no. 207 RRMAM 2, 1. 686 (notice only)
<i>Description</i>	“On a pillar . . . . The stone is defaced above and hacked away below” (Yorke); “Columna alta m.2, lata infra c.75, supra c.50 . . . . ” (CIL 3.6893); “Die Hauptinschrift, 4 (nach Hog(arth 6) Zeilen, in ca. 5 cm grossen Buchstaben . . . . ” (Lehmann)
<i>Dimensions</i>	Not given
<i>Text</i>	<div style="text-align: right;"> <b>Imp [Ca]es</b>  2     <b>/M///</b>  <b>Fl Iuli////////</b>  4     <b>et Fl I////////</b>  <b>pp ff MA////////</b>  6     <b>semper Aug</b> </div>

lines 3-5: **Fl Iuli**[io Constantio] | **et Fl I**[ulio Constanti] | **pp ff ma**[ximis] (CIL 3. 13642)

*Date* AD 340, beg. iv–350, 18.i Constantius and Constans (CIL 3. 13642)

**156. Bahçebaşı, form. Orduzu**

<i>Province, Sub-Province + Admin. Code</i>	Malatya 44-00-0
<i>Map</i>	Malatya 107 Ii
<i>Location</i>	“e stato rinvenuto da alcuni operai addetti alla costruzione di una casa di Orduzu” (Equini). Now in the Malatya Museum
<i>Copy</i>	Equini 1968. DHF 06.viii.1974; Mitford October 1984 (photo. and squeeze). DHF squeeze in BIA. Text here from DHF squeeze (drawing, Fig. 6.2.35 [p. 369] and photo., Pl. 7.2.3 [p. 410])
<i>BIA Collections:</i>	<i>Squeeze and Stone Photographs</i> Squeeze: 44. Malatya 01, Bahçebaşı (photo. B/W Neg.: DHF M/90/34.14-15)
<i>Publication</i>	Equini 1970, 51 and Pl. 33 nos 1-2 French 1976, 53 (notice only) Mitford 1988, 173 no. 5 and Pl. 14 RRMAM 2, 1. 684 (notice only)

<i>Description</i>	“ . . . . , un miliario in pietra vulcanica e di forma cilindrica, frammentario per colpi di piccone, . . . . ” (Equini). Simple cylinder. Broken below. Hard grey limestone. Top flat.	
<i>Dimensions</i>	Ht 0.34; diam. 0.36. Letters: 0.050-65	
<i>Text</i>		<p><b>Impp Caes[s]</b></p> <p>2 <b>Caio Valerio</b></p> <p><b>Diocletiano</b></p> <p>4 <b>p f in<u>v</u>ict<u>o</u></b></p> <p>-----</p>
<i>Caput Viae</i>	[Melitene]	
<i>Date</i>	AD 286-293 Diocletianus [and Maximianus] <i>Augusti</i> (or AD 293-305 with <i>Caesares</i> )	

**P. PER PONTUM ET BITHYNIAM, GALATIAM, CAPPADOCIAM ET CILICIAM,  
ISAURIAM ET LYCAONIAM AD SYRIAM USQUE**

**P.1 (Pilgrim's Road) (Chalcedon - Nicaea - Iuliopolis - Ancyra) - COLONIA ARCHELAÏS  
- TYANA - *Via Tauri* (- Tarsus - Antiochia)**

**157. Gülhüyük**

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Şereflikoçhisar 06-20-0
<i>Map</i>	Kırşehir 65-Ie
<i>Location</i>	At the village cemetery; used as a post on the left-hand side of the gate
<i>Publication</i>	RRMAM 1. 53 (notice only) RRMAM 2, 1. 140 (notice only)

In its present position it has not been possible to record the description and text.

**158. Değirmenyolu**

<i>Province, Sub-Province + Admin. Code</i>	Ankara, Şereflikoçhisar 06-20-0
<i>Map</i>	Kırşehir 65-If
<i>Location</i>	In the village; at a çeşme, on the N side of the village
<i>Copy</i>	Anderson Summer 1898; MHB 1956; SM (? date); DHF 18.viii.1974. A facsimile of Anderson's printed copy is given here (Fig. 6.1.105 [p. 351]). SM photo. (Pl. 7.1.104 [p. 406]). DHF squeeze in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Photograph</i>	Squeeze: Ankara 76, Değirmenyolu Stone: (1) B/W Neg.: SM (? date) Stone: (2) Col. Slide: DHF 401.13
<i>Publication</i>	Anderson 1897-98, 74 (notice only) Anderson 1899, 108 no. 96 (facsimile, Fig. 6.1.105 [p. 351]) CIL 3. 14184 <sup>53,54</sup> (text of Anderson) Hild 1977, 39 and Fig. 1 (photo. of stone) RRMAM 1. 54 (text from DHF squeeze) RRMAM 2, 1. 128 (notice only)
<i>Description</i>	"On a column now split." (Anderson). A simple, cylindrical shaft. Broken above, below and behind. Hard, white, coarse-crystalline, granular marble. Surface: slightly worn. Letters: some wear but mostly clear and legible, very variable in size and shape; (text 2) diagonal-bar <i>alpha</i> , lunate <i>epsilon</i> , <i>sigma</i> and <i>omega</i> , short-bar <i>kappa</i> . Some letters survive on the left and right-hand sides of text 2 ("On the edges are fragments of a Latin inscription" [Anderson]). These letters, clearly constituting the beginning and end of lines, belong to an earlier text (here text 1), now almost wholly lost, on the rear face of the shaft; from their position (on the stone) relative to text 2 they probably survive from the last lines of the inscription. Embedded in the lines on the right-hand side of text 2 are the letters which survive from the left-hand side of the earlier text; the letter T can be read between lines 6 and 7, and E between lines 7 and 8, of text 1.
<i>Dimensions</i>	Ht 1.14; diam. (top) 0.35, (bottom) 0.41. Letters: (text 1) 0.055-60, (text 2) 0.020-45

*Text* (Text 1) (CIL 3. 14184<sup>54</sup>) (“On the left-hand edge . . . .” [Anderson]); on the rear face (now lost)

(on r. of text [2]) (on l. of text [2])

— — — —  
 2 [ — — — — — ] **resti-**  
**t**[uit per — — — — ] **TIS**  
 4 **E**[ — — — — — ] (vac)  
 — ? —

lines 2-3: *viis*] RESTI|*tu*]TIS (CIL)

(Text 2) (CIL 3. 14184<sup>53</sup>) (on the existing face; broken on r.)

(vac) **A**I **N**N (vac)  
**Αὐτοκράτορσιν Κέσα**[ρσιν]  
**Φλ’ Οὐαλ’ Κωνσταντί**[νφ]  
 4 **εὐσεβῖ εὐτυχῖ Σεβ μ**[εγ κὲ] (sic)  
**Οὐαλ’ Δικιννιανφ Δικινγ**[ίφ]  
**εὐσεβῖ εὐτυχῖ Σεβ μεγίς**[τφ κὲ] (sic)  
**Φλα’ Οὐαλ Κρίσπφ κὲ**  
 8 **Οὐαλ Δικινίφ καὶ Φλα**  
**Κλαυδίφ Κωνσταντίνφ**  
**ἐπιφ’ Καίσαρσιν**  
 (vac)  
 — ? —

line 1: **A**I for ΔΔ ?

lines 4 and 6: **εὐσεβῖ εὐτυχῖ** for **εὐσεβεῖ εὐτυχεῖ**

*Caput Viae* [Colonia Archelaïs]

*Date* (1) (?)

(2) AD 317, 01.iii-324, 19.ix Constantinus and Licinius *Augusti* with Crispus,  
 Licinius and Constantinus *Caesares*

### 159. Topakkaya, form. Çimeliarzartık

*Province, Sub-Province + Admin. Code* Aksaray 68-00-0 (form. Niğde 51-01-0)

*Map* Aksaray 70-Ij

*Location* Formerly in the village. The upper piece was seen (by Ballance) at a fountain in the village, the lower piece in a cemetery wall at the lower end of the village. The upper piece is now in the Aksaray Museum [Inv. no. 42.2.74]

*Copy* Ballance 1957(?); DHF 18.ix.1976. DHF squeeze and photos (Pl. 7.1.105 [p. 406]) in BIA. Text here from DHF squeeze

*BIA Collections:* *Squeeze and Photograph*

Squeeze: Aksaray 03 (Niğde 46), Topakkaya (photo. Col. Slide DHF 294.33-34)

Stone: (1) B/W Neg.: DHF R/76/04.07

(2) Col. Slide: DHF 419.07

*Publication* Ballance 1958, 230 no. 22, and 234

AE 1960. 36 (text of Ballance)

French 1976, 52 (notice only)

	RRMAM 1. 55 (text only)
	RRMAM 2, 1. 870 (notice only)
<i>Description</i>	A simple cylinder. Broken into two pieces; the upper piece is chipped around the top edge. Hard, white, coarse-crystalline, granular marble. Surface and letters: well preserved. The letters were carefully and neatly cut, regular in shape and size.
<i>Dimensions</i>	Ht (upper piece) 0.97 + (lower piece) 1.00; diam. 0.46. Letters: 0.040-45, (line 10) O of NOV 0.028
<i>Text</i>	<p><b>Imp Caes M</b>  <b>[Opell]iūſ Seve-</b>  <b>rus Maçrinus</b></p> <p>4    <b>pius feli[x] Aug</b> (leaf)  <b>sanctissimus ac</b>  <b>providentissi</b> (leaf)  <b>mus princeps et</b></p> <p>8    <b>M·Opellius Antoni-</b>  <b>nus nobillissimus</b>  <b>Caesar viam novam</b>  <b>institutam perfec-</b></p> <p>12    <b>çerunt curante</b>  <b>Şulla [C]ereçale le[g]</b>  <b>Aug [pr pr]</b>  (vac) <b>A Col·m p</b> (vac)</p> <p>16    <b>(?)</b></p> <p>line 10: ligature AM in NOVAM  line 15: m I (?)</p>
<i>Caput Viae</i>	Colonia Archelaïs
<i>Date</i>	AD 217, April 11–mid-June Macrinus <i>Augustus</i> with Diadumenianus <i>Caesar</i>

## 160. Aksaray

<i>Province, Sub-Province + Admin. Code</i>	Aksaray 68-00-0 (form. Niğde 51-01-0)
<i>Map</i>	Aksaray 70-Ik
<i>Location</i>	Formerly the stone stood in front of the Kızılminare (or Eğriminare) Cami, in the Şamlı Mahalle. Now in the Aksaray Museum [Inv. no. ?]
<i>Copy</i>	Sarre Summer 1895; DHF 09.xi.1974. Text here from Sarre
<i>Publication</i>	<p>Sarre 1896a, 32</p> <p>Sarre 1896b, 174 no.13a</p> <p>CIL 3. 14186, 14187 (copy and squeeze given by Sarre)</p> <p>Ramsay 1904, 127 no. 48 (comment on the abbreviation CO = CO(lonia))</p> <p>Ramsay 1916, 101 and n.2 (comment on the abbreviation CO = CO(lonia))</p> <p>Ballance 1958, 230 nos 25 and 27 (notice only)</p> <p>French 1976, 52 (notice only)</p> <p>RRMAM 1. 56 (text only)</p> <p>RRMAM 2, 1. 860 (notice only)</p>
<i>Description</i>	A re-used column. The face has now been completely re-worked into the shape of a pilaster. Hard, white, coarse-crystalline, granular marble. The first line of text 1

was cut immediately below the column-moulding. The letters (of text 1) were carefully cut with a narrow-pointed chisel. Letters: (text 1) (lines 1-2) very worn; diagonal-bar A

The two inscriptions are now almost completely illegible.

*Dimensions* Ht c. 2.00. Letters: (text 1) (line 1) 0.060, (line 2) 0.050, (text 2) (line 1) D 0.058, (line 2) 0.045 but O 0.030

*Text* (1) (on the full face of the column)

**Imprrrb**  
**Caessbb**  
**Caio A**[ur Val]  
4 **Diocletia**[no]  
**et Marc A**[u]r **G**[al]  
**Maximiano**  
[p] **f invic Aug**  
8 **et Imp**  
**Caes Fla**  
**Constantio**  
**et Caio A**[ur Val]  
12 **Maxim**[iano]  
**p f invic**  
**Caes**  
**A Co mil X**

line 15: A Co(lonia); “fortasse a Co(*manis*) mil(*ia*) X, sed numerus dubius est” (CIL)

(2) (on the rear of the column)

**DD nn**  
**Constantino**  
[[et Licinio]]  
4 **Augg**  
**et Crispo et**  
[[Licini]]o e[t]  
**Constantino**  
8 **nobb Caess**  
[ ? ]

*Caput Viae*  
*Date*

Colonia Archelaïs

(1) AD 293-305 Diocletianus and Maximianus *Augusti* with Constantius and Galerius *Caesares*

(2) AD 317-324 Constantinus and Licinius (name erased) *Augusti* with Crispus, Licinius (name erased) and Constantinus *Caesares*

## 161. Demirci

*Province, Sub-Province + Admin. Code*

Aksaray 68-00-0 (form. Niğde 51-01-0)

*Map*

Niğde 72-Ik

*Location*

Brought from the village to the Aksaray Museum

*Copy*

DHF 24.xi.1987, 13.x.1988, 20.xii.1991 and 20.x.1992. DHF squeeze (photo. Pl.



7.2.4 [p. 411]) in BIA

*BIA Collections:* Squeeze and Photograph*Publication* Squeeze: Aksaray 02 (Niğde 45), Demirci (photo. B/W Neg.: Squ. M/07.07-14)

French 2008, 128-129 (text and comments)

AE 2008. 1475 (text of French)

*Description* A simple cylinder, perhaps from a re-used column. Chipped at the bottom; otherwise complete. Hard, white, coarse-crystalline, granular marble (as the Topakkaya milestone, above, no. 159). The top and bottom are flat. The surface was roughly dressed. At the top of the shaft: a simple garland.*Dimensions* Letters: slightly worn; irregular in shape and size; diagonal-bar A  
Ht 2.06; diam. c. 0.40; ht (garland) c. 0.20. Letters: 0.038-55 but (line 12) 0.060*Text*

**Imp Caes M** [[Q[pe]llius]]  
**Severus** [[Ma]crinus]  
**pius felix Aug sanc-**  
4 **tissimu**<s> **ac provi-**  
/d/entissimus **prin-**  
**ceps et M** [[Q[p]e]llius]  
**Antoninus nobi-**  
8 **lissimus Caesar**  
**viam novam i**<n>**sti-**  
**tutam per**/f/ecerunt  
**curante Sulla Ce-**  
12 **reale v c leg eo-**  
**rum pr pr**  
(vac)  
(vac) **MP**  
(vac)  
(vac) **MP**

line 5: /O/ENT (lapis)

line 10: PER/T/ECERUNT (lapis)

lines 12-13: v(iro) c(larissimo) leg(ato) eolrum pr(o) pr(aetore)

lines 14-15: ligature MP

*Caput Viae* (Colonia Archelaïs)*Date* AD 217, April 11–mid-June Macrinus *Augustus* with Diadumenianus *Caesar**Commentary* A near-replicate of the Topakkaya text (above, no. 159); for the date, see above 3.**Notes and Comments 3.3 The Date of 108(C). Kanlıkavak 3.****162(A). Kemerhisar, Salmanlı Çiftlik 1***Province, Sub-Province + Admin. Code* Niğde, Bor 51-02-2*Map* Ulukışla 75-İp*Location* In a cemetery called ‘Talman’, c. 6 km S of Kemerhisar, c. 2.24 km E of the Niğde-Adana highway, and c. 2.50 km S of the junction for Bor. The cemetery is located c. 0.40 km N of a *bahçe* (orchard), ‘Salmanlı Çiftlik’. Now in the Niğde Museum [Inv. no. 20.1.76]*Copy* DHF 10.xi.1974, 20.xi.1976. DHF squeeze and photo. (Pl. 7.1.106 [p. 407]) in BIA. Text here from DHF squeeze

*BIA Collections: Squeeze and Stone Photographs*

Squeeze: 51. Niğde 14, Salmanlı Çiftlik

Stone: (1) B/W Neg.: DHF R/75/01.08

*Publication*

RRMAM 1. 57 (text only)

SEG 31. 1324 (text of French)

RRMAM 2, 1. 866 (notice only)

IK 55, 1 (Berges and Nollé eds). 44-45

*Description*

A simple cylinder. Broken above and below. Hard, pale, coarse-crystalline, granular marble. At the top of the shaft: a wreath with ties. The inscription is cut immediately below the wreath.

Letters: (text 1) mostly well preserved, sharp and clear, A without central bar, diagonal-form M; (text 2) broken-bar *alpha*, short-bar *kappa*; (text 3) lunate *epsilon* and *sigma*

*Dimensions*

Ht 0.65; diam. 0.52. Letters: (text 1) 0.030-45, (line 1) I of IMP 0.080, (line 3) O of PO 0.020, (text 2) K 0.034, (text 3) c. 0.025

*Text*

(1) (on the full face of the column)

**Imp Caesar·M·Ant[onius]**  
 2 **Gordianus·pius·[felix·invi]-**  
**ctus Aug pont·m[ax·trib]**  
 4 **potē[st] cos p[ro]cos**  
 [per - - - -]  
 6 - - - -

(2) (on the r. of text [1])

- - - -  
 [ - - - - ]  
 K[ - - - - ] (level with l. 2 of text [1])  
**AΦ**[ - - - - ]  
 [.]**P**[ - - - - ] (level with l. 4 of text [1])  
 - - - -

(3) (on the face behind text [1])

[Τοῖς δεσπόταις]  
 [ἡμῶν]  
 [τῷ ν]εικτητῇ (sic)  
 4 [Κωνστ]αντεῖνφ  
 [Cεβαστ]ῷ καὶ  
 [[Κρίσφ]] [καὶ]  
 [Κωνσταν]τίνφ καὶ  
 8 **Χ**ωνστ[αντίφ]  
 [ἐπιφφ Καίσαρσιν]  
 - (?) -

line 1: [Τοῖς Κυρίοις] (ed. pr.); [Τοῖς δεσπόταις] (IK)

lines 4-7: [Κωνστ]αντεῖνφ | [καὶ Λικινί]φ καὶ | [[Κρεῖσφ]] [καὶ] |  
 [Λικ]ινίφ καὶ (ed. pr.), corrected by Nollé (IK)

<i>Caput Viae</i>	[Tyana]
<i>Date</i>	(1) AD 239 Gordianus <i>Augustus</i> (2) AD (?) (3) AD 324-326 Constantinus <i>Augustus (maximus) victor</i> with Crispus (name erased), Constantinus and Constantius <i>Caesares</i>
<i>Commentary</i>	(Text 1) “ . . . Gordianus III im Jahre 238 nur ‘cos. design.’ war, seinen ersten ersten Konsulat aber erst 239 bekleidete.” (IK)

**162(B). Kemerhisar, Salmanlı Çiftlik 2**

<i>Province, Sub-Province + Admin. Code, and Map</i>	As 162(A)
<i>Location</i>	“Gefunden bei Salmanlı Mevkii, dort in einem Stall als Pfostenbasis verbaut” (IK)
<i>Copy</i>	Berges (date ?)
<i>Publication</i>	IK 55, 1 (Berges and Nollé eds). 47 and Pl. 108, 1-2
<i>Description</i>	“Fragment eines zylindrischen Meilensteins aus Marmor; über der Inschrift Ehrenkranz mit waagrechten Tänien” (IK)
<i>Dimensions</i>	“H.: 0,40m; Dm.: 0,44m” (IK)

<i>Text</i>	Τοῖς δε[σπόταις ἡμῶ]ν 2 Φλ Κων[σταντίνῳ νε]ικητῇ σεβ μεγ καὶ Φλ Κωνσταντίνῳ 4 κὲ Φλ Κω[νστ]αντίῳ κὲ Φλ [Κωνσταντ]ῇ [ἐπιφ Καίcc] 6 [ ? ]
-------------	--

<i>Caput Viae</i>	[Tyana]
<i>Date</i>	AD 333, 25.xii-335, 18.ix Constantinus <i>Augustus</i> with Constantinus, Constantius and Constans <i>Caesares</i>

**162(C). Kemerhisar, Salmanlı Çiftlik 3**

<i>Province, Sub-Province + Admin. Code, and Map</i>	As 162(A)
<i>Location</i>	“Ein Fragment vom oberen Teil des Meilensteins” [= 164(B)] “wurde 1994 von Berges in Salmanlı Mevkii auf dem alten Friedhof gefunden” (IK)
<i>Copy</i>	Berges (date ?), copy and photo.
<i>Publication</i>	IK 55, 1 (Berges and Nollé eds). 51 and Pl. 108, 5
<i>Description</i>	The top of a cylindrical shaft
<i>Dimensions</i>	“Dm. (oben): 0,35m; BH. (Z. 1-3) 0,03m.” (IK)

<i>Text</i>	<b>Imp Caes</b> [divi Severi nep] 2 [d]ivi <b>Antonin</b> [i mag Pii] [fil M] <b>Aur Severo</b> [Alex]]- 4 [[andro]] [pio fel Aug pont] - - - -
-------------	---

<i>Caput Viae</i>	[Tyana]
<i>Date</i>	Severus Alexander, ? AD 222
<i>Comment</i>	Thought (IK l.c.) to be the top of the milestone recorded by Jacopi in the Eminlik mosque (no. 164[A]). The editors of IK 55, however, have overlooked – most uncharacteristically

– the relative letter-positions in the first two lines of the two inscriptions, here and at Eminlik; the two texts are, in fact, not identical. Unlike the arrangement of the letters on the Eminlik stone (164[A] below), on the inscription here the position of the T of ANTO lies directly below the S of CAES and the O of ANTO falls on the the rt of the S, cp. the photo. Pl. 108, 5 in IK and the drawing Fig. 131 of Jacopi (see below, 164[A]).

In fact, the Eminlik stone is still (14.ix.2008) – indeed, as it was in 1977 – complete and unbroken, albeit thickly coated with whitewash, and one of the four central pillars inside the mosque.

### 163(A). Kavuklu 1

<i>Province, Sub-Province + Admin. Code</i>	Niğde, Bor 51-02-2
<i>Map</i>	Ulukışla 75-Ir
<i>Location</i>	In the village; in a <i>ahır</i> (stable), at the house (no. 23) owned by Ali Şahin. Partly buried, used as a base for a wooden column
<i>Copy</i>	DHF 22.vii.1973, 22.xi.1976. DHF squeeze in BIA. Text here from DHF squeeze
<i>BIA Collections: Squeeze and Photograph</i>	Squeeze: 51. Niğde 05, Kavuklu 1
<i>Publication</i>	RRMAM 1. 58(A) (text only) RRMAM 2, 1. 863 (notice only) IK 55, 1 (Berges and Nollé eds). 49 (text of RRMAM 1. 58[A]) AE 2000. 1476 (text in IK)
<i>Description</i>	A re-used column. Broken above and below. Pale limestone. Above the inscription: a wreath, the ties of which are preserved. Letters: mostly well preserved but some damage; A without bar
<i>Dimensions</i>	Ht c. 0.70; diam. (top) 0.042. Letters: 0.035-45, (line 1) I of IMP 0.070, O of TO 0.025, (line 3) F 0.055
<i>Text</i>	<p><b>Imp·Caē[s]ar·M·Anto-</b>  <b>nius·Gordianus·pius</b>  <b>felix·invictus·Aug</b>  <b>pon̄tifex·max·trib</b>          [potest cos p p procos]          - - - -</p>
<i>Caput Viae</i>	[Tyana]
<i>Date</i>	Gordianus <i>Augustus</i> , (?) AD 239

### 163(B). Kavuklu 2

<i>Province, Sub-Province + Admin. Code, and Map</i>	As 163(A)
<i>Location</i>	In the village; in a <i>ahır</i> (stable), at the house (no. 32) owned by Heybet Avcıoğlu. Used as a support for the roof
<i>Copy</i>	DHF 22.vii.1976. DHF squeeze in BIA squeeze. No photo. Text here from DHF squeeze and notes
<i>BIA Collections: Squeeze and Photograph</i>	Squeeze: 51. Niğde 06, Kavuklu 2
<i>Publication</i>	RRMAM 1. 58(B) (text only) RRMAM 2, 1. 864 (notice only) IK 55, 1 (Berges and Nollé eds). 48 (text of RRMAM 1. 58[B])

*Description* AE 2000. 1475 (text in IK)  
A simple cylinder. Broken below. The inscription has been almost wholly erased. A Christian Chi-Rho symbol on the front face. Surface and letters: very worn

*Dimensions* Ht 0.84; diam. 0.47. Letters: c. 0.035-40

*Text*

[[Imp·C[esar]]  
[[M A[urelius]]  
[[Severus [Alexander]]  
[[pius felix - - - ]]  
5 [[ - - - - ]  
[[ - - - - ]  
[[ - - - - ]  
[[ - - - - ]  
[[ - - - - ]  
10 [[ - - - - ]

line 3: [[Antoninus]] (ed. pr.); better [[Alexander]] (as Nollé in IK)

*Caput Viae* [Tyana]  
*Date* Severus Alexander, (?) year

### 163(C). Kavuklu 3

*Province, Sub-Province + Admin. Code, and Map* As 163(A)

*Location* In the village; in the *avlu* (courtyard) of the house (no. 32) owned by Ahmet Erdoğan

*Copy* DHF 27.xi.1976. DHF squeeze in BIA squeeze. No photo. Text here from DHF squeeze

*BIA Collections:* *Squeeze and Photograph*  
Squeeze: 51. Niğde 07, Kavuklu 3

*Publication* RRMAM 1. 58(C) (text only)  
RRMAM 2,1. 865 (citation of existing lines)  
IK 55, 1 (Berges and Nollé eds). 50 (text of RRMAM 1. 58[C])  
AE 2000. 1477 (text in IK)

*Description* A simple cylinder, on a round plinth. Broken above. Hard, white coarse-crystalline, granular marble.

*Dimensions* Letters: well preserved, sharp and clear; diagonal-bar A  
Ht 0.68, (plinth) 0.26; diam. 0.435. Letters: K of KAPP 0.060

*Text*

-----  
**Kapp mil**  
**I**

*Caput Viae* (Tyana?)  
*Date* AD (?)

### 164(A). Eminlik 1

<i>Province, Sub-Province + Admin. Code</i>	Niğde, Ulukışla 51-05-0
<i>Map</i>	Ulukışla 75-Is
<i>Location</i>	In the village mosque; one (the southwestern) of four pillars, all thickly coated with whitewash, in the centre of the main room. Brought from Bağdere (6 km N of the village) c. 1943 according to the villagers (DHF visit 21.xi.1977). Jacopi was given, in 1936, the same provenance.
<i>Copy</i>	Jacopi August-October 1936; French 21.xi.1976. DHF squeeze in BIA. Text here from DHF squeeze
<i>BIA Collections:</i>	<i>Squeeze and Photograph</i>
<i>Publication</i>	Squeeze: 51. Niğde 04, Eminlik 1 Jacopi 1938, 32 and Figs 131-132 (facsimile [of Fig. 132] Fig. 6.1.106 [p. 351]) Jacopi 1939, 213 (notice only) AE 1941. 163 (text of Jacopi 1938) Ballance 1964, 142 n.4 (note on the provenance of the stone) Harper 1964, 165 n.12 (note on text) RRMAM 1. 59(A) (text only) RRMAM 2, 1. 861 (notice only) Drew Bear 1991, 134 n.20 (comment on RRMAM 1. 59[A]) IK 55, 1 (Berges and Nollé eds). 51 (text of Jacopi 1938)
<i>Description</i>	A re-used column. Complete. Hard, grey limestone. Surface and letters: well preserved
<i>Dimensions</i>	Ht (vis.) 1.63; diam. (top) 0.47. Letters: (lines 1-3) 0.030-35

*Text*

**Imp·Caes·divi·Severi nep  
divi·Antonini·mag·Pii  
fil·M·Aur·Severo·[[Ale]]-  
4 [[xandro]]·pio·fel·Aug  
pont·max·trib·potest  
imp·I·I·cos·p·p·pro·cos  
per Asinium·Lepidum  
8 leg·Aug·pr·pr·praesid  
provinc·Capp  
ια'**

line 4: [[Alexandro]] Jacopi, followed by RRMAM 1 and IK. On the DHF squeeze, however, there are clear traces of an erasure at the end of line 3 in addition to the erasure – the space is indicated on Jacopi's Fig. 132 – at the beginning of line 4

<i>Caput Viae</i>	(Colonia Faustinopolis)
<i>Date</i>	AD 222 Severus Alexander <i>Augustus</i> ("zwischen 14.iii-9.xii" [IK], cp. Kienast [1996, 178])
<i>Commentary</i>	"Die Entfernungsangabe IA - 11 bezieht sich auf die Entfernung von Tyana" (IK); 11 MP from Faustinopolis (DHF)

**164(B). Eminlik 2**

<i>Province, Sub-Province + Admin. Code, and Map</i>	As 164(A)
<i>Location</i>	"In village" (Jacopi). Present whereabouts not established (DHF visit 21.xi.1976)
<i>Copy</i>	Jacopi August-October 1936. The stone has not been examined by DHF. Text

	here of Jacopi
<i>Publication</i>	Jacopi 1938, 33 and Figs 133-134 (facsimile [of Fig. 134] Fig. 6.1.107 [p. 351]) AE 1974. 639 (text of Jacopi 1938) RRMAM 1. 59(B) (text of Jacopi 1937; text only) RRMAM 2, 1. 862 (notice only) IK 55, 1 (Berges and Nollé eds). 52 (text of Jacopi 1938)
<i>Description</i>	Not recorded
<i>Dimensions</i>	Ht 0.49; diam. 0.45 (Jacopi)
<i>Text</i>	[Imp] Ca[es divi] [Se]veri Pii nepo divi Antonini 4 magni Pii filio Marco [Au]re[lio] [Se]vero [[Alexan]]- [[dro]] - - - - ] 8 - - - -
<i>Caput Viae</i>	[Colonia Faustinopolis]
<i>Date</i>	Severus Alexander <i>Augustus</i> , year (?)

### 165. Kırkgeçit Deresi

<i>Province, Sub-Province + Admin. Code</i>	Niğde, Ulukışla 51-05-1
<i>Map</i>	Ulukışla 77-Iş
<i>Location</i>	Found at Tahta Köprü in the Kırkgeçit Deresi
<i>Copy</i>	Christol and Drew Bear ****
<i>Publication</i>	Christol and Drew Bear 2009, 245 AE 2009. 1527 (text of Christol and Drew Bear)
<i>Description</i>	
<i>Dimensions</i>	“210 x 51 x 51-54 diam.” (Christol and Drew Bear)

<i>Text</i>	(wreath) <b>Imp</b> [[Caes]] [[M̄arç̄us̄ [Opellius Se]]- [[verus Macrinus]] [pius] 4 <b>felix Augustus</b> s[antissimus] <b>ac providentis</b> [simus prin]- <b>ceps</b> [et]] <b>Marcus Aure</b> [lius An]- <b>toninus</b> [Diadumenianus]] 8 <b>nobilissimus Ca</b> [esar viam] <b>Tauri montis</b> fr[equentissi]- <b>mis inluvionibus</b> [dirutam ac cae]- <b>sis rupibus ac dilat</b> [atis itineri]- 12 <b>bus cum pontibus</b> [institutis] [restit]utam perfece[runt] <b>A Pylas</b> m[ilia - ] <b>Ἀπὸ Π μί</b> [λια - ]	(sic)
-------------	--	-------

[restit]utam perfece[runt]

A Pylas m[ilia - ]

(sic)

Ἀπὸ Π μί[λια - ]

line 15: Ἀπὸ Π(υλῶν) μί[λια - ]

*Caput Viae* Pylae*Date* AD 217, May–218, 08.vi Macrinus *Augustus* with Diadumenianus *Caesar* (edd.);  
AD 217, April 11-mid-June Macrinus *Augustus* with Diadumenianus *Caesar*  
(DHF)*Commentary* I suggest that the work on the *Via Tauri* under Macrinus can be interpreted as a continuation of similar work undertaken by Caracalla (below, no. 166) earlier in the same year, AD 217, the work of both Emperors being supervised by the same governor, namely Sulla Cerialis; see above **3. Notes and Comments 3.3 The Date of 108(C). Kanlıkavak 3.****166. Pozantı 1***Province, Sub-Province + Admin. Code* Adana, Pozantı 01-09-0*Map* Ulukışla 78-It*Location* “Immediately S of the main ruin area . . . on the east bank of the Çakıt about a mile upstream from Pozantı . . . now covered by orchards” (Harper 1970). Set up (date ? at the Pelit Tesisleri, c. 5 km N of Pozantı, beside the old highway. Now in the Niğde Museum*Copy* Harper 1964; Harper squeeze in BIA. DHF photos (Pl. 7.1.107 [p. 407]) in BIA. Text here of Harper 1970 and 1972, and DHF autopsy 31.v.1987, 18.viii.1990 and 04.viii.1992*BIA Collections: Squeeze and Stone Photographs*  
Squeeze: 01. Adana 46, Pozantı 1  
Stone: (1) B/W Neg.: DHF M/90/21.14 and M/92/01.03  
(2) Col. Slide: DHF 326.28-29 and 355.04-06*Publication* Harper 1970, 151 and Fig. 1 and Pl. 21c  
AE 1969/70. 607 (text of Harper)  
Bull 1971. 678 (text of Harper)  
Harper 1972, 163  
RRMAM 1. 61 (text [of Harper 1970] only)  
RRMAM 2, 1. 026 (notice only)  
IK 55, 1 (Berges and Nollé eds). 132 (text of Harper 1970)*Description* Christol and Drew-Bear 2009, 245 and Figs 1-4 (comments on text and road)  
A simple cylinder. Broken at the top and on the l. side. Hard, pale limestone. The surface was finely smoothed.  
Letters: bright and sharp, exceptionally neat in size shape and alignment; (line 12) lunate *epsilon**Dimensions* Ht 1.60; diam. 0.60; ht “2.10” and diam. (top) “0.51” and (base) 0.54 (Christol and Drew-Bear). Letters: 0.030-35*Text*

[Imp Caes]

[M Aurelius Severus Antoninus]

[pius feli]x·{c} A[ug Parth max]

4 [Brit m]ax·Ger[m max] pontif  
[max tr]ib·potest·XX·imp·III·cos IIII



[proco]s·p p·Viam Tauri vetustate  
 [conl]apsam conplanatis·monti-  
 8 [bus e]t caesis rupibus·ac dilata-  
 [tis i]tineribus·cum pontibus  
 in·stituitis·restituit  
 A·Pylas·m·p·XV (sic)  
 12 A·πὸ Π·μί·ιε´

lines 5 and 11: horizontal line over the numerals

line 12: horizontal line over MI IE; A·πὸ Π(υλῶν) μί(λια) ιε´

*Caput Viae* Pylae  
*Date* AD 216, 10.xii – 217, 08.iv Caracalla *Augustus*

### 167. Pozantı 2

*Province, Sub-Province + Admin. Code* Adana, Pozantı 01-09-0

*Map* Ulukışla 78-It

*Location* Said to have been brought, by Yaşar Pelit, from a quarry on the N side of the modern highway, at the locality called Şekerpınar (not marked on the 1:200,000 map), c. 0.5 km N of the Pelit Tesisleri, c. 5.5 km N of Pozantı and c. 9 km SE of Çiftehan. Correctly, the stone would have been found within the boundary of Niğde province. In 1987 standing in front of the road-restaurant (located within the boundary of Adana province) adjacent to the Pelit Tesisleri

*Copy* DHF 31.v.1987. DHF photos in BIA. Text here from DHF copy and from a student's copy Sept. 1986 conveyed by Prof. Dr Hasan Malay 05.04.1988

*BIA Collections:* *Squeeze and Stone Photographs*

Stone: (2) Col. Slide: DHF 326.30-31 and 355.07-09

*Publication* RRMAM 2, 1. 026 bis (notice only)

IK 55, 1 (Berges and Nollé eds). 131 (notice of text in RRMAM; citation of lines 7-9)

*Description* A simple cylinder. Broken at the top. Hard, pale limestone

*Dimensions* Ht c. 1.70

*Text* (1) (below lines 2-8 of text [2])  
 erased lines  
 (vac) θι´

(2) (within the erased area on top of text [1])

-----  
 Λικινίῳ εὐτυχ(ε)ῖ Σεβαστῷ  
 3 Αὐτοκράτορσιν Καίσαρ[σιν καὶ]  
 Κρείσπῳ καὶ Λικιν[ιανῷ]  
 Λικινίῳ καὶ Φλ Κων[σταντίνῳ]  
 6 ἐπιφανεστάτοις Κέ[αரசιν]  
 Ἀπὸ Ποδάνδου  
 (vac) μ γ´

*Caput Viae* (1) Pylae

- Date** (2) Podandus  
(1) AD (?)  
(2) AD 317, 01.iii-324, 19.ix Constantinus and Licinius *Augusti* with Crispus, Licinius and Constantinus *Caesares*
- Commentary** The stone has been re-cut. The first text was erased (the area of erasure is clear) and the second text was then cut on the new surface which is slightly sunken. Of the earlier inscription only the distance figure has survived (on the level of the original surface). As found, the milestone was probably *in situ*. The ancient and modern distances to Şekerpınar from the ruins of Podandus, γ' - III MP - 4.455 km, coincide exactly. The second figure, θι' – XIX MP – 28.215 km, was measured from the Cilician Gates, as were the Kırkgeçit Deresi, Pozantı 1 and Soğukpınar milestones (here **165**, **166** and **168**).

### 168. Pozantı, Soğukpınar

- Province, Sub-Province + Admin. Code and Map** Adana, Pozantı 01-09-0
- Map** Ulukışla 77-Iu
- Location** “Found at Soğukpınar three miles south of the modern town of Pozantı” (Harper 1970); “This milestone stands in the forecourt of a petrol station about three miles south of Pozantı . . . . It was said to have been found in 1961 during ploughing of an adjacent field” (Harper 1964). Seen in its location at Soğukpınar by DHF 31.v.1987; c. January 1988 it was taken to the Pelit Tesisleri, 5 km N of Pozantı, beside the old highway
- Copy** Harper 1963; Harper squeeze in BIA. DHF photos (Pl. 7.1.108 [p. 407]) in BIA. Text and notes here are taken from Harper squeeze
- BIA Collections:** *Squeeze and Stone Photographs*  
Squeeze: 01. Adana 47, Pozantı  
Stone: (1) B/W Neg.: DHF M/90/21.15 and M/92/01.01-02  
(2) Col. Slide: DHF 094.30
- Publication** Harper 1964, 164  
AE 1964. 5 (text of Harper)  
Harper 1970, 149 and Pl. 21a  
Harper 1972, 162 (inscription printed as continuous text)  
RRMAM 1. 62 (text only)  
RRMAM 2, 1. 027 (notice only)  
IK 55, 1 (Berges and Nollé eds). 133 (text of Harper 1970)
- Description** Letters: slightly worn but clear and legible, neat in size, shape and alignment; broken-bar A
- Dimensions** Letters: 0.035-40, (line 1) 0.070
- Text**
- |   |                                 |
|---|---------------------------------|
|   | <b>Imp Caes div[i]</b>          |
|   | <b>Severi Pii nepoti</b>        |
|   | <b>divi Antonini</b>            |
| 4 | <b>magni Pii filio</b>          |
|   | <b>Marco Aurelio</b>            |
|   | <b>Severo [[Alexandro]] pio</b> |
|   | <b>felici invicto Aug pont</b>  |
| 8 | <b>max trib pot X cos</b>       |
|   | <b>III p p procos</b>           |
|   | <b>per Aradium Paternum</b>     |
|   | <b>leg Aug praes prov</b>       |

12    **A Pylas m p XI**  
         **ια'**

(sic)

*Caput Viae*  
*Date*

Pylae  
AD 230/231, 10.xii-09.xii. Severus Alexander *Augustus*

## 4.5 Concordances

### 1. Topographic. Old and Modern Place-names

Ağvanis	Gölova	Melikşerif	Yurtbaşı
Araplar	Alayurt	Muhlisoba	Gülhüyük
Aziz	Yağmurlu	Ohtap	Yağmurlu
Bebük	Boğazkaya	Oluz	Toklucak
Burtu	Yapraklı	Omala	Gözova
Çimenliyolu	Topakkaya	Orduzu	Bahçebaşı
Dabana	Çamsaray	Parlasan	Değirmenyolu
Dönekse	Boğazbaşı	Sipdiğin	Olgunlar
Elemanlı	Çakırlar	Sonusa	Uluköy
Fidi	Akça	Taf	Özlüce
Gömenek	Kılıçlı	Yornus	Çakırsu
Harzadin	Çeşmeören	Zana	Çiğdemlik
Hasanbadri	Fethiye	Zara	Doğantepe
Haydan	Doğankonak	Zilhor	Çaltılı
Malumseyit	Dutluca		

### 2. Epigraphic

#### 2.1 Collections

##### CIL 3

306	- 004	6919	- 108(L)	6945	- 098(B)
307	- 054(A)	6920	- 108(L)	6946	- 098(A)
308	- 029(A)	6921/2	- 108(H)	6947	- 093(A)
6057	- 048	6923	- 108(K)	6948	- 093(B)
6749	- 061	6924	- 108(C)	6949	- 093(C)
6893	- 155	6925	- 108(B)	6950	- 085(A)
6894	- 061	6926	- 108(E)	6951	- 083
6896	- 019	6927	- 107(B)	6952	- 085(B)
6903	- 123(A)	6928	- 105(A)	6953	- 087(B)
6904	- 120(A)	6929	- 107(C)	6954	- 087(A)
6905	- 120(B)	6930	- 104(A)	6955	- 085(C)
6906	- 118(C)	6931	- 104(D)	12154	- 048
6907	- 118(B)	6932	- 107(D)	12155	- 052(A)
6908	- 116(A)	6933	- 104(C)	12156	- 052(B)
6909	- 116(B)	6934/5	- 104(B)	12157	- 054(B)
6910	- 117(A)	6936	- 105(D)	12162	- 123(F)
6911	- 108(I)	6937	- 107(E)	12163	- 123(A)
6912	- 108(D)	6938	- 105(C)	12164	- 123(B)
6913	- 108(F)	6939	- 104(F)	12165	- 123(C)
6914	- 108(A)	6940	- 104(E)	12166	- 123(D)
6915/6	- 108(J)	6941	- 107(A)	12167	- 123(E)
6917	- 108(G)	6942/3	- 103(B)	12168	- 120(B)
6918	- 108(L)	6944	- 103(A)	12169	- 118(C)

12170	- 118(D)	12195	- 100(A)	14184 <sup>17</sup>	- 057
12171	- 110	12196	- 100(B)	14184 <sup>18</sup>	- 055(B)
12172	- 112	12197	- 089(A)	14184 <sup>19</sup>	- 010
12173	- 108(E)	12198	- 089(B)	14184 <sup>20</sup>	- 013
12174	- 109(C)	12199	- 089(C)	14184 <sup>21</sup>	- 012
12175	- 109(E)	12200	- 089(D)	14184 <sup>22</sup>	- 148
12176	- 108(M)	12201	- 089(E)	14184 <sup>23</sup>	- 011
12177	- 108(N)	12202	- 089(F)	14184 <sup>37</sup>	- 029(B)
12178	- 109(A)	12203	- 088(D)	14184 <sup>38</sup>	- 031
12179	- 109(B)	12204	- 088(B)	14184 <sup>39</sup>	- 035
12180	- 108(O)	12205	- 088(C)	14184 <sup>40</sup>	- 037(A)
12181	- 109(D)	12206	- 088(A)	14184 <sup>44</sup>	- 042
12182	- 110(P)	12207	- 092(A)	14184 <sup>45</sup>	- 041
12183	- 108(R)	12208	- 085(B)	14184 <sup>45</sup>	- 041
12184	- 108(Q)	12209	- 083	14184 <sup>53,54</sup>	- 158
12185	- 109(F)	12210	- 087(B)	14186	- 160
12186	- 105(A)	12211	- 087(A)	14187	- 160
12187	- 104(F)	12212	- 085(C)	p. 975 ad n.306	- 004
12188	- 104(I)	12213	- 133(C)	p. 975 ad n.6053	- 150
12189	- 104(J)	12214	- 133(A)	p. 1251 ad n.306	- 004
12190	- 104(G)	13642	- 155	p. 2328 <sup>82</sup> ad n.14184 <sup>45</sup> ,	
12191	- 105(E)	13643	- 033(A)	14184 <sup>17</sup>	- 041, 057
12192	- 106(A)	14184 <sup>12</sup>	- 048		
12193	- 106(B)	14184 <sup>16</sup>	- 061		

**IGRR 3**

131 - 093(C)

**IK 57**

44-45	- 162(A)	51	- 162(C)	127	- 133(B)
47	- 162(B)	51	- 164(A)	131	- 167
48	- 163(B)	52	- 164(B)	132	- 166
49	- 163(A)	125	- 133(A)	133	- 168
50	- 163(C)	126	- 133(C)		

**ILS 3**

8904 - 004

**Le Bas and Waddington**  
**1870, 2**

430 no. 1814a	- 054(A)	431 no. 1814d	- 048
430 no. 1814b	- 004	431 no. 1814h	- 151

**RRMAM 1**

60(A)	- 133(A)	55	- 159	58(C)	- 163(C)
60(B)	- 133(B)	56	- 160	59(A)	- 164(A)
60(C)	- 133(C)	57	- 162(A)	59(B)	- 164(B)
53	- 157	58(A)	- 163(A)	61	- 166
54	- 158	58(B)	- 163(B)	62	- 168

**RRMAM 2**

007	- 079(A)	075	- 016	520	- 071(A)
008	- 079(A)	128	- 158	521	- 071(B)
009	- 079(B)	140	- 157	522	- 072(A)
010	- 079(C)	319	- 041	523	- 072(B)
011	- 079(D)	322	- 029(A)	524	- 072(C)
012	- 079(E)	323	- 029(B)	525	- 072(D)
013	- 079(F)	324	- 029(C)	526	- 072(E)
014	- 079(G)	325	- 029(D)	527	- 072(F)
015	- 076	327	- 042	528	- 072(G)
016	- 078(A)	329	- 037(A)	529	- 073
017	- 078(B)	331	- 047	530	- 075(A)
018	- 078(C)	332	- 035	531	- 075(B)
019	- 077(A)-(C)	333	- 046	532	- 075(C)
020	- 080(A)	336	- 030(A)	533	- 075(D)
021	- 080(B)	337-8	- 030(B), (C)	534	- 075(E)
022	- 080(C)	339	- 036	535	- 075(F)
023	- 080(D)	341	- 043	536	- 075(G)
024	- 080(E)	347	- 031	538	- 075(H)
026	- 166	348	- 034(A)	539	- 075(I)
026bis	- 167	349	- 039	540	- 074(A)
027	- 168	350	- 044	541	- 074(B)
028	- 083	351	- 045	542	- 074(C)
029	- 082	364	- 005	543	- 074(D)
056	- 019	365	- 004	544	- 065
057	- 017(A)	378	- 152	545	- 087(A)
058	- 017(B)	379	- 153	546	- 087(B)
059	- 021	380	- 154	547	- 088(A)
060	- 023(A)	505	- 068(A)	548	- 088(B)
061	- 028	506	- 068(B)	549	- 088(C)
062	- 022	507	- 068(C)	550	- 088(D)
063	- 015	508	- 068(D)	551	- 089(A)
064	- 027	509	- 068(E)	552	- 089(B)
065	- 018	510	- 069	553	- 089(C)
066	- 024	511	- 090(A)	554	- 089(D)
067	- 146(A)	512	- 090(C)	555	- 089(E)
068	- 146(B)	513	- 090(B)	556	- 089(F)
069	- 146(C)	514	- 090(D)	557	- 086(A)
070	- 146(D)	515	- 091	558	- 086(B)
071	- 147	516	- 070(A)	559	- 085(A)
072	- 148(A)	517	- 070(B)	560	- 085(B)
073	- 148(B)	518	- 070(C)	561	- 085(C)
074	- 148(C)	519	- 070(D)	562	- 084

563	- 085(D)	755	- 104(F)	805	- 113(C)
564	- 085(E)	756	- 104(G)	806	- 098(A)
565	- 067(A)	757	- 105(A)	807	- 098(B)
566-8	- 067(B)-(D)	758	- 105(B)	808	- 099
569	- 066	759	- 105(C)	809	- 100(A)
570	- 093(A)	760	- 105(D)	810	- 100(B)
571	- 093(B)	761	- 105(E)	811	- 098(C)
572	- 093(C)	762	- 104(I)	812-6	- 101(A)-(E)
573	- 093(D)	763	- 104(J)	817	- 103(A)
574	- 092(A)	764	- 106(A)	818	- 103(B)
575	- 092(B)	765	- 106(B)	819	- 102(A)
576-7	- 092(C)-(D)	766	- 104(K)	820	- 102(B)
578	- 003	767	- 104(L)	821	- 114
684	- 156	768	- 104(H)	822	- 126
685	- 130	769	- 129(A)	823	- 127
686	- 155	770	- 129(B)	824	- 107(A)
687	- 132	771	- 129(C)	825	- 107(B)
715	- 116(A)	772	- 125(A)	826	- 107(C)
716	- 116(B)	773	- 125(B)	827	- 107(D)
717	- 116(C)	774	- 122	828	- 107(E)
718	- 115	775	- 120(A)	829	- 107(F)
719	- 119(A)	776	- 120(B)	830	- 107(G)
720	- 119(B)	777	- 118(A)	831	- 121
721	- 124(A), (B)	778	- 118(B)	832	- 128(A)
722	- 094(A)	779	- 118(C)	833	- 128(B)
723	- 094(B)	780	- 118(D)	834	- 128(C)
724	- 094(C)	781	- 108(A)	835	- 109(A)
725	- 094(D)	782	- 108(B)	836	- 109(B)
726	- 095	783	- 108(C)	837	- 109(C)
727	- 096	784	- 108(D)	838	- 109(D)
728	- 097(A)	785	- 108(E)	839	- 109(E)
729	- 097(B)	786	- 108(F)	840	- 109(F)
730	- 097(C)	787	- 108(G)	858	- 002
731	- 097(D)	788	- 108(H)	859	- 001
732	- 097(E)	789	- 108(I)	860	- 160
733	- 097(F)	790	- 108(J)	861	- 164(A)
734	- 112	791	- 108(K)	862	- 164(B)
735	- 123(A)	792	- 108(L)	863	- 163(A)
736	- 123(B)	793	- 108(M)	864	- 163(B)
737	- 123(C)	794	- 108(N)	865	- 163(C)
738	- 123(D)	795	- 108(O)	866	- 162(A)
739	- 123(E)	796	- 108(P)	867	- 133(A)
740	- 123(F)	797	- 108(Q)	868	- 133(B)
741-8	- 123(G)-(N)	798	- 108(R)	869	- 133(C)
749	- 117(A)	799	- 108(S)	870	- 159
750	- 104(A)	800	- 110	929	- 048
751	- 104(B)	801	- 111(A)	930-2	- 049(A)-(C)
752	- 104(C)	802	- 111(B)	933	- 006
753	- 104(D)	803	- 113(A)	934	- 008
754	- 104(E)	804	- 113(B)	935	- 007

935 bis	- 131	948	- 053	963	- 056(A)
936	- 012	949	- 057	964	- 056(B)
937	- 050(A)	950	- 009	965	- 056(C)
938	- 013	951	- 061	969	- 134
939	- 011	952	- 054(A)	972	- 138
940	- 059	953	- 054(B)	975	- 064
941	- 062	954-6	- 054(C)-(E)	978	- 135
942	- 052(A)	957	- 054(F)	979	- 136
943	- 052(B)	958	- 054(G)	980	- 137
944	- 140(A)	959	- 054(H)	991	- 037(C)
945	- 140(B)	960	- 055(A)	993	- 033(A)
946	- 058	961	- 055(B)		
947	- 060	962	- 063		

**St. Pont. 1**

7 (no. 448)	- 037(A)	55 (no. 454)	- 013
8	- 029(B), 031	55 (no. 455)	- 012
11 (no. 449)	- 035	58 (no. 456)	- 010
16 (no. 450)	- 031	59 n.2 (no. 466)	- 050(A)
16 (no. 451)	- 029(B)	61 (no. 464)	- 052(A)
16 (no. 452)	- 029(A)	62 (no. 465)	- 052(B)
18 (no. 444)	- 042	67	- 055(B)
22 (no. 445)	- 041	67 (nos 460-2)	- 054(C)-(E)
23 (no. 446)	- 034(A)	67	- 055(A)
31	- 135	72 (no. 459)	- 055(B)
34 (no. 472)	- 061	74 (no. 420)	- 011
44 (no. 467)	- 057	87 and n.4 (no. 477)	- 004
50 (no. 447)	- 148		

**St. Pont. 2**

185 (no. 458)	- 147(A)	314 (no. 473)	- 048
194 (no. 468)	- 056(A)	319 (no. 372)	- 007
196 (no. 469)	- 140(A)	319-320 (no. 475)	- 006
196 (no. 470)	- 140(B)	324 (no. 476)	- 005
197	- 056(A), 062	328 (no. 477)	- 004
213	- 049(A)-(C)		

**St. Pont. 3, 1**

32 and n.1	- 136
221 (no. 248)	- 033(A)
221 (no. 446a)	- 028

**2.2 Annual Bulletins****AE**



1888. 179	- 108(I)	1986. 652	- 043
180	- 108(D)	654	- 138
181	- 104(B)	655	- 037(C)
182	- 108(A)	656	- 029(C)
183	- 108(L)	657	- 054(H)
184	- 108(C)	662	- 033(A)
1900. 148	- 011	664	- 149(A)
1905. 132	- 056(A)	665	- 147(D)
133	- 062	690	- 114
1912. 290	- 104(K)	1989. 731	- 065
1961. 25	- 056(A)	1990. 895	- 054(G)
26b	- 015	982	- 114
1964. 5	- 168	1991. 1542	- 133(C)
1969/70. 607	- 166	1993. 1563	- 050(B)
1974. 640	- 133(C)	1564	- 053
1975. 785	- 015	2000. 1479	- 133(C)
1977. 814	- 002	2008. 1473a-b	- 066

**Bull.**

1971. 678 - 166

**2.3 Journals**

none

**2.4 Authors**

Anderson 1897-98	144 + n.9	- 133(B)	78 no. 26	- 089(F)
	142 + n. 4	- 164(A)	78 no. 27	- 092(A)
74	- 158		79 no. 28	- 088(D)
	Baz 2007		80 no. 29	- 088(B)
Anderson 1899			82 no. 30	- 088(C)
	62 no. 9	- 098(B)	82 no. 31	- 088(A)
108 no. 96	- 158	- 098(A)	83 no. 32	- 087(A)
	65 no. 11	- 093(C)	85 no. 33	- 086(A)
Babinger 1923	66 no. 12	- 093(A)	85 no. 34	- 087(B)
	68 no. 13	- 093(B)	86 no. 35	- 085(C)
206	- 029(A)	- 093(D)	88 no. 36	- 085(B)
	69 no. 14	- 092(C)	90 no. 37	- 085(A)
Ballance 1958	69 no. 15	- 092(D)	91 no. 38	- 085(D)
	69 no. 16	- 090(C)	91 no. 39	- 084
230 no. 22	- 159	- 091	91 no. 40	- 083
230 nos 25, 27	- 160	- 090(A)	93 no. 41	- 082
234	- 159	- 090(B)	93 no. 42	- 080(E)
	70 no. 20	- 089(A)	94 no. 43	- 080(B)
Ballance 1964	70 no. 21	- 089(E)	94 no. 44	- 080(A)
	73 no. 22	- 089(B)	94 no. 45	- 080(C)
	74 no. 23	- 089(C)	94 no. 46	- 080(D)
144 + n.8	- 133(A)	- 089(D)	95 no. 47	- 078(B)
144 + n.9	- 133(C)			
	77 no. 25			

95 no. 48	- 075(A)	Christol & Drew-Bear 1987	Cumont 1905b
95 no. 49	- 075(C)		
96 no. 50	- 075(B)	21 n.32	- 015
96 no. 51	- 075(D)		201 - 004
96 no. 52	- 072(E)	Christol & Drew-Bear 2009	221 n.3 - 005
97 no. 53	- 072(C)		233 n.1 - 054(F)
97 no. 54	- 072(G)	243	- 133(A)
98 no. 55	- 072(A)	245	- 165
98 no. 56	- 072(B)	245	- 166
98 no. 57	- 072(D)		Dodgeon and Lieu 1991
98 no. 58	- 071(B)	Christol and Lorient 1986	
98 no. 59	- 071(A)		Drew Bear 1991
99 no. 60	- 070(C)	16 and n.22	- 056(A)
		17	- 114
Bittel 1955		17 and n.22	- 62
		17 and n.32	- 016
24	- 041, 042	20-21	- 043
		22 and n.49	- 61
Boré 1840, 1		23	- 044
		22	- 061
336	- 054(A)	24	- 138
357	- 054(A)		
370	- 004	Christol and Lorient 1993	French 1976
Boybeyi & Probst 2008		210-211	- 065
		218	- 108(M)
135	- 098(D)	218 and n.46	- 108(C)
Brant 1836		Christol and Lorient 2001	
			French 1980
212	- 132	110 no. 7	- 065
Cagnat 1894		Cousin 1904	
			716 no. 7 - 004
132 and n.1	- 033(A)	365	- 103(B)
			721 no. 20 - 088(D)
Carolides 1882		Cumont 1902	723 no. 25 - 109(C)
			724 no. 27 - 087(A)
67	- 083	312 no. 1	- 053
		329	- 033(A)
Christol, Drew-Bear & Özsait 1993		333 no. 53	- 050(A)
		Cumont 1904	
159	- 050(B)		
161	- 053	334	- 060
161 n.10	- 108(I)		
		Cumont 1905a	
Christol & Drew Bear 1986			
		347	- 056(A), 062
47 n.31	- 015		
			151 no. 4 - 029(C)
			153 no. 5 - 138
			153 no. 6 - 037(C)
			155 - 054(H)
			156 - 029(B)
			157 - 033(A),
			- 056(B),

	056(C)	French 1987	Grothe 1911, 1
162	- 033(A),		
	056(B)-(C)	191	- 032(A)
167	- 056(A)	192	- 023(B), 025
167 n.*2	- 061, 062	192	- 143, 146
		193	- 009, 051
French 1983		193	- 141, 142
			Harper 1964
87	- 114, 115	French 1989	164
			- 168
French 1984		39 and Fig. 1	- 164(A)
			- 065
			Harper 1970
123 and Fig. 2	- 036, 044	French 1990	
			149
			- 168
French 1985a		231	- 037(B)
			151
			- 166
			Harper 1972
147 and Fig.1	- 114	French 1991a	
147 and Fig. 2	- 118(C)		
148 and Fig. 3	- 056(B)	150	- 033(B),
150 and Fig. 5	- 054(G)		144(A), (B)
150 and n.15	- 068(A)		
150 and n.16	- 072(E)	French 1991b	
150 and n.17	- 075(H)		
150 and n.18	- 087(A)	84	- 033(A)
150 and n.19	- 091		
150 and n.20	- 076	French 1995	
151 and n.21	- 104(F)		
151 and n.22	- 119(A)	1	- 050(B),
			056(D)
French 1985b		2	- 139, 144
			Hogarth and Munro 1893
143	- 043, 046	French 2008	686
144	- 021, 023(A),		- 118(C), (D)
	024		686
			- 124(A), (B)
145 & Fig. 7	- 149(A)	126	- 093(C)
145	- 149(B)	127 no. 3	- 108(C)
145 & Fig. 8	- 016	128	- 161
		131	- 183
		133	- 103(A)-(B)
French 1986a		133	- 128(B)
77 no. 3	- 149(A)	Garstang 1908	
78, 79	- 147(D)		
80 no. 4	- 043	8	- 003
French 1986b		Grégoire 1909	
109	- 043	27	- 056(B)
110	- 018, 019,	33	- 007
	021-023(A)	36	- 007
		37	- 008
			695 “147”
			- 092(A)
			695 “147”
			- 092(B)

695 “148” - 092(C)-(D)	704 “115 (ii)” - 109(B)	441 no. 1 - 017(A)
695 “146 (i)” - 093(A)	704 “115 (iii)” - 109(C)	441-442 no. 2 - 017(B)
695 “146 (ii)” - 093(B)	705 “115 (iv)” - 109(D)	452 no. 13 - 137
696 “144” - 093(C)	705 “115 (v)” - 109(E)	457 no. 24 - 116(C)
696 “141 (i)” - 104(G)	705 “115 (vi)” - 109(F)	457 v.s. no. 24 - 116(A), (B)
696 “141 (ii)” - 104(B)	706 “113” - 110	458 no. 27 - 110
696 “141 (iii)” - 104(C)	706 “114” - 112	
697 “138” - 098(B)	706 “99 to 95 (i)” - 116(A)	Keppie 1991
697 “137” - 098(A)	706 “99 to 95 (ii)” - 116(B)	127 & Fig. 78 - 103(B)
697 “136 (i)” - 100(A)	706 “100 (ii)” - 117(A)	
697 “136 (ii)” - 100(B)	706 “100 (i)” - 118(B)	Le Guen-Pollet 1989
698 “134” - 104(I)	706 “94 (i)” - 118(C)	80 no. 31 and n.45
698 “133” - 104(A)	706 “94 (ii)” - 118(D)	- 056(A)
698 “132” - 104(J)	707 “93 to 59 (ii)” - 120(A)	81-82 - 062
698 “131” - 103(A)	707 “93 to 59 (i)” - 120(B)	82 no. 32 - 054(G)
698 “130 ?(i)” - 103(B)	707 “93 to 59 (iii)” - 123(A)	83 no. 33 - 061
699 “130 (ii)” - 104(E)	707 “93 to 59 (iv)” - 123(B)	83 no. 34 - 136
699 “125 ?(i)” - 104(D)	707 “93 to 59 (v)” - 123(C)	84 no. 36 - 064
699 “125 (ii)” - 104(F)	708 “93 to 59 (vi), (vii)”	
699 “125 (iii)” - 108(C)	- 123(D)	
700 “124 ?(i)” - 105(A)	708 “93 to 59 (viii)”	
700 “124 ?(ii)” - 105(E)	- 123(E)	
700 “124 ?(iii)” - 105(D)	708 “58” - 123(F)	Le Guen-Pollet 1991
700 “124 (iv)” - 105(C)	727 - 048	102 - 054(G)
701 “123 (i)” - 106(A)	733 (i) - 052(A)	102 - 056(A)
701 “123 (ii)” - 106(B)	733 (ii) - 052(B)	102 - 062
701 “122 ?(i)” - 107(B)	735 - 054(B)	
701 “121 ?(ii)” - 107(A)		Lehman 1903
701 “121 ?(i)” - 107(C)	Jacopi 1938	392 - 155
701 “122 (ii)” - 107(D)	32 - 164(A)	
701 “121 ?(iii)” - 107(E)	33 133(A),(C),	
701 “120” - 108(B)	164(B)	Loriot 1976
702 “118 (i)” - 108(M)		53 n.4 - 033(A)
702 “118 (ii)” - 108(N)		57 - 029(A)
702 (i) - 108(O)	Jacopi 1939	
702 (ii) - 108(E)	213 - 164(A)	Loriot 1996
702 (iii) - 108(P)		226 n.17 and 227 no. 7
703 (iv) - 108(Q)	de Jerphanion 1914-21	- 098(A)
703 (v) - 108(R)	9 - 137	
703 (vi) - 108(K)	9 no. 12 - 064	
703 (vii) - 108(E)		McCrum and Woodhead
703 (viii) - 108(L)	de Jerphanion 1928	1961
703 (ix) - 108(H)		
703 (x) - 108(G)	34 n.1 - 137	46 no. 86 - 004
703 (xi) - 108(J)	de Jerphanion and Jalabert	Magioncalda 1984/5
703 (xii) - 108(A)	1908	127 - 138
703 (xiii) - 108(F)		
703 (xiv) - 108(D)		
703 (xv) - 108(I)		
704 “115 (i)” - 109(A)		

Mitford 1972, 3		Petolescu 1991		Ritter 1843	
no. 200-1	- 008	203	- 087(B)	863	- 132
no. 201-1	- 048				
no. 202	- 007	Pflaum 1948		Sarre 1896a	
no. 203-1	- 006				
no. 204	- 005	66	- 029(A)	32	- 160
no. 205	- 004				
no. 206	- 153	Polacco 1970 (1972)		Sarre 1896b	
no. 206-2	- 033(A)				
no. 207	- 155	188	- 002	174 no. 13a	- 160
Mitford 1974		Polacco 1971		Stein 1957	
173 and n.93	- 054(F)	29	- 002	6	- 029(A)
175 n.102	- 128(A), (B)				
Mitford 1980		Polacco 1972/3		Sterrett 1883-84	
		88 and n.9	- 002	240 no. 269	- 104(A)
1201 n.93	- 007			241 no. 270-1	- 104(B)
		Ramsay 1882a		244 no. 272-3	- 104(C)
Mitford 1988				245 no. 274-5	- 104(D)
		155 no. 16	- 019	246 no. 276	- 104(E)
173 no. 5	- 156			247 no. 277	- 104(F)
		Ramsay 1883		254 no. 288-9	- 103(A)
Mommsen 1884a				255 no. 290-1	- 103(B)
		328	- 085(B)	256 no. 292	- 098(A)
36 no. 73	- 085(A)			256	- 099
36 no. 74	- 104(A)	Ramsay 1903		257 no. 293	- 098(B)
36 no. 75	- 083			258	- Keklikoluk
37 no. 76	- 085(B)	401	- 133(A)-(C)	259 no. 295	- 093(A)
37 no. 77	- 087(B)			260 no. 296	- 093(B)
38 no. 78	- 087(A)	Ramsay 1904		260 no. 297	- 095(C)
38 no. 79	- 085(C)			264 no. 300	- 105(A)
39 no. 82	- 019	111	- 133(C)	264	- 105(B)
		127 no. 48	- 160	265 no. 301	- 105(C)
Mommsen 1884b				265 no. 302-4	- 105(D)
		Ramsay 1916		267 no. 305	- 107(A)
584 no. 1366	- 085(C)			267 no. 306	- 107(B)
584 no. 1369	- 155	101 + n.2	- 160	267	- 105(B)
				268 no. 307	- 107(C)
Munro 1900		Ramsay 1941		269 no. 308	- 107(E)
				269 no. 309	- 107(D)
159 no. 1	- 011	97 no. 67	- 098(A)	270 no. 310	- 108(A)
		109 no. 90	- 085(B)	271 no. 311	- 108(B)
Olshausen and Biller 1984		109 no. 91	- 085(A)	272 no. 312	- 108(C)
		109 no. 92	- 087(B)	272 no. 313	- 108(D)
228 and Fig. 40	- 058	110 no. 93	- 085(C)	273 no. 314	- 108(E)
238 and Fig. 4	- 154	110 no. 94	- 083	273 no. 315-6	- 108(F)
239	- 063			275 no. 317	- 108(G)

275 no. 318-9	- 108(H)	29 no. 34	- 108(A)	140 no. 27	- 083
277 no. 320-1	- 108(I)	30 no. 35	- 108(B)	140 no. 28	- 085(B)
279 no. 322-3	- 108(J)	30 no. 36	- 108(C)	141 no. 29	- 085(A)
281 no. 324	- 108(K)	30 no. 37	- 108(D)	142 no. 30	- 085(C)
282 no. 325-7	- 108(L)	31 no. 38	- 108(E)	143 no. 31	- 087(A)
285 no. 329	- 116(A)	31 no. 39	- 108(F)	144 no. 32	- 087(B)
285 no. 330	- 116(B)	31 no. 40	- 108(G)	145	- 104(A)
288 no. 337	- 117(A)	31 no. 41	- 108(H)		
291 no. 341	- 118(B)	32 no. 42	- 108(I)	Wagner 1985	
292 no. 342	- 118(C)	32 nos 43-4	- 108(J)		
293 no. 343	- 120(A)	33 no. 45	- 108(K)	49	- 128(A)-(C)
293 no. 344	- 120(B)	34 no. 46-8	- 108(L)		
294 no. 345	- 123(A)	35 no. 49	- 117(A)	Wilson 1958	
294 no. 346-7	- 085(C)	35 no. 50	- 116(A)		
294	- 123(G)-(N)	36 no. 51	- 116(B)	Notes 58/11	- 015
297 no. 348	- 083	36 no. 52	- 118(B)		
297 no. 349	- 085(B)	36 no. 53	- 118(C)	Wilson 1960	
		37 no. 54	- 120(A)		
Sterrett 1885		37 no. 55	- 120(B)	133 no. 1	- 056(A)
		37 no. 56	- 123(A)	134	- 060
20 no. 13	- 104(A)			135	- 062
21 no. 14	- 104(B)	Taylor 1868		137 no. 2	- 015
21 no. 15	- 104(C)				
22 no. 16	- 104(D)	294-295	- 151	Yavi 1986	
22 no. 17	- 104(E)	302	- 048		
22 no. 18	- 104(F)			163	- 56(B)
23 no. 19	- 103(A)	Thompson 1910			
23 no. 20	- 103(B)			Yorke 1898	
24	- Keklikoluk	291	- 001		
24 no. 21	- 098(A)			319 no. 33	- 155
24 no. 22	- 098(B)	Tibiletti 1971		319	- 132
25 no. 23	- 093(A)			324	- 153
25 no. 24	- 093(B)	67	- 002		
25 no. 25	- 093(C)			Yüce 1992	
27 no. 26	- 105(A)	Tibiletti 1977			
27 no. 27	- 105(C)	168	- 002	209	- 144(A)
27 no. 28	- 105(D)			210	- 144(B)
28 no. 29	- 107(A)	Townsend 1955			
28 no. 30	- 107(B)				
28 no. 31	- 107(C)	41	- 108(C)		
28 no. 32	- 107(E)				
29 no. 33	- 107(D)	Waddington 1883			

## 4.6 Indices

### 4.6.1 Imperial Milestones

<b>Vespasianus and Titus with Domitianus</b>	AD 76 (TR·P·VII·IMP·XIII·COS·VII)
004. Yurtbaşı	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
<b>Titus with Domitianus</b>	AD 81, 01.01-30.06 ([TR·P·X·IMP·XV·COS·VIII·DESIG·V]III)
066. Sakaltutan (1)	C.3 Caesaria - Melitena
<b>Domitianus</b>	(?) AD 92 ([TR·P·XI·IMP·XXI]I·COS·XVI)
005. Olgunlar (1) (rest.)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
<b>Nerva</b>	AD 96, 18.09-31.12 (TR·P·COS·II)
066. Sakaltutan (2)	C.3 Caesaria - Melitena
	(?) AD 96, 18.09-31.12 ([TR·P·COS·II])
091(C). Yalak 3 (rest.)	C.3 Caesaria - Melitena
	AD 97, 01.01-17.09 (TR·P·COS·III)
019. Amasya	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
	(?) AD 97, 01.01-17.09 (TR·P·[COS·III])
042. Çeşmeören	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
	(?) YEAR
031. Köseeyüp (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
054(F). Tokat 6 (rest.)	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
149(B). Uluköy 2	F.2 Neocaesaria ([ - Pompeiopolis] - Nicomedia)
<b>Nerva or Traianus</b>	
011. Çaltılı (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
035. Elvançelesi (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
<b>Traianus</b>	AD 98 ([TR·P]·COS·II)
041. Abdalata, Tekke	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
	AD 100 (TR·P·[III] COS·III)
003. Yavaşhan	A.9 Caesaria - Tyana - Sidamaria (- Col. Iconium)

**Hadrianus**

AD 128/129 (TR·P·XIII·IMP·XIII·COS·III)

036. Güngörmez

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

048. Akşar

A.10 Nicopolis - Sebastia (- Tavium)

060. Kervansaray

A.12 Sebastia - Sebastopolis (- Tavium)

(?)AD 128/129 (TR·P·[XIII]·IMP·XIII·[COS·III])

023(A). Bağlıca 2(1)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

(?) YEAR

005. Olgunlar (2)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

051. Yağmurlu

A.11 Neocaesaria - Zela (- Tavium - Ancyra)

**Hadrianus or Severus Alexander**

056(C). Zile 3(1)

A.11 Neocaesaria - Zela (- Tavium - Ancyra)

**Sept. Severus and Caracalla with Geta**

AD 197/198 (TR·P·VI·IMP·XI·COS·II)

032(B). Kozören 2

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

037(B). Çorum 2(1)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

050(B). Boğazbaşı 2

A.11 Neocaesaria - Zela (- Tavium)

053. Kılıçlı

A.11 Neocaesaria - Zela (- Tavium)

056(B). Zile 2(1)

A.11 Neocaesaria - Zela (- Tavium)

069. Aslanbeyli Yaylası, Hanyeri

C.3 Caesaria - Melitena

072(F). Değirmentaş, Arkaçlar Mvk. 2.6

C.3 Caesaria - Melitena

074(A). İmirzağa, Eski Harabe Mvk. 1

C.3 Caesaria - Melitena

075(A). İmirzağa, Barçın Mvk. 1

C.3 Caesaria - Melitena

085(A). Mollahüseyin 1

C.3 Caesaria - Melitena

088(B). Kemer 4

C.3 Caesaria - Melitena

088(D). Kemer 6

C.3 Caesaria - Melitena

089(A). Kemer 7(1)

C.3 Caesaria - Melitena

089(D). Kemer 10 (?)

C.3 Caesaria - Melitena

089(E). Kemer 11(1)

C.3 Caesaria - Melitena

090(B). Dayıoluk 2

C.3 Caesaria - Melitena

090(C). Dayıoluk 3

C.3 Caesaria - Melitena

098(C). Keklikoluk 6 (rest.)

C.3 Caesaria - Melitena

104(L). Göksun 18

C.3 Caesaria - Melitena

105(A). Göksun 8(2)

C.3 Caesaria - Melitena

107(B). Yağmurlu 2

C.3 Caesaria - Melitena

107(C). Yağmurlu 3

C.3 Caesaria - Melitena

107(F). Yağmurlu 6

C.3 Caesaria - Melitena

108(H). Kanlıkavak 8(1)

C.3 Caesaria - Melitena

108(I). Kanlıkavak 9(1)

C.3 Caesaria - Melitena

109(A). Yeniyapan 1

C.3 Caesaria - Melitena

109(B). Yeniyapan 2 (rest.)

C.3 Caesaria - Melitena

110. Karaömer 1

C.3 Caesaria - Melitena

118(B). Izgın,Çatburun 2

C.3 Caesaria - Melitena



120(A). Izgın 1(2)	C.3 Caesaria - Melitena
123(B). Elbistan 2 (rest.)	C.3 Caesaria - Melitena
147(D). Kapıkaya 4(1)	F.1 Caesaria - Zela - Amasia (- Amisus)
149(A). Uluköy 1	F.2 Neocaesaria ([ - Pompeiopolis] - Nicomedia)

### **Caracalla** AD 217

166. Pozantı 1	P.1 The Pilgrim's Road
----------------	------------------------

### **Macrinus with Diadumenianus** AD 217-218

108(C). Kanlıkavak 3 (rest.)	C.3 Caesaria - Melitena
159. Topakkaya	P.1 The Pilgrim's Road
161. Demirci	P.1 The Pilgrim's Road
165. Kırkgeçit Deresi	P.1 The Pilgrim's Road

### **Elagabalus** AD 218

068(B). Aslanbeyli Yaylası, Hanboğaz 2	C.3 Caesaria - Melitena
078(A). Çakırlar, Beşiktaş 1(1)	C.3 Caesaria - Melitena
080(E). Çakırlar, Meşelik 5	C.3 Caesaria - Melitena
093(F). Yalak 10	C.3 Caesaria - Melitena
094(B). Doğankonak 2	C.3 Caesaria - Melitena
097(A). Doğankonak, Şabanağa Mvk. 1	C.3 Caesaria - Melitena
104(A). Göksun 1	C.3 Caesaria - Melitena
104(D). Göksun 4(1)	C.3 Caesaria - Melitena
104(E). Göksun 5	C.3 Caesaria - Melitena
104(F). Göksun 6(1)	C.3 Caesaria - Melitena
104(G). Göksun 7(2) (rest.)	C.3 Caesaria - Melitena
104(H). Göksun 19	C.3 Caesaria - Melitena
105(E). Göksun 12	C.3 Caesaria - Melitena
107(G). Yağmurlu 7	C.3 Caesaria - Melitena
108(D). Kanlıkavak 4	C.3 Caesaria - Melitena
108(L). Kanlıkavak 12(1)	C.3 Caesaria - Melitena
109(C). Yeniyapan 3	C.3 Caesaria - Melitena
118(C). Izgın, Çatburun 3(1) (rest.)	C.3 Caesaria - Melitena
123(A). Elbistan 1	C.3 Caesaria - Melitena
129(C). Gözecik 3	C.3 Caesaria - Melitena

### AD 219 (TR·P·COS)

133(A). Porsuk 1	P.1 The Pilgrim's Road
------------------	------------------------

### **Elagabalus with Severus Alexander as Caesar** AD 221

065. Kayseri	C.2 Caesaria - Sebastia
--------------	-------------------------

### **Severus Alexander** AD 222 (TR·P·IMP·II·COS)

164(A). Eminlik 1	P.1 The Pilgrim's Road
-------------------	------------------------

## AD 222 (?)

068(A). Aslanbeyli Y., Hanboğaz 1	C.3 Caesaria - Melitena
072(E). Değirmentaş, Arkaçlar Mvk. 2.5	C.3 Caesaria - Melitena
075(H). İmirzağa, Barçın Mvk. 8	C.3 Caesaria - Melitena
076. Çakırlar, Barçın Y.	C.3 Caesaria - Melitena
087(A). Kemer 1	C.3 Caesaria - Melitena
091. Dayıoluk 5(2)	C.3 Caesaria - Melitena
104(F). Göksun 6(2)	C.3 Caesaria - Melitena
118(C). İzgin, Çatburun 3(2)	C.3 Caesaria - Melitena
119(A). Çağılhan 1	C.3 Caesaria - Melitena

## AD 231 (TR·P·X·COS·III)

168. Pozantı, Soğukpınar	P.1 The Pilgrim's Road
--------------------------	------------------------

## AD 234 (TR·P·XIII·IMP·XIII)

054(G). Tokat Museum 1	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
------------------------	---

## (?) AD 234-235

079(B). Çakırlar, Barçın Gç. 2(1)	C.3 Caesaria - Melitena
083. Şar 2(1)	C.3 Caesaria - Melitena
085(B). Mollahüseyin 2(1)	C.3 Caesaria - Melitena

## (?) Year

056(A). Zile 1	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
062. Dutluca	A.15 Sebastia - Sebastopolis (- Tavium)
114. Ördek (2) (rest.)	C.3 Caesaria - Melitena
162(C). Kemerhisar, Salmanlı Çift. 3	P.1 The Pilgrim's Road
163(B). Kavuklu 2 (rest.)	P.1 The Pilgrim's Road
164(B). Eminlik 2	P.1 The Pilgrim's Road

**Severus Alexander or Hadrianus**

056(C). Zile 3(1)	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
-------------------	---

**Maximinus**

## (?) AD 235

043. Hamdi	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
052(A). Gözova 1	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
079(B). Çakırlar, Barçın Gç. 2(2)	C.3 Caesaria - Melitena
079(E). Çakırlar, Barçın Gç. 5	C.3 Caesaria - Melitena
083. Şar 2(2)	C.3 Caesaria - Melitena
085(B). Mollahüseyin 2(2)	C.3 Caesaria - Melitena
086(A). Kemer 13	C.3 Caesaria - Melitena
097(B). Doğankonak, Şabanağa Mvk. 2	C.3 Caesaria - Melitena

098(B). Keklikoluk 2	C.3 Caesaria - Melitena
100(A). Keklikoluk 4	C.3 Caesaria - Melitena
107(D). Yağmurlu 4	C.3 Caesaria - Melitena
108(R). Kanlıkavak 18(2) (no text)	C.3 Caesaria - Melitena
113(A). Karaömer, Kızılcaşu Mah. 1	C.3 Caesaria - Melitena
118(A). Izgın, Çatburun 1	C.3 Caesaria - Melitena
118(D). Izgın, Çatburun 4	C.3 Caesaria - Melitena
126. Sevdilli, Büyükköy Mz.	C.3 Caesaria - Melitena
127. Sevdilli, Gülpınar Mz. (2)	C.3 Caesaria - Melitena
128(B). Yaztopallı 2(2)	C.3 Caesaria - Melitena
129(A). Gözecik 1 (rest.)	C.3 Caesaria - Melitena
145(B). Uygur 2(1)	F.1 Caesaria - Zela - Amasia (- Amisus)

**Maximinus with Maximus**

(?) Year

002. Çalış	A.2 Caesaria (- Ancyra)
029(A). Boğazkaya 1	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
029(C). Boğazkaya 3(1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
085(D). Mollahüseyin 5	C.3 Caesaria - Melitena
094(A). Doğankonak 1 (rest.)	C.3 Caesaria - Melitena
104(C). Göksun 3(1)	C.3 Caesaria - Melitena

**Pupienus and Balbinus** (erased) with **Gordianus** as *Caesar*

AD 238

087(B). Kemer 2	C.3 Caesaria - Melitena
093(H). Yalak 12	C.3 Caesaria - Melitena
104(B). Göksun 2(1)	C.3 Caesaria - Melitena

**Gordianus III Augustus**

AD 238

068(C). Aslanbeyli Yaylası, Hanboğaz 3	C.3 Caesaria - Melitena
072(C). Değirmentaş, Arkaçlar Mvk. 2.3	C.3 Caesaria - Melitena
074(C). İmirzağa, Eski Harabe Mvk. 3	C.3 Caesaria - Melitena
075(C). İmirzağa, Barçın Mvk. 3	C.3 Caesaria - Melitena
079(D). Çakırlar, Barçın Gç. 4(1)	C.3 Caesaria - Melitena
080(B). Çakırlar, Meşelik 2	C.3 Caesaria - Melitena
084. Mollahüseyin 4	C.3 Caesaria - Melitena
089(B). Kemer 8	C.3 Caesaria - Melitena
092(A). Yalak 5 (rest.)	C.3 Caesaria - Melitena
095. Doğankonak, Kumocağı (1)	C.3 Caesaria - Melitena
097(C). Doğankonak, Şabanağa Mvk. 3	C.3 Caesaria - Melitena
098(D). Keklikoluk 7	C.3 Caesaria - Melitena
105(D). Göksun 11(1)	C.3 Caesaria - Melitena
108(F). Kanlıkavak 6	C.3 Caesaria - Melitena
108(M). Kanlıkavak 13	C.3 Caesaria - Melitena
108(O). Kanlıkavak 15 (rest.)	C.3 Caesaria - Melitena
109(E). Yeniyan 5 (rest.)	C.3 Caesaria - Melitena

**Gordianus III**

(?) Year

023(B). Bağlıca 2	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
038. Saray (2) (rest.)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
044. Sapa	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
048(A). Boğazbaşı 1	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
120(B). İzgin 2	C.3 Caesaria - Melitena
133(B). Porsuk 2 (rest.)	C.14 Tyana - Pylae
133(C). Porsuk 3	C.13 Cybistra - Pylae
162(A). Kemerhisar, Salmanlı Çiftlik 1 (1)	P.1 The Pilgrim's Road
163(A). Kavuklu 1	P.1 The Pilgrim's Road

### Gordianus III and Tranquillina

61. Sulusaray	A.12 Sebastia - Sebastopolis (- Tavium)
---------------	---

### Philippus

(?) Year

102(D). Mürsel 4	C.3 Caesaria - Melitena
108(R). Kanlıkavak 18(3)	C.3 Caesaria - Melitena

### Philippus with Philippus

(?) Year

032(A). Kozören 1	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
034(B). Mecitözü 2	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
068(D). Aslanbeyli Yaylası, Hanboğaz 4	C.3 Caesaria - Melitena
075(B). İmirzağa, Barçın Mvk. 2	C.3 Caesaria - Melitena
078(B). Çakırlar, Beşiktaş 2(1)	C.3 Caesaria - Melitena
080(A). Çakırlar, Meşelik 1 (rest.)	C.3 Caesaria - Melitena
085(C). Mollahüseyin 3(1) (rest.)	C.3 Caesaria - Melitena
088(A). Kemer 3	C.3 Caesaria - Melitena
089(C). Kemer 9	C.3 Caesaria - Melitena
093(A). Yalak 1	C.3 Caesaria - Melitena
093(D). Yalak 4(1)	C.3 Caesaria - Melitena
093(E). Yalak 9 (rest.)	C.3 Caesaria - Melitena
093(G). Yalak 11	C.3 Caesaria - Melitena
094(C). Doğankonak 3 (rest.)	C.3 Caesaria - Melitena
098(A). Keklikoluk 1	C.3 Caesaria - Melitena
103(A). Mehmetbey 1(1)	C.3 Caesaria - Melitena
103(B). Mehmetbey 2(1)	C.3 Caesaria - Melitena
106(A). Göksun 15	C.3 Caesaria - Melitena
107(A). Yağmurlu 1 (rest.)	C.3 Caesaria - Melitena
108(A). Kanlıkavak 1	C.3 Caesaria - Melitena
108(G). Kanlıkavak 7(2)	C.3 Caesaria - Melitena
108(J). Kanlıkavak 10(1)	C.3 Caesaria - Melitena
108(R). Kanlıkavak 18 (no text)	C.3 Caesaria - Melitena
109(D). Yeniyan 4 (rest.)	C.3 Caesaria - Melitena
119(B). Çağılhan 2	C.3 Caesaria - Melitena
123(C). Elbistan 3 (rest.)	C.3 Caesaria - Melitena

### Philippus and Philippus and Severina

(?) Year

138. Çamsaray	F.1 Caesaria - Zela - Amasia (- Amisus)
<b>Traianus Decius</b>	(?) Year
001. Sarılar	A.2 Caesaria (- Ancyra)
020. Bulduklu	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
037(A). Çorum 1	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
128(A). Yaztopallı 1(2)	C.3 Caesaria - Melitena
<b>Traianus Decius and Herennius Etruscus with Hostilianus Caesar</b>	AD 251
072(G). Değirmentaş, Arkaçlar 2.7	C.3 Caesaria - Melitena
089(E). Kemer 11(2)	C.3 Caesaria - Melitena
<b>Trebonianus Gallus with Volusianus Caesar</b>	AD 251
141. Yıldıztepe (1)	F.1 Caesaria - Zela - Amasia (- Amisus)
<b>Trebonianus Gallus and Volusianus</b>	(?) Year
032(C). Kozören 3	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
038. Tolahmet	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
098(B). Keklikoluk 5	C.3 Caesaria - Melitena
108(L). Kanlıkavak 12(2)	C.3 Caesaria - Melitena
108(P). Kanlıkavak 16 (rest.)	C.3 Caesaria - Melitena
108(Q). Kanlıkavak 17 (rest.)	C.3 Caesaria - Melitena
<b>Aurelianus</b>	AD 271
147(C). Kapıkaya 3	F.1 Caesaria - Zela - Amasia (- Amisus)
<b>Tacitus</b>	AD 275-276
147(B). Kapıkaya 2	F.1 Caesaria - Zela - Amasia (- Amisus)
<b>Probus</b>	AD 279 (TR·P·III)
037(C). Çorum Museum	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
054(H). Tokat Museum 2	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
	(?) YEAR
115. Alımpınar	C.3 Caesaria - Melitena
139. Özükevavak (2) (rest.)	F.1 Caesaria - Zela - Amasia (- Amisus)
<b>Carus with Carinus</b>	AD 282
055(B). Turhal 2 (rest.)	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
147(A). Kapıkaya 1 (no text)	F.1 Caesaria - Zela - Amasia (- Amisus)

**Carus with Carinus and Numerianus**

AD 282

016. Yerkozlu (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
025. Toklucak (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
033(B). Çitli 2(1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)

**Carus and (?)**

(?) YEAR

029(A). Figani 1	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
------------------	--

**Diocletianus and Maximianus with Constantius and Galerius**

(?) Year

009. Hatipli (1) (rest.)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
012. Akça (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
013. Çalkara (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
015. Çakırsu (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
016. Yerkozlu (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
018. Çiğdemlik (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
021. Aydoğdu (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
022. Boğa (rest.)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
023(A). Bağlıca 1(2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
029(B). Boğazkaya 2(1a,b)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
029(D). Boğazkaya 4(1) (rest.)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
033(A). Çitli 1(1) (rest.)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
033(B). Çitli 2(2) (rest.)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
035. Elvançelebi (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
037(B). Çorum 2(2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
047. Deniz	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
052(B). Gözova 2(1) (?)	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
054(A). Tokat 1	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
054(B). Tokat 2	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
056(B). Zile 2(2)	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
056(C). Zile 3(2)	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
056(D). Zile 4(1)	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
107(E). Yağmurlu 5	C.3 Caesaria - Melitena
108(H). Kanlıkavak 8(2)	C.3 Caesaria - Melitena
108(I). Kanlıkavak 9(2)	C.3 Caesaria - Melitena
108(J). Kanlıkavak 10(2)	C.3 Caesaria - Melitena
108(K). Kanlıkavak 11	C.3 Caesaria - Melitena
108(L). Kanlıkavak 12(3)	C.3 Caesaria - Melitena
108(R). Kanlıkavak 18(4) (no text)	C.3 Caesaria - Melitena
123(D). Elbistan 4(2)	C.3 Caesaria - Melitena
137. Kadişehri (2)	F.1 Caesaria - Zela - Amasia (- Amisus)
140(A). Güzelbeyli 1	F.1 Caesaria - Zela - Amasia (- Amisus)
141. Yıldıztepe (2)	F.1 Caesaria - Zela - Amasia (- Amisus)
143. Akyazı	F.1 Caesaria - Zela - Amasia (- Amisus)
144. Mahmatlar	F.1 Caesaria - Zela - Amasia (- Amisus)
145(B). Uygur 2(2)	F.1 Caesaria - Zela - Amasia (- Amisus)
147(D). Kapıkaya 4(3)	F.1 Caesaria - Zela - Amasia (- Amisus)
148. Suluova	F.1 Caesaria - Zela - Amasia (- Amisus)

150(B). Ilıca 2  
156. Bahçebaşı  
160. Aksaray (1)

F.2 Neocaesaria (- Neoclaudiopolis - Pompeiopolis)  
L.1 (Trapezus) - Satala - Melitena (- Samosata)  
P.1 The Pilgrim's Road

### **Diocletianus *et coll.*: Truncated Texts**

078(A). Çakırlar, Beşiktaş 1(2)	C.3 Caesaria - Melitena	Diocletianus
078(B). Çakırlar, Beşiktaş 2(2)	C.3 Caesaria - Melitena	Galerius
079(D). Çakırlar, Barçın Gç. 4(2)	C.3 Caesaria - Melitena	Maximianus
085(C). Mollahüseyin 3(2)	C.3 Caesaria - Melitena	Galerius
089(A). Kemer 7(2)	C.3 Caesaria - Melitena	Constantius
089(D). Kemer 10(2)	C.3 Caesaria - Melitena	Diocletianus
093(D). Yalak 4(2)	C.3 Caesaria - Melitena	Galerius
093(H). Yalak 12(2)	C.3 Caesaria - Melitena	Maximianus
095. Doğankonak, Kumocağı (2)	C.3 Caesaria - Melitena	Maximianus
096. Doğankonak, Sakaltutan Boğazı	C.3 Caesaria - Melitena	Galerius
103(A). Mehmetbey 1(2)	C.3 Caesaria - Melitena	Diocl. & Maximianus
103(B). Mehmetbey 2(2)	C.3 Caesaria - Melitena	Constantius
104(B). Göksun 2(2)	C.3 Caesaria - Melitena	Galerius
104(C). Göksun 3(2)	C.3 Caesaria - Melitena	Diocletianus
104(D). Göksun 4(2)	C.3 Caesaria - Melitena	Galerius
105(C). Göksun 10	C.3 Caesaria - Melitena	Galerius
105(D). Göksun 11(2)	C.3 Caesaria - Melitena	Maximianus
128(B). Yaztopallı 2(4)	C.3 Caesaria - Melitena	Const. & Galerius
129(A). Gözecik 1(2)	C.3 Caesaria - Melitena	Diocletianus

### **Constantius and Galerius with Severus and Maximinus** AD 305-306

017(A). Aş. Baraklı 1(1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
029(D). Boğazkaya 4(2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
146. Ezinepazar	F.1 Caesaria - Zela - Amasia (- Amisus)

### **Galerius and Severus with Maximinus and Constantinus** AD 306-307

023(A). Bağlıca 1(3)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
026. Karayakup	A.9 Satala - Neocaesaria - Amasia (- Ancyra)

### **Galerius and Licinius with Maximinus and Constantinus, filii Augg** (?) Year

029(C). Boğazkaya 3(2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
------------------------	--

### **Constantinus and Licinius** (?) Year

064. Elmalı (1)	A.12 Sebastia - Sebastopolis (- Tavium)
145(A). Uygur 1(2)	F.1 Caesaria - Zela - Amasia (- Amisus)
150(A). Ilıca 1(2)	F.2 Neocaesaria ([- Pompeiopolis] - Nicomedia)

### **Constantinus and Licinius with Crispus, Licinius and Constantinus** AD 317

015. Çakırsu (2) (rest.)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
--------------------------	--

056(D) Zile 4(2) (rest.)	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
158. Değirmenyolu (2)	P.1 The Pilgrim's Road
160. Aksaray (2)	P.1 The Pilgrim's Road
167. Pozantı 2(2)	P.1 The Pilgrim's Road

**Constantinus with Crispus, Constantinus and Constantius** AD 324-326

162(A). Kemerhisar, Salmanlı Çiftlik 1(3)	P.1 The Pilgrim's Road
---	------------------------

**Constantinus with Constantinus, Constantius and Constans** (?) Year

010. Niksar	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
025. Toklucak (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
029(B). Boğazkaya 2(2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
031. Köseeyüp (3)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
033(A). Çitli 1(2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
033(B). Çitli 2(3)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
052(B). Gözova 2(2)	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
057. Kurupınar	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
141. Yıldıztepe (3)	F.1 Caesaria - Zela - Amasia (- Amisus)
142. Alayurt (2)	F.1 Caesaria - Zela - Amasia (- Amisus)
147(D). Kapıkaya 4(4)	F.1 Caesaria - Zela - Amasia (- Amisus)
158. Değirmenyolu (2)	P.1 The Pilgrim's Road
162(B). Kemerhisar, Salmanlı Çift. 2	P.1 The Pilgrim's Road

**Constantinus with Constantinus, Constantius, Constans and Delmatius** AD 335-337

009. Hatipli (2) (rest.)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
012. Akça (3) (rest.)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
013. Çalkara (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
014. Karaağaç	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
015. Çakırsu (3)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
017(A). Aş. Baraklı 1(2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)

**(?) Constantinian**

007. Sevindik	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
064. Elmalı (2)	A.12 Sebastia - Sebastopolis (- Tavium)

**(?) Constantius and Constans** AD 340-350

155. Eskimalatya	L.1 Trapezus - Satala - Melitena (- Samosata)
------------------	---

**Iulianus**

150(A). Ilıca 1(3)	F.2 Neocaesaria ([- Pompeiopolis] - Nicomedia)
--------------------	--

**Valentinianus I and Valens** AD 364-367

150(A). Ilıca 1(4)	F.2 Neocaesaria ([- Pompeiopolis] - Nicomedia)
--------------------	--



**Valentinianus I, Valens and Gratianus**

AD 367-375

006. Gölova  
015. Çakırsu (6)  
021. Aydoğdu (3)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)  
A.9 Satala - Neocaesaria - Amasia (- Ancyra)  
A.9 Satala - Neocaesaria - Amasia (- Ancyra)

**Honorius**

AD 408-423

015. Çakırsu (7)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

**4.6.2 Illegible, incomplete, non-restorable**

007. Sevindik	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
008. Küçük Güzel	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
024. Doğanstepe	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
029(D). Boğazkaya 4(1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
030(B)(C). Figani 2-3	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
034(A). Mecitözü 1	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
039. Karapınar	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
045. Seyfe	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
046. Ertuğrul	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
052(B). Gözova 2(3)	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
067(A). Özlüce 1	C.3 Caesaria - Melitena
068(E). Aslanbeyli Yaylası, Hanboğaz 5(2)	C.3 Caesaria - Melitena
070(A)(C). Değirmentaş 1, 3	C.3 Caesaria - Melitena
072(B). Değirmentaş, Arkaçlar Mvk. 2.2(3)	C.3 Caesaria - Melitena
074(B). İmirzağa, Eski Harabe Mvk. 2	C.3 Caesaria - Melitena
075(D)(F). İmirzağa, Barçın Mvk. 4, 6	C.3 Caesaria - Melitena
079(A). Çakırlar, Barçın Geçidi 1	C.3 Caesaria - Melitena
080(C)(D). Çakırlar, Meşelik 4	C.3 Caesaria - Melitena
088(C). Kemer 5	C.3 Caesaria - Melitena
089(F). Kemer 12	C.3 Caesaria - Melitena
090(A). Dayıoluk 1	C.3 Caesaria - Melitena
093(B). Yalak 2	C.3 Caesaria - Melitena
096. Doğankonak, Sakaltutan Boğazı (1)	C.3 Caesaria - Melitena
097(D). Doğankonak, Şabanağa Mvk. 4(1),(2)	C.3 Caesaria - Melitena
102(D)-(F). Mürsel 4-6	C.3 Caesaria - Melitena
104(G)(I)(J)(K). Göksun 7,13,14,17	C.3 Caesaria - Melitena
105(A). Göksun 8(1)	C.3 Caesaria - Melitena
106(B). Göksun 16	C.3 Caesaria - Melitena
108(B)(E)(G)(N)(R)(S). Kanlıkavak 2,5,7(1),14,18,19	C.3 Caesaria - Melitena
109(F). Yeniyapan 6	C.3 Caesaria - Melitena
111(A). Karaömer 2	C.3 Caesaria - Melitena
112. Düğünyardu	C.3 Caesaria - Melitena
116(A)-(C). Afşin 1-3	C.3 Caesaria - Melitena
117(A)(B). Emirli 1-2	C.3 Caesaria - Melitena
123(D)(E)(F). Elbistan 4(1),5,6	C.3 Caesaria - Melitena
127. Sevdilli, Gülpınar Mz. (1)	C.3 Caesaria - Melitena
128(A)-(C). Yaztopallı 1(1),2(1),3	C.3 Caesaria - Melitena
129(A). Gözecik 1(1)	C.3 Caesaria - Melitena
131. Şekerpınar	C.4 Sebastia - Melitena
132. Fethiye	C.4 Sebastia - Melitena
133(B). Porsuk 2	C.14 Tyana - Pylae
137. Kadışehri (1)	F.1 Caesaria - Zela - Amasia (- Amisus)
139. Özükevank (1)	F.1 Caesaria - Zela - Amasia (- Amisus)
142. Alayurt (1)	F.1 Caesaria - Zela - Amasia (- Amisus)
145(A). Uygur 1(1)	F.1 Caesaria - Zela - Amasia (- Amisus)
147(D). Kapıkaya 4(2)	F.1 Caesaria - Zela - Amasia (- Amisus)
150(A). Ilıca 1(1)	F.2 Neocaesaria ([ - Pompeiopolis] - Nicomedia)
151. Şebinkarahisar	F.5 Nicopolis - Colonia (- Cerasus)

153. Sadak	L.1 (Trapezus) - Satala - Melitena (- Samosata)
157. Gülhüyük	P.1 The Pilgrim's Road
158. Değirmenyolu (1)	P.1 The Pilgrim's Road
162(A). Kemerhisar, Salmanlı Çiftlik 1(2)	P.1 The Pilgrim's Road
163(C). Kavuklu 3	P.1 The Pilgrim's Road
167. Pozantı 2(1)	P.1 The Pilgrim's Road

#### 4.6.3 No legible or visible Inscription

011. Çaltılı (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
012. Akça (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
015. Çakırsu (4),(5)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
018. Çiğdemlik (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
021. Aydoğdu (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
027. Çavuş	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
028. Beke	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
031. Köseeyüp (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
040. Saray (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
047. Deniz (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
048. Akşar (1)	A.10 Nicopolis - Sebastia (- Tavium)
049(A)-(C). Aş. Ekecik 1-3	A.10 Nicopolis - Sebastia (- Tavium)
054(C)-(E). Tokat 3-5	A.11 Neocaesaria - Zela (- Tavium)
055(A). Turhal 1	A.11 Neocaesaria - Zela (- Tavium)
057. Kurupınar (1)	A.11 Neocaesaria - Zela (- Tavium)
058. Kargın	A.12 Sebastia - Sebastopolis (- Tavium)
059. Çamlıbel	A.12 Sebastia - Sebastopolis (- Tavium)
063. Uylubağ	A.12 Sebastia - Sebastopolis (- Tavium)
067(B)-(D). Özlüce 2-4	C.3 Caesaria - Melitena
068(C). Aslanbeyli Yaylası, Hanboğaz 5(1)	C.3 Caesaria - Melitena
070(B)(D). Değirmentaş 2,4	C.3 Caesaria - Melitena
071(A)(B). Değirmentaş, Arkaçlar Mvk. 1.1-2	C.3 Caesaria - Melitena
072(A)(D). Değirmentaş, Arkaçlar Mvk. 2.1,4	C.3 Caesaria - Melitena
073. İmirzaga	C.3 Caesaria - Melitena
074(D). İmirzağa, Eski Harabe Mvk. 4	C.3 Caesaria - Melitena
075(E)(G)(I). İmirzağa, Barçın Mvk. 5,7,9	C.3 Caesaria - Melitena
077(A)-(C). Çakırlar, Karapınar 1-3	C.3 Caesaria - Melitena
078(C). Çakırlar, Beşiktaş 3	C.3 Caesaria - Melitena
079(C)(F)(G). Çakırlar, Barçın Gç.. 3,6,7	C.3 Caesaria - Melitena
080(C). Çakırlar, Meşelik 3	C.3 Caesaria - Melitena
082. Şar 1	C.3 Caesaria - Melitena
085(E). Mollahüseyin 6	C.3 Caesaria - Melitena
086(B). Kemer 14	C.3 Caesaria - Melitena
090(B). Dayıoluk 2(2)	C.3 Caesaria - Melitena
090(D). Dayıoluk 4	C.3 Caesaria - Melitena
090(D). Dayıoluk 5(1)	C.3 Caesaria - Melitena
092(B)-(D). Yalak 6-8	C.3 Caesaria - Melitena
094(D). Doğankonak 4	C.3 Caesaria - Melitena
097(E)(F). Doğankonak, Şabanağa Mvk. 5,6	C.3 Caesaria - Melitena
099. Keklikoluk 3	C.3 Caesaria - Melitena

101(A)-(E). Keklikoluk, Kayapınar Mvk. 1-5	C.3 Caesaria - Melitena
– Keklikoluk	C.3 Caesaria - Melitena
102(A)-(C). Mürsel 1-3	C.3 Caesaria - Melitena
105(B). Göksun 9	C.3 Caesaria - Melitena
– Kanlıkavak	C.3 Caesaria - Melitena
– Yeniyapan	C.3 Caesaria - Melitena
111(B). Karaömer 3	C.3 Caesaria - Melitena
113(B)(C). Karaömer, Kızılcasuyu Mah. 2-3	C.3 Caesaria - Melitena
114. Ördek (1)	C.3 Caesaria - Melitena
115. Alımpınar (1)	C.3 Caesaria - Melitena
118(B). İzgın, Çatburun 2(1)	C.3 Caesaria - Melitena
120(A). İzgın 1(1)	C.3 Caesaria - Melitena
121. Yapraklı	C.3 Caesaria - Melitena
122. Hasankendi	C.3 Caesaria - Melitena
123(G)-(N). Elbistan 7-14	C.3 Caesaria - Melitena
– Elbistan	C.3 Caesaria - Melitena
124(A)(B). Demircilik 1-2	C.3 Caesaria - Melitena
125(A)(B). Gücük 1-2	C.3 Caesaria - Melitena
128(B). Yaztopallı 2(3)	C.3 Caesaria - Melitena
129(B). Gözecik 2	C.3 Caesaria - Melitena
130. Darıca	C.3 Caesaria - Melitena
134. Akbenliçiftlik	F.1 Caesaria - Zela - Amasia (- Amisus)
135. İzibüyük	F.1 Caesaria - Zela - Amasia (- Amisus)
136. Kabalı	F.1 Caesaria - Zela - Amasia (- Amisus)
140(B). Güzelbeyli 2	F.1 Caesaria - Zela - Amasia (- Amisus)
149(C). Uluköy 3	F.2 Neocaesaria ([ - Pompeiopolis] - Nicomedia)
152. Elmelik	L.1 (Trapezus) - Satala - Melitena (- Samosata)
154. Tütenli	L.1 (Trapezus) - Satala - Melitena (- Samosata)

#### 4.6.4 Ancient Geography

##### Amasia

023(A). Bağlıca 1(1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
036. Güngörmez	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
037(C). Çorum Museum	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
040. Saray (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
044. Sapa	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
046. Ertuğrul	A.9 Satala - Neocaesaria - Amasia (- Ancyra)

##### Cappadocia

163(C). Kavuklu 3	P.1 The Pilgrim's Road
164(A). Eminlik 1	P.1 The Pilgrim's Road

##### Colonia (Archelaïs)

159. Topakkaya	P.1 The Pilgrim's Road
160. Aksaray (1)	P.1 The Pilgrim's Road

##### Comana

054(H). Tokat Museum 2	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
------------------------	---

##### Diospontus

029(C). Boğazkaya 3(2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
------------------------	--

##### Faustiniana Colonia

133(B). Porsuk 2	P.1 The Pilgrim's Road
------------------	------------------------

##### Fines Galatorum

023(A). Bağlıca 1(1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
036. Güngörmez	A.9 Satala - Neocaesaria - Amasia (- Ancyra)

##### Helenopontus

025. Toklucak	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
029(B). Boğazkaya 2(2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
031. Köseeyüp (3)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
033(B). Çitli 2(3)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
057. Kurupınar	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
142. Alayurt (2)	F.1 Caesaria - Zela - Amasia (- Amisus)

##### Neocaesaria

010. Hatipli (rest.)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
----------------------	--

**Nicopolis**

048. Akşar (2)

A.10 Nicopolis - Sebastia (- Tavium)

**Paflagonia**

146. Ezinepazar

F.1 Caesaria - Zela - Amasia (- Amisus)

**Podandus**

166. Pozantı 2(2)

P.1 The Pilgrim's Road

**Pontus**

012. Akça

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

013. Çalkara(1)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

015. Çakırsu

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

016. Yerkozlu

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

018. Çiğdemlik (2)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

022. Boğa

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

029(A). Boğazkaya 1

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

029(B). Boğazkaya 2(1a)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

033(A). Çitli 1(1)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

033(B). Çitli 2(2)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

035. Elvançelebi (2)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

037(C). Çorum Museum

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

056(B). Zile 2(2)

A.11 Neocaesaria - Zela (- Tavium - Ancyra)

056(D). Zile 4(1)

A.11 Neocaesaria - Zela (- Tavium - Ancyra)

138. Camsaray

F.1 Caesaria - Zela - Amasia (- Amisus)

140(A). Güzelbeyli 1

F.1 Caesaria - Zela - Amasia (- Amisus)

143. Akyazı

F.1 Caesaria - Zela - Amasia (- Amisus)

145(B). Uygur 2(2)

F.1 Caesaria - Zela - Amasia (- Amisus)

146. Ezinepazar

F.1 Caesaria - Zela - Amasia (- Amisus)

150(B). Ilıca 2

F.2 Neocaesaria ([ - Pompeiopolis] - Nicomedia)

**Pylae**

133(A). Porsuk 1

C.13 Cybistra - Pylae

165. Kırkgeçit Deresi

P.1 The Pilgrim's Road

166. Pozantı 1

P.1 The Pilgrim's Road

168. Pozantı, Soğukpınar

P.1 The Pilgrim's Road

**Sebastopolis**

054(G). Tokat Museum 1

A.11 Neocaesaria - Zela (- Tavium - Ancyra)

060. Kervansaray (rest.)

A.12 Sebastia - Sebastopolis (- Tavium)

061. Sulusaray

A.12 Sebastia - Sebastopolis (- Tavium)

062. Dutluca

A.12 Sebastia - Sebastopolis (- Tavium)

139. Özükev

F.1 Caesaria - Zela - Amasia (- Amisus)

**Tyana**

133(B). Porsuk 2

C.14 Tyana – Pylae

**Via Tauri**

165. Kırkgeçit Deresi

P.1 The Pilgrim's Road

166. Pozantı 1

P.1 The Pilgrim's Road

**Zela**

056(A). Zile 1

A.11 Neocaesaria - Zela (- Tavium - Ancyra)

056(B). Zile 2 (1),(2)

A.11 Neocaesaria - Zela (- Tavium - Ancyra)

056(C). Zile 3 (2)

A.11 Neocaesaria - Zela (- Tavium - Ancyra)

056(D) Zile 4 (1)

A.11 Neocaesaria - Zela (- Tavium - Ancyra)

**4.6.5 Roman Officials****Aelius Quintianus**

Probus

AD 279

037(C). Çorum Museum

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

054(H). Tokat Museum 2 (rest.)

A.11 Neocaesaria- Zela (- Tavium - Ancyra)

**Aelius Vibianus**

Maximinus with Maximus

029(A),(C). Boğazkaya 1, 3

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

**Antonius Memmius Hiero**

Philippus with Philippus

068(D). Aslanbeyli Yaylası, Hanboğaz 4

C.3 Caesaria - Melitena

075(B). İmirzağa, Barçın Mvk. 2

C.3 Caesaria - Melitena

078(B). Çakırlar, Beşiktaş 2(1)

C.3 Caesaria - Melitena

080(A). Çakırlar, Meşelik 1

C.3 Caesaria - Melitena

085(C). Mollahüseyin 3(1)

C.3 Caesaria - Melitena

088(A). Kemer 3

C.3 Caesaria - Melitena

089(C). Kemer 9

C.3 Caesaria - Melitena

093(A),(E),(G). Yalak 1, 9, 11 (rest.)

C.3 Caesaria - Melitena

094(C). Doğankonak 3

C.3 Caesaria - Melitena

098(A). Keklioluk 1

C.3 Caesaria - Melitena

103(A),(B). Mehmetbey 1(1), 2(1)

C.3 Caesaria - Melitena

106(A). Göksun 15

C.3 Caesaria - Melitena

107(A). Yağmurlu 1

C.3 Caesaria - Melitena

108(A),(J). Kanlıkavak 1, 10(1)

C.3 Caesaria - Melitena

109(D). Yeniyapan 4

C.3 Caesaria - Melitena

119(B). Çağılhan 2

C.3 Caesaria - Melitena

123(C). Elbistan 3

C.3 Caesaria - Melitena

**Aradius Paternus**

Severus Alexander

AD 231

167. Pozantı, Soğukpınar	P.1 The Pilgrim's Road	
<b>Asinius Lepidus</b>	Severus Alexander	AD 222
164(A). Eminlik 1	P.1 The Pilgrim's Road	
<b>Aurelius Basileus</b>	Elagabalus with Severus Alexander	AD 221
065. Kayseri	C.2 Caesaria - Sebastia	
<b>Aurelius Hierax</b>	Constantius and Galerius with Severus and Maximinus	
146. Ezinepazar	F.1 Caesaria - Zela - Amasia (- Amisus)	
<b>Aurelius Priscianus</b>	Diocletianus and Maximianus with Constantius and Galerius	
012. Akça (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)	
013. Çalkara (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)	
015. Çakırsu (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)	
018. Çiğdemlik (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)	
022. Boğa	A.9 Satala - Neocaesaria - Amasia (- Ancyra)	
029(B). Boğazkaya 2(1a,b)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)	
033(A),(B). Çitli 1(1), 2(2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)	
035. Elvançelebi (2)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)	
054(A). Tokat 1	A.11 Neocaesaria- Zela (- Tavium - Ancyra)	
056(B),(C),(D). Zile 2(2), 3(2), 4(1)	A.11 Neocaesaria- Zela (- Tavium - Ancyra)	
140(A). Güzelbeyli 1	F.1 Caesaria - Zela - Amasia (- Amisus)	
141. Yıldıztepe (2)	F.1 Caesaria - Zela - Amasia (- Amisus)	
143. Akyazı	F.1 Caesaria - Zela - Amasia (- Amisus)	
145(B). Uygur 2(2)	F.1 Caesaria - Zela - Amasia (- Amisus)	
147(D). Kapıkaya 4(3)	F.1 Caesaria - Zela - Amasia (- Amisus)	
150(B). Ilıca 2	F.2 Neocaesaria ([ - Pompeiopolis] - Nicomedia)	
<b>Aurelius Valentinianus</b>	Diocletianus and Maximianus with Constantius and Galerius	
029(D). Boğazkaya 4(1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)	
<b>Caesennius Gallus, A.</b>	Titus with Domitianus	AD 81
066. Sakaltutan (1) (rest.)	C.2 Caesaria - Melitena	
<b>Catius Clement</b> [ - ]	(?)Macrinus with Diadumenianus	(?) AD 217
108(C). Kanlıkavak 3	C.3 Caesaria - Melitena	
<b>Claudianus</b> or <b>Cl(audius) Audianus</b>	Maximinus	AD 235



043. Hamdi 145(B). Uygur 2(1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra) F.1 Caesaria - Zela - Amasia (- Amisus)
<b>Cl. Aurelius Tiberius</b>	Philippus and Philippus II and Otacilia Severa
138. Çamsaray	F.1 Caesaria - Zela - Amasia (- Amisus)
<b>Cl. Longinus</b>	(?) Probus (?) date
139. Özükev	F.1 Caesaria - Zela - Amasia (- Amisus)
	Carus with Carinus AD 282
055(B). Turhal 2 (rest.)	A.11 Neocaesaria - Zela (- Tavium - Ancyra)
	Carus with Carinus and Numerianus AD 282
016. Yerkozlu (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra))
025. Toklucak (1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
033(B). Çitli 2(1)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)
<b>Cl. Marcel(l)us</b>	Gordianus and Tranquillina
061. Sulusaray	A.12 Sebastia - Sebastopolis (- Tavium)
<b>Clodius Saturninus</b>	(?) (?) date
133(B). Porsuk 2	C.14 Tyana - Pylae
<b>Cuspidius Flaminius Severus</b>	Pupienus & Balbinus (erased), Gordianus <i>Caesar</i> AD 238
087(B). Kemer 2	C.3 Caesaria - Melitena
093(H). Yalak 12	C.3 Caesaria - Melitena
104(B). Göksun 2	C.3 Caesaria - Melitena
	Gordianus III AD 238
068(C). Aslanbeyli Yaylası, Hanboğaz 3	C.3 Caesaria - Melitena
072(C). Değirmentaş, Arkaçlar Mvk.2.3	C.3 Caesaria - Melitena
074(C). İmirzağa, Eski Harabe Mvk. 3	C.3 Caesaria - Melitena
075(C). İmirzağa, Barçin Mvk. 3	C.3 Caesaria - Melitena
079(D). Çakırlar, Barçin Gç. 4	C.3 Caesaria - Melitena
080(B) Çakırlar, Meşelik 2	C.3 Caesaria - Melitena
084. Mollahüseyin 4	C.3 Caesaria - Melitena
089(B). Kemer 8	C.3 Caesaria - Melitena
092(A). Yalak 5 (rest.)	C.3 Caesaria - Melitena
095. Doğankonak, Kumocağı	C.3 Caesaria - Melitena
097(C). Doğankonak, Şabanağa Mvk. 3	C.3 Caesaria - Melitena
098(D). Keklikoluk 7	C.3 Caesaria - Melitena
105(D). Göksun 11(1)	C.3 Caesaria - Melitena

108(F),(M),(N). Kanlıkavak 6, 13, 15  
109(E). Yeniyapan 5 (rest.)

C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena

Gordianus III

AD 238

120(B). Izgın 2  
133(C). Porsuk 3

C.3 Caesaria - Melitena  
C.13 Cybistra - Pylae

### Fl. Iulius Leontius

Constantinus with Constantinus, Constantius and Constans

025. Toklucak (2)  
029(B). Boğazkaya 2(2)  
031. Köseeyüp (3)  
033(A). Çitli 1(2), 2(3)  
057. Kurupınar  
142. Alayurt (2)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)  
A.9 Satala - Neocaesaria - Amasia (- Ancyra)  
A.9 Satala - Neocaesaria - Amasia (- Ancyra)  
A.9 Satala - Neocaesaria - Amasia (- Ancyra)  
A.11 Neocaesaria - Zela (- Tavium - Ancyra)  
F.1 Caesaria - Zela - Amasia (- Amisus)

### Fl. Severus

Galerius and Licinius with Maximinus and Constantinus

029(C). Boğazkaya 3(2)

A.9 Satala - Neocaesaria - Amasia (- Ancyra)

### Iulius Flaccus Aelianus, C.

Septimius Severus and Caracalla with Geta AD 198

032(B). Kozören 2  
037(B). Çorum 2(1)  
050(B). Boğazbaşı 2  
056(B). Zile 2(1)  
074(A). İmirzağa, Eski Harabe Mvk. 1  
075(A). İmirzağa, Barçın Mvk. 1  
085(A). Mollahüseyin 1  
088(B),(D). Kemer 4, 6  
089(A). Kemer 7  
090(C). Dayıoluk 3  
098(C). Keklikoluk 6  
105(A). Göksun 8(2)  
107(B),(C),(F). Yağmurlu 2, 3, 6 (rest.)  
108(H),(I). Kanlıkavak 8(1), 9(1)  
109(A),(B). Yeniyapan 1, 2  
110. Karaömer 1  
118(B). Izgın, Çatburun 2  
120(A). Izgın 1(2)  
147(D). Kapıkaya 4(1)  
149(A). Uluköy 1

A.9 Satala - Neocaesaria - Amasia (- Ancyra)  
A.9 Satala - Neocaesaria - Amasia (- Ancyra)  
A.11 Neocaesaria - Zela (- Tavium - Ancyra)  
A.11 Neocaesaria - Zela (- Tavium - Ancyra)  
C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena  
C.3 Caesaria - Melitena  
F.1 Caesaria - Zela - Amasia (- Amisus)  
F.2 Neocaesaria (- Neoclaudiopolis - Pompeiopolis)

[?C. Iulius] **Procel**[..]A[.]PC (?)

(?) date

137. Kadışehri (1)

F.1 Caesaria - Zela - Amasia (- Amisus)

**Iuli**[us ..]oci[-] or **Iul I**[....]oci[- ]

117(A). Emirli 1	C.3 Caesaria - Melitena	
<b>Iulius Proculianus, Q.</b>	Severus Alexander	(?) date
056(A). Zile 1	A.11 Neocaesaria - Zela (- Tavium - Ancyra)	
062. Dutluca (Proc <u>u</u> lianus)	A.12 Sebastia - Sebastopolis (- Tavium)	
<b>Iul [...].anus, Q.</b>	Severus Alexander (?)	
114. Ördek (2)	C.3 Caesaria - Melitena	
<b>Iunius Valerius Nepotianus</b>	Traianus Decius	
037(A). Çorum 1 (rest.)	A.9 Satala - Neocaesaria - Amasia (- Ancyra)	
<b>Licinnius Serenianus</b>	Severus Alexander	(?) AD 234 - 235
079(B). Çakırlar, Barçın Gç. 2(1)	(erased)	C.3 Caesaria - Melitena
083. Şar 2(1)	(erased)	C.3 Caesaria - Melitena
085(B). Mollahüseyin 2(1)	(erased)	C.3 Caesaria - Melitena
	Maximinus	AD 235
079(B). Çakırlar, Barçın Gç. 2(2)	(erased)	C.3 Caesaria - Melitena
079(E). Çakırlar, Barçın Gç. 5(1)	(erased)	C.3 Caesaria - Melitena
083. Şar 2(2)	(erased)	C.3 Caesaria - Melitena
085(B). Mollahüseyin 2(2)	(erased)	C.3 Caesaria - Melitena
086(A). Kemer 13	(erased)	C.3 Caesaria - Melitena
097(B). Doğankonak, Şabanağa Mvk. 2	(erased)	C.3 Caesaria - Melitena
098(B). Keklikoluk 2	(erased)	C.3 Caesaria - Melitena
100(A). Keklikoluk 4	(erased?)	C.3 Caesaria - Melitena
107(D). Yağmurlu 4		C.3 Caesaria - Melitena
118(D). İzgın, Çatburun 4	(erased?)	C.3 Caesaria - Melitena
126. Sevdilli, Büyük Mezraası	(erased)	C.3 Caesaria - Melitena
128(B). Yaztopallı 2	(erased)	C.3 Caesaria - Melitena
	Maximinus with Maximus	AD 236
085(D). Mollahüseyin 5	(erased)	C.3 Caesaria - Melitena
094(A). Doğankonak 1	(erased)	C.3 Caesaria - Melitena
104(C). Göksun 3	(erased)	C.3 Caesaria - Melitena
<b>Pompeius Collega, Cn.</b>	Vespasianus and Titus with Domitianus	AD 76
004. Yurtbaşı	A.9 Satala - Neocaesaria - Amasia (- Ancyra)	
<b>Pomponius Bassus, T.</b>	Nerva	AD 96
066. Sakaltutan (2)	C.3 Caesaria - Melitena	
093(C). Yalak 3 (rest.)	C.3 Caesaria - Melitena	

AD 97

019. Amasya A.9 Satala - Neocaesaria - Amasia (- Ancyra)

(?) AD 97

041. Abdalata, Tekke A.9 Satala - Neocaesaria - Amasia (- Ancyra)

(?) YEAR

042. Çeşmeören A.9 Satala - Neocaesaria - Amasia (- Ancyra)  
 149(B). Uluköy 2 C.2 Neocaesaria (- Neoclaudiopolis - Pompeiopolis)

Traianus

AD 100

003. Yavaşhan A.7 Caesaria - Tyana - Sidamaria (- Col. Iconium)

Nerva or Traianus

011. Çaltılı (2) A.9 Satala - Neocaesaria - Amasia (- Ancyra)  
 035. Elvançelesi (1) A.9 Satala - Neocaesaria - Amasia (- Ancyra)  
 054(F). Tokat 6 A.11 Neocaesaria - Zela (- Tavium - Ancyra)

**Sulla Cerialis** Macrinus with Diadumenianus AD 217

159. Topakkaya P.1 The Pilgrim's Road  
 161. Demirci P.1 The Pilgrim's Road

**Ulpianus Ofellius Theodorus, M.** Elagabalus

068(B). Aslanbeyli Yaylası, Hanboğaz 2 C.3 Caesaria - Melitena  
 078(A). Çakırlar, Beşiktaş 1(1) C.3 Caesaria - Melitena  
 080(E). Çakırlar, Meşelik 5 C.3 Caesaria - Melitena  
 093(F). Yalak 10 C.3 Caesaria - Melitena  
 094(B). Doğankonak 2 C.3 Caesaria - Melitena  
 097(A). Doğankonak, Şabanağa Mvk. 1 C.3 Caesaria - Melitena  
 104(A),(D),(E),(G),(H). Göksun 1, 4, 5, 7(2) (rest.), 19 C.3 Caesaria - Melitena  
 105(E). Göksun 12 C.3 Caesaria - Melitena  
 107(G). Yağmurlu 7 C.3 Caesaria - Melitena  
 108(D),(L). Kanlıkavak 4, 12(1) C.3 Caesaria - Melitena  
 109(C). Yeniyan 3 C.3 Caesaria - Melitena  
 123(A). Elbistan 1 C.3 Caesaria - Melitena  
 129(C). Gözecik 3 C.3 Caesaria - Melitena

**Vergilius Maximus, A.** Trebonianus Gallus and Volusianus

100(B). Keklikoluk 5 C.3 Caesaria - Melitena  
 108(L),(Q). Kanlıkavak 12(2), 17 C.3 Caesaria - Melitena

[-]ANT[-]S (?)

146(D). Kapıkaya 4(2)

C.1 Caesaria - Zela - Amasia (- Amisus)

[ - ]TISIE[ - ]

(?)

158. Değirmenyolu (1)

P.1 The Pilgrim's Road

**4.6.6 Notable Words and Phrases****(1) curante . . . .**

F.1 Caesaria - Zela - Amasia (- Amisus)	Philippus	138
F.1 Caesaria - Zela - Amasia (- Amisus)	Probus	139
P.1 The Pilgrim's Road	Macrinus	159
P.1 The Pilgrim's Road	Macrinus	161

**(2) DNMQEorum, d(evotus) n(umini) m(aiestati)q(ue) eorum**

A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	012
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	013
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	015
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	016
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	018
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	022
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	033(A)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	033(B)(2)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	035(2)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Tetrarchic ?	029(B)(1)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Constantinus et al.	029(B)(2)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Constantinus et al.	031
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Constantinus et al.	033(B)(3)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Probus	054(H)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Diocletianus et coll.	054(A)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Diocletianus et coll.	056(B)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Diocletianus et coll.	056(C)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Diocletianus et coll.	056(D)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Constantinus et al.	057
F.1 Caesaria - Zela - Amasia (- Amisus)	Diocletianus et coll.	140(A)
F.1 Caesaria - Zela - Amasia (- Amisus)	Diocletianus et coll.	141
F.1 Caesaria - Zela - Amasia (- Amisus)	Diocletianus et coll.	142
F.1 Caesaria - Zela - Amasia (- Amisus)	Diocletianus et coll.	143
F.1 Caesaria - Zela - Amasia (- Amisus)	Diocletianus et coll.	145(B)(2)
F.1 Caesaria - Zela - Amasia (- Amisus)	Diocletianus et coll. ?	147(D)(3)
F.1 Caesaria - Zela - Amasia (- Amisus)	Constantius	146
F.1 Caesaria - Zela - Amasia (- Amisus)	(?)	147(D)(2)
F.2 Neocaesaria ([ - Pompeiopolis] - Nicomedia)	Diocletianus et coll.	150(B)

**(3) milia restituta**

C.3 Caesaria - Melitena	Elagabalus	078(A) (rest.)
C.3 Caesaria - Melitena	Elagabalus	080(E)
C.3 Caesaria - Melitena	Elagabalus	093(F)
C.3 Caesaria - Melitena	Elagabalus	094(B)
C.3 Caesaria - Melitena	Elagabalus	097(A)
C.3 Caesaria - Melitena	Elagabalus	104(A)
C.3 Caesaria - Melitena	Elagabalus	104(D)
C.3 Caesaria - Melitena	Elagabalus	104(E)
C.3 Caesaria - Melitena	Elagabalus	104(H) (rest.)
C.3 Caesaria - Melitena	Elagabalus	105(E)
C.3 Caesaria - Melitena	Elagabalus	107(G)
C.3 Caesaria - Melitena	Elagabalus	108(D)
C.3 Caesaria - Melitena	Elagabalus	108(L) (rest.)
C.3 Caesaria - Melitena	Elagabalus	109(C)
C.3 Caesaria - Melitena	Elagabalus	123(A) (rest.)
C.3 Caesaria - Melitena	Elagabalus	129(C)
F.5 Nicopolis - Colonia (- Cerasus)	?	151 (rest.)

**(4) miliaria restituta**

C.3 Caesaria - Melitena	Elagabalus	068(B)
C.3 Caesaria - Melitena	Sev. Alexander ?	114 (rest.)

**(5) miliaria a Sebastopoli restituit**

A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Sev. Alexander	054G)
---	----------------	-------

**(6) praeses**

A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Carus	033(B)
--	-------	--------

**(7) praeses provinciae**

A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Maximinus	029(C)(1)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Maximinus	043
C.2 Caesaria - Sebastia	Elagabalus	065
C.3 Caesaria - Melitena	(?)	108(C)
F.1 Caesaria - Zela - Amasia (- Amisus)	Maximinus	145(B)(1)
P.1 The Pilgrim's Road	Sev. Alexander	167

**(8) praeses provinciae Cappadociae**

P.1 The Pilgrim's Road	Sev. Alexander	164(A)
------------------------	----------------	--------

**(9) praeses provinciae Diosponti**

A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Galerius et coll.	029(C)(2)
--	-------------------	-----------

**(10) praeses provinciae Helenoponti**

A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Constantinus et al.	025(2)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Constantinus et al.	029(B)(2)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Constantinus et al.	031(3)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Constantinus et al.	033(A)(rest.)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Constantinus et al.	033(B)(3)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Constantinus et al.	057
F.1 Caesaria - Zela - Amasia (- Amisus)	Constantinus et al..	142(2)

**(11) praeses provinciae Paflagoniae Ponti**

F.1 Caesaria - Zela - Amasia (- Amisus)	Constantius et coll.	146
---	----------------------	-----

**(12) praeses provinciae Ponti**

A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Maximinus	029(A)(C)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Probus	037(C)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Carus	016(1)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	012(2)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	013(1)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	015(1)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	018(2)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	022
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	029(B)(1)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	033(A)(1)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	033(B)(2)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Diocletianus et coll.	035(2)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Probus	054(H)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Diocletianus et coll.	054(A)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Diocletianus et coll.	056(B)(2)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Diocletianus et coll.	056(C)(2)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Diocletianus et coll.	056(D)(1)
F.1 Caesaria - Zela - Amasia (- Amisus)	Philippus	138
F.1 Caesaria - Zela - Amasia (- Amisus)	Diocletianus et coll.	140(A)
F.1 Caesaria - Zela - Amasia (- Amisus)	Diocletianus et coll.	141(2)
F.1 Caesaria - Zela - Amasia (- Amisus)	Diocletianus et coll.	143
F.1 Caesaria - Zela - Amasia (- Amisus)	Diocletianus et coll.	145(B)(2)
F.1 Caesaria - Zela - Amasia (- Amisus)	(?)	147(D)(2)(rest.)
F.2 Neocaesaria ([- Pompeiopolis] - Nicomedia)	Diocletianus et coll.	150(B)

**(13) restitui/-erunt**

A.7 Caesaria - Tyana - Sidamaria (- Col. Iconium)	Traianus	003
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Nerva	042
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Nerva/Traianus	035
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Traianus	041
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Gordianus III	046
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Nerva	054(F)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Sept. Severus	050(B)
C.3 Caesaria - Melitena	Sept. Severus	075(A)
C.3 Caesaria - Melitena	Sept. Severus	085(A)

C.3 Caesaria - Melitena	Sept. Severus	088(B)
C.3 Caesaria - Melitena	Sept. Severus	088(D)
C.3 Caesaria - Melitena	Sept. Severus	089(A)
C.3 Caesaria - Melitena	Sept. Severus	090(C)
C.3 Caesaria - Melitena	Sept. Severus	098(C)
C.3 Caesaria - Melitena	Sept. Severus	105(A)
C.3 Caesaria - Melitena	Sept. Severus	107(B) (rest.)
C.3 Caesaria - Melitena	Sept. Severus	107(C) (rest.)
C.3 Caesaria - Melitena	Sept. Severus	107(F)
C.3 Caesaria - Melitena	Sept. Severus	108(H)
C.3 Caesaria - Melitena	Sept. Severus	108(I)
C.3 Caesaria - Melitena	Sept. Severus	109(A)
C.3 Caesaria - Melitena	Sept. Severus	109(B)
C.3 Caesaria - Melitena	Sept. Severus	110
C.3 Caesaria - Melitena	Sept. Severus	118(B)
C.3 Caesaria - Melitena	Sept. Severus	120(A)
C.3 Caesaria - Melitena	Gordianus <i>Caesar</i>	087(B)
C.3 Caesaria - Melitena	Gordianus <i>Caesar</i>	093(H)
C.3 Caesaria - Melitena	Gordianus <i>Caesar</i>	104(B)
C.3 Caesaria - Melitena	Gordianus III	068(C)
C.3 Caesaria - Melitena	Gordianus III	074(C)
C.3 Caesaria - Melitena	Gordianus III	075(C)
C.3 Caesaria - Melitena	Gordianus III	079(D)
C.3 Caesaria - Melitena	Gordianus III	080(B)
C.3 Caesaria - Melitena	Gordianus III	084
C.3 Caesaria - Melitena	Gordianus III	089(B)
C.3 Caesaria - Melitena	Gordianus III ?	092(A)
C.3 Caesaria - Melitena	Gordianus III	095
C.3 Caesaria - Melitena	Gordianus III	097(C)
C.3 Caesaria - Melitena	Gordianus III	098(D)
C.3 Caesaria - Melitena	Gordianus III	105(D)
C.3 Caesaria - Melitena	Gordianus III	108(F)
C.3 Caesaria - Melitena	Gordianus III	108(M)
C.3 Caesaria - Melitena	Gordianus III	120(B)
F.1 Caesaria - Zela - Amasia (- Amisus)	Sept. Severus	147(D)
F.2 Neocaesaria ([- Pompeiopolis] - Nicomedia)	Nerva	149(B)
F.2 Neocaesaria ([- Pompeiopolis] - Nicomedia)	Sept. Severus	149(A)

**(14) itinera: itineribus cum pontibus institutis**

P.1 The Pilgrim's Road	Caracalla	166
P.1 The Pilgrim's Road	Macrinus & Diadumenianus	165

**(14) transita: transita a solo composita**

A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Probus	037(A)
--	--------	--------

**(15) via: viam ab Amasia**

A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Hadrianus	036
--	-----------	-----



**(16) via: viam Tauri**

P.1 The Pilgrim's Road	Caracalla	166
P.1 The Pilgrim's Road	Macrinus & Diadumenianus	165

**(17) via: viam stravit**

A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Vespasianus [rest.]	004
--	---------------------	-----

**(18) via: (viam) stravit**

A.3 Caesaria - per Therma - Tavium	Nerva	066
------------------------------------	-------	-----

**(19) via: viam restituit**

A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Domitianus	005 (rest.)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Gordianus III	040
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Gordianus III	044
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Philippus	032(A)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Philippus	034(B)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Traianus Decius	020
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Traianus Decius	037(A)
A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra)	Trebonianus Gallus	038(A)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Gordianus III	050(A)
A.11 Neocaesaria - Zela (- Tavium - Ancyra)	Maximinus	052(A)
A.12 Sebastia - Sebastopolis (- Tavium)	Gordianus III	061

**(20) via: vias restituit**

C.3 Caesaria - Melitena	Nerva [L+Gk]	066
C.3 Caesaria - Melitena	Nerva [ ?+Gk]	093(C)

**(21) via: vias et pontes restituerunt**

C.3 Caesaria - Melitena	?	117(A)
-------------------------	---	--------

**(22) via: viam Tauri vetustate conlapsam . . . . restituit**

P.1 The Pilgrim's Road	Caracalla	166
------------------------	-----------	-----

**(23) via: viam Tauri frequentissimis diluvionibus [dirutam]**

P.1 The Pilgrim's Road	Macrinus & Diadumenianus	165
------------------------	--------------------------	-----

**(24) via: vias et pontes a vetustate conlapsas restitu-it/-erunt**

A.2 Caesaria per Aquas Saruvenas (- Ancyra)	Maximinus	002
C.3 Caesaria - Melitena	Sev Alexander	068(A)
C.3 Caesaria - Melitena	Sev Alexander	072(E)

C.3 Caesaria - Melitena	Sev Alexander	075(H)
C.3 Caesaria - Melitena	Sev Alexander	076
C.3 Caesaria - Melitena	Sev Alexander	087(A)
C.3 Caesaria - Melitena	Sev Alexander	087(A)
C.3 Caesaria - Melitena	Sev Alexander	091
C.3 Caesaria - Melitena	Sev Alexander	104(F)
C.3 Caesaria - Melitena	Sev Alexander ?	114
C.3 Caesaria - Melitena	Sev Alexander	118(C)
C.3 Caesaria - Melitena	Sev Alexander	119(A)
C.3 Caesaria - Melitena	Maximinus	085(D)
C.3 Caesaria - Melitena	Maximinus	094(C)
C.3 Caesaria - Melitena	Maximinus	104(C)
C.3 Caesaria - Melitena	Philippus	068(D)
C.3 Caesaria - Melitena	Philippus	075(B)
C.3 Caesaria - Melitena	Philippus	078(B)
C.3 Caesaria - Melitena	Philippus	085(C)
C.3 Caesaria - Melitena	Philippus	088(A)
C.3 Caesaria - Melitena	Philippus	089(C)
C.3 Caesaria - Melitena	Philippus	093(A)
C.3 Caesaria - Melitena	Philippus	093(D)
C.3 Caesaria - Melitena	Philippus	093(G)
C.3 Caesaria - Melitena	Philippus	094(A)
C.3 Caesaria - Melitena	Philippus	098(A)
C.3 Caesaria - Melitena	Philippus	100(B)
C.3 Caesaria - Melitena	Philippus	103(A)
C.3 Caesaria - Melitena	Philippus	103(B)
C.3 Caesaria - Melitena	Philippus	106(A)
C.3 Caesaria - Melitena	Philippus	108(A)
C.3 Caesaria - Melitena	Philippus	108(J)
C.3 Caesaria - Melitena	Philippus	109(D)
C.3 Caesaria - Melitena	Philippus	119(B)
C.3 Caesaria - Melitena	Philippus	123(C)
C.3 Caesaria - Melitena	Treb. Gallus	108(L)
C.3 Caesaria - Melitena	Treb. Gallus	108(Q)
C.3 Caesaria - Melitena	?	070(A)
C.3 Caesaria - Melitena	?	070(C)

**(25) via: viam novam institutam perfecerunt**

P.1 The Pilgrim's Road	Macrinus & Diadumenianus	159
P.1 The Pilgrim's Road	Macrinus & Diadumenianus	161

**(26) via: viam . . . . restitutam perfecerunt**

P.1 The Pilgrim's Road	Macrinus & Diadumenianus	165
------------------------	--------------------------	-----

## **5. ILLUSTRATIONS: MAPS**

### **5.1 Conspectus Maps**

5.1.1 Cappadocia West

5.1.2 Cappadocia East

### **5.2 Distribution Maps: Milestones and Governors**


5.2.1. C. Iulius Flaccus Aelianus

### 5.2.1 Distribution Map of Milestones: C. Iulius Flaccus Aelianus

#### AD 197/198

- |                                    |  |
|------------------------------------|--|
| 1. 032(B). Kozören 2               | A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra) |
| 2. 037(B). Çorum 2(1)              | A.9 Satala - Nicopolis - Neocaesaria - Amasia (- Ancyra) |
| 3. 050(B). Boğazbaşı 2             | A.11 Neocaesaria - Zela (- Tavium - Ancyra)              |
| 4. 056(B). Zile 2(1)               | A.11 Neocaesaria - Zela (- Tavium - Ancyra)              |
| 5. 074(A). İmirzağa, Eski Harabe 1 | C.3 Caesaria - Melitena                                  |
| 6. 075(A). İmirzağa, Barcın Mvk. 1 | C.3 Caesaria - Melitena                                  |
| 7. 085(A). Mollahüseyin 1          | C.3 Caesaria - Melitena                                  |
| 8. 088(B). Kemer 4                 | C.3 Caesaria - Melitena                                  |
| 9. 088(D). Kemer 6                 | C.3 Caesaria - Melitena                                  |
| 10. 089(A). Kemer 7                | C.3 Caesaria - Melitena                                  |
| 11. 090(C). Dayıoluk 3             | C.3 Caesaria - Melitena                                  |
| 12. 098(C). Keklikoluk 6           | C.3 Caesaria - Melitena                                  |
| 13. 105(A). Göksun 8               | C.3 Caesaria - Melitena                                  |
| 14. 107(B). Yağmurlu 2             | C.3 Caesaria - Melitena                                  |
| 15. 107(C). Yağmurlu 3             | C.3 Caesaria - Melitena                                  |
| 16. 107(F). Yağmurlu 6             | C.3 Caesaria - Melitena                                  |
| 17. 108(H). Kanlıkavak 8(1)        | C.3 Caesaria - Melitena                                  |
| 18. 108(I). Kanlıkavak 9(1)        | C.3 Caesaria - Melitena                                  |
| 19. 109(A). Yeniyapan 1            | C.3 Caesaria - Melitena                                  |
| 20. 109(B). Yeniyapan 2            | C.3 Caesaria - Melitena                                  |
| 21. 110. Karaömer 1                | C.3 Caesaria - Melitena                                  |
| 22. 118(B). İzgın, Çatburun 2      | C.3 Caesaria - Melitena                                  |
| 23. 120(A). İzgın 1(2)             | C.3 Caesaria - Melitena                                  |
| 24. 147(D). Kapıkaya 4             | F.1 Caesaria - Zela - Amasia (- Amisus)                  |
| 25. 149(A). Uluköy 1               | F.2 Neocaesaria ([ - Pompeiopolis] - Nicomedia)          |

## 5.2 Distribution Maps: Milestones and Governors



**5.2.1** Distribution Map of Milestones: C. Iulius Flaccus Aelianus

## 6. ILLUSTRATIONS: FIGURES

### 6.1 Facsimiles of Published Texts

001. 004. Yurtbaşı	[p. 32]	Le Bas and Waddington 1870, 430 no. 1814 <i>b</i> Vespasianus & Titus with Domitianus AD 76
002. 004. Yurtbaşı	[p. 32]	Cumont 1905b, 201 Vespasianus & Titus with Domitianus AD 76
003. 005. Olgunlar	[p. 33]	Cumont 1905b, 221 n.3 (1) Domitianus (?)AD 92 (2) Hadrianus AD 128/129
004. 007. Sevindik	[p. 35]	Mitford 1972, 3, no. 202 (?) Constantinian
005. 008. Kü. Güzel	[p. 35]	Mitford 1972, 3, no. 200-1 (?)
006. 015. Çakırsu	[p. 40]	Wilson 1960, 137 no. 2 (1) Diocletianus <i>et coll.</i> (2) Crispus, Licinnius II and Constantinus II (3) Constantinus with Constantinus, Constantius, Constans and Delmatius (4) (?) (5) (?) (6) Valentinianus I, Valens and Gratianus (7) Honorius
007. 017(B). Aş. Baraklı 2	[p. 44]	de Jerphanion and Jalabert 1908, 441 no. 2 Constantinus with Constantinus, Constantius, Constans and Delmatius
008. 053. Kılıçlı	[p. 83]	Cumont 1902, 312 no.1 Sept. Severus and sons
009. 054(A). Tokat 1	[p. 84]	Le Bas and Waddington 1870, 430 no. 1814 <i>a</i> Diocletianus <i>et coll.</i>
010. 056(B). Zile 1	[p. 88]	Cumont 1905a, 347 Severus Alexander
011. 056(B). Zile 1	[p. 88]	Wilson 1960, 133 Severus Alexander
012. 060 Kervansaray	[p. 96]	Cumont 1904, 334 Hadrianus (?)AD 128/9
013. 083. Şar 2	[p. 132]	Sterrett 1883-84, 297 no. 348 Maximinus AD 235
014. 085(B). Mollahüseyin 2	[p. 135]	Sterrett 1883-84, 297 no. 349 Maximinus AD 235
015. 085(C). Mollahüseyin 3	[p. 136]	Sterrett 1883-84, 294 nos 346-347 (1) Philippus (2) Tetrarchic
016. 087(A). Kemer 1	[p. 139]	Hogarth and Munro 1893, 691 “152 (ii)” Severus Alexander
017. 087(B). Kemer 2	[p. 140]	Hogarth and Munro 1893, 691 “152 (iii)” Pupienus and Balbinus, then Gordianus III
018. 088(A). Kemer 3	[p. 141]	Hogarth and Munro 1893, 692 “151(iii)” Philippus with Philippus

019. 088(B). Kemer 4	[p. 142]	Hogarth and Munro 1893, 692 “151(i)” Sept. Severus and sons AD 198
020. 088(C). Kemer 5	[p. 143]	Hogarth and Munro 1893, 692 “151(ii)” (?)
021. 088(D). Kemer 6	[p. 143]	Hogarth and Munro 1893, 693 “150” Sept. Severus and sons AD 198
022. 089(A). Kemer 7	[p. 144]	Hogarth and Munro 1893, 693 “149(i)” Sept. Severus and sons
023. 089(B). Kemer 8	[p. 145]	Hogarth and Munro 1893, 694 “149(ii)” Pupienus and Balbinus, then Gordianus III
024. 089(C). Kemer 9	[p. 146]	Hogarth and Munro 1893, 694 “149(iii)” Pupienus and Balbinus, then Gordianus III
025. 089(D). Kemer 10	[p. 147]	Hogarth and Munro 1893, 694 “149(iv)” (1) (?)Sept. Severus and sons (2) Tetrarchic
026. 089(E). Kemer 11	[p. 148]	Hogarth and Munro 1893, 694 “149(v)” (1) (?)Sept. Severus and sons (2) Traianus Decius and sons
027. 092(A). Yalak 5	[p. 152]	Hogarth and Munro 1893, 695 “147” Pupienus and Balbinus, then Gordianus III
028. 093(A). Yalak 1	[p. 153]	Sterrett 1883-84, 259 no. 295 Philippus with Philippus
029. 093(B). Yalak 2	[p. 154]	Sterrett 1883-84, 260 no. 296 (?)
030. 093(C). Yalak 3	[p. 154]	Sterrett 1883-84, 260 no. 297 (?)Nerva AD 96
031. 098(A). Keklikoluk 1	[p. 166]	Sterrett 1883-84, 256 no. 292 Philippus with Philippus
032. 098(B). Keklikoluk 2	[p. 167]	Sterrett 1883-84, 257 no. 293 Maximinus
033. 100(A). Keklikoluk 4	[p. 169]	Hogarth and Munro 1893, 697 “136 (i)” Maximinus
034. 100(B). Keklikoluk 5	[p. 170]	Hogarth and Munro 1893, 697 “136 (ii)” Trebonianus Gallus and Volusianus
035. 103(A). Mehmetbey 1	[p. 171]	Sterrett 1883-84, 264 nos 288-289 (1) Philippus with Philippus (2) Tetrarchic
036. 103(A). Mehmetbey 1	[p. 171]	Hogarth and Munro 1893, 698 “131” (1) Philippus with Philippus (2) Tetrarchic
037. 103(B). Mehmetbey 2	[p. 172]	Sterrett 1883-84, 255 nos 290-291 (1) Philippus with Philippus (2) Tetrarchic
038. 104(A). Göksun 1	[p. 173]	Sterrett 1883-84, 240 no. 269 Elagabalus
039. 104(B). Göksun 2	[p. 174]	Sterrett 1883-84, 241 nos 270-271 Pupienus and Balbinus, then Gordianus III
040. 104(C). Göksun 3	[p. 175]	Sterrett 1883-84, 244 nos 272-273 (1) Maximinus with Maximus (2) Tetrarchic

041.	104(D). Göksun 4	[p. 176]	Sterrett 1883-84, 245 nos 274-275 Elagabalus
042.	104(E). Göksun 5	[p. 177]	Sterrett 1883-84, 246 no. 276 [Elagabalus]
043.	104(F). Göksun 6	[p. 178]	Sterrett 1883-84, 247 no. 277 (1) Elagabalus (2) Severus Alexander
044.	104(F). Göksun 6	[p. 178]	Hogarth and Munro 1893, 699 “125 (ii)” (1) Elagabalus (2) Severus Alexander
045.	104(G). Göksun 7	[p. 179]	Hogarth and Munro 1893, 696 “141(i)” (1) (?) (2) Elagabalus
046.	104(I). Göksun 13	[p. 181]	Hogarth and Munro 1893, 698 “134” (?)
047.	104(K). Göksun 17	[p. 181]	Grothe 1911,1, lxxxv no. 41 (?)
048.	104(L). Göksun 18	[p. 182]	Grothe 1911,1, lxxxv no. 42 Sept. Severus and sons
049.	105(A). Göksun 8	[p. 182]	Sterrett 1883-84, 264 no. 300 (1) (?) (2) Sept. Severus and sons AD 198
050.	105(A). Göksun 8	[p. 182]	Hogarth and Munro 1893, 700 “124?(i)” (1) (?) (2) Sept. Severus and sons AD 198
051.	105(C). Göksun 10	[p. 184]	Sterrett 1883-84, 265 no. 301 Tetrarchic
052.	105(D). Göksun 11	[p. 184]	Sterrett 1883-84, 265 302-304 (1) Pupienus and Balbinus, then Gordianus III (2) Tetrarchic
053.	105(E). Göksun 12	[p. 185]	Hogarth and Munro 1893, 700 “124?(ii)” Elagabalus
054.	106(A). Göksun 15	[p. 186]	Hogarth and Munro 1893, 701 “123 (i)” Philippus with Philippus
055.	106(B). Göksun 16	[p. 187]	Hogarth and Munro 1893, 701 “123 (ii)” (?)
056.	107(A). Yağmurlu 1	[p. 187]	Sterrett 1883-84, 267 no. 305 (?) Philippus
057.	107(B). Yağmurlu 2	[p. 188]	Sterrett 1883-84, 267 no. 306 Sept. Severus and sons
058.	107(C). Yağmurlu 3	[p. 188]	Sterrett 1883-84, 268 no. 307 Sept. Severus and sons
059.	107(D). Yağmurlu 4	[p. 189]	Sterrett 1883-84, 269 no. 309 Maximinus
060.	107(E). Yağmurlu 5	[p. 190]	Sterrett 1883-84, 269 no. 308 Diocletianus <i>et coll.</i>
061.	108(A). Kanlıkavak 1	[p. 192]	Sterrett 1883-84, 270 no. 310 Philippus with Philippus
062.	108(B). Kanlıkavak 2	[p. 193]	Sterrett 1883-84, 271 no. 311 (?)



063.	108(C). Kanlıkavak 3	[p. 194]	Sterrett 1883-84, 272 no. 312 (?) Macrinus with Diadumenianus
064.	108(D). Kanlıkavak 4	[p. 195]	Sterrett 1883-84, 272 no. 313 Elagabalus
065.	108(E). Kanlıkavak 5	[p. 196]	Sterrett 1883-84, 273 no. 314 (?)
066.	108(E). Kanlıkavak 5	[p. 196]	Hogarth and Munro 1893, 702 (ii) (?)
067.	108(F). Kanlıkavak 6	[p. 196]	Sterrett 1883-84, 273 nos 315-316 Pupienus and Balbinus, then Gordianus III
068.	108(G). Kanlıkavak 7	[p. 197]	Sterrett 1883-84, 275 no. 317 (1) (?) (2) Philippus
069.	108(H). Kanlıkavak 8	[p. 197]	Sterrett 1883-84, 275 nos 318-319 (1) Sept. Severus and sons (2) Diocletianus <i>et coll.</i>
070.	108(I). Kanlıkavak 9	[p. 198]	Sterrett 1883-84, 277 nos 320-321 (1) Sept. Severus and sons (2) Diocletianus <i>et coll.</i>
071.	108(J). Kanlıkavak 10	[p. 200]	Sterrett 1883-84, 279 nos 322-323 (1) Philippus with Philippus (2) Diocletianus <i>et coll.</i>
072.	108(K). Kanlıkavak 11	[p. 201]	Sterrett 1883-84, 281 no. 324 Diocletianus <i>et coll.</i>
073.	108(L). Kanlıkavak 12	[p. 202]	Sterrett 1883-84, 282 nos 325-327 (1) Elagabalus (2) Trebonianus Gallus and Volusianus (3) Diocletianus <i>et coll.</i>
074.	108(M). Kanlıkavak 13	[p. 203]	Hogarth and Munro 1893, 702 “118(i)” Pupienus and Balbinus, then Gordianus III
075.	108(O). Kanlıkavak 15	[p. 204]	Hogarth and Munro 1893, 702 “(i)” Gordianus III (rest.)
076.	108(P). Kanlıkavak 16	[p. 205]	Hogarth and Munro 1893, 702 “(iii)” Trebonianus Gallus and Volusianus (rest.)
077.	108(Q). Kanlıkavak 17	[p. 205]	Hogarth and Munro 1893, 703 “(iv)” Trebonianus Gallus and Volusianus (rest.)
078.	109(A). Yeniyapan 1	[p. 207]	Hogarth and Munro 1893, 704 “115(i)” Sept. Severus and sons
079.	109(B). Yeniyapan 2	[p. 207]	Hogarth and Munro 1893, 704 “115(ii)” Sept. Severus and sons (rest.)
080.	109(C). Yeniyapan 3	[p. 208]	Hogarth and Munro 1893, 704 “115(iii)” Elagabalus
081.	109(D). Yeniyapan 4	[p. 209]	Hogarth and Munro 1893, 705 “115(iv)” Philippus (rest.)
082.	109(F). Yeniyapan 6	[p. 210]	Hogarth and Munro 1893, 705 “118(vi)” (?)
083.	110. Karaömer 1	[p. 210]	Hogarth and Munro 1893, 705 “113” Sept. Severus and sons
084.	110. Karaömer 1	[p. 210]	de Jerphanion and Jalabert 1908, 458 no. 27 Sept. Severus and sons

085.	112. Dügünyurdu	[p. 212]	Hogarth and Munro 1893, 705 “114” (?)
086.	116(A). Afşin 1	[p. 215]	Sterrett 1883-84, 285 no. 329 (?)
087.	116(B). Afşin 2	[p. 215]	Sterrett 1883-84, 285 no. 330 (?)
088.	116(C). Afşin 3	[p. 215]	de Jerphanion and Jalabert 1908, 457 no. 24 (?)
089.	117(A). Emirli 1	[p. 216]	Sterrett 1883-84, 288 no. 337 (?)
090.	118(B). Izgın, Çatburun 2	[p. 218]	Sterrett 1883-84, 291 no. 341 Sept. Severus and sons
091.	118(C). Izgın, Çatburun 3	[p. 219]	Sterrett 1883-84, 292 no. 342 (1) Elagabalus (rest.) (2) Severus Alexander
092.	118(C). Izgın, Çatburun 3	[p. 219]	Hogarth and Munro 1893, 706 “94 (i)” (1) Elagabalus (rest.) (2) Severus Alexander
093.	118(D). Izgın, Çatburun 4	[p. 220]	Hogarth and Munro 1893, 706 “94 (ii)” Maximinus
094.	120(A). Izgın 1	[p. 221]	Sterrett 1883-84, 293 no. 343 (1) (?) (2) Sept. Severus and sons
095.	120(B). Izgın 2	[p. 222]	Sterrett 1883-84, 293 no. 344 Gordianus III
096.	120(B). Izgın 2	[p. 222]	Hogarth and Munro 1893, 707 “93 to 59(i)” Gordianus III
097.	123(A). Elbistan 1	[p. 224]	Sterrett 1883-84, 294 no. 345 Elagabalus
098.	123(A). Elbistan 1	[p. 224]	Hogarth and Munro 1893, 707 “93 to 59(iii)” Elagabalus
099.	123(B). Elbistan 2	[p. 224]	Hogarth and Munro 1893, 707 “93 to 59(iv)” Sept. Severus (rest.)
100.	123(C). Elbistan 3	[p. 225]	Hogarth and Munro 1893, 707 “93 to 59(v)” Philippus (rest.)
101.	123(D). Elbistan 4	[p. 225]	Hogarth and Munro 1893, 708 “93 to 59(vi) – (vii)” (1) (?) (2) Diocletianus <i>et coll.</i>
102.	123(E). Elbistan 5	[p. 226]	Hogarth and Munro 1893, 707 “93 to 59(viii)” (?)
103.	123(F). Elbistan 6	[p. 226]	Hogarth and Munro 1893, 707 “58” (?)
104.	151. Şebinkarahisar	[p. 259]	Taylor 1868, 295 (?)
105.	158. Değirmenyolu	[p. 263]	Anderson 1899, 108 no. 96 (1) (?) (2) Constantinus I and Licinius I with Crispus, Licinius II and Constantinus II <i>Caesares</i>
106.	164(A). Eminlik 1	[p. 272]	Jacopi 1938, 32 and Fig. 132
107.	164(B). Eminlik 2	[p. 272]	Jacopi 1938, 33 and Fig. 134

## 6.1 Facsimiles of Published Texts

IMP. VESPASIANO  
CAESARE.....  
IMP XIII COS. O VII  
IMP TITO CAESARE COS V  
CN POMPEIVS COS II  
PRO. PR. III  
T

AVG·P·M·TRIB·POT·VII  
I // III COS·VII·P·P·  
IMP·TITO·CAESARE·AVG·F·COS·V  
!!!!!!!!!!O!!!!ARE!!G·F·COS·II  
CN·POMPEIVS·COLLEGA·LEG·AVG  
PRO·PR· //

**6.1.1** 004. Yurtbaşı [p. 32]  
Le Bas and Waddington 1870, 430 no. 1814 b

**6.1.2** 004. Yurtbaşı [p. 32]  
Cumont 1905b, 201

DIVIRI MP111  
NERVAENEPOTITRAIA  
NOHADRIANOAVGICOSXXI vIRO  
PM TR P XIII COS IIII  
P P  
MIL P  
XXXXV

Λ C I Y J L  
 ✓ [X λ N 6 // 10  
 C O N F . 1 9 Z Γ  
 ' Y O C Z E I M I  
 5 I H  
 E T O Y E P N A


**6.1.3 005. Olgunlar** [p. 33]  
Cumont 1905b, 221 n.3

**6.1.4** 007. Sevindik [p. 35]  
Mitford 1972, 3, no. 202

$$C \equiv C O H \equiv \frac{R}{H} \quad \frac{ER}{F}$$

**6.1.5** 008. Kü. Güzel [p. 40]  
Mitford 1972, 3, no. 200-1

## 6.1 Facsimiles of Published Texts




**6.1.6** 015. Çakırsu [p. 40] Wilson 1960, 137 no. 2

IIERATORCAES  
 AL CONSTANTINO  
 IMOMICTOR  
 TRIYMFATOR  
 EMPERAYG  
 EL CONSTANTINO  
 VL CONSTANTIO  
 VL CONSTANTIAE  
 B B B B CAESSSS  
 4 L Æ E  
 +

**6.1.7** 017(B). Aş. Baraklı 2 [p. 44] de Jerphanion and Jalabert 1908, 441 no. 2

## 6.1 Facsimiles of Published Texts



### 6.1.8 053. Kılıçlı [p. 83] Cumont 1902, 312 no.1

Copie de Boré, *Correspondance d'un voyageur en Orient*, I, p. 356 et 357.  
 — A Tokat, dans les ruines de la citadelle.


A N I  
 T A L V A L  
 M A X I M I A N O  
 N O B I L I S S C A E S S  
 M I L P  
 A V P E L . R I S C I A N V S  
 V P P R R R . . . . . N T I  
 D N M . . . . . T V M

### 6.1.9 054. Tokat 1 [p. 84] Le Bas and Waddington 1870, 430 no. 1814 a

## 6.1 Facsimiles of Published Texts

//////////CAESAR  
 MA!P!!V!!!!  
 !!!!!!!!!!!!!  
 PIVSFELIX~IN  
 VICTVSAVG  
 PONTMAXTRIB  
 POTESTAXCOS  
 III PROCOS  
 PERQIVLPROCVLE  
 IANVM LEG PR  
 //////////PA////////IL  
 Z

6.1.10 056(B). Zile 1 [p. 88] Cumont 1905a, 347



CAESAR  
 M. AVR. EVERV  
 IIVSEELIX IN  
 VICTVSAVG  
 PONT·MAX TRIB  
 POTESTAS  
 PP PROCO  
 PERQIVLPROCVLE  
 IANVM LEG PR  
 PR MILI  
 ZEIT.

[Imp.] Caesar  
 M. Aur. [S]everu[s]  
 A[lexa]n[der]  
 [P]ius Felix In-  
 5 victus Aug.  
 pont. max. trib.  
 potestas [cos.]  
 p. p. proco[s].  
 per Q. Iul. Procule-  
 10 ianum leg. pr.  
 pr. Mil. I  
 12 Zelit.

0 10 20 30 40 50 cm

6.1.11 056(B). Zile 1 [p. 88] Wilson 1960, 133

## 6.1 Facsimiles of Published Texts

DIVI TRA  
RTHICI  
NERVAE  
ANVS  
VS A/G  
MAX

et sur un autre fragment de  
colonne qui pourrait avoir fait  
partie du même milliaire :

XLII MIL

### 6.1.12 060 Kervansaray [p. 96] Cumont 1904, 334

I C VE  
O A X I M I N O  
P I O F E L I C I  
V I C T O A V G  
P M T R I B  
P O T E S T P P

### 6.1.13 083. Şar 2 [p. 132] Sterrett 1883-84, 297 no. 348

C A E S G  
I V L I O  
M A X I M  
P I O F E L I C  
I N V I C T O  
P M T  
P O T E S T  
P E R  
L E G A V G P R  
M P N

### 6.1.14 085(B). Mollahüseyin 2 [p. 135] Sterrett 1883-84, 297 no. 349

## 6.1 Facsimiles of Published Texts

<p> CAIUAN  MAXIMIANO  OBIIC  —  CONIAIJA  5 R TITVERVIT  R \NTONIVΛ  ΛΛIVΛ  ONEΛVCIEG  A\ GPRPR  10 PNB </p>	<p> IMPCAES  A.MAVR  ELIVSSEVER  ALEXAND  ERPIVSFELIX  AUG J TRIB..  TEST J COS J PP  J VIA.ETPO  TESVETOSTA  TECONLAPSA  SRESTITVT  PNB </p>	<p> Imp[erator] Caes-  a[r] M. Aur-  elius Sever[us]  Alexand-  er pius felix  aug. trib. [po-  test. cos. p. p.  via[s] et po-  n]tes vetosta-  te conlapsa-  s restitu[i]t.  PNB. </p>
---	---	--

**6.1.15** 085(C). Mollahüseyin 3 [p. 136]  
Sterrett 1883-84, 294 nos 346-347b

IMP  
CAESAR  
[Six lines erased.]  
MANTONIVS  
DIANVSNOBILISIMVS  
AESARRESTITVT  
PERCVSPIDIUMPIAN  
VMSEVERVMLEG  
OPRETOREM  
....MP

**6.1.16** 087(A). Kemer 1 [p. 139]  
Hogarth and Munro 1893, 691 “152 (ii)”

Imp[erator]  
Caesar  
[Names of Pupienus and Balbinus  
erased.]  
M. Antonius  
Gor]dianus nobilis(s)imus  
C]aesar restituit  
per Cuspidium [Fl]a[m]-  
ini]um Severum leg-  
atum pr]opretorem  
M. P. (PNB)

**6.1.17** 087(B). Kemer 2 [p. 140] Hogarth and Munro 1893, 691 “152 (iii)”

IMP.....  
....VS.....  
...USPIUS.....  
INVICTVSAVG  
.....IUS  
.....SSI...  
.....A.E.PONT.S  
V.....ATE...  
LAPSASRESTITU  
.....  
....ONE.LE....  
.....TO...

Imp. [Caesar  
Marc]us [Jul. Phil-  
ipp]us pius [felix  
invictus aug.  
et Marcus Jul]ius  
Philippus nobili]ssi[mus  
Caesar vi]a[s] e[t] pont[e]s  
v[etust]ate [con-  
lapsas restitu[erunt  
[per Antonium Memm]ium  
Hier]one[m] le[g. aug.  
proprae]to[rem.

**6.1.18** 088(A). Kemer 3 [p. 142] Hogarth and Munro 1893, 692 “151(iii)”



## 6.1 Facsimiles of Published Texts

IMPCAES	Imp[erator] Caes[ar]
LSEPTIMIUS	L. Septimius
SEVERVSPIVS	Severus Pius
PERTINAXAVG	Pertinax Aug[ustus]
ARABADIABPA	rab[icus] Adiab[enicus] Pa-
RTHMAXPONT	[icus] Max[imus] pont[ifex]
MAXTRIBPOTVI	nus] trib[uniciae] pot[estatis] vi
IMPXICOSIIPP	rator] xi cos. ii p[ater] p[atriae]
PROCOSETIMP	procos: et Imp[erator]
CAESMAVREL	Caes[ar] M. Aurel[ius]
ANTONINVSAVG	Antoninus Aug[ustus] et
[Erasure.]	.....
..RESTITVERVNT	.. restituerunt
PERCIVLIVMFLAC	per G. Julium Flac-
CVMAELIANVM	cum Aelianum
LE....PR.PR.....	le[gatum] pr[o] pr[aetore]
CLI.PNA.	CLI.PNA.

## 6.1.19 088(B). Kemer 4 [p. 142] Hogarth and Munro 1893, 692 “151(i)”

(ii.) R. 1890. In the cemetery at Kemer, upside down, fragmentary.

CLI PNA

## 6.1.20 088(C). Kemer 5 [p. 143] Hogarth and Munro 1893, 692 “151(ii)”

IMPCAES	Imp. Caes.
SEPTIMIUS	L.] Septimius
SEVERVSPIVS	Severus Pius
PERTINAXAVG	Pertinax Aug.
ARABADIABPARTH	Arab. Adiab. Parth.
....PONTMAX	Max.] pont. max.
TRIBPOTVIIMPXI	trib. pot. vi. imp. xi.
....IPPPROCOS	cos. i]i p. p. procos.
ETIMPCAESMAVR	et Imp. Caes. M. Aur.
ANTONINVSAVG	Antoninus Aug.
[Erasure.]	.....
[Erasure.]	.....
RESTIT	restit-
VERVNT	uerunt
PERCIVLIVM	per G. Julium
FLACCVM AELI	Flaccum Aeli-
.NVMLEPR..	a]num le. pr. [pr.
CL PN	CL PN.

## 6.1.21 088(D). Kemer 6 [p. 144] Hogarth and Munro 1893, 693 “150”

## 6.1 Facsimiles of Published Texts

IMPCAES	Imp. Caes.
SEPTIMIVS	L.] Septimius
SEVERVSPIVS	Severus Pius
PERTINAXAVG	Pertinax Aug.
ARABADIABPARTH	Arab. Adiab. Parth.
....PONTMAX	Max.] pont. max.
TRIBPOTVIIMPXI	trib. pot. vi. imp. xi.
....IPPPROCOS	cos. i]i p. p. procos.
ETIMPCAESMAVR	et Imp. Caes. M. Aur.
ANTONINVS AVG	Antoninus Aug.
[Erasure.]	.....
[Erasure.]	.....
RESTIT	restit-
VERVNT	uerunt
PERCIVLIVM	per G. Julium
FLACCVMAELI	Flaccum Aeli-
.NVMLEPR..	a]num le. pr. [pr.
CL PN	CL PN.

## 6.1.22 089(A). Kemer 7 [p. 144] Hogarth and Munro 1893, 693 “149(i)”

IMPCAL	Imp. Ca[esar
LSEPTIMIV	L. Septimiu[s
SEVERVSPIVS	Severus Pius
PERTINAXAVG	Pertinax Aug.
ARABADIABPARTH	Arab. Adiab. Parth.
MAXPONTMAX	Max. pont. max.
TRIBPOTVI.IMPVI	trib. pot. vi. imp. [x]i
COSIIPP.PROCOS	cos. ii. p. p. procos.
ETIMP.CAES	et Imp. Caes.
MAVRELANTON	M. Aurel. Anton-
..VSAVG.....	[in]us Aug. ....
.....RESTIT	..... restit-
VERVNTPERIVLFLAC	uerunt per [G.] Jul. Flac-
CVMAELIANVM	cum Aelianum
LE.PR.PR	le. pr. pr.
CXLIXPM⊙	CXLIXPM⊙

## 6.1.23 089(B). Kemer 8 [p. 145] Hogarth and Munro 1893, 694 “149(ii)”

ES VIA	Ca]es[ar] via[s et
NTESVI	po]ntes v[et-
AT.CONLA..	ust]at[e] conla[p-
....ESTITVE	sas r]estitue-
PERANT	runt] per Ant-
VMMEMM	oni]um Memm-
IVMHIERONEM	ium Hieronem
LEGA VG	leg. Aug.
PR PR	pr. pr.
PM⊙	PM⊙.

## 6.1.24 089(C). Kemer 9 [p. 146] Hogarth and Munro 1893, 694 “149(iii)”

## 6.1 Facsimiles of Published Texts

(iv.)  
 I V G  
 I B  
 I M P C A E S  
 R E S T I T V E R V N T  
 C A I O V A L  
 Δ I O C L E T I A O  
 I A N

## 6.1.25 089(D). Kemer 10 [p. 147] Hogarth and Munro 1893, 694 “149(iv)”

(v.)	I M P C A S	Imp. Ca[e]s.
	U S S E P T M	
	Δ I A M O A P I O A	Tr]aia(n)o (D)[e](c)io a[ug.
	V E R	
	E N N I O A	et Q. Her]ennio [Et-
	C C O M A E S I	ru](s)co Maesi-
	C A E S I C E T I M P	(o D)e(c)i(o) et (G.)
	E N T I O S T I O S	Val]enti Osti(li)-
	N O M E S I O	a]no Mesio
	I N T O N O	Qu]into no-
	B I L L C A E S S	bill. Caess.
	P M Θ	P M Θ.

## 6.1.26 089(E). Kemer 11 [p. 148] Hogarth and Munro 1893, 694 “149(v)”

P I	A R C
G V S	L I P P V S
R V	S S I M V S
N	S A R V I A S E T P
V	O N T E S V E T V
I E	S T A T E C O N L
M E	P S A S R S T I
	E R V N
	N I V X
	I V M
	M V C
	M

6.1.27 092(A). Yalak 5 [p. 152]  
 Hogarth and Munro 1893, 695 “147”

6.1.28 093(A). Yalak 1 [p. 153]  
 Sterrett 1883-84, 259 no. 295

## 6.1 Facsimiles of Published Texts

C A E S A  
 L I  
 O C  
 U I D A E  
 O U  
 L C I S A  
 P O N  
 O N L A P S A S

**6.1.29** 093(B). Yalak 2 [p. 154]  
 Sterrett 1883-84, 260 no. 296

C A E  
 A R M A R C V  
 P H I L I P P V S P I V S F  
 N V I C T V S A V G  
 5 R C V S I V L P H I L I P P  
 B I L I S S I M V S C A E S  
 A S E T P O N T E S V E T  
 A T E C O N L A P S A S R E S  
 R A P E R A N T O N V  
 10 M I V M H I E R O N E M  
 E G A V G G P R  
 P R

**6.1.31** 098(A). Keklikoluk 1 [p. 166]  
 Sterrett 1883-84, 256 no. 292

... I M I N O P I O  
 ... I C I A V G T R I B  
 .....  
 ... P L ... N ...  
 ..... A V G  
 P R ... P R  
 P A S

**6.1.33** 100(A). Keklikoluk 4 [p. 169] Hogarth and Munro 1893, 697 “136 (i)”

C I A C Y T A T O  
 O C T A C O Δ O Y C  
 T O I O I O Y  
 N T I C T  
 P M Δ


**6.1.30** 093(C). Yalak 3 [p. 154]  
 Sterrett 1883-84, 260 no. 297

I M P C A  
 E S A R I G A  
 I O I V I I O V E  
 R O M A  
 [uncut space]  
 M I N O P I O  
 F E L I C I A V G  
 T R I B P P E  
 L I C I N N I V M  
 S E S E I M I A N  
 V I L E G A V G  
 P R P R  
 P H

**6.1.32** 098(B). Keklikoluk 2 [p. 167]  
 Sterrett 1883-84, 257 no. 293

[Gaio Julio Vero]  
 Max]imino pio [fel.  
 inv]ic(t). aug. trib.  
 [pot. pont. max.]  
 p. p. pe]r L[ici]a[ium  
 [Serenianum leg.] aug.  
 pr. pr.  
 P A S

## 6.1 Facsimiles of Published Texts

(ii.)	IM. CAE... VIVI..... N...GAL... E...MP..... .VIVIVS .ELDVMI... .VSVOLV... .VSPFIIFELICI... ....AVG..... .TPONTES.. VSTATECON. .PSASRESTITV. V..VTPERAN..... MAXIMVM.. ...AVG.PR.. 	Im[p. Cae[sar G.] Vivi[us Trebo- n[ius] Gal[us e[t I]mp [Caesar G.] Vivius V]eldumi[nia- n]us Volu[sia- n]us pii felic. i[nv- icti] aug[g. vias e]t pontes [ve- t]ustate con[l- a]psas restitu[e- r]u[n]t per A. (V)[irgilium Maximum [v. c. leg.] aug[g]. pr. [pr.
-------	---	--

## 6.1.34 100(B). Keklikoluk 5 [p. 170] Hogarth and Munro 1893, 697 “136 (ii)”

I M P  
 Y I D I O C L E T I A N O  
 P C I U , I I  
 A C  
 T I T  
 M P  
 I E

IMPCI...L.....  
 DIOCLETIANO  
 ESMA  
 ..AN...  
 ....IVL...  
 AVGG...TITV..  
 ....M....  
 V.....IE...

6.1.35 103(A). Mehmetbey 1 [p. 171]  
Sterrett 1883-84, 264 nos 288-2896.1.36 103(A). Mehmetbey 1 [p. 171]  
Hogarth and Munro 1893, 698 “131”

A. I M P C A E S  
 A R M A R C V  
 V L P H I L I P P V S  
 F E L I X I N V I C T V S  
 5 V G E T M A R C V S  
 H I L I P P V S N O B I L I S S I  
 V S C A E S A R V I A  
 P O N T E S V E T V  
 E C O N L A P S A S R  
 10 S T I T V E N I P E R A  
 O N M M E M M I V M H I  
 B. E T F U A L  
 C O N S T A N T  
 N O B C A  
 15 S C

## 6.1.37 103(B). Mehmetbey 2 [p. 172] Sterrett 1883-84, 255 nos 290-291

## 6.1 Facsimiles of Published Texts

I M P  
 CAES  
 DIVISEVERINEP  
 DIVIMANTONINI  
 5 FIL.  
 MAVRANTONINO  
 PIOFELICIAVG  
 MILIARESTITVTA  
 PERMVLPOFELLI  
 10 VMTHEODORVM  
 LEG AVG  
 PR PR  
 P Λ Γ

**6.1.38** 104(A). Göksun 1 [p. 173]  
 Sterrett 1883-84, 240 no. 269

I M P  
 CAESARCIVL  
 VERVSMA XIMINV  
 CAESSNC  
 5 GAIOVIA L  
 DL LCIANO  
 ETINVICTO XV  
 NOBILISSIMVSCAESAR  
 VIASETPONTESVETV  
 10 TATECONLABSASRES  
 TITVERVIT  
 PER  
 LEG  
 AVGG PR PR  
 15 XII PMA

**6.1.40** 104(C). Göksun 3 [p. 175]  
 Sterrett 1883-84, 244 nos 272-273

LEG  
 PR PR  
 P Λ

**6.1.42** 104(E). Göksun 5 [p. 177] Sterrett 1883-84, 246 no. 276

A.  
 SALUAL  
 XIMIANO  
 LVI CAES

B.  
 ANTONIVSGORDIA  
 5 NVS OBILISIMVS  
 ESARRESTITVIT  
 PERCVSPIDI  
 AMINIVMSE  
 VERVMLEGETPR  
 10 PRETOREM  
 P M A

**6.1.39** 104(B). Göksun 2 [p. 174]  
 Sterrett 1883-84, 241 nos 270-271

IMPCAESAR  
 DIVISEVERI  
 NEPDIVIM  
 ANTONINIFIL  
 5 MAVRANTON  
 NO  
 FE  
 LICIAVG  
 SIS  
 10 MILIARE  
 STITVTA PER  
 MVLPOFEL  
 LIVMTH  
 14 OP

**6.1.41** 104(D). Göksun 4 [p. 176]  
 Sterrett 1883-84, 245 nos 274-275

## 6.1 Facsimiles of Published Texts

I M P  
 A V R  
 R I B  
 C O S A P P  
 T E S V E T T V S T A  
 N L A P S A R E S T I T V  
 I T A P K E

## 6.1.43 104(F). Göksun 6 [p. 178] Sterrett 1883-84, 247 no. 277

IMP	Imp. [Caes.
LUCE	Luc. [Domitio
AVRELIANO	Aureliano
N	.....
NV	i]nv[icto aug.
TRIB P O	trib. P o[t.
COS P P	cos. P p. [vias et
TESVETTVSTA	pon]tes vettusta[te
NLAPSASRESTITV	co]nlapsas restitu-
IT PKE	it PKE

## 6.1.44 104(F). Göksun 6 [p. 178] Hogarth and Munro 1893, 699 “125 (ii)”

IMP  
 CAESAR  
 .....VIAI.....I  
 .....V.....S  
 .....NO  
 ....R.....NI  
 ....P.....  
 ....L.....  
 ....AMP C  
 .....M O.....V..  
 ....PIA OGT....  
 .....AIE...  
 ....O.....A.....  
 CXLIPMA

On the opposite side the following letters of another inscription can be read:—

CC  
 MTHEO

## 6.1.45 104(G). Göksun 7 [p. 179] Hogarth and Munro 1893, 696 “141(i)”

## 6.1 Facsimiles of Published Texts

P R  
 A N O R V F O  
 T S S  
 .....  
 .....  
 .....  
 ..... S E T  
 I I G E N  
 .....  
 .....  
 ... O ..... R E  
 C X ..... P A Δ

## 6.1.46 104(I). Göksun 13 [p. 181] Hogarth and Munro 1893, 698 “134”

41. Gökssün-ssu. Brücke, Meilenstein aus Marmor, schlecht erhalten; auf der Straße nach Seitun. Die Abschrift gibt:

V S N -  
 T I A = S Diocle]tia[nu]s  
 E S = V E pont]es ve[tustate  
 O I N A P S Δ c]on(l)aps[os resti-  
 E R V tu] erunt.

## 6.1.47 104(K). Göksun 17 [p. 181] Grothe 1911,1, lxxxv no. 41

42. Gökssün, nahe Brücke über Gökssün-ssu auf der Straße nach Seitun. Meilenstein. Veröffentlicht: CIL. III, 12186. Die Abschrift gibt die unterstrichenen Buchstaben:

Imp. Caesar  
 L. Septimius Seuerus  
 Pius Pertinax Aug. Arab. Adiab.  
 Part. max. pont. max. trib. pol. VI  
 imp. XI cos. II p. p. procos.

## 6.1.48 104(L). Göksun 18 [p. 182] Grothe 1911,1, lxxxv no. 42



## 6.1 Facsimiles of Published Texts

RVS  
 ARAOIA R  
 POTIVII  
 TIMPCAESI  
 RESTITVERVNT  
 ANVMLEGPRPR

**6.1.49** 105(A). Göksun 8 [p. 182] Sterrett 1883-84, 264 no. 300

IMPCAESAR  
 LSEPTIMIUS SEVERVS  
 PIVS PERTINAX AVG ARABADIAB  
 PARTHMAXPONTMAXTRIBPOTVI  
 IMPXICOSII PP PROCOS ET IMP CAES  
 MAVREL ANTONINVS AVG  
 ET SEPTIMIUS AVGG RESTITVERVNT  
 PERICIVLIVM FLACCVMAELIANVM LEGPRPR

**6.1.50** 105(A). Göksun 8 [p. 182] Hogarth and Munro 1893, 700 “124?(i)”

MAXIMIAN  
 NOBCAE  
 SS

**6.1.51** 105(C). Göksun 10 [p. 184]  
 Sterrett 1883-84, 265 no. 301

IMP  
 MAV  
 MPER  
 CAC MAXIM  
 5 COANTOR  
 GORLNOGCAE  
 LICIAVCVTO  
 RESTITSSVNT  
 PERCVSPIDIM  
 10 MINIVMSEVERVM  
 CATVMPOPRA C  
 IOA

**6.1.52** 052. 105(D). Göksun 11 [p. 184]  
 Sterrett 1883-84, 265 302-304

## 6.1 Facsimiles of Published Texts

I...	I[mp.
CAES	Caes.
DIVISEVE..	divi Seve[ri
NEP DIVIM..	nep. divi M. [An-
TONINI	tonini
FIL	fil.
MAVRAN..	M. Aur. An[to-
NINOPIOFELIC.	nino pio felic[i
AVG	aug.
MILIARESTITV	milia restituta
TAPERMVLPOFELL	per M. Ulp. Ofell-
I V M T H E O D O R V M	ium Theodorum
LEG AVG	leg. aug.
PR PR	pr. pr.

## 6.1.53 105(E). Göksun 12 [p. 185] Hogarth and Munro 1893, 700 “124?(ii)”

VSIV	[Imp. Caes.]
SFU	Marc]us Ju[l. Phil-
VSJET	ippus piu]s f[elix in-
P	victus a]u[g.] et [Marcus
I..S	Jul. Phil]p[us nobili-
O F	ss]i[mu]s [Caesar vias
CONSSSA	et p]o[ntes vetustate
ATPETLA	con[lap]s[as rest-
MEMMIVM	ituerun]t pe[r Anton-
LEG AV	ium] Memmium [Hieronem
PRPR	leg. Au[g.
	pr. pr.

## 6.1.54 106(A). Göksun 15 [p. 186] Hogarth and Munro 1893, 701 “123 (i)”

A.....	P E R M E M M
PH.....IP.....	
CET...A...	
TRIBP....	
....PC...O	

## 6.1.56 107(A). Yağmurlu 1 [p. 187]

Sterrett 1883-84, 267 no. 305

6.1.55 106(B). Göksun 16 [p. 187]  
Hogarth and Munro 1893, 701 “123 (ii)”

T I M A X I O N T I M  
 M X I I C O S I I I P I B O  
 I M A V B E A N T O N I N Y S  
 I V T  
 P E P H Y L I Y M F L A C I C Y M I A E W A Y M E O

## 6.1.57 107(B). Yağmurlu 2 [p. 188] Sterrett 1883-84, 267 no. 306

## 6.1 Facsimiles of Published Texts

IM  
LSE  
PIVS  
PARTI  
IMPXI  
UAVR  
ETLISE  
PERCIVL

**6.1.58** 107(C). Yağmurlu 3 [p. 188]  
Sterrett 1883-84, 268 no. 307

DIOCLETIA  
ET  
ITC  
CONSTATIO  
ETCAIUM  
MAXIMIANO  
NPR

**6.1.60** 107(E). Yağmurlu 5 [p. 190]  
Sterrett 1883-84, 269 no. 308

V  
M  
  
E  
5 ICI  
VNI  
ION  
PRPR  
  
PK

**6.1.62** 108(B). Kanlıkavak 2 [p. 193]  
Sterrett 1883-84, 271 no. 311

AES  
CIVL  
ROMAXIMI  
PIOFELICIA  
VGTRIBPPERLI  
CINNIVMSERENI  
ANVNLEGAVG  
PRPR  
  
PKB

**6.1.59** 107(D). Yağmurlu 4 [p. 189]  
Sterrett 1883-84, 269 no. 309

MP  
SPI  
ICTV  
ARCVS  
NOBILISSIM  
SARVIASETPO  
TSVETVSTATE  
CONLAPSASRESTITVE  
PERANTONIVMM  
MIVMHIERONEM  
LEGAVG  
PRPR

**6.1.61** 108(A). Kanlıkavak 1 [p. 192]  
Sterrett 1883-84, 270 no. 310

ANINO  
LISSIMOCASA  
CATCLEMENT  
CRCRCROVINCIA  
5 IMP  
  
PK

**6.1.63** 108(C). Kanlıkavak 3 [p. 194]  
Sterrett 1883-84, 272 no. 312

## 6.1 Facsimiles of Published Texts

I M P  
 D I V I S E V E R I  
 N E P D I V I M A N  
 T O N I N I F I L  
 M A V R  
 N O P I O F E L I C I  
 A V G  
 M I L I A R E S T I T V T A  
 M P O F E L L I V M  
 T H E O D O R V M  
 L E G A V G P R P R  
 M I K

**6.1.64** 108(D). Kanlıkavak 4 [p. 195]  
Sterrett 1883-84, 272 no. 313

I M P  
 C A E S A R I M A  
 R C O A N T O N I  
 O G O R A I A N O P I  
 5 O F E L I C I A V G V S  
 T O R E S T I T V E R V  
 N T P E R C V S P I A  
 I V M F S A M I N I  
 V M S E V E R V M  
 10 L E G A T V M P R O P  
 P A C T O R E M

**6.1.67** 108(F). Kanlıkavak 6 [p. 196]  
Sterrett 1883-84, 273 nos 315-316

P R P R

**6.1.65** 108(E). Kanlıkavak 5 [p. 196]  
Sterrett 1883-84, 273 no. 314

I M P  
 C A E S A R  
 I I A V C P  
 E R V  
 G M A X  
 C O S P R O C O S  
 I V

**6.1.66** 108(E). Kanlıkavak 5 [p. 196]  
Hogarth and Munro 1893, 702 (ii)

I M  
 C A E S M A R C V S  
 I V L P H I L I P P V S  
 P I V S F E L I X

**6.1.68** 108(G). Kanlıkavak 7 [p. 197]  
Sterrett 1883-84, 275 no. 317

## 6.1 Facsimiles of Published Texts

A. IMP P  
 O C T I A I  
 E T I A L T I U A L  
 MAXIMIANO  
 5 P P F F I N U A U G  
 E T F I A I  
 C O N S T A N T I O  
 E T A I  
 C A E S  
 10 M A X I M I A N O  
 S E V E R V S

[A blank, apparently uncut space.]

B. H M A X P O N T M A X T R I B P O T V I O  
 I P X I C O S I I P P P R O C O S E T I M P C A E S  
 M A V R E L . A N T O N I  
 N V S A V G [name erased]  
 5 [name erased] T I T V E R V N T  
 P E R C . I V L I V M F L A C  
 C V M A E L I A N V M L E G P R P R

## 6.1.69 108(H). Kanlıkavak 8 [p. 197] Sterrett 1883-84, 275 nos 318-319

IM P P  
 D I O C L E T I A N O  
 I M P C A E S M A V R U A L  
 L S E P T I M I V S S E V E R V S A V G  
 5 P I V S P E R T I N A X A V G A R A B I A D I A B  
 P A R T H M A X P O N T M A X T R I B T I O T V I  
 I M P X I C O S I I P P P R O C O S E T I M P C A E S  
 M A V R E L A N T O N I N V S A V G N O  
 E T L S E P T V S N O B C A E S S E T I T V E R V N T  
 10 P E R C . I V L I V M F L A C C V M A E L I A N V M L E G P R P R

## 6.1.70 108(I). Kanlıkavak 9 [p. 198] Sterrett 1883-84, 277 nos 320-321

## 6.1 Facsimiles of Published Texts

*A.*

I M

R C A E S M A  
R C V S I V L P  
H I L I P P V S P I V  
5 S E E L I X I N V I  
C T V S A V G E  
T M A R C V S  
I V L I V S P H I  
L I P P V S N O  
10 B I L I S S I M V S  
C A E S A R V I A  
S E T P O N T E  
E T V S T A T  
N L A P S A S  
15 V E R  
A

On the other side of the stone.

*B.*

I M P P E C C N A I  
D I O C L E T I A N O  
E T M A U R U A L  
M A X I M I A N O  
5 P P F F I N U I A U G  
U I U A I  
C O N S T A N T I O  
E T C A I A E  
M A X I M I A N O  
10 N O B C A E S S

**6.1.71** 108(J). Kanlıkavak 10 [p. 200] Sterrett 1883-84, 279 nos 322-323

A X

5 P P F F I N V I A V G  
E T F L A V I V A L  
C O N S T A N T I O  
E T C U A L E N  
M A X I M I A N O  
10 N O B C A E S S  
P

**6.1.72** 108(K). Kanlıkavak 11 [p. 201] Sterrett 1883-84, 281 no. 324

## 6.1 Facsimiles of Published Texts

A.

IMPCA  
 ESARGVIVIVSTREBO  
 NGALLVSETIMPCAES  
 ARGVIVIVS VELDVMI  
 5 NIANVS VOLVSIANV  
 PII FELICIN VICTIAVGGVIAS  
 ETPONTESVETVSTATECON  
 LAPSASRESTITVERVNTPERA  
 VERGIQIVMMAXIMVMVC  
 10 VGGPRPR

B.

8 RESTITVTA  
 ERMULP  
 10 OFELLIUM  
 THEODORV  
 MLEGAVG  
 PRPR

M

C.

IMPPCC  
 DIOCLETIANO  
 ETMAVRULI  
 MAXIMIANO  
 5 PPFFINVIAUG  
 ETFLAUVIAL  
 CONSTANTIO  
 ETCAIUAL  
 MAXIMIANO  
 10 NOBBCLAESS

**6.1.73** 108(L). Kanlıkavak 12 [p. 202] Sterrett 1883-84, 282 nos 325-327

<p>.....N...</p> <p>..D...A...NOP...</p> <p>GVSTORI</p> <p>ERCVS</p> <p>MINIUM</p> <p>ATVMPPROP</p> <p>EM</p> <p>PIH</p>	<p>Imp. Caes.</p> <p>[Marco A]n[ton-          io Gordi]a[no pi]o felici          au]gusto r[esti-          tuerunt p]er Cus[pidium          Fla]minium [Severum          leg]atum propr[ae-          tor]em</p> <p>PIH</p>
--	--

**6.1.74** 108(M). Kanlıkavak 13 [p. 203] Hogarth and Munro 1893, 702 “118(i)”

## 6.1 Facsimiles of Published Texts

E . C V S P I . . . .  
M I N . . . . . I E R O N  
P R P

p]e[r] Cuspi[dium  
Fla]min[ium (Severum)  
legatum] pr[o]p[raetorem]

**6.1.75** 108(O). Kanlıkavak 15 [p. 204] Hogarth and Munro 1893, 702 “(i)”

V O L  
I N V I C T I

Vol[usianus pii felic.  
invicti [Augg.]

**6.1.76** 108(P). Kanlıkavak 16 [p. 205] Hogarth and Munro 1893, 702 “(iii)”

. . . . . T . . . . .  
. . . . . N . A P S . .  
. . . . . T V . . . N T . . . .  
. . . C I I . . . . .  
M V M . . . . . C . . . . . S . . . . .  
G A V G G  
P R P R

vias et pon]t[es vetus-  
tate co]n[l]aps[as  
restitu[er]ut [per A.  
Vir]gil[ium Maxi-  
mum [virum] c[lari]s[simum  
leg. augg.  
pr. pr.]

**6.1.77** 108(Q). Kanlıkavak 17 [p. 205] Hogarth and Munro 1893, 703 “(iv)”

IMPCA..  
LSEPTMIVSISEVERVS  
PIVSIPERTINAXIAVGIVRARADIIAR  
PARTHMAXPONTMAXTRIRPOTVI  
IMPXICOSIIPPPROCOSIETIMPCAES  
MAVRELANTONINVSIAVG.....  
.....TITVERV..  
PERCIVLF...CVM AELIANVMILEGIPRIPRI

**6.1.78** 109(A). Yenyapan 1 [p. 207] Hogarth and Munro 1893, 704 “115(i)”

P E R C . . . I V M F L A .  
C V M . . . . A . L I A N V M C U S

per G. [Jul]ium Fla[c-  
cum A[el]ianum [leg.  
[aug. pr. pr.]

**6.1.79** 109(B). Yenyapan 2 [p. 207] Hogarth and Munro 1893, 704 “115(ii)”



## 6.1 Facsimiles of Published Texts

IMP	Imp.
CAESDI	Caes. di-
VISEVERI	vi Severi
NEPDIIVIMAN	nep. divi M. An-
TONINIFILM	tonini fil. M.
AVRELANT...	Aurel. Ant[oni-
NOPIOFELICI	no pio felici
AVGMILIA	aug. milia
RESTITVTAPER.	restituta per [M.
VLPOFELLIVM	Ulp. Ofellium
THEODORVMLEG	Theodorum leg.
AVG PR PR	aug. pr. pr.
MPIE	MPIE





## 6.1.80 109(C). Yenyapan 3 [p. 208] Hogarth and Munro 1893, 704 “115(iii)”

CIC	
C...APSASR.....	c[onl]apsas r[estituerunt]
PERANTO.....	per Anto[nium Memmi-
...IE.ON..	um H[j]e[r]on[em]

## 6.1.81 109(D). Yenyapan 4 [p. 209] Hogarth and Munro 1893, 705 “115(iv)”

E	LSEPTIMIVS.....
M	PIVSPERTIN.....
VAVG	PARTHMAXPON.....
C	IMPXI'COS'II'PPPR.....
	MAVREL'ANTO..
	NVSİAVGET....
	.....RES.....
	PERCIVLIVM....
	CVMANVM'L.....

6.1.82 109(F). Yenyapan 6 [p. 210]  
Hogarth and Munro 1893, 705 “118(vi)”6.1.83 110. Karaömer 1 [p. 210]  
Hogarth and Munro 1893, 705 “113”

 C SEPTIMIV  
 PIVS PERTIN  
 PARTH MAX PON  
 IMP XII COS III PPP  
 5 MAVRELIAN TE  
 NVS AVG ET  
 RES  
 PER POSVI  
 CVMANVMIL

## 6.1.84 110. Karaömer 1 [p. 210] de Jerphanion and Jalabert 1908, 458 no. 27

## 6.1 Facsimiles of Published Texts

Lower fragment of a stone in the Duniyat Bel.

PR  
MPIΔ

### 6.1.85 Düğünyardu [p. 212] Hogarth and Munro 1893, 705 “114”

NOBILISSIMI  
CAES

CONLAP

### 6.1.86 116(A). Afşin 1 [p. 215] Sterrett 1883-84, 285 no. 329

■■■■■A■OR  
■■■■■OC  
■■■■■O■A■N  
ON■■■■■  
■■■■■M■■■■■  
■■■■■N  
■N■■■■■OP■■■■■

### 6.1.87 116(B). Afşin 2 [p. 215] Sterrett 1883-84, 285 no. 330

IMPTRIBPOTVIA  
ET NTE  
SR STITVERVN  
CIVLI OCI  
5 AVG PR  
C

### 6.1.88 116(C). Afşin 3 [p. 215] de Jerphanion and Jalabert 1908, 457 no. 24

I  
RESTIT  
PER  
CIVLIVMFLAC  
CVMAELIANVMLEGPRPR  
MIL P

### 6.1.89 117(A). Emirli 1 [p. 216] Sterrett 1883-84, 288 no. 337

IMP%CAESAR  
AVREL  
[Space overwritten.]  
%POTEST%COS  
UIASETPONT  
5 UETTUSTAT  
APSASREST  
T%

### 6.1.90 118(B). Izgın, Çatburun 2 [p. 218] Sterrett 1883-84, 291 no. 341

### 6.1.91 118(C). Izgın, Çatburun 3 [p. 219] Sterrett 1883-84, 292 no. 342

## 6.1 Facsimiles of Published Texts

IMP CAESAR  
MAVRELIVSSEV  
VSALE.....  
PIVSFELICT..TR  
IB POTEST COS  
PP V IASETPONT  
ESVETTVSTATE  
NLAPSASREST  
T

Imp. Caesar  
M. Aurelius Sev-  
er]us Ale[xander  
pius fel. i(nv). [Aug.] tr-  
ib. potest. cos.  
p. p. vias et pont-  
es vettustate  
co]nlapsas rest-  
itui]t.

## 6.1.92 118(C). Izgın, Çatburun 3 [p. 219] Hogarth and Munro 1893, 706 “94 (i)”

I.....  
G....R(?)  
VIOVL....VS  
XIMI..P..  
FELIC.AVG..

..LEG..

I[mp.  
C[aesa]r[i  
G]aio [J]ul[io Vero Ma-  
ximi[no] p[io  
felic[i] aug. [p. m.  
[trib. potest. p. p.]  
[per Licinnium]  
[Serenian-]  
um] leg. [Aug.  
[pr. pr.]

## 6.1.93 118(D). Izgın, Çatburun 4 [p. 220] Hogarth and Munro 1893, 706 “94 (ii)”

EROCOS  
TIMPCAES.M.AVREL  
ANTONINVS.AVG  
ETI SEPTIMIVS  
GEIACAESRESTIT  
VERVNT.PEP.C.IVLIVM  
ELACCVMAELIANVM  
LE PR PR

CAES  
TRIBPOTEST  
ASRESTIT

6.1.95 120(B). Izgın 2 [p. 222]  
Sterrett 1883-84, 293 no. 3446.1.94 120(A). Izgın 1 [p. 221]  
Sterrett 1883-84, 293 no. 343”

## 6.1 Facsimiles of Published Texts

IMPCAES  
MANT  
CORDIANO  
PUSFE  
UC CAES  
MAXIMIA  
TRIBPOTEST  
ESRESTIT  
PERCUSPIDIUM  
F AM  
UG

CAES  
EP  
NIC A  
RESTITVTA  
POFELLI  
VM THEODORVM  
AVG PRPR

**6.1.96** 120(B). Izgin 2 [p. 222]  
Hogarth and Munro 1893, 707 “93 to 59(i)”

... CAES  
..... VER. NEP  
..... ARI  
..... N. U M...  
.... E.... AVG  
..... RESTITV F.  
... M v LPOFELLI...  
THEODORUM  
... AVGPRPR

**6.1.97** 123(A). Elbistan 1 [p. 224]  
Sterrett 1883-84, 294 no. 345

Imp.] Caes.  
divi Se]ver[i] nep.  
[divi M. Antonini fil.]  
M. Aur. A]n[t]on[ino]  
pio f]e[lici] aug.  
milia] restitut[a]  
per] M. Ulp. Ofelli[um]  
Theodorum  
leg.] aug. pr. pr.

**6.1.98** 123(A). Elbistan 1 [p. 224] Hogarth and Munro 1893, 707 “93 to 59(iii)”

... ER..  
.. AB  
O

Sev]er[us  
Ar]ab.

**6.1.99** 123(B). Elbistan 2 [p. 224] Hogarth and Munro 1893, 707 “93 to 59(iv)”

(v.) *Ibid.*, intentionally defaced.

[Several lines gone.]  
vetust ATECO nlapsas  
RE stituiT per  
Antoni] VM Memmium HIER onem  
leg. AVG

.. GUS  
ANC.....ISJ A..  
E.....F.....CIG  
.....  
NOBBCE

(vii.) On the other side of the same stone.

IUU  
COC...ANTIO  
ICA  
NOO

**6.1.100** 123(C). Elbistan 3 [p. 225]  
Hogarth and Munro 1893, 707 “93 to 59(v)”

**6.1.101** 123(D). Elbistan 4 [p. 225] Hogarth  
and Munro 1893, 708 “93 to 59(vi) and (vii)”

## 6.1 Facsimiles of Published Texts

LI<sup>-</sup> S R  
C  
.....  
AV  
RIS V  
T  
A

**6.1.102** 123(E). Elbistan 5 [p. 226] Hogarth and Munro 1893, 707 “93 to 59(viii)”

..... FEA .....  
..... GAVG  
NH

**6.1.103** 123(F). Elbistan 6 [p. 226] Hogarth and Munro 1893, 707 “58”



**6.1.104** 151. Şebinkarahisar [p. 259] Taylor 1868, 295

96. On a pillar now split. On the edges are fragments of a Latin

ΑΥΤΟΚΡΑΤΟΡΩΝ ΚΕΣ // // //  
ΦΛΟΥΑΛΚΩΝΣΤΑΝΤΙΝ // //  
ΕΥΣΕΒΙΕΥΤΥΧΙΣΕΒ // //  
ΟΥΑΛΛΙΚΙΝΝΙΑΝΩΛΙΚ // //  
ΕΥΣΕΒΙΕΥΤΥΧΙΣΕΒΜΕΡΙΕΤ // //  
ΦΛΟΥΑΛΚΡΙΣΤΩΚΕ // // //  
ΟΥΑΛΛΙΚΙΝΙΩΚΑΙΦΛΑΕ // //  
ΚΛΑΥΔΙΩΚΩΝΣΤΑΝΤΙΝΩ  
ΕΠΙΦ·ΚΑΙΣΑΡCIN

*vacat*

On the left-hand edge is:—

//RESTI  
*tuerunt* . . . . //TIS

Αὐτοκράτορ(σι)ν Κέσ[αρσι  
Φλ. Οὐαλ. Κωνσταντί[νω  
εὐσεβί εὐτυχί Σεβ. μ[εγίστῳ κέ  
Οὐαλ. Δικιννιανῶ Δικιν[νίῳ  
εὐσεβί εὐτυχί Σεβ. μεγίστῳ,  
Φλα. Οὐαλ. Κρίσπῳ κέ  
Οὐαλ. Δικιννίῳ καὶ Φλα.  
Κλαυδίῳ Κωνσταντίνῳ  
ἐπιφ(ανεστάτοις) Καίσαρσιν.

**6.1.105** 158. Değirmenyolu [p. 263] Anderson 1899, 108 no. 96

## 6.1 Facsimiles of Published Texts

IMP·CAES·DIVI·SEVERI·NEP  
 DIVI·ANTONINI·MAG·PII  
 FIL·M·AVR·SEVERO  
 PIO·FEL·AVG  
 PONT·MAX·TRIB·POTEST  
 IMP·II·COS·PPRO·COS  
 PERASINIVM·LEPIDVM  
 LEG·AVG·PR·PR·PRAESID  
 PROVINC·CAPP

IA

**6.1.106** 164(A). Eminlik 1 [p. 272] Jacopi 1938, 32 and Fig. 132




**6.1.107** 164(B). Eminlik 2 [p. 272] Jacopi 1938, 33 and Fig. 134

## 6.2 Drawings from Squeezes

01.	002. Çalış	[p. 29]	Maximinus with Maximus
02.	011. Çaltılı	[p. 37]	Nerva or Traianus
03.	014. Karaağaç	[p. 40]	Constantinus and four sons
04.	018. Çiğdemlik	[p. 45]	(2) Diocletianus <i>et coll.</i>
05.	019. Amasya	[p. 46]	Nerva
06.	021. Aydoğdu	[p. 48]	(2) Diocletianus <i>et coll.</i>
07.	022. Boğa	[p. 49]	Diocletianus <i>et coll.</i>
08.	023(B). Bağlıca 2	[p. 50]	Gordianus III
09.	036. Güngörmez	[p. 66]	Hadrianus
10.	037(C). Çorum Museum	[p. 69]	Probus
11.	038. Tolahmet	[p. 70]	Trebonianus Gallus and Veldumnianus
12.	039. Karapınar	[p. 71]	(?)
13.	040. Saray	[p. 71]	(1) (?), (2) Gordianus III
14.	042. Çeşmeören	[p. 73]	Nerva
15.	044. Sapa	[p. 74]	Gordianus III
16.	045. Seyfe	[p. 75]	(?)
17.	046. Ertuğrul	[p. 76]	(?)
18.	047. Deniz	[p. 76]	Diocletianus <i>et coll.</i>
19.	051. Yağmurlu	[p. 81]	Hadrianus
20.	054(F). Tokat 6	[p. 85]	Nerva
21.	054(G). Tokat Museum 1	[p. 86]	Severus Alexander
22.	054(H). Tokat Museum 2	[p. 87]	Probus
23.	056(A). Zile 1	[p. 88]	Severus Alexander
24.	056(B). Zile 2	[p. 90]	(1) Sept. Severus and sons (2) Diocletianus <i>et coll.</i>
25.	056(B). Zile 3	[p. 91]	(1) (?) Hadrianus or Severus Alexander (2) Diocletianus <i>et coll.</i>
26.	068(A). Aslanbeyli Yaylası, Hanboğaz 1	[p. 104]	Severus Alexander
27.	068(B). Aslanbeyli Yaylası, Hanboğaz 2	[p. 105]	Elagabalus
28.	068(C). Aslanbeyli Yaylası, Hanboğaz 3	[p. 105]	Pupienus and Balbinus, then Gordianus III
29.	068(D). Aslanbeyli Yaylası, Hanboğaz 4	[p. 106]	Philippus with Philippus
30.	070(C). Değirmentaş 3	[p. 109]	(?)
31.	114. Ördek	[p. 213]	(?) Severus Alexander
32.	115. Alımpınar	[p. 214]	(2) Probus
33.	118(C). Izgın, Çatburun 3	[p. 219]	(1) Elagabalus (2) Severus Alexander
34.	137. Kadişehri	[p. 238]	(1) (?) (2) Diocletianus <i>et coll.</i>
35.	156. Bahçebaşı	[p. 261]	Diocletianus <i>et coll.</i>

## 6.2 Drawings of Squeezes



6.2.1 002. Çalış [p. 29]




6.2.2 011. Çaltılı [p. 37]




## 6.2 Drawings of Squeezes

IMPERATOR CAES  
 FIVLCOMVICTOR  
 MAXIMO VICTOR  
 ACTRIVM FATOR  
 SE MPERAVC  
 ET CLCONSTANTINO  
 ET FVLCONSTANTIO  
 ET FVLCONSTANTAE  
 ET FLEIMATIO  
 INI



6.2.3 014. Karaağaç [p. 40]

F VIC VAJHO  
 CON, TINTIC  
 ET GALIA  
 MAXIMIANO  
 NOBIL CAESS  
 MILP IB  
 APRISCIANVS  
 VPRAESPPONT  
 DNMQEORVA



6.2.4 018. Çiğdemlik [p. 45]

## 6.2 Drawings of Squeezes

IMI  
PONTIF.  
TEST·CO  
TVITPEK  
VMB/  
A'IC

 10 cm

6.2.5 019. Amasya [p. 46]

IMD D N N  
AVRENTUANSY  
DIOCLETIANO  
FETINVAUGET  
IMP CAES M  
AVRELIOVAL  
I. A. I. U.  
PF INVAUGET  
FUA IERA  
GO  
C  
A

 10 cm

6.2.6 021. Aydoğdu [p. 48]

VIII  
Θ  
AVRPRISCJANVS  
VPPRAESP P  
DNMQSOR·I·I

 10 cm


6.2.7 022. Boğa [p. 49]

IMP·CAES M A A N  
TONIVSEORΔIAN  
VSAIVIEORΔIAN  
I NEPOS PIVS FEL  
X INVICTVS AVC V  
CTVS TRIBVI


 10 cm

6.2.8 023(B). Bağlıca 2 [p. 50]


## 6.2 Drawings of Squeezes



6.2.9 036. Güngörmez [p. 66]




6.2.10 037(C). Çorum Museum [p. 69]




6.2.11 038. Tolahmet [p. 70]

## 6.2 Drawings of Squeezes



6.2.12 039. Karapınar [p. 70]



6.2.13 040. Saray [p. 71]

IMP·NERVA·  
 AVG·PONT  
 TRIB·POTIS  
 P·P·RESTI  
 POMPOI  
 BA VA  
 AV·P


MB PL  
 N

10 cm

6.2.14 042. Çeşmeören [p. 72]


## 6.2 Drawings of Squeezes

IMP·CAES  
 M·ANTONIVS  
 CORDIANVSDIVI  
 CORDIANINEPOS·  
 PIVS·FELIX·INVICTVS  
 AVGVSTVS·  
 PP·TRIBVN CIAE·  
 POTESTATIS  
 VIAM·RESTITVIT  
 MP·AMASEN  
 ORVM




6.2.15 044. Sapa [p. 74]

MIL·P LXXVI  
 O5



6.2.16 045. Seyfe [p. 75]


RESTITVIT  
 MP·AMASENO  
 RVM MILPLXXV  
 S  
 OE



6.2.17 046. Ertuğrul [p. 75]

## 6.2 Drawings of Squeezes

IIM 3ISAYAZERIO L  
 CZHTIANNOPI FL  
 TQAVETINI E  
 AVR MAXIMIAN  
 INAVRETEIAVIO  
 IMIANOTETRA  
 STANTIONOT  
 REYAL



25 cm

6.2.18 047. Deniz [p. 76]


IM  
 CAESA.  
 IANIPA  
 FILDIV  
 NEPOC  
 MP



10 cm

6.2.19 051. Yağmurlu [p. 81]


P·P·RESIIIVIT  
 POMPONIVMBA  
 IEC AVG·PR·PR



10 cm

6.2.20 054(F). Tokat 6 [p. 85]


POT·XIII·I AP·XIII  
 P·P·MILITARIA  
 A·SEBASTOPOLI  
 RESTITVIT  
 MIL·P



10 cm

6.2.21 054(G). Tokat Museum 1 [p. 86]


MAAL I TIP I U I III I I  
 PROC·ACOMANA  
 MI·P·II·CURAN  
 TEAE·QVINTIANO  
 V·P·PR P·P



10 cm


6.2.22 054(H). Tokat Museum 2 [p. 87]

## 6.2 Drawings of Squeezes



6.2.23 056(A). Zile 1 [p. 88]

## 6.2 Drawings of Squeezes




6.2.24 056(B). Zile 2 [p. 90]



## 6.2 Drawings of Squeezes


IMPER CAES  
 CAIOAVR VAL  
 DIOCLETIANO  
 PIO FELINVC AVG  
 ET IMPER CAES A  
 MARAVR VAL  
 MAXIMIANO II<sup>ST</sup>  
 PIO FELINVC AVG  
 ET FLAV VAL  
 CONSTANTIO I  
 AETCAL VAL TIF  
 MAXIMIANO III<sup>ST</sup>  
 P<sup>R</sup>INOBISSIMIS I  
 CAESARIBVS  
 ZELIT MIL<sup>IT</sup> P I  
 AVR PRIS  
 VP PRAES  
 DN M Q EC



6.2.25 056(B). Zile 3 [p. 91]


## 6.2 Drawings of Squeezes

IΛPQC  
 ESARMQAU  
 REKIUS SEUEI  
 USA KEXA'IDE  
 RPI USFE IXA  
 USQTRIGQPC  
 TESTQCO SQ  
 PPQUIAS ETPO  
 NTESUE TUS  
 TATECONKAPS  
 ASRES TITUITQ  
 NΓ




6.2.26 068(A). Aslanbeyli Yaylası,  
Hanboğaz 1 [p. 104]

IΛ PCAES  
 DIVISEVE  
 INEP DIVIΛA  
 NTONINIFIL  
 MAVRANTII  
 NO PIO FELICIAI  
 SMILIAP  
 NE TITVTAP  
 ERUVLF  
 FELLIVUTH  
 E ODORVULF  
 GAVSPRP  
 NΓ




6.2.27 068(B). Aslanbeyli Yaylası,  
Hanboğaz 2 [p. 105]

## 6.2 Drawings of Squeezes




6.2.28 068(C). Aslanbeyli Yaylası, Hanboğaz 3 [p. 105]

## 6.2 Drawings of Squeezes




6.2.29 068(D). Aslanbeyli Yaylası, Hanboğaz 4 [p. 106]

## 6.2 Drawings of Squeezes



6.2.30 070(C). Değirmentaş 3 [p. 109]



6.2.31 114. Ördek [p. 213]

## 6.2 Drawings of Squeezes

IIM.  
 CAES  
 MA AV  
 , PP ORU  
 PF INVI  
 LAUS A  
 MCV

10 cm


6.2.32 115. Alımpınar [p. 214]

IAKPOCAES  
 MA AURELIXISSE  
 VERUSALEKANDER  
 PFUSAEVLIXADTR  
 IBOPOTES TACQS  
 PPQIMSETPONT  
 -SUE TTUSNATE  
 LAESASREST  
 ' T Q


10 cm

6.2.33 118(C). Izgın, Çatburun 3 [p. 219]

## 6.2 Drawings of Squeezes



6.2.34 137. Kadışehri [p. 238]



6.2.35 156. Bahçebaşı [p. 261]

## 7. ILLUSTRATIONS: PLATES

### 7.1 Milestones

001. 009. Hatipli	[p. 36]	(1) Diocletianus <i>et coll.</i> (2) Constantinus I with 4 <i>Caesares</i>
002. 014. Karaağaç	[p. 40]	Constantinus I with 4 <i>Caesares</i>
003. 015. Çakırsu	[p. 40]	
004. 016. Yerkozlu	[p. 43]	(1) Carus with Carinus and Numerianus (2) Diocletianus <i>et coll.</i>
005. 019. Amasya	[p. 46]	Nerva
006-007. 021. Aydoğdu	[p. 48]	(1) Diocletianus <i>et coll.</i> (2) Valentinianus, Valens and Gratianus
008-010. 023(A). Bağlıca 1	[p. 49]	(1) Hadrianus (2) Tetrarchic <i>et seqq.</i>
011. 023(A). Bağlıca 2	[p. 50]	Gordianus III
012-013. 025. Toklucak	[p. 52]	(1) Carus with Carinus and Numerianus (2) Constantinus I with 3 <i>Caesares</i>
014. 026. Karayakup	[p. 53]	Galerius and Severus with <i>Caesares</i>
015. 031. Köseeyüp	[p. 59]	(1) Nerva, (2) Constantinus I with 3 <i>Caesares</i>
016. 032(A). Kozören 1	[p. 60]	Philippus with Philippus
017. 032(B). Kozören 2	[p. 61]	Sept. Severus and sons
018. 036. Güngörmez	[p. 66]	Hadrianus
019. 037(C). Çorum Museum	[p. 69]	Probus
020. 042. Çeşmeören	[p. 73]	Nerva
021. 044. Sapa	[p. 74]	Gordianus III
022. 046. Ertuğrul	[p. 76]	(?)
023. 050(C). Boğazbaşı 2	[p. 80]	Sept. Severus and sons
024. 051. Yağmurlu	[p. 81]	Hadrianus
025. 056(B). Zile 2	[p. 90]	(1) Sept. Severus and sons, (2) Diocletianus <i>et coll.</i>
026. 056(C). Zile 3	[p. 91]	(1) Hadrianus ? or Severus Alexander ? (2) Diocletianus <i>et coll.</i>
027. 056(D). Zile 4	[p. 92]	(1) Diocletianus <i>et coll.</i> (2) Constantinus I and Licinius I with <i>Caesares</i>
028. 057. Kurupınar	[p. 94]	Constantinus I with 3 <i>Caesares</i>
029. 061. Sulusaray	[p. 97]	Gordianus III and Tranquillina
030. 065. Kayseri	[p. 100]	Elagabalus with Severus Alexander
031. 065. Kayseri	[p. 100]	Elagabalus with Severus Alexander
032. 067. Özlüce 1-4	[p. 103]	milestone cluster
033. 068. Aslanbeyli Yaylası, Hanboğazı	[p. 104]	milestone-cluster
034. 068(A). Aslanbeyli Yaylası, Hanboğazı 1	[p. 104]	Severus Alexander
035. 070. Değirmentaş 2-4	[p. 109]	milestone-cluster
036. 072. Değirmentaş, Arkaçlar Mevkii 2	[p. 111]	milestone-cluster
037. 072(D). Değirmentaş, Arkaçlar Mevkii 2.4	[p. 112]	(?)
038. 072(E). Değirmentaş, Arkaçlar Mevkii 2.5	[p. 112]	Severus Alexander
039. 072(F). Değirmentaş, Arkaçlar Mevkii 2.6	[p. 113]	Sept. Severus [and sons]
040. 072(G). Değirmentaş, Arkaçlar Mevkii 2.7	[p. 114]	Traianus Decius and Her. Etruscus
041. 074(A). İmirzağa, Eski Harabe Mevkii 1	[p. 115]	Sept. Severus and sons
042. 074(B). İmirzağa, Eski Harabe Mevkii 2	[p. 116]	(?)
043. 075. İmirzağa, Barcın Mevkii	[p. 117]	milestone-cluster



044. 076. Çakırlar, Barcın Yayla	[p. 121]	Severus Alexander
045. 079. Çakırlar, Beşiktaş 1-2	[p. 122]	
046. 079. Çakırlar, Barcın Geçidi 1-3	[p. 126]	milestone-cluster
047. 080(A). Çakırlar, Meşelik 1	[p. 128]	[Philippus]
048. 080(B). Çakırlar, Meşelik 2	[p. 129]	Gordianus III
049. 080(C). Çakırlar, Meşelik 3	[p. 130]	(?)
050. 084. Mollahüseyin 4	[p. 133]	Gordianus III
051. 085(B). Mollahüseyin 2	[p. 135]	Maximinus
052. 085(E). Mollahüseyin 5	[p. 137]	Maximinus with Maximus
053. 088(B). Kemer 4	[p. 142]	Sept. Severus and sons
054-055. 089(C). Kemer 9	[p. 146]	[Philippus]
056. 090(A). Dayıoluk 1	[p. 149]	(?)
057. 090(C). Dayıoluk 3	[p. 150]	[Sept. Severus]
058. 092(G). Yalak 4	[p. 155]	(1) Philippus with Philippus, (2) Galerius
059. 094(A). Doğankonak 1	[p. 158]	[Maximinu]
060. 094(B). Doğankonak 2	[p. 159]	Elagabalus
061. 094(C). Doğankonak 3	[p. 160]	Philippus
062. 094. Doğankonak 3+4	[p. 160]	milestone-cluster
063. 095. Doğankonak, Kumocağı	[p. 161]	Gordianus III
064. 096. Doğankonak, Sakaltutan	[p. 162]	(1) (?), (2) Galerius
065. 097(A). Doğankonak, Şabanağa Mevkii 1	[p. 163]	Elagabalus
066. 097(B). Doğankonak, Şabanağa Mevkii 2	[p. 164]	Maximinus
067. 098(B). Keklikoluk 2	[p. 166]	Maximinus
068. 101(A). Keklikoluk, Kayapınar 1	[p. 170]	(?)
069. 103(A). Mehmetbey 1	[p. 171]	(1) Philippus, (2) Diocletianus
070. 104(C). Göksun 3	[p. 175]	(1) Maximinus, (2) Diocletianus
071. 104(D). Göksun 4	[p. 176]	(1) Elagabalus, (2) Galerius
072. 104(E). Göksun 5	[p. 177]	Elagabalus
073. 104(F). Göksun 6	[p. 178]	(1) Elagabalus, (2) Severus Alexander
074. 104(H). Göksun 19	[p. 180]	[Elagabalus]
075. 105(A). Göksun 8	[p. 182]	(1) (?), (2) Sept. Severus and sons
076. 105(E). Göksun 12	[p. 185]	Elagabalus
077. 107. Yağmurlu	[p. 187]	milestone-cluster
078. 107(D). Yağmurlu 4	[p. 189]	Maximinus
079. 108(A). Kanlıkavak 1	[p. 192]	Philippus with Philippus
080. 108(B). Kanlıkavak 2	[p. 193]	(?)
081. 108(S). Kanlıkavak 19	[p. 206]	(?)
082. 109. Yeniyapan	[p. 207]	milestone-cluster
083. 109(E). Yeniyapan 5	[p. 209]	[Gordianus III]
084. 113(A). Karaömer, Kızılcıksuyu Mevkii 1	[p. 212]	Maximinus
085. 117. Izgin, Catburun	[p. 218]	milestone-cluster
086. 129(A). Gözecik 1	[p. 231]	(1) (?), (2) Diocletianus
087. 130. Darıca	[p. 233]	(?)
088. 131. Şekerpınar	[p. 234]	(?)
089. 137. Kadışehri	[p. 238]	(1) (?), (2) Diocletianus <i>et coll.</i>
090. 138. Çamsaray	[p. 239]	Philippus I and II and Otacilia
091. 138. Çamsaray	[p. 239]	milestone base
092. 139. Özükkavak	[p. 240]	(1) (?), (2) Probus
093. 140(A). Güzelbeyli 1	[p. 242]	Diocletianus <i>et coll.</i>
094. 141. Yıldıztepe	[p. 243]	(1) Trebonianus Gallus

			(2) Diocletianus <i>et coll.</i> ,
			(3) Constantinus I with 3 sons
095.	142. Alayurt	[p. 244]	(1) (?), (2) Diocletianus <i>et coll.</i>
096.	143. Akyazı	[p. 245]	Diocletianus <i>et coll.</i>
097.	144. Mahmatlar	[p. 246]	Diocletianus <i>et coll.</i>
098.	145(A). Uygur 1	[p. 247]	(1) (?), (2) Constantinus I and Licinius I
099.	146. Ezinepazar	[p. 250]	Constantius and Galerius
100.	147(B). Kapıkaya 2	[p. 251]	Tacitus
101.	147(C). Kapıkaya 3	[p. 251]	Aurelianus
102.	147(D). Kapıkaya 4	[p. 252]	(1) Sept. Severus and sons, (2) (?), (3) Diocletianus <i>et coll.</i> , (4) Constantinus I and 3 sons
103.	149(A). Uluköy 1	[p. 255]	Sept. Severus and sons
104.	158. Değirmenyolu	[p. 263]	Constantinus I and Licinius I with Crispus, Licinius II and Constantinus II <i>Caesares</i>
105.	159. Topakkaya	[p. 264]	Macrinus with Diadumenianus
106.	162(A). Kemerhisar, Salmanlı Çiftlik 1	[p. 267]	Gordianus III
107.	166. Pozantı 1	[p. 274]	Caracalla
108.	168. Pozantı, Soğukpınar	[p. 276]	Severus Alexander

## 7.1 Photographs of Milestones



7.1.1 009. Hatipli [p. 36]




7.1.2 014. Karaağaç [p. 40]

## 7.1 Photographs of Milestones



7.1.3 015. Çakırsu [p. 40]



7.1.4 016. Yerkozlu [p. 43]



7.1.5 019. Amasya [p. 46]

## 7.1 Photographs of Milestones



7.1.6 021. Aydoğdu [p. 48]




7.1.7 021. Aydoğdu [p. 48]

## 7.1 Photographs of Milestones




7.1.8 023(A). Bağlıca 1 [p. 49]



7.1.9 023(A). Bağlıca 1 [p. 49]



7.1.10 023(A). Bağlıca 1 [p. 49]



7.1.11 023(A). Bağlıca 2 [p. 50]

## 7.1 Photographs of Milestones




**7.1.12** 025. Toklucak [p. 52]



**7.1.13** 025. Toklucak [p. 52]



## 7.1 Photographs of Milestones



7.1.14 026. Karayakup [p. 53]



7.1.15 031. Köseeyüp [p. 59]



7.1.16 032(A). Kozören 1 [p. 60]



## 7.1 Photographs of Milestones



7.1.17 032(B). Kozören 2 [p. 61]



7.1.18 036. Güngörmez [p. 66]



7.1.19 037(C). Çorum Museum [p. 69]




7.1.20 042. Çeşmeören [p. 73]

## 7.1 Photographs of Milestones



7.1.21 044. Sapa [p. 74]



7.1.22 046. Ertuğrul [p. 75]




7.1.23 050(C). Boğazbaşı 2 [p. 80]

## 7.1 Photographs of Milestones



7.1.24 051. Yağmurlu [p. 81]




7.1.25 056(B). Zile 2 [p. 90]


## 7.1 Photographs of Milestones



7.1.26 056(C). Zile 3 [p. 91]



7.1.27 056(D). Zile 4 [p. 92]



7.1.28 057. Kurupınar [p. 94]



7.1.29 061. Sulusaray [p. 97]

## 7.1 Photographs of Milestones



**7.1.30** 065. Kayseri [p. 100]



**7.1.31** 065. Kayseri [p. 100]



**7.1.32** 067. Özlüce 1-4 [p. 103]



## 7.1 Photographs of Milestones



**7.1.33** 068. Aslanbeyli Yaylası, Hanboğazı [p. 104]




**7.1.34** 068(A). Aslanbeyli Yaylası, Hanboğazı 1 [p. 104]

## 7.1 Photographs of Milestones



**7.1.35** 070. Değirmentaş 2-4 [p. 109]



**7.1.36** 072. Değirmentaş,  
Arkaçlar Mevkii 2 [p. 111]



**7.1.37** 072(D). Değirmentaş,  
Arkaçlar Mevkii 2.4 [p. 112]



**7.1.38** 072(E). Değirmentaş,  
Arkaçlar Mevkii 2.5 [p. 112]

## 7.1 Photographs of Milestones



**7.1.39** 072(F). Değirmentaş,  
Arkaçlar Mevkii 2.6 [p. 113]



**7.1.40** 072(G). Değirmentaş,  
Arkaçlar Mevkii 2.7 [p. 114]



**7.1.41** 074(A). İmirzağa,  
Eski Harabe Mevkii 1 [p. 115]



**7.1.42** 074(B). İmirzağa,  
Eski Harabe Mevkii 2 [p. 116]



## 7.1 Photographs of Milestones




**7.1.43** 075. İmirzağa, Barcın Mevkii [p. 117]



**7.1.44** 076. Çakırlar, Barcın Yayla [p. 121]



**7.1.45** 079. Çakırlar, Beşiktaş 1-2 [p. 122]



**7.1.46** 079. Çakırlar, Barcın Geçidi 1-3  
milestone cluster [p. 124]

## 7.1 Photographs of Milestones




**7.1.47** 080(A). Çakırlar, Meşelik 1 [p. 129]



**7.1.48** 080(B). Çakırlar, Meşelik 2 [p. 129]




**7.1.49** 080(C). Çakırlar, Meşelik 3 [p. 130]




**7.1.50** 084. Mollahüseyin 4 [p. 133]

## 7.1 Photographs of Milestones



**7.1.51** 085(B). Mollahüseyin 2 [p. 135]



**7.1.52** 085(E). Mollahüseyin 5 [p. 137]



**7.1.53** 088(B). Kemer 4 [p. 142]

## 7.1 Photographs of Milestones



**7.1.54** 089(C). Kemer 9 [p. 146]



**7.1.55** 089(C). Kemer 9 [p. 146]




**7.1.56** 090(A). Dayıoluk 1 [p. 149]



## 7.1 Photographs of Milestones




**7.1.57** 090(C). Dayıoluk 3 [p. 150]




**7.1.58** 092(G). Yalak 4 [p. 155]

## 7.1 Photographs of Milestones



**7.1.59** 094(A). Doğankonak 1 [p. 158]



**7.1.60** 094(B). Doğankonak 2 [p. 159]



**7.1.61** 094(C). Doğankonak 3 [p. 160]



**7.1.62** 094. Doğankonak 3+4  
milestone cluster [p. 160]

## 7.1 Photographs of Milestones



**7.1.63** 095. Doğankonak, Kumocağı [p. 161]



**7.1.64** 096. Doğankonak, Sakaltutan [p. 162]



**7.1.65** 097(A). Doğankonak,  
Şabanağı Mevkii 1 [p. 163]



**7.1.66** 097(B). Doğankonak,  
Şabanağı Mevkii 2 [p. 164]

## 7.1 Photographs of Milestones



**7.1.67** 098(B). Keklikoluk 2 [p. 166]



**7.1.68** 101(A). Keklikoluk,  
Kayapınar 1 [p. 171]



**7.1.69** 103(A). Mehmetbey 1 [p. 171]



## 7.1 Photographs of Milestones




**7.1.70** 104(C). Göksun 3 [p. 175]



**7.1.71** 104(D). Göksun 4 [p. 176]



**7.1.72** 104(E). Göksun 5 [p. 177]




**7.1.73** 104(F). Göksun 6 [p. 178]

## 7.1 Photographs of Milestones



**7.1.74** 104(H). Göksun 19 [p. 180]



**7.1.75** 105(A). Göksun 8 [p. 182]



**7.1.76** 105(E). Göksun 12 [p. 185]

## 7.1 Photographs of Milestones



7.1.77 107. Yağmurlu [p. 187]



7.1.78 107(D). Yağmurlu 4 [p. 189]



7.1.79 108(A). Kanlıkavak 1 [p. 192]

## 7.1 Photographs of Milestones



**7.1.80** 108(B). Kanlıkavak 2 [p. 193]



**7.1.81** 108(S). Kanlıkavak 19 [p. 206]




**7.1.82** 109. Yenyapan [p. 207]



## 7.1 Photographs of Milestones



**7.1.83** 109(E). Yenyapan 5 [p. 209]



**7.1.84** 113(A). Karaömer,  
Kızılcıksuyu Mevkii 1 [p. 212]



**7.1.85** 118. Izgın, Çatburun milestone cluster [p. 218]

## 7.1 Photographs of Milestones



**7.1.86** 129(A). Gözecik 1 [p. 231]




**7.1.87** 130. Darıca [p. 233]

## 7.1 Photographs of Milestones



**7.1.88** 131. Şekerpınar [p. 234]



**7.1.89** 137. Kadışehri [p. 238]



**7.1.90** 138. Çamsaray [p. 239]



**7.1.91** 138. Çamsaray [p. 239]


## 7.1 Photographs of Milestones



**7.1.92** 139. Özükevâk [p. 240]



**7.1.93** 140(A). Güzelbeyli 1 [p. 242]



**7.1.94** 141. Yıldıztepe [p. 243]



## 7.1 Photographs of Milestones




**7.1.95** 142. Alayurt [p. 244]



**7.1.96** 143. Akyazı [p. 245]

## 7.1 Photographs of Milestones



7.1.97 144. Mahmatlar [p. 246]



7.1.98 145(A). Uyгур 1 [p. 247]


## 7.1 Photographs of Milestones



**7.1.99** 146. Ezinepazar [p. 250]



**7.1.100** 147(B). Kapıkaya 2 [p. 251]



**7.1.101** 147(C). Kapıkaya 3 [p. 251]


## 7.1 Photographs of Milestones




**7.1.102** 147(D). Kapıkaya 4 [p. 252]



**7.1.103** 149(A). Uluköy 1 [p. 255]




**7.1.104** 158. Değirmenyolu [p. 263]




**7.1.105** 159. Topakkaya [p. 264]

## 7.1 Photographs of Milestones



**7.1.106** 162(A). Kemerhisar,  
Salmanlı Çiftlik 1 [p. 267]



**7.1.107** 166. Pozantı 1 [p. 274]



**7.1.108** 168. Pozantı, Soğukpınar [p. 276]

**7.2 Squeezes**

01.	043. Hamdi	[p. 73]	Maximinus
02.	147(D). Kapıkaya 4	[p. 252]	(1) Sept. Severus and sons
03.	156. Bahçebaşı	[p. 261]	Diocletianus and [Maximianus]
04.	161. Demirci	[p. 266]	Macrinus with Diadumenianus



## 7.2 Photographs of Squeezes




7.2.1 043. Hamdi [p. 73]



7.2.2 147(D). Kapıkaya 4 [p. 252]


## 7.2 Photographs of Squeezes



7.2.3 156. Bahçebaşı [p. 261]



## 7.2 Photographs of Squeezes



**7.2.4** 161. Demirci [p. 266]